This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

GANOT'S PHYSICS BY ATKINSON.

The Sixth Edition, revised and enlarged, in One thick Volume, with 4 Coloured Plates and 746 Woodcuts, post 8vo. price 15*s.* cloth,

ELEMENTARY TREATISE ON PHYSICS,

EXPERIMENTAL AND APPLIED,

FOR THE USE OF COLLEGES AND SCHOOLS.

Translated and Edited from GANOT'S *Éléments de Physique* (with the Author's sanction).

By E. ATKINSON, Ph.D. F.C.S.

Professor of Experimental Science, Staff College, Sandhurst.

In the present edition a somewhat larger and more elegant type and a larger page have been adopted. Thus while adding twenty-eight new illustrations, and a considerable quantity of new matter, the actual number of pages has been diminished, and the book has thereby been rendered more convenient. In making the additions, while the wants of the general reader have been attended to, the principal aim of the Editor has been, as in former editions, to render the book more useful for the student of physical science. Accordingly, as regards new matter, the main additions have been in those subjects which are calculated to take a permanent place in elementary instruction.

'This treatise is too well-known and appreciated to require any special notice beyond the fact that the present edition has received numerous additions, both in the way of letterpress and illustrations. Those parts referring to physiological electricity have been revised, and in a great measure rewritten, by DR. MARTIN, of Christ's College, Cambridge. Altogether the sixth edition of GANOT'S *Physics* is in every way an excellent book for students of physical science.'

LANCET.

GANOT'S *Treatise on Physics.*

'It is a question which enjoys the greatest popularity, the *Éléments de Physique*, or Dr. ATKINSON'S translation of it. Perhaps we should be almost inclined to say that the translation has the best of it. This is the fifth edition, and we have no doubt that it will be exhausted as rapidly as were its four predecessors. We have plenty of books of the sort in English; LARDNER'S are about the best among popular books, but there is none that rivals GANOT. Its accuracy is as great as its extent is wide, and its descriptions are as intelligible and popular as they are correct. As Mr. LOWE said at Halifax—speaking of a serial devoted to technical instruction—he might have said of it, *A man who really has read and thoroughly knows the contents of that work, is a man who will understand the greatest part of what is going on around him (in the physical world), which is a great deal more than can be said of the best Greek or Latin scholar, or even the most accomplished lawyer.* Anybody who has attained a mastery, even an incomplete one, over this remarkable book, will have laid up a store of knowledge sufficient to raise him considerably above the average host. To those who know the book, we need say nothing in its praise. To those who do not, we can say that though scientific, it is not dry or dull; that though deeply learned, it is as far from being uninteresting as it well can be. The deep study of science is too apt to make DRYASDUSTS of its votaries, and the consequence is that most of our scientific books are either immensely valuable but unutterably dull, or else very amusing but entirely useless. The one sort are written by *savans*, who cannot, and would not if they could, make their subject attractive to outsiders; the other by men who are ignorant of what they are writing about. Now and then some one, more happy than his fellows, strikes the *via media*, and when he does, he generally gets a thoroughly warm welcome. Such a welcome has always been accorded to *Ganot's Physics*; and such a welcome this, the last edition, will meet with. Of it in particular, it is enough to say that sufficient additions have been made to bring the book up to the knowledge of the present time, and that the size of the pages has been slightly enlarged so as to increase the capacity of the book, while lessening the number of its pages.'

LAND AND WATER.

London, LONGMANS & CO.

NATURAL PHILOSOPHY.



LONDON : PRINTED BY
SPOTTISWOODE AND CO., NEW-STREET SQUARE
AND PARLIAMENT STREET



NATURAL PHILOSOPHY

FOR

GENERAL READERS AND YOUNG PERSONS.

TRANSLATED AND EDITED FROM

GANOT'S COURS ÉLÉMENTAIRE DE PHYSIQUE

(*with the Author's sanction*)

BY

E. ATKINSON, PH.D. F.C.S.

PROFESSOR OF EXPERIMENTAL SCIENCE IN THE STAFF COLLEGE.

SECOND EDITION.

LONDON:

LONGMANS, GREEN, AND CO.

1875.

All rights reserved.

PREFACE.

THE present work has its origin in an attempt to comply with a suggestion which has frequently been made to me, that I should prepare an abridged edition of my translation of Ganot's *Éléments de Physique*, which could be used for purposes of more elementary instruction than that work, and in which the use of mathematical formulæ would be dispensed with. But I soon found that to do anything of the kind which would be more than a mere series of extracts would be very difficult, and hence I turned my attention to another book by the same author, which has had a very extensive circulation in France, his *Cours élémentaire de Physique*, and this I have taken as the basis of the present book.

It is not a mere translation, but such additions and alterations have been made as I thought fitted to render the book

useful to the classes for which it was more especially designed—namely, as a text-book of physics for the middle and upper classes of boys' and of girls' schools, and as a familiar account of physical phenomena and laws for the general reader. In range it may perhaps be nearly taken to represent the amount of knowledge required for the matriculation examination of the London University.

Although English scientific literature is not wanting in works in which the main physical phenomena are explained in familiar language, they are for the most part—whether from too much conciseness in some parts or from too minute details in others, or again as being too costly—not suited for direct teaching purposes.

To facilitate reference, the articles of the present work have been numbered, and a copious index has been drawn up in accordance with this arrangement.

E. ATKINSON.

STAFF COLLEGE:
1872.

ADVERTISEMENT

TO

THE SECOND EDITION.

IN a work which only proposes to serve as an introduction to the study of a science, no great additions can be made without exceeding the range within which it is limited Hence in the present edition I have not thought it desirable to add more than about twenty pages of new matter, together with twenty-four new woodcuts and a coloured plate.

E. A.

STAFF COLLEGE:
June 1875.

CONTENTS.

BOOK I.

GENERAL PROPERTIES OF MATTER, AND UNIVERSAL ATTRACTION.

CHAP.		PAGE
I.	PRELIMINARY NOTIONS	1
II.	GENERAL PROPERTIES OF BODIES	4
III.	MOTION AND FORCE	12
IV.	MOTION AND FORCE (*continued*)	29
V.	LAWS OF FALLING BODIES. INCLINED PLANE. THE PENDULUM	44
VI.	MOLECULAR ATTRACTION	56
VII.	PROPERTIES SPECIAL TO SOLIDS	62

BOOK II.

HYDROSTATICS.

CHAP.		PAGE
I.	PRESSURES TRANSMITTED AND EXERTED BY LIQUIDS . .	65
II.	EQUILIBRIUM OF LIQUIDS	74
III.	PRESSURES SUPPORTED BY BODIES IMMERSED IN LIQUIDS. SPECIFIC GRAVITIES. AREOMETERS . . .	83

BOOK III.

ON GASES.

I.	PROPERTIES OF GASES. ATMOSPHERE. BAROMETERS .	98
II.	MEASUREMENT OF THE ELASTIC FORCE OF GASES . .	118
III.	APPARATUS FOUNDED ON THE PROPERTIES OF AIR .	126
IV.	PRESSURE ON BODIES IN AIR. BALLOONS . . .	143

BOOK IV.

ACOUSTICS.

I.	PRODUCTION, PROPAGATION, AND REFLECTION OF SOUND	150
II.	MUSICAL SOUND. PHYSICAL THEORY OF MUSIC . .	163
III.	TRANSVERSE VIBRATIONS OF STRINGS. STRINGED INSTRUMENTS	175
IV.	SOUND PIPES AND WIND INSTRUMENTS . . .	179

BOOK V.

HEAT.

CHAP.		PAGE
I.	General Effects of Heat. Thermometers	189
II.	Radiation of Heat	202
III.	Reflection of Heat. Reflecting, absorbing, and emissive Powers	204
IV.	Conducting Power of Bodies	213
V.	Measurement of the Expansion of Solids, Liquids, and Gases	217
VI.	Changes of State of Bodies by the Action of Heat	225
VII.	Formation of Vapours. Measurement of their Elastic Force	231
VIII.	Liquefaction of Vapours and Gases	246
IX.	Specific Heat. Calorimetry	252
X.	Steam Engines	256
XI.	Hygrometry	270
XII.	Meteorological Phenomena which depend upon Heat	274
XIII.	Sources of Heat and Cold	287

BOOK VI.

ON LIGHT.

CHAP.		PAGE
I.	TRANSMISSION, VELOCITY, AND INTENSITY OF LIGHT	294
II.	REFLECTION OF LIGHT. MIRRORS	302
III.	REFRACTION OF LIGHT	322
IV.	EFFECTS OF REFRACTION THROUGH PRISMS AND THROUGH LENSES	329
V.	DECOMPOSITION OF LIGHT BY PRISMS	348
VI.	INJURIOUS EFFECTS OF COLOUR IN LENSES. ACHROMATISM	361
VII.	OPTICAL INSTRUMENTS	363
VIII.	OPTICAL RECREATIONS	374

BOOK VII.

ON MAGNETISM.

I.	PROPERTIES OF MAGNETS	400
II.	TERRESTRIAL MAGNETISM. COMPASSES	406
III.	METHODS OF MAGNETISATION	411

BOOK VIII.

FRICTIONAL ELECTRICITY.

CHAP.		PAGE
I.	FUNDAMENTAL PRINCIPLES	415
II.	ACTION OF ELECTRIFIED BODIES ON BODIES IN THE NATURAL STATE. INDUCED ELECTRICITY. ELECTRICAL MACHINES	427
III.	ELECTRICAL EXPERIMENTS	437
IV.	CONDENSATION OF ELECTRICITY	445
V.	VARIOUS EFFECTS OF ACCUMULATED ELECTRICITY .	454
VI.	ATMOSPHERIC ELECTRICITY. THUNDER AND LIGHTNING	461
VII.	ELECTRICITY DUE TO CHEMICAL ACTION. VOLTAIC BATTERY	470
VIII.	EFFECTS OF THE BATTERY	483
IX.	ELECTROMAGNETISM	493
X.	ELECTRODYNAMICS	499
XI.	ELECTROMAGNETS. TELEGRAPHS AND ELECTROMAGNETIC MOTORS	504
XII.	INDUCTION BY CURRENTS	519
XIII.	THERMO-ELECTRIC CURRENTS	528

INDEX 532

PLATES.

ELECTRICAL DISCHARGE IN HIGHLY RAREFIED GASES . *Frontispiece*

SPECTRA OF METALS &c. . . . . *page* 355

[redacted]

ELEMENTARY COURSE

OF

PHYSICS.

BOOK I.

GENERAL PROPERTIES OF MATTER, AND UNIVERSAL ATTRACTION.

CHAPTER I.

PRELIMINARY NOTIONS.

1. **Definition of physics.**—The word *physics* is derived from the Greek φύσις, nature; for the ancients understood by the term physics the study of the whole of nature. They comprised within the domain of this science *mechanics*, *astronomy*, *chemistry*, *botany*, *zoology*, *medicine*, and even *astrology* and *divination*, whether by the stars or by the observation of physiognomy.

The province of physics is at present much more restricted. Its object may be considered to be *the study of those phenomena which do not depend on changes in the composition of bodies;* for these belong to chemistry.

Thus, when water by cooling is changed into ice, and by heat this ice is again changed into water, the liquid is exactly the same as before; not merely are all its properties the same, but its substance is identical with what it originally was. The passage of water to the state of ice, and the return of the latter to the liquid state, are *physical phenomena.* In like manner, when a brittle object, of porcelain or glass, for instance, falls to the ground and breaks, each piece retains exactly the same chemical composition. The fall of the vessel and its fracture against the ground are then physical phenomena.

On the other hand, when wood burns, its substance is profoundly

16

modified. It consists of several different forms of matter, and is decomposed; one part of its elements passes into the atmosphere as smoke, while another is left as a residue consisting of ash and charcoal. In short, the substance we know as wood has disappeared, and is replaced by others which are entirely different. The combustion of wood is then a *chemical phenomenon.*

2. **Matter, mass, density.**—We understand by the term *matter* whatever can affect one or more of our senses; that is to say, anything whose existence can be recognised by the sight, touch, taste, smell, or hearing.

The *mass* of a body is the quantity of matter contained in this body. Different substances may contain very different quantities of matter in the same volume. It will subsequently be shown, for instance, that, for equal volumes, lead contains nearly eleven times as much matter as water, and gold nineteen times as much. This is expressed by saying that the masses of lead and of gold, are respectively eleven and nineteen times as *dense* as water. When one body has, for the same volume, twice or thrice the mass of another, it is said to be twice or thrice as dense; and the *density* of one substance in reference to another is the number which expresses how much matter the first body contains as compared with the second.

3. **Simple and compound substances.**—It has been ascertained that all the various forms of matter with which we are acquainted may be resolved into about sixty-five different kinds, which are called *simple substances* or *elements*, to express that each only contains one kind of matter. Many of these are very rare, and are found in very minute quantities; others are more widely diffused, and have important uses, but are not abundant; and the great mass of the universe is made up of about fourteen; the *non-metallic bodies*, or *metalloids*, oxygen, hydrogen, nitrogen, silicon, carbon, sulphur, phosphorus, and chlorine; and the *metals* aluminium, potassium, sodium, calcium, magnesium, and iron.

Very few of these elements occur in nature in the free state; by far the greater number of the substances we know are *compound*; that is, formed by the union of two, three, or four of these elements. Thus water consists of hydrogen and oxygen; marble, of carbon, oxygen, and calcium; muscular tissue, of carbon, hydrogen, oxygen, and nitrogen. The number of substances containing more than four elements is very small.

The force in virtue of which different substances unite to form compounds, and which opposes the resolution of compounds into their elements, is called the force of *chemical attraction* or *affinity.*

4. **Internal constitution of bodies. Atoms, molecules, molecular forces.**—The properties of bodies prove that they are not formed of continuous and compact matter as they seem to be, but that they are agglomerations of excessively small material particles, which are called *atoms*. The elementary atoms can unite with each other to form compounds, but cannot be destroyed by any known process.

The term *molecule* is given to the smallest cluster of atoms of any substance which is conceived capable of existing by itself; every pure substance consists of similar molecules.

The same properties which have led physicists to assume the existence of atoms and molecules have also led to the assumption that these small particles do not touch, but are simply juxtaposed, retaining between them excessively small intervals, which we shall afterwards become acquainted with under the name of *pores* (9).

But it may be asked, How is it that bodies do not spontaneously fall into powder? What gives them solidity and hardness? What is the invisible force that unites atoms and molecules?

This force is the reciprocal attraction which the molecules of bodies exert upon each other and which is continually drawing them together. The force which holds together particles of the same kind of matter is called *molecular attraction*; the force which holds together particles of different kinds of matter is called *chemical attraction or affinity*. When hydrogen and oxygen unite to form water, they do so by reason of the exercise of the latter force, while the particles of water are held together by molecular attraction.

If molecular attraction were the only force acting upon the small particles of which bodies are composed, they would come into complete contact, which is never the case. They are also under the influence of a repulsive force, in virtue of which their particles continually tend to separate themselves; this is the force of *heat*. Experiment shows, in fact, that whenever a body is heated, its volume increases because its molecules are driven apart; while on the contrary its volume diminishes when it is cooled, because the molecules then become closer. The particular form which matter assumes—whether solid, liquid, or gaseous—depends on the extent to which it is influenced by these antagonistic forces.

5. **Different states of matter.**—All different substances present characters in virtue of which they may be divided into three distinct classes, *solids*, *liquids*, and *gases*.

Solids, such as wood, stones, metals, &c., are substances which

are more or less hard, and retain the form which they possess naturally, or which has been given them by art. It is assumed that in solids molecular attraction preponderates over repulsion.

Liquids, such as water, oil, mercury, are bodies which have no hardness, and present but little resistance when a body is immersed in them; they have no shape of their own, but at once take that of the vessels in which they are contained; they are virtually incompressible. It is assumed that in them molecular attraction is balanced by the repulsive force of heat, and, that while the molecules can freely glide over each other, they keep an invariable distance apart if the temperature be not altered.

Gases, such as hydrogen, oxygen, carbonic acid, are also called *aeriform fluids*, from their analogy with our air, which is a mixture of oxygen and nitrogen. They are very light bodies; excepting a small number, which are coloured, they are invisible; and hence a vessel filled with air, hydrogen, or any colourless gas, appears quite empty. Like liquids, they have no shape of their own, but, unlike liquids, they are eminently compressible and expansible. In them the repulsive force of heat preponderates over molecular attraction (4); whence it follows that they are continually tending to occupy a larger space. This property will be described as the *expansibility* of gases (110).

There are many bodies which can exist in these three different forms; thus water, exposed to great cold, becomes solid in the form of ice; at ordinary temperatures it is liquid, while at higher temperatures it becomes a gas. Sulphur, iodine, and several metals present the same phenomena.

CHAPTER II.

GENERAL PROPERTIES OF BODIES.

6. **Extension.**—By *general properties* we understand those which are common to all bodies, whether solids, liquids, or gases; such for instance are *extension*, *impenetrability*, *divisibility*, *porosity*, *compressibility*, *elasticity*, *inertia*, and *gravity*.

Specific properties are such as we observe only in certain bodies, or in certain states of those bodies; *solidity*, *fluidity*, *tenacity*, *malleability*, *colour*, *hardness*, etc. are properties of this class.

The first general property of bodies with which we are concerned

is their *extension* or *magnitude*; that is, the extent of space they occupy. All bodies, even the smallest atoms, have a certain extension.

Extension considered in only one direction, that of length, gives a *line*; in two directions, length and breadth, a *surface*; and, in the three directions, length, breadth, and thickness, a *volume*.

With respect to the above general properties, it may be remarked that *impenetrability* and *extension* might be more aptly termed essential attributes of matter, since they suffice to define it; and that divisibility, porosity, compressibility, and elasticity do not apply to atoms, but only to bodies or aggregates of atoms.

7. **Impenetrability.**—This is the property in virtue of which two portions of matter cannot simultaneously occupy the same portion of space. Strictly speaking, this property only applies to the atoms of bodies.

In many phenomena bodies appear to penetrate each other. Thus, if a pint of water and a pint of alcohol be mixed, the volume of the mixture is less than two pints. A similar contraction occurs in the formation of certain alloys; thus brass, which is an alloy of copper and zinc, occupies a less volume than the united volumes of its constituents.

This penetration is, however, only apparent, and is due to an alteration in the position of the molecules; they come nearer each other, and the space occupied by the pores is diminished.

A nail driven into wood is not a case of penetration. The molecules of the latter are driven apart by the nail, but wherever it has penetrated there is no wood. When water has been poured upon a heap of sand it at once disappears; the water, however, does not penetrate the substance of the sand itself, but merely fills the interstices between the grains.

8. **Divisibility.**—This is the property which all bodies have of being divided into distinct parts.

Numerous examples may be cited of the extreme divisibility of matter. The tenth part of a grain of musk will continue for years to fill a room with its odoriferous particles, and at the end of that time will scarcely be diminished in weight.

A piece of carmine not larger than a grain of corn, gives a distinct colour to two gallons of water, from which it can be deduced that this small quantity of colouring matter cannot contain less than ten million particles.

Blood is composed of red, flattened globules floating in a colour-

less liquid called *serum.* In man the diameter of one of these globules is less than the 3,500th part of an inch, and the drop of blood which might be suspended from the point of a needle would contain about a million of globules.

Again, the microscope has disclosed to us the existence of insects smaller even than these particles of blood; the struggle for existence reaches even to these little creatures, for they devour still smaller ones. If blood runs in the veins of these devoured ones, how infinitesimal must be the magnitude of its component globules?

Has then the divisibility of matter no limit? Although experiment fails to determine such limit, many facts in chemistry, such as the invariability in the relative weights of the elements which combine with each other, would lead us to believe that a limit does exist. It is on this account that bodies are conceived to be composed of extremely minute and indivisible parts called *atoms* (4).

Fig. 1.

9. **Porosity.**—*Pores* are the extremely small intervals which exist between the molecules of bodies, and *porosity* is the property which bodies possess of having pores.

Two kinds of pores may be distinguished: *physical* or *intermolecular* pores, where the interstices are so small that the molecules remain within the sphere of each other's attracting or repelling forces; and *sensible* pores, or actual cavities, across which these molecular forces cannot act.

The contractions and expansions resulting from variations of temperature are due to the existence of physical pores; whilst in the organic world the sensible pores are the seat of the phenomena of exhalation and absorption.

In wood, sponge, pumice stone, and in animal and vegetable

tissues, the sensible pores are apparent: physical pores never are seen. Yet since the volume of every body may be diminished, we conclude that all possess physical pores.

The existence of sensible pores may be shown by the following experiment :—A long glass tube, A (fig. 1) is provided with a brass cup, *m*, at the top, and a brass foot made to screw on to the plate of an air-pump. The bottom of the cup consists of a thick piece of leather. After pouring mercury into the cup so as entirely to cover the leather, the air-pump is worked, and a partial vacuum produced in the tube. By so doing, a shower of mercury is at once produced within the tube, for the atmospheric pressure on the mercury forces that liquid through the pores of the leather. In the same manner water or mercury may be forced through the pores of wood, by replacing the leather in the above experiment by a disc of wood cut perpendicular to the fibres.

When a piece of chalk is thrown into water, air-bubbles at once rise to the surface, in consequence of the air in the pores of the chalk being expelled by the water. The chalk will be found to be heavier after immersion than it was before, and from the increase of its weight the volume of its pores may be easily determined.

The porosity of gold was demonstrated by the celebrated Florentine experiment made in 1661. Some academicians at Florence, wishing to try whether water was compressible, filled a thin globe of gold with that liquid, and, after carefully closing the orifice hermetically, they exposed the globe to pressure with a view of altering its form, well knowing that any alteration in form must be accompanied by a diminution in volume. The consequence was, that the water forced its way through the pores of the gold, and stood on the outside of the globe like dew. This experiment has since been repeated with globes of other metals, and like results obtained.

The Florentine academicians had concluded from their experiments that liquids were incompressible ; that is, could not be reduced in volume by pressure. This, however, is not the case; liquids are compressible, though to a very small extent (74). By cooling, a far greater diminution in volume can be produced.

From these facts we conclude that the molecules of liquids may be brought nearer each other, and therefore that there are pores between them. The facility, moreover, with which liquids mix is a proof of their porosity.

10. **Applications of porosity.**—The property of porosity is

frequently utilised, more especially in the process of *filtration*. This consists in clarifying liquids by freeing them from particles of matter which they hold in suspension ; as is done, for instance, with river water, which is turbid, owing to the earthy matter it carries along with it.

The apparatus used for this purpose are called *filters*, and are usually constructed of unsized paper, felt, charcoal, etc. The pores of these substances are sufficiently large to allow liquids to pass, but small enough to arrest the particles held in suspension. Figure 2 represents a *filtering fountain*, one side of which is sup-



Fig. 2.

Fig. 3.

posed to have been removed, so that its construction can be seen. It consists of a box about a yard high divided in the inside into two compartments by a porous slab, A. The water to be filtered is placed in the upper compartment, whence it slowly percolates through the pores of the stone into the lower one, leaving behind it the foreign substances. In one of the sides of the box is a tube *a*, which terminates in the lower compartment, and allows the air to escape in proportion as water enters.

Figure 3 represents a filter known as the *strainer of Hippocrates*. It is a conical felt bag suspended by three cords, into which is poured the turbid liquor ; it slowly traverses the pores, while all

the solid particles to which the turbidity is due, remain behind on the filter. This method is well-adapted for clarifying syrups, jellies, and liqueurs.

Layers of powdered wood charcoal are also used for filtration. A layer of sand or of broken glass produces the same effect. The limpidity of well-water is due to the filtration through strata of earth.

11. **Compressibility.**—This is the property which bodies possess of being diminished in volume by pressure without undergoing any loss of weight. Being due to the approach of the molecules, it is both a consequence and a proof of porosity.

Compressibility is very marked in sponge, caoutchouc, cork, pith, paper, cloth, etc. Their volume is considerably diminished by mere pressure between the fingers. The compressibility of metals is proved by the impression which they receive from the die, in the process of coining. There is, in most cases, a limit beyond which, when the pressure is increased, solids are fractured or reduced to powder.

The compressibility of liquids is so small as to have remained for a long time undetected: it may, however, be proved by experiment, as will be seen in the chapter on HYDROSTATICS (74).

The most compressible bodies are gases, which by pressure may be made to occupy ten, twenty, or a hundred times less space than under ordinary circumstances. The great compressibility of gases may be demonstrated by means of a glass tube with very thick sides, closed at one end and provided with a tight-fitting solid piston (fig. 4). The enclosed air cannot escape, and yet when the handle

Fig. 4.

of the piston is pressed it can be moved down to one-half to three-quarters the length of the tube; proving that the volume of the air is reduced necessarily to half or a quarter what it was originally. Most gases, when thus compressed, exhibit a remarkable property, to which we shall afterwards return, that, namely, of *liquefying*, or passing from the gaseous to the liquid state.

12. **Elasticity.**—*Elasticity* is the property which bodies possess of resuming their original form or volume, when, after having been compressed, bent, twisted, or pulled, the force which altered them has ceased to act.

Four kinds of elasticity may be distinguished: the elasticity by *pressure*, as in the case of gases; the elasticity by *flexure* or *bending*, observed in springs; the elasticity of *torsion* or *twisting*, which is produced in linen or cotton threads when they are untwisted; and, finally, the elasticity of *tension* or *stretching*, which is that of piano or violin strings when they are stretched.

Whatever be the kind of elasticity, it is always due to a displacement of molecules. If the molecules have been brought nearer by pressure, the repulsive force of heat tends to separate them; if, on the contrary, they have been separated, molecular attraction tends to bring them near each other again. If a piece of whalebone be bent, the molecules in the concave part being compressed repel each other; in the convex part, where they are separated, they tend to approach each other; both these actions tend, therefore, to straighten it as soon as it is free.

Gases and liquids are perfectly elastic; in other words, they regain exactly the same volume when the pressure becomes the same. Solid bodies present different degrees of elasticity, though none present the property in the same perfection as liquids and gases, and in all it varies according to the time during which the body has been exposed to pressure. Caoutchouc, ivory, glass, and marble possess considerable elasticity; lead, clay, and fats scarcely any.

There is a limit to the elasticity of solids, beyond which they either break or are incapable of regaining their original form and volume. In sprains, for instance, the elasticity of the tendons has been exceeded, so also when glass breaks. In gases and liquids, on the contrary, no such limit can be reached; they always regain their original volume.

The elasticity of solids may be demonstrated by the following experiment:—On a slab of polished black marble thinly smeared

with oil, an ivory ball is allowed to drop from gradually increasing heights. Each time it will rebound and rise to a height a little less than that from which it fell, after having formed on the layer of oil a circular impression which is larger the greater the height of the fall (fig. 5). From this we conclude that the ball was flattened each time, and that it rebounded in consequence of the reaction of its compressed molecules.



Fig. 5.

13. **Applications of elasticity.**—Numerous applications of the property of elasticity may be mentioned. It is owing to their elasticity that corks are used for closing bottles. Pushed into the neck by the exercise of a certain force, they become compressed, and then their elasticity causing them to press against the sides, they completely close the neck.

Children's balls depend upon the elasticity of gas: they are made of caoutchouc, and are inflated by air; when they strike against the ground, or against a wall, their volume diminishes, and the air which they contain being suddenly compressed, expands, and, acting like a spring, makes the ball rebound. A similar application is met with in air-cushions. They are made of an air-tight material, and being inflated by air, are both compressible and elastic, and thus form a very soft seat.

Air-guns are a further application. The breech in these is made of steel, and is hollow; air is compressed in it by means of an instrument called the *compression-pump*, and being suddenly liberated its expansive force is sufficient to expel the projectile.

The use of carriage, and of watch and clock, springs depends upon the elasticity of steel. In like manner the elasticity of wool, hair, feathers, is made use of in mattresses, pillows, and seats.

Lastly, it is owing to their elasticity that piano, guitar, or violin strings are capable of being put into a vibratory motion, which, as we shall prove, is the origin of the sounds which stringed instruments yield.

CHAPTER III.

MOTION AND FORCE.

14. **Rest and motion.**—To understand what we have to say about inertia, weight, universal gravitation, and the motion of liquids and gases, it is first of all necessary to give some very elementary notions about motion and force.

A body is said to be at *rest*, when it remains in the same place; to be in *motion* when it passes from one place to another. Both rest and motion are either absolute or relative.

Absolute rest would be the entire absence of motion. No such condition, however, is known in the universe; for the earth and the other planets rotate both about the sun and about their own axes; and therefore, all the parts composing them share this double motion. Even the sun itself has a motion of rotation which excludes the idea of absolute rest.

Relative or apparent rest is the condition of a body which appears fixed in reference to surrounding objects, but which really shares with them a double motion. For instance, a passenger in a railway carriage may be in a state of relative rest with respect to the train in which he travels, but he is in a state of relative motion with respect to the objects (fields, houses, etc.) past which the train rushes. These houses again enjoy merely a state of relative rest, for the earth itself which bears them is in a state of incessant relative motion with respect to the celestial bodies of our solar system.

The absolute motion of this passenger would be that measured in regard to a fixed point in space, which cannot be realised, for we know no such point. In short, absolute motion and rest are unknown to us; in nature, relative motion and rest are alone presented to our observation.

15. **Different kinds of motion.**—Motion is either rectilinear or curvilinear: *rectilinear* when the moving body travels along a straight line, as when a body falls to the ground; *curvilinear* when it goes along a curved line, as in the case of a horse turning in a mill.

Each kind of motion is either *uniform* or *varied.*

16. **Uniform motion.**—Motion is said to be uniform when the moving body passes over equal spaces in equal intervals of time; such, for instance, as the motion of a water-wheel when it makes exactly the same number of turns in a minute. Such, again, is the motion of the hands of a watch. A regiment of soldiers marching in step affords a further example of uniform motion.

The *velocity* of motion is the space traversed in a given time, a second or an hour, for example. A train which moves thirty miles in each successive hour is said to have a velocity of thirty miles an hour.

17. **Varied motion.**—Varied motion is that in which unequal spaces are traversed in equal times. If the spaces traversed in the same time go on increasing, the motion is said to be *accelerated;* such is the motion of a train starting from a station; if the spaces decrease, as is the case when a train comes into a station, the motion is retarded.

If the distances, traversed in equal times, always increase by the same amount, the motion is said to be *uniformly accelerated*; if, on the other hand, they constantly decrease by the same amount, the motion is *uniformly retarded.* We shall soon see examples of these kinds of motion in the case of falling bodies.

18. **Inertia.**—*Inertia* is a purely negative property of matter; it is the incapability of matter to change its own state of motion or of rest.

Daily observation shows that a body never spontaneously passes from a state of rest into one of motion. Bodies in falling to the ground seem to set themselves in motion. This is, however, not in consequence of any inherent property; but, as we shall afterwards see, because they are acted upon by the force of gravity.

Not merely do bodies at rest persist in a state of rest, but bodies in motion continue to move. This principle may seem less obvious than the former, because we are accustomed to see many bodies gradually move more slowly, and ultimately stop, as is the case with a billiard-ball, for example. But this is not due to any inherent preference for a state of rest on the part of the billiard-ball, but because its motion is impeded by the friction of the cloth on which it rolls, and by the resistance of the air. The smaller these resistances, the more prolonged is its motion; as is observed, for instance, if a ball be set rolling on a smooth sheet of ice. If all impeding causes were removed, a body once in motion would continue to move for ever.

19. **Effects due to inertia.**—Innumerable phenomena may be explained by the inertia of matter. For instance, before leaping a ditch we run towards it, in order that the motion of our bodies at the time of leaping may add itself to the muscular effort then made.

On descending carelessly from a carriage in motion, the upper part of the body retains its motion, whilst the feet are prevented from doing so by friction against the ground; the consequence is we fall towards the moving carriage.

If a man in running strikes his foot against an obstacle he is apt to fall down in front, because the rest of his body tends to retain the motion it has acquired. When a horse at full gallop suddenly stops, if the rider does not hold fast with his knees, he is thrown over the horse's head in virtue of his inertia. A grindstone only gradually acquires its full speed, but then continues its movement even after the force has ceased to act.

The terrible accidents on our railways are chiefly due to inertia. When the motion of the engine is suddenly arrested the carriages strive to continue the motion they had acquired, and in doing so are shattered against each other.

The action of projectiles is another case. When a bullet traverses a wall, or cuts a tree in two, it is owing to its tendency to retain the velocity which the explosion of the powder had imparted to it. In the action of hammers, and of pile driving, we have analogous cases.

The actions of beating a coating with a stick to expel dust; of shaking the snow from our shoes by kicking against the door-post; of cleaning a dusty book by striking it against another, all depend upon the property of inertia. The *hoop*, the *top*, and other toys are further illustrations.

20. **Forces, powers, resistances.**—Bodies being of themselves inert, and having no tendency to change either their state of rest or that of motion, any cause capable of making them pass from a state of rest to one of motion, or conversely from a state of motion to one of rest, is called a *force*.

The attractions and repulsions exerted between the molecules are forces; the muscular action which men and animals bring into play is a force, as is also the elasticity of gases and vapours which we shall subsequently discuss.

The forces which tend to produce motion are called *powers;* those which tend to destroy motion are called *resistances*. Thus,

when a man drags a burden along the ground his muscular force is a power, while the friction of the burden against the ground is a resistance.

Forces of the kind called powers are always tending to accelerate motion, and are called *accelerating forces.* Resistances, on the contrary, always tending to retard it, are called *retarding forces.*

21. **Friction.** — The surfaces of bodies are never perfectly smooth; even the smoothest possess roughnesses which cannot be detected by the touch nor by ordinary sight; and *friction* consists in the fact that the body must be raised over these obstacles or must break them down. They fit in each other like toothed wheels.

Friction is of two kinds: *sliding*, in which one body *slides* over another, as when a box is dragged along a floor; it is least when the two surfaces are always in contact, as in the motion of an axle in its bearing; and *rolling* friction, as when a cylindrical body moves over a horizontal surface like an ordinary wheel.

Friction is lessened by rubbing on the surfaces in contact fatty materials which are not absorbed by them. Moisture and oil increase the friction of wood, for they are absorbed by it, while tallow, soap, and black lead lessen it. Oil and lard lessen the friction of metallic surfaces. Rolling friction is less than sliding friction, hence the use of castors on pianos and other heavy furniture. On the other hand, rolling is sometimes changed into sliding friction, in order to increase it, as when a drag is applied to a wheel. The friction of carriage-wheels is less, the greater the diameter of the wheel and the less that of the axle.

Without friction on the ground neither man nor animals, neither ordinary carriages nor railway ones, could move; without it no book would remain on a desk, and without it we could hold nothing in the hands.

22. **Distinctive characters of forces.**—Three things are to be distinguished in each force; the point of application, the direction, and the intensity.

The *point of application of a force* is the point at which it exerts its action. Having attached a cord to a sledge, as shown in fig. 6, the point of application is the point A, at which the cord is actually attached.

The *direction of a force* is the right line along which it urges or tends to urge the point of application. In fig. 6 the cord A B represents the direction of the force.

The *intensity of a force* is its energy, its magnitude, or value, in reference to a certain standard. In fig. 6, which represents a horse drawing a cask on a sledge, a certain exertion of force is

Fig. 6.

required on the part of the horse; if the sledge were loaded twice or thrice as much, the force required must be twice or thrice as great.

23. **Measurement of forces. Dynamometer.**—The force which a motor (32) developes in pushing or drawing a body, is measured by the number of pounds necessary to produce the same pressure or the same pull; so that a force is said to be a force of 40 or 50 pounds, when it can be replaced by the action of a weight of 40 or 50 pounds.

The weight which thus represents the intensity of a force is determined by means of the *dynamometer*. There are several forms of this instrument, one of the simplest being that represented in fig. 7. It consists of a V-shaped plate of tempered steel, AB. At one end of the arm B is fixed an iron arc, *n*, which passes freely through an aperture at the end of the arm A. To this latter is fixed an arc, *m*, fitting in the same manner in the arm B. The arc *m* is provided at the end with a crook, and *n* with a ring, and on the latter *n* there is a graduation obtained in the following manner :—

The apparatus being fixed to a resisting support, weights of 1, 2, 3, 4, or more pounds are successively suspended to the crook. The arm B, supported by the arc *n*, remains fixed, while the arm A, being moved by the weight attached to the arc *m*, is lowered to an extent dependent on the weight. The load is gradually increased until it has reached the utmost limit possible without breaking, care

being taken at each load to mark a line on the arc *n* at the point at which the arm A stops.



Fig. 7.



Fig. 8.

In order to apply it to the measurement of forces, to estimate, for instance, the effort necessary to drag a load (fig. 8), the crook of the arc *m* is fixed to the load, then holding in the hand the ring of the arc *n* it is pulled until the load is moved. The flexure of the arm A marks on the arc *n* the value in pounds of the effort of traction.

The apparatus described is also used as a balance to determine the weight of bodies, and is known as *the steelyard.*

When forces are once measured or expressed in weight, they may be represented as to their intensity by means of the line which indicates their direction. For this purpose a length is measured off on this line, starting from the point of application, which contains the unit of length as many times as the intensity of the force contains pounds. Thus, if in fig. 6 the effort of traction is 15 pounds, a length, AB, would be measured from A equal to 15 times the unit of length, which may be an inch for distance. Thus the work of the horse in drawing the sledge would be represented both in direction and intensity by the line AB.

24. **Resultant and component forces.**—When a body is acted upon by only a single force, it is clear that, if it is not hindered by any obstacle, it will move in the direction of this force; but if it is simultaneously acted upon by several forces in different directions, its direction will not, speaking generally, coincide with that of any

one of these forces. If two men, for example, on the banks of a river, tow a boat by means of ropes, as shown in fig. 9, the boat follows

Fig. 9.

neither the direction AB, nor the direction AC, in which these men are respectively pulling, but takes an intermediate direction, AE; that is, it moves as if it were acted upon by a single force in the direction AE.

As the single force, which we conceive as having the direction AE, produces the same effect as the forces of traction of these two men, is called the *resultant* of these two forces; and conversely these, in reference to their resultant, are spoken of as the *components*.

25. **Value of the resultant of two concurring forces. Parallelogram of forces.**—When two forces having different directions are applied to the same point of a body, as represented in fig. 9, there is a very simple ratio between their intensities and the intensity of their resultant, which is of great importance from the number of its applications.



Fig. 10.

It will first of all be necessary to define the word *parallelogram*, of which we shall make use. The parallelogram is a geometrical figure, formed of four right lines, each pair of which is parallel (fig. 10), that is, the two lines AB and CD are parallel, and also the lines AD and BC. These lines form the sides of the parallelogram, and the points A, B, C, D, the angles. The *diagonal* is the line, like AC, joining two opposite angles A and C.

In treatises on mechanics, proofs are given of the following im-

portant theorem, which is known as the ***principle of the parallelogram of forces :***

When two forces applied at the same point A (fig. 11) *are represented in direction, and in intensity by the sides* AB *and* AD *of the*



Fig. 11.

parallelogram ABCD, *their resultant is represented both as to its intensity and direction by the diagonal* AC *of this parallelogram.*

That is, that the point A being simultaneously acted upon by two forces, whose directions and intensities are respectively represented by AB and AD ; this point moves in the direction AC exactly as if it were acted upon by a single force, the direction and intensity of which are represented by the line AC.

Frequent applications are met with of the principle of the parallelogram of forces. Thus, in the flight of a bird, when the wings strike against the air, a resistance is offered which is equal to an impulsive force from back to front in the directions AH and AK (fig. 12) ; hence, representing by AB and AD, the intensities and directions of these impulsive forces, if the parallelogram be completed, we shall find that the resultant, or the single force which makes the bird advance, is represented in direction and magnitude by the diagonal AC. The same reasoning applies to the swimming both of men and fishes.

26. **Another effect of the parallelogram of forces.**—We have seen that, in accordance with the principle of the parallelogram of

forces, two forces applied at the same point of a body may be reduced to a single one. By the aid of the same principle a single



Fig. 12

force applied to a body may be replaced by two other forces producing together the same effect as the first. This force is then said to be *decomposed* into two others.

It is but seldom indeed that the action of a force is entirely utilised; it may almost always be decomposed into two others, only one of which produces a useful effect. Thus when the wind blows

Fig. 13.

against the sails of a vessel, not quite directly, but a little on one side, as shewn in fig. 13, the effect of the wind in the direction *va*

may be considered to be resolved into two others, one in the direction *ca*, and the other in a lateral direction *ba*, of which the first moves the vessel. The second only guides it.

27. **Case in which the forces are parallel. Value of the resultant.**—In the case of the boat drawn by a rope (fig. 9), the forces were *concurrent*, that is, their directions if produced would meet in one point; but it may happen that the forces applied to the same body are parallel, and then two cases present themselves; that is, they either act in the same direction as in the case of two horses drawing a carriage; or they may act in opposite directions; when a steamer for instance ascends a river, the current acts in opposition to the force which urges the steamer. It can be proved that, in the first case, *the resultant of the forces is equal to their sum*; and that in the second *it is equal to their difference.*

28. **Equilibrium of forces.**—When several forces act upon a body at the same time, they do not always put it in motion; it may happen that while some of these forces tend to produce motion in a certain direction, the others tend to produce an equal and contrary motion in the opposite direction. It is clear that in this case, since the forces just neutralise each other, no effect can be produced. Whenever several forces applied to the same body thus mutually destroy each other, we have what is called *equilibrium.*

The simplest case of equilibrium is that of two equal and opposite forces applied at the same point of a body. For instance, if two men pull at a cord with the same intensity, one in one direction, and the other in the opposite one, equilibrium will be produced (fig. 14). In like manner if, in a well, two buckets of the same size

Fig. 14.

each full of water, are suspended at the end of a rope which passes round a pulley, the weight of one holds the other in equilibrium.

The bodies which we consider ordinarily to be in a state of rest, are really in a state of equilibrium. For instance, when a body rests on a table, there is equilibrium between the force of gravity which tends to make the body fall, and the resistance which the table offers to the fall. If the weight of the body exceeds this re-

sistance, equilibrium is destroyed, the table is broken, and the body falls.

29. **Centrifugal force.**—We shall conclude these notions about forces by mentioning a force to which curvilinear motion is due namely *centrifugal force.* This may be explained as follows Whenever a body has been put in motion in a particular direction in virtue of its inertia, it tends always to move in this direction Hence whenever a line is seen to move in a circle, this can only be due to some obstacle, or some new force which deviates it. In fact, since a curved line may be considered to consist of a series of infinitely small straight lines, the moving body, owing to its inertia always tends to follow the prolongation of the small straight line which it traverses. It tends then to retain its motion in a straight line, and to fly from the curve which it is compelled to describe. This action is called the *centrifugal force*, from two Latin words which signify to fly from the centre.



Fig. 15.

The production of centrifugal force in circular motion may be demonstrated by means of the apparatus represented in fig. 15. On

a brass frame AB is stretched a stout brass wire, and on which are slid two ivory balls which can move freely along the wire: the balls being arranged as shown in the figure, the frame is rapidly rotated by means of the *turning table*. The balls, projected by the centrifugal force, glide along the wire; and strike the ends with the greater force, the greater the velocity of rotation.

30. **Effects of centrifugal force.**—The centrifugal force is greater the greater the velocity, and the more marked the curvature of the line along which the movable body passes. Hence railways should be as straight as possible, for as the trains have a great velocity, when they move along a curve the centrifugal force is continually tending to throw them off, and the more so the sharper the curve.

It is owing to centrifugal force that the wheels of a carriage moving along a muddy road throw off the mud that adheres to the rim.

In a circus, the horses and their riders always incline their bodies towards the centre, and the greater their speed the greater their inclination. The object of this is to allow their weight to counteract the influence of the centrifugal force, which would throw them off if they stood upright.

In sugar refineries centrifugal force is applied in removing syrup from crystallised sugar. The sugar is placed in a cylindrical vessel, whose sides are made of wire gauze, and which is put in rapid rotation. The centrifugal force scatters the coloured syrup through the meshes of the sieve, while the solid crystals are left behind colourless and pure. The same principle is applied in drying clothes in large washing establishments. A wet mop made to turn quickly about its own handle as an axis throws the water off on all sides, and quickly dries itself.

A hoop trundled along the ground may move for a long time before falling, but if we attempt to keep it upright while in a state of rest, it at once falls. The reason of this is that, while in motion, if it inclines to one side, the inclination causes it to describe a curved line, whence arises a centrifugal force which opposes the fall of the hoop at any rate so long as it retains a sufficient velocity.

31. **Flattening of the earth at the poles.**—One of the most remarkable effects of centrifugal force is the flattening of the earth at the two poles. To explain this phenomenon we must premise that the earth, which is nearly spherical in form, rotates about an imaginary axis passing through its two poles, and that, in this rotation, all points on the surface have not the same velocity, for they

do not describe the same paths. For, at the equator, they describe every twenty-four hours a circumference equal to that of the earth, while points taken at increasing distances from the equator gradually describe smaller and smaller circles to the poles where they have no motion. Hence, owing to the daily rotation about the earth's axis, a centrifugal force is produced which is greatest at the equator, and gradually diminishes up to the poles, where there is none at all. Hence, owing to this inequality in the intensity of the centrifugal force, there must arise an accumulation of matter about the equator, especially if, as geologists assume, the earth was originally in a state of fusion.



Fig. 16.

It has in fact been ascertained by direct measurement, that the radius of the earth at the poles is less than that at the equator by about $\frac{1}{289}$ the latter, or 13½ miles. A similar flattening has been observed in other planets.

To demonstrate this bulging at the equator and flattening at the poles, use is made of the apparatus represented in fig. 16. It consists of an iron rod, which may be fixed upon the turning-table, instead of the piece A B (fig. 15). At the bottom of the rod are fixed four thin elastic metal plates, which are joined at the top to a ring which can slide up and down the rod. The apparatus being then put in rapid rotation, the rings slide down the rod as represented in the figure to an extent depending on the rapidity of the rotation.

LEVERS.

32. **Mechanics. Machines.**—*Mechanics* is the science which treats of forces and of motion. Several forces being applied to the same body, it indicates the relation which must exist between them in order to produce equilibrium, or in order to produce a given effect.

Any apparatus which serves to transmit the action of a force is a *machine*; and any force which moves a machine is a *motor*. In cutting an apple with a knife, the hand is the motor, and the knife which transmits its action is a machine. A horse drawing a cart is

a motor, and the cart which utilises the force of the horse in conveying loads is a machine. The watercourse which works a wheel, the wind which turns a mill, and the steam which moves a locomotive, are all motors; and the water-wheel, the wind-mill, and the locomotive are all machines.

Machines do not increase the force of a motor: whatever is gained in force by a machine is lost in distance or in time; but, by modifying its action, they render it capable of performing work which it alone could not do. For instance, by the aid of a lever, a man can raise burdens, which, without such help, would be impossible. We shall only describe here the lever, the simplest of all machines, and shall afterwards see its action in the case of balances.

33. **Levers.**—A lever is a rigid bar of wood or of metal movable about a fixed point or edge called the *fulcrum*; and subject to the action of two forces which tend to move it in opposite directions. The force which acts as motor is called the *power*, and the other the *resistance.* Levers are divided into three classes, according to the different positions of the power, and resistance in reference to the fulcrum.

A lever of the first kind is one in which the fulcrum is between the power and the resistance. Fig. 17 represents one of this kind, in which the hand is the power, the weight P the resistance, while C is the fulcrum.

Fig. 17.

A lever of the second kind has the resistance between the power and the fulcrum, as in fig. 18.

A lever of the third kind is one in which the power is applied between the resistance and the fulcrum as represented in fig. 19.

In these different kinds of levers, the distances from the fulcrum

to the power and to the resistance are called the *arms of the le*
In fig. 19, for instance, the arm of the power is the distance fro
to B, and that from C to A is the arm of the resistance.



Fig. 18



Fig. 19.

34. **Effect of levers. Condition of equilibrium.**—It ma
shown that the effect produced by a force by means of a leve
creases with the length of the arm upon which it acts, that is, if

arm is twice, thrice, or four times as long, the useful effect is two, three, or four times as great. This is what led Archimedes to say, that, give him a fulcrum, and he would lift the world.

Since a force produces a greater effect the longer the arm of the lever, it follows that in order to produce equilibrium between the power and the resistance, acting at the same time on a lever, if the arms are equal, *the two forces themselves must be equal*, and that if the arms of the lever are unequal, *the two forces must be inversely as the arms of the lever*; thus, if the power is one-third that of the resistance, the arm of the power should be three times as long as that of the resistance.

In a lever of the third kind the power must be always greater than the resistance, for the distance of the resistance from the fulcrum (AC, fig. 19) is always greater than the distance BC from the power B to the fulcrum. In a lever of the second kind the power is always smaller than the resistance, for the arm BC is longer than the arm AC (fig. 18). These properties are expressed by saying that, in a lever of the third kind there is a loss of power, and in one of the second kind a gain. In a lever of the first kind there may be either gain, or loss, or they may just balance each other, for the arm BC of the power (fig. 17) may be either greater, or less than, or equal to, the arm AC.

35. **Various applications of levers.**—Numerous applications of the different kinds of levers are met with in articles of every-day use. The ordinary balance (fig. 34) is a lever of the first kind, as is also a pump handle. Scissors are another instance; each handle is a lever, the fulcrum of which is the pivot C, the power is the hand and the resistance is the material to be cut (fig. 20).



Fig. 20.

As levers of the second class may be enumerated the oars of a boat. The resistance of the water to the motion of the feather of the oar represents the fulcrum, the hand of the oarsman is the power, and the boat, or rather the water it displaces, is the resistance. The knife fixed at one end and used in slicing roots, or cutting bread, is a lever of the second

Fig. 21.

kind. Nutcrackers (fig. 21) afford a third illustration, as also doe the common wheelbarrow.

When two porters carry on a pole a load placed midway be tween them, they share it equally, that is, each bears half, for th pole becomes a lever, of which each porter is a fulcrum as regard the other; but if the load be nearer one than the other, he t whom it is nearer bears proportionally more of its weight.

The consideration of this kind of lever explains why a finge caught near the hinge of a shutting door, is so severely crushed.

The third kind of lever is less frequently met with. The peda used in pianos and in grindstones are instances. In the latter ca the pedal consists of a wooden board AC (fig. 22) forming a leve

Fig. 22.

The fulcrum is at C on a bolt fixed to the frame; the power is th foot of the man turning, and the resistance, which is the motion t be transmitted to the wheel, is applied at A by means of a rod joine to a crank in the centre of the mill.

In the common fire-tongs each leg is a lever of the third kind The hand of a man pushing open a gate while standing near th

hinges moves through much less space than the end of the gate, and must exert, therefore, a proportionally greater force.

The most beautiful and numerous instances are met with in the muscular system of men and animals, almost all motions of which are effected by this mechanism.

CHAPTER IV.

36. **Universal attraction.**—It is stated that Newton, sitting one day in his garden and seeing an apple fall from a tree, was led by this circumstance to reflect upon the cause why bodies fell to the ground, and ultimately to the discovery of the important laws which govern the motion of the earth and of the stars.

They may be thus stated:

1. *All bodies in nature exert a mutual attraction upon each other at all distances, in virtue of which they are continually tending towards each other.*

2. *For the same distance the attractions between bodies are proportional to their masses.*

3. *The masses being equal, the attraction varies with the distance, being inversely proportional to the square of the distances asunder.*

To illustrate this, we may take the case of two spheres which, owing to their symmetry, attract each other just as if their masses were concentrated in their centres. If without other alteration the mass of one sphere were doubled, trebled, etc., the attraction between them would be doubled, trebled, etc. If, however, the mass of one sphere being doubled, that of the other were increased three times, the distance between their centres remaining the same, the attraction would be increased six times. Lastly, if, without altering their masses, the distance between their centres were *increased* from 1 to 2, 3, 4, . . . units, the attraction would be diminished the 4th, 9th, 16th . . . part of its former intensity.

37. **Gravitation.**—The term *gravitation* is applied more especially to the attraction exerted between the heavenly bodies. The sun, being that member of our planetary system which has the largest mass, exerts also the greatest attraction, from which it might seem that the earth and the other planets ought to fall into the sun in virtue of this attraction. This would indeed be the case

if they were only acted upon by the force of gravitation ; but owi to their inertia, the original impulse which they once received, co stantly tends to carry them away from the sun in a straight lir This acquired velocity, combined with gravitation, makes the plan describe curves about the sun which are almost circular, and a called their *orbits*.

38. **Gravity.**—This is the force in virtue of which bodies *f* when they are no longer supported, that is, tend towards t centre of the earth. It is a particular case of universal attractio and is due to the reciprocal attraction exerted between the ea and bodies placed on its surface : it acts equally upon all bodi whether they are at rest or in motion ; whether they are soli liquids, or gases. Some bodies, such as clouds and smoke, appe not to be influenced by this force, for they rise in the atm sphere instead of sinking ; yet this, as will afterwards be se is no exception to the action of gravity.

Gravity, being a particular case of universal attraction, a upon bodies proportionally to their mass and inversely as the squa of their distance ; that is, a body which contains twice or thrice much matter as another, is attracted by the earth with a twofold threefold force ; or, in other words, weighs twice or thrice as mu In like manner if one and the same body could be moved to twice thrice its present distance from the *centre* of the earth, it would ha one-fourth or one-ninth of its present weight ; we say the *centre* a not the *surface* of the earth, for it is demonstrated in treatises mechanics that the attractive force of the earth which cau bodies to fall must be calculated from its centre.

From the magnitude of the earth's radius, which is about 4,0 miles, all bodies on its surface may be considered to be virtually the same distance from the centre, and we may therefore conclu that their difference in weight is merely due to their difference in ma

39. **The weight of a body increases from the equator to t poles.**—The force which makes bodies fall is not exactly the sa at all points of the earth's surface. Two causes make it increa from the equator to the poles : the daily rotation of the earth abc its axis, and the flattening at the poles. For the rotation of t earth gives rise to a centrifugal force acting from the centre to t surface, that is, in the opposite direction to the force of gravi Hence bodies are continually acted upon by two forces in oppos directions ; the force of gravity which draws them towards t centre, and the centrifugal force which tends to drive them aw

from it. So that it is really the excess of the first force over the second which makes bodies fall. But as the centrifugal force decreases from the equator to the poles (30), the excess of gravity over this force becomes greater, and thus the weights of bodies increase as they come nearer the poles.

The flattening of the earth concurs in producing the same effect; for, in consequence of it, bodies placed on the surface of the earth are nearer the centre at the poles than they are at the equator, and are therefore more attracted. It must be added, that the increase in weight due to these two causes is very small, and is inappreciable by ordinary balances.

40. **Vertical and horizontal lines.**—At any point of the earth's surface, the direction of gravity, that is, the line which a falling body describes, is called the *vertical* line. The vertical lines drawn at different points of the earth's surface converge very nearly to the earth's centre. Hence, owing to the great distance from the surface of the earth to its centre, for points on the surface *a* and

Fig. 23.

b (fig. 23), not far apart, these verticals may be assumed to be parallel; but they are less parallel the further apart the points, as shown by the verticals *a* and *d*. For points situated on the same meridian the angle contained between the vertical lines equals the difference between the latitudes of those points.

At each point on the surface of the earth a man standing upright is in the direction of the vertical. But, as we have just seen, this direction changes from one place to another, and the same is the case with the position of the inhabitants of the various countries on the earth. As the earth is spherical, it follows that at two points, exactly opposite, two men will be in inverted positions in reference

to each other; from which is derived the term ***antipodes*** (opposite as regards the feet), given to the inhabitants of two diametrically opposite places.

A plane or a line is said to be ***horizontal*** when it is perpendicular to the direction of the vertical. The surface of water in a state of equilibrium is always horizontal. In speaking of the ***level*** we shall learn how the horizontality of any surface or line is determined.

41. **Plumb-line.**—The vertical line at any point of the globe is generally determined by the ***plumb-line*** (fig. 24), which consists of a cylindrical weight attached to the end of a string. In obedience to the action of gravity this weight draws the string in the direction of this force, and when it is at rest the string is in the vertical direction. To ascertain by aid of the plumb-line whether a given surface, a wall for example, is vertical, a small metal plate is used

Fig. 24.

the side of which is equal to the diameter of the weight. In the centre of this plate is a small hole, through which passes the string: holding in one hand the plate, and in the other the string, the edge of the plate is placed against the wall (fig. 24); if the weight just touches it the wall is vertical; if the cylinder does not touch the wall, it shows that the wall is inclined outwards; it is inclined inwards if the weight touches the wall when the plate is a little removed from it.

42. **Weight of a body.**—The *weight* of a body is the sum of the partial attractions which the earth exerts upon each of its molecules. Hence the weight of a body must increase as its mass does; that is, if it contains twice or thrice as much matter, its weight must be twice or thrice as great. The weight of a body is not to be confounded with *gravity*; this is the cause which produces the fall of bodies; the weight is only the effect. We shall presently see how weight is determined by means of the balance; gravitation is measured by the aid of the pendulum.

43. **Centre of gravity.**—We have seen that all the partial attractions which the earth exerts upon each of the molecules of a body are equivalent to a single force which is the weight of the body. Now it may be shown in mechanics, that whatever be the shape of any body, there is always a certain point through which this single force, the weight acts, in whatever position the body be placed in respect to the earth; this point is called *the centre of gravity* of the body.

To find the centre of gravity of a body is a purely geometrical problem; in many cases, however, it can be at once determined. For instance, the centre of gravity of a right line of uniform density is the point which bisects its length; in the circle and sphere it coincides with the geometrical centre; in cylindrical bars it is the middle point of the axis; in a square or a parallelogram it is at the point of intersection of the two diagonals. These rules, it must be remembered, presuppose that the several bodies are of uniform density.

44. **Experimental determination of the centre of gravity.**—The centre of gravity of a body may also be found by experiment.

Fig. 25.

When its weight is not too great it is suspended by a string in two different positions; the centre of gravity of the body is necessarily below the point of suspension, and therefore in the prolonga-

tion of the vertical cord which sustains it. If then, i ferent positions, the vertical lines of suspension be prolo cut one another, and the point of intersection is the gravity sought.

In the case of thin flat substances, like a piece of car a sheet of tin plate, the centre of gravity may be found by the body in two different positions on a horizontal edg stance sliding them near the edge of a table until they to turn in either direction (fig. 25). The centre of grav on the line *ab*. Seeking, in a similar manner, a second equilibrium in which the line of contact is *cd* for ins centre of gravity must necessarily be on both these lines must be at the point of their intersection *g* ; or, more ac little below this point, in the interior of the body, and a distance from its two faces.

If the body be thicker, three positions of equilibriu found ; the centre of gravity is then at the point of ir of the three plan vertically through of contact when t in equilibrium.

Fig. 26.

45. **Equilibrium bodies.**—As the gravity is the point whole action of concentrated, it fo whenever this p upon any support, of gravity is dest therefore the bod in equilibrium. T however, several cording as the bod or more points of s

Where the bod one point of sup librium is only pos the centre of gra coincides with this point, or is exactly above or belov same vertical line ; for then the action of gravity is de the resistance of the fixed point through which this fo

The plumb-line (fig. 24) is a case of this kind, the centre of gravity being below the point of support. Another example is the case of a stick balanced on the finger, as seen in fig. 26, in which the letter *g* indicates the position of equilibrium exactly over the point of support.

Fig. 27.

If the body has two points of support, it is not necessary for equilibrium that its centre of gravity coincide with either of these points, or be exactly above or below: it is sufficient if it be exactly below or above the right line which joins these two points, for the action of gravity may then be decomposed into two forces applied at the points of support, and destroyed by the resistance of these points. A man on stilts (fig. 27) is an example of this case of equilibrium.

Lastly if a body rests on the ground by three or more points of support (fig. 28), equilibrium is produced whenever the centre of gravity is above the *base* formed by these points of support, that is, whenever the vertical let fall from the centre of gravity to the earth is within the points of support; for gravity cannot then overturn the body beyond the points of support, and its only effect is to settle it more firmly on the ground.

Fig. 28.

Different states of equilibrium. — Although a body supported by a fixed point is in equilibrium whenever its centre of gravity is in the vertical through that point, the fact that the centre of gravity tends constantly to occupy the lowest possible position leads us to distinguish between three states of equilibrium—*stable, unstable, neutral.*

A body is said to be in *stable equilibrium* if it tends to return to its first position after the equilibrium has been slightly disturbed. Every body is in this state when its position is such that the slightest alteration of the same elevates its centre of gravity; for the centre of gravity will descend again when permitted, and after a few oscillations the body will return to its original position.

The pendulum of a clock continually oscillates about its position of stable equilibrium, and an egg on a level table is in this state when its long axis is horizontal. We have another illustration in the toy represented in fig. 29.

These little figures, which are hollow and light, are loaded at the base with a small mass of lead, so that the centre of gravity is very

Fig. 29.

low. Hence when the figure is inclined, the centre of gravity is raised, and gravity tending to make it descend, the figure reverts to its original position after a number of oscillations on the right and left of its final position of equilibrium.

A body is said to be in *unstable equilibrium*, when, after the slightest disturbance, it tends to depart still more from its original position. A body is in this state when its centre of gravity is vertically above the point of support, or higher than it would be in any adjacent position of the body. An egg standing on its end, or a stick balanced upright on the finger, is in this state (fig. 26). As soon as the stick is out of the vertical its centre of gravity descends, and gravity acting with increasing force, the stick falls, if care be not taken to bring the point of support below the centre of gravity, by which equilibrium is restored.

Neutral equilibrium. A body is in a state of neutral equilibrium

when it remains at rest in any position which can be given to it. This can only be the case when an alteration in the position of the body neither raises nor lowers its centre of gravity. A perfect sphere resting on a horizontal plane is in this state.

Fig. 30 represents three cones A, B, C, placed respectively in stable, unstable, and neutral equilibrium upon a horizontal plane. The letter g in each shows the position of the centre of gravity.



Fig. 30.

47. **Examples of stable equilibrium.**—From what has been said it follows, that the wider the base on which a body rests the greater is its stability; for then, even with a considerable inclination, its centre of gravity is above its base.

The well-known leaning towers of Pisa and Bologna, are so much out of the vertical that they seem ready to fall at any moment; and yet they have remained for centuries in their present position, because their centres of gravity are above the base. Fig. 31 represents the tower of Bologna, built in the year 1112, and known as the *Garisenda*. Its height is 165 feet, and it is 7 or 8 feet out of the vertical. The leaning is due to the foundations having given way. The tower on the side is that of Asarelli, the highest in Italy.

In the cases we have hitherto considered, the position of the centre of gravity is fixed: this is not the case with men and animals, whose centre of gravity is continually varying with their attitudes, and with the loads they support.

When a man, not carrying anything, stands upright, his centre of gravity is about the middle of the lower part of the pelvis, that is, between the two thigh bones. This, however, is not the case with a man carrying a load, for his own weight being added to that of the load, the common centre of gravity is neither that of the man nor of his burden.

In this case, in order to retain his stability, the man must so modify his attitude as to keep his centre of gravity above the base

formed by his two feet. Thus a porter with a load on his l is obliged to lean forward (fig. 32), while a man carryir load in one hand is obliged to lean his body on the opposite (fig. 33).

Again, it is impossible to stand on one leg if we keep one



Fig. 31.

of the foot and head close to a vertical wall, because the latter vents us from throwing the body's centre of gravity vertically al the supporting base.

In the art of rope-dancing the difficulty consists in maintai the centre of gravity exactly above the rope. In order more e to accomplish this the performer holds in his hands a long which, as soon as he feels himself leaning on one side, he incl towards the opposite one; and thus contrives to keep the centi

gravity common to himself and to the pole, in a vertical line above the rope, and so preserves his equilibrium.

Fig. 32. Fig. 33.

48. **The balance.**—The balance is an instrument for determining the relative weights or masses of bodies. There are many varieties.

The ordinary balance (fig. 34) consists of a lever of the first kind, called the *beam*, with its fulcrum in the middle; at the extremities of the beam are suspended two *scale-pans*, D and C; one intended to receive the object to be weighed, and the other the counterpoise. The fulcrum consists of a steel prism, *n*, commonly called a *knife-edge*, which passes through the beam, and rests with its sharp edge, or *axis of suspension*, upon two supports; these are formed of agate or polished steel, in order to diminish the friction. A needle or pointer is fixed to the beam, and oscillates with it in front of a graduated arc, *a*; when the beam is perfectly horizontal, the needle points to the zero of the graduated arc.

Since (34) two equal forces in a lever of the first kind cannot be in equilibrium unless their leverages are equal, the length of the arms *n*A and *n*B ought to remain equal during the process of weighing. To secure this the scales are suspended from hooks, whose curved parts have sharp edges, and rest on similar edges at the ends of the beam. In this manner the scales are supported on mere points, which remain unmoved during the oscillations of the beam. This mode of suspension is represented in the following figure.

The weight of any body is determined by placing it in one of the pans of the balance D, for instance, and adding weights to the other until equilibrium is established, which is the case when the beam is quite horizontal.

Fig. 34.

49. **Conditions to be satisfied by a good balance.**—A good balance should be *accurate*, that is, it should give exactly the weight of a body ; it should also be *delicate*, that is, the beam should be inclined by a very small difference between the weights in the two scales.

Conditions of accuracy. i. *The two arms of the beam ought to*

be precisely equal, otherwise, according to the principle of the lever (34), unequal weights will be required to produce equilibrium. To test whether the arms of the beam are equal, weights are placed in the two scales until the beam becomes horizontal; the contents of the scales being then interchanged, the beam will remain horizontal if its arms are equal, but if not it will descend on the side of the longer arm.

ii. *The balance ought to be in equilibrium when the scales are empty*; for otherwise, unequal weights must be placed in the scales in order to produce equilibrium. It must be borne in mind, however, that the arms are not necessarily equal, even if the beam remains horizontal when the scales are empty; for this result might also be produced by giving to the longer arm the lighter scale.

iii. *The beam being horizontal, its centre of gravity ought to be in the same vertical line with the edge of the fulcrum, and a little below the latter.* For if the centre of gravity coincided with this line, the action of gravity on the beam would be null, and it would not oscillate. If the centre of gravity were above the edge of the fulcrum, the beam would be in unstable equilibrium; while, if it is below the fulcrum, the weight of the beam is continually tending to bring it back to the horizontal position as soon as it diverges from it, and the balance oscillates with regularity.

Conditions of delicacy. 1. *The centre of gravity of the beam should be very near the knife edge*; for then, when the beam is inclined, its weight only acting upon a short arm of the lever, offers but little resistance to the excess of weight in one of the pans.

2. *The beam should be light*; for then the friction of the knife edge upon the supports is smaller the less the pressure. In order more effectually to diminish friction, the edges from which the beam and scales are suspended are made as sharp as possible, and the supports on which they rest are very hard.

3. Lastly, *the longer the beam the more delicate is the balance*; because the difference in the weights in the pans then acts upon a longer arm of the lever.

50. **Method of double weighing.**—Notwithstanding the inaccuracy of a balance, the true weight of a body may always be determined by it. To do so, the body to be weighed is placed in one scale, and shot or sand poured into the other until equilibrium is produced; the body is then replaced by known weights until equilibrium is re-established. The sum of these weights will necessarily be equal to the weight of the body, for, acting under

precisely the same circumstances, both have produced preci
same effect.

51. **Weighing machines.**—One of the forms of these
ments, which are of frequent use in railway stations, coa
etc., for weighing heavy loads, is represented in fig. 35.
sists of a platform, A, on which the body to be weighed is
and to which an upright B is fixed; the whole rests on
HE, by the following mode of suspension.



Fig. 35.

To the upright, E, are adapted two pieces of iron, which
a beam, LR, by the aid of a knife edge, which traverses
The two arms of the beam are unequal in length; one
supports a scale, D, in which are placed the weights; the o
of the beam has two rods, by which is suspended the
part, AB. In order to relieve the knife edge which sup
platform, and to avoid a shock when it is unloaded,
weighing has been made, the arm, OR, is lifted by raising
port, *r*, which is below the beam, by means of the handle,
horizontality of the beam is ascertained by means of two in
m and *n*, the first fixed to the frame and the second to the

To understand the working of the mechanism referer

be made to fig. 36, in which the principal pieces only are represented. A lever, *ih*, which bifurcates underneath the platform, rests at one end on a double knife edge, *i*, and at the other, on the lower end of the rod, L*h*, which is fixed to the beam. A second lever, *eg*, rests at *s* on the lever *ih*, attached at *g* to the rod *ag*, which is also supported by the beam. Lastly, the distance *is* being the fifth of *ih*, *a*O is also a fifth of OL.

From this division of the two levers, *ih* and OL into proportional parts two important consequences follow. First, that when the beam oscillates, the points *a* and *g* being lowered by a certain amount, the points L and *h* are lowered five times as much. But



Fig. 36.

for a similar reason, since the lever *ih* oscillates upon the knife edge *i*, the knife edge *s* is lowered one fifth as much as the point, *h*, and therefore just as much as *g*. The lever *eg* therefore descends parallel to itself, and therefore also the platform A.

Secondly: it follows moreover, from the proportional division of the levers OL and *ih*, that the pressure at the points of suspension, exercised by the load *g* on the platform, is independent of the place which it occupies on the latter, so that it just acts as if it were applied along the rod *ag*. This may be deduced from the properties of the lever by a simple calculation, which cannot however be given here.

Lastly, since the weight is applied at *a*, the longer the arm of the lever OC as compared with O*a*, the smaller need be the weight in the scale D, in order to produce equilibrium. In most weighing machines O*a* is the tenth of OC. Hence the weights in the scale D represent one-tenth the weight of the body on the platform.

CHAPTER V

LAWS OF FALLING BODIES. INCLINED PLANE. THE PENDULUM.

52. **Laws of falling bodies.**—When bodies fall in a vacuum—that is, when they experience no resistance—their fall is subject to the following laws :—

I. *In a vacuum all bodies fall with equal rapidity.*

II. *The space which a falling body traverses is proportional to the square of the time during which it has fallen*; that is, that if the space traversed in a second is 16 feet, in two seconds it will be 64 feet; that is, 4 times as much, and in 3 seconds 9 times as much, or 144 feet, and so on.

Fig. 37.

III. *The velocity acquired by a falling body is proportional to the duration of its fall*; that is, that if the velocity at the end of a second is 16 feet, at the end of two seconds it is twice 16, or 32 feet, at the end of 3 seconds 48 feet, and so forth.

To demonstrate the first law by experiment a glass tube about two yards long (fig. 37) may be taken, having one of its extremities completely closed, and a brass cock fixed to the other. After having introduced bodies of different weights and densities (pieces of lead, paper, feather, &c.) into the tube, the air is withdrawn from it by an air-pump, and the cock closed. If the tube be now suddenly reversed, all the bodies will fall equally quickly. On introducing a little air and again inverting the tube the lighter bodies become slightly retarded, and this retardation increases with the quantity of air introduced.

It is, therefore, concluded that terrestrial attraction which is the cause to which the fall of bodies is due, is equally exerted on all substances, and that the difference in the velocity with which bodies fall is occasioned by the resistance of the air which is more perceptible the smaller the mass of bodies and the greater the surface they present.

The resistance opposed by the air to falling bodies is especially remarkable in the case of liquids. The Staubbach in Switzerland is a good illustration; an immense mass of water is seen falling over a high precipice, but before reaching the bottom it is shattered by the air into the finest mist. In a vacuum, however, liquids fall like solids, without separation of their molecules. The *water hammer* illustrates this; the instrument consists of a thick glass tube about a foot long, half filled with water, the air having been expelled by ebullition previous to closing one extremity with the blow-pipe. When such a tube is suddenly inverted the water falls in one undivided mass against the other extremity of the tube, and produces a sharp dry sound, resembling that which accompanies the shock of two solid bodies.

The two other laws are verified by the aid of the inclined plane, and of Atwood's machine (fig. 40).

53. **Inclined plane.**—Any plane surface more or less oblique in



Fig. 38.

reference to the horizon is an *inclined plane.* Such is the surface (fig. 38), and such also that of an ordinary desk and of most roads.

When a body rests on a horizontal plane, the action of gravity is entirely counteracted by the resistance of this plane. This, however, is not the case when it is placed upon an inclined plane:

the action of gravity is then decomposed into two forces (26), one perpendicular to the inclined plane, that is, acting along its surface, and the other parallel to the plane. The only effect of the first force is to press the first on the plane without imparting to it any motion; while the second makes the body descend along the plane. This latter, however, is only one component of gravity: it is only a fraction, a third, or a quarter, according to the degree of inclination of the plane. Hence a body will roll down an inclined plane, but more slowly than if it fell vertically; and the velocity is indeed less the smaller the angle which the plane makes with the horizon.

A horse drawing a carriage on a road where there is a rise of one in twenty is really lifting one-twentieth of the load, besides overcoming the friction of the carriage. Hence the importance of making roads as level as possible; it is for this reason that a road up a very steep hill is made to wind or zig-zag all the way, and an intelligent driver in ascending a steep hill on which is a broad road usually winds from side to side.

The principle of the inclined plane is made use of in rolling heavy casks into or out of a waggon by means of two combined beams.

54. **Demonstration of the second law of falling bodies by the inclined plane.**—The above property which the inclined plane possesses, of slackening the fall of bodies, has been used to demonstrate the second law of their fall (52), that *the space traversed by a falling body is proportional to the square of the time during which it has been falling.*

To make this experiment, an inclined plane is taken, along which is traced a scale graduated in inches; then taking a well-polished ivory ball, a position is found by trial, at which it just takes a second to reach the bottom of the inclined plane A. Let us suppose that this is at the eleventh division. The experiment is then repeated by making the ball traverse four times the distance, that is, placing it at the forty-fourth division, and it will then be found to take two seconds in so doing. In like manner it will be found that in passing through nine times the distance, or through ninety-nine divisions, three seconds are required. Hence it is concluded, that the spaces traversed increase as the squares of the times.

55. **Atwood's machine.**—Mr. Atwood invented a machine by which the velocity of falling bodies is slackened, and the laws of motion may be demonstrated. It consists of a wooden pillar

about $2\frac{1}{2}$ yards high (fig. 40). On the front of the pillar is a clockwork motion, H, regulated in the usual way by a seconds' pendulum, P. On the right of the column is a graduated scale which measures the spaces traversed by the falling bodies. Along this scale two sliders move, which can be fixed by a screw in any position; one of these has a disc, A, and the other a ring, B (fig. 44). At the top of the column is a brass pulley whose axis instead of resting on pivots, turns on four other wheels, *r*, *r*, *r'*, *r'*, called *friction wheels*, since they serve to diminish friction (fig. 39). Two exactly equal weights, K and K', are attached to the end of a fine silk thread, which passes round the pulley.



Fig. 39.

At the top of the column is a plate, *n*, on which is placed the falling body (fig. 41). This plate is fixed to a horizontal axis which carries a small catch *i*, supported, when the plate is horizontal, by a lever, *ab*, movable in the middle. A spring placed behind the dial tends to keep this lever in the position represented in fig. 41, while an excentric, *e*, moved by the clockwork, tends to incline towards the right the upper arm of the lever *ab*. The parts are so arranged, that when the needle is at zero of the graduation, the lever *ab* is moved by the excentric; the plate *n* then lets fall the body which it sustained (fig. 42).

These details being premised, we may add that the slackening which it produces in the fall of a body depends on the mechanical principle that when a moving body meets another at rest it imparts to this latter a part of its velocity, which is greater the greater the mass of the second body compared with the first. For instance if a body with the mass 1, strikes against another at rest with the mass 19, the total mass being now 20, the common velocity after the impact is only a twentieth of the original velocity of the first.

First experiment. To demonstrate the second law, that *the spaces traversed are proportional to the squares of the times*, a weight K is placed upon the ledge *n* (fig. 41), and it is loaded with an overweight, which consists of a brass disc, *m* (fig. 47,) open at the side, so as to let pass a rod fixed to the weight K. Then below the ledge *n* the slider A is placed at such a distance that K*m* requires a second to traverse the space *n*A, which is easily obtained after a



Fig. 40.



Fig. 41.



Fig. 42.

Fig. 43.

Fig. 44.



Fig. 45.

Fig. 46.

Fig. 47.

few trials. If the mass *m* fell alone it would traverse in a second about 32 feet; but from the principle stated above, it can only fall by imparting to the masses K and K′ what it carries with it, and hence its fall is the more diminished the smaller the mass *m*, as compared with the sum of the masses K and K′.

The experiment being prepared as indicated in fig. 41 the pendulum is made to oscillate; the clockwork then begins to move, and as soon as the needle arrives at zero the plate *n* drops (fig. 42), the weights K and *m* fall too, and the space *n*A is traversed in a second by a uniformly accelerated motion. The experiment is recommenced, the slider A being placed at four times its original distance, that is, that if the distance A*n* were 8 inches (fig. 41) it is now 32 inches (fig. 43). But here when the plate *n* drops it is found that the weight K*m* requires exactly two seconds to traverse the space A*n*. Increasing the space traversed to 72 inches the time required for the purpose is found to be three seconds. That is, that when the times are twice or thrice as great, the spaces traversed are four or nine times as great.

Second experiment.—To prove the law that *the velocities are proportional to the times*, the experiment is arranged as shown in figs. 44, 45, and 46, that is the weights K and *m* being arranged as in the first experiment on the ledge *n*, at a distance of 8 inches below this the sliding ring B is placed, and at 16 inches below the disc A. When the ledge *n* has dropped, the weights K and *m* still require a second to fall from *n* to B. But then the over-weight *m* being arrested by the ring B (fig. 45), the weight K only falls in virtue of its acquired velocity. The motion which was uniformly accelerated from *o* to B (19) is kept uniform from B to A; for the weight *m* was the cause of the acceleration, and this having ceased to act, the acceleration ceases. It is then found that the space *o*B, equal to 8 having been traversed in one second, the space BA, equal to 16, is also traversed in a second. That is, 16 represents the velocity of the uniform motion, which, starting from the point B, has succeeded to the uniformly accelerated motion.

The experiment is finally recommenced by placing the sliding-ring B at the distance 32 (fig. 46), and sliding-disc below B, also at the distance 32. The space *o*B being then four times as great as in fig. 44, the weights K and *m* require, in accordance with the second law, twice the time. But the mass *m* being again arrested by the slider B, it is found that the weight K falls alone and uniformly from B to A in one second. The number 32 from B to A

represents then the velocity acquired, starting from the point I after two seconds of fall. In the first part of the experiment it wa ascertained that the velocity acquired after one second was 16 hence, in double the time, the velocity acquired is double. It ma be shown, in like manner, that after three times the time, th velocity is trebled, and so on ; thus proving the third law.

56. **Pendulum.**—This is the name given to any heavy mass s pended by a thread to a fixed point, or to any metallic rod mova bl about a horizontal axis. The ball, *m*, suspended by the thread *cm* which is fixed at the top at *c* (fig. 48), is a pendulum.

So long as the thread is vertical, which is the case when th centre of gravity of the ball is exactly below the point of suspensi or *c*, the pendulum remains at rest, for the action of gravity is de



Fig. 48. Fig. 49. Fig. 50.

stroyed by the resistance at this point. This is no longer the case when the pendulum is removed from its vertical position ; when it is placed, for instance, in the direction *cn* (fig. 49). The ball being raised, gravity tends to make it fall ; it returns from *n* to *m*, and reaches the latter point with exactly the velocity it would have acquired by falling vertically through the height, *om*. The ball, accordingly, does not stop at *m*, but, in virtue of its inertia, and of its acquired velocity, it continues to move in the direction *mφ* ; as

the ball rises, however, gravity, which had acted from *n* to *m* as an accelerating force, now exerts a retarding action, for it acts in a direction contrary to that of the motion; the motion, accordingly, becomes slower, and the ball stops at a distance, *mp*, which would be exactly equal to *mn*, were it not for the resistance of the air, and also the rigidity of the thread, *cm*, which, as it is, offers a certain resistance to being bent about the point *c*, in passing from the position *cn* to *cp*, and *vice versâ*.

This being premised, the moment the ball stops at *p*, gravity acting so as to make it fall again, brings it from *p* to *m*, when, owing to its inherent velocity, it rises in effect as far as *n*, and so on; a backward and forward motion is thus produced from *n* towards *p*, and from *p* towards *n*, which may last several hours.

This motion is described as an *oscillating motion*. The path of the ball from *n* to *p*, *or* from *p* to *n*, is known as a *semi-oscillation*, a *complete oscillation* being the motion from *n* to *p*, *and* from *p* to *n*. In France the former is known as a *single* oscillation, and the backward and forward motion as a *double* oscillation.

The extent or *amplitude* of the oscillation is the distance between the extreme positions, *cn* and *cp*, and is measured by the arc, *pn*.



Fig. 51.

57. **Simple and compound pendulum.**—A distinction is made in physics between the *simple* and the *compound* pendulum. A *simple* pendulum would be that formed by a *single* material point, suspended by a thread *without* weight. Such a pendulum has only a theoretical existence; and it has only been assumed in order to arrive at the laws of oscillations of the pendulum which we shall presently describe.

A *compound* or *physical pendulum* may be defined to be any body which can oscillate about a point or an axis. The pendulum

described above (fig. 48) is of this kind. The form may be great varied, but the most ordinary one is a glass or steel rod (fig. 5 fixed at the top to a thin flexible steel plate, or to a knife edge li that of the balance (fig. 34). At the bottom of the rod is a hea lens-shaped mass of metal, usually of brass, and known as the *b* The lenticular is preferred to the spherical form, for it prese less resistance to the air during each oscillation.

58. **Laws of the pendulum. Galileo.**—Whatever be the fo of the pendulum, its oscillations always fall under the follow laws. The first of these, that one and the same pendulum ma its oscillations in equal times, was discovered by Galileo, celebrated physicist and astronomer, at the end of the sixteer century. It is related that he was led to this discovery, while s young, by observing the regular motion of a lamp suspended the vault of the cathedral at Pisa. This property of the pendul has received the name of *isochronism*, from two Greek words whi mean equal times, and such oscillations are said to be *isochrono*

First law; or, law of isochronism.—*The oscillations of one a the same pendulum are isochronous, that is, are effected in equ times.* This law is only perfectly exact when the oscillations are small amplitude, four or five degrees at most; for a greater amp tude the oscillation is longer.

Second law; or, law of lengths.—With pendulums of differe lengths *the durations of the oscillations are proportional to t square roots of the lengths of the pendulums*, that is to say, that the lengths of the pendulums are as 1, 4, 9, 16, the times of oscill tions will be as 1, 2, 3, 4; these being the square roots of the form set of numbers.

Third law.—If the length of the pendulum remains the sam but the substances are different, the *duration of the oscillations independent of the substance of which the pendulums are formed* that is, that whether of wood, or of ivory, or of metal, they a oscillate in the same length of time.

Fourth law.—*The duration of the oscillations of a given pen dulum is inversely as the square root of the force of gravity in th place in which the observation is made.*

59. **Verification of the laws of the pendulum.** In order t verify the laws of the simple pendulum we are compelled to em- ploy a compound one, the construction of which differs as little as possible from that of the simple one (57). For this purpose a small sphere of a very dense substance, such as lead or platinum,

is suspended from a fixed point by means of a very fine thread. A pendulum thus formed oscillates almost like a simple pendulum, the length of which is equal to the distance of the centre of the sphere from the point of suspension.

In order to verify the isochronism of small oscillations, it is merely necessary to count the number of oscillations made in equal times, as the amplitudes of these oscillations diminish from *pn* to *rq* (fig. 50) say from three degrees to a fraction of a degree; this number is found to be constant.

That the times of vibration are proportional to the square roots of the lengths is verified by causing pendulums, whose lengths are as the numbers 1, 4, 9, ... to oscillate simultaneously. (A B, fig. 51). The corresponding numbers of oscillations in a given time are then found to be proportional to the fractions 1, $\frac{1}{2}$, $\frac{1}{3}$, etc. . . . . , which shows that the times of oscillation increase as the numbers 1, 2, 3, ... etc.

By taking several pendulums of exactly equal lengths B, C, D (fig. 51) but with spheres of different substances, lead, copper, ivory; it is found that, neglecting the resistance of the air, these pendulums oscillate in equal times, thereby showing that the accelerating effect of gravity on all bodies is the same at the same place.

60. **Measurement of the force of gravity.**—The relation which the fourth law of the pendulum establishes between the number of oscillations in a given time, and the force of gravity, is used to determine the magnitude of this force at different places on the globe. By counting the number of oscillations which one and the same pendulum makes in a given time, a minute, for example, in proceeding from the equator towards the poles, it has been found that this number continually increases, proving, therefore, that the force of gravity increases from the equator towards the poles.

Fig. 52.

By means of the pendulum the velocity has been calculated which a body acquires in falling, in a second of time, in vacuo, that

is to say, when it experiences no resistance from the air. At London this is 32·19 feet.

Since the velocity which a force imparts to a movable body in a given time is greater in proportion as this force is more intense, the force of gravity in different places is measured by the velocity which it imparts to a body falling freely in a vacuum: in London, for instance, its intensity is 32·19 feet, at the equator, 32·09, and at Spitzbergen 32·25 feet.

61. **Application of the pendulum to clocks.**—The regulation of the motion of clocks is effected by means of pendulums, that of watches by balance-springs. Pendulums were first applied to this purpose by Huyghens in 1658, and in the same year Hooke applied a spiral spring to the balance of a watch. The manner of employing the pendulum is shown in fig. 52. The pendulum rod passing between the prongs of a fork, *a*, communicates its motion to a rod, *b*, which oscillates on a horizontal axis, *o*. To this axis is fixed a piece, *mn*, called an *escapement* or *crutch*, terminated by two projections or *pallets*, which work alternately with the teeth of the *escapement wheel*, R. This wheel being acted on by the weight tends to move continuously, let us say, in the direction indicated by the arrow-head. Now if the pendulum is at rest, the wheel is held at rest by the pallet, *m*, and with it the whole of the clockwork and the weight. If, however, the pendulum moves and takes the position shown by the dotted line, *m* is raised, the wheel *escapes* from the confinement in which it was held by the pallet, the weight descends, and causes the wheel to turn until its motion is arrested by the other pallet, *n*; which in consequence of the motion of the pendulum will be brought into contact with another tooth of the escapement wheel. In this manner the descent of the weight is alternately permitted and arrested—or, in a word, *regulated*—by the pendulum. By means of a proper train of wheelwork the motion of the escapement is communicated to the hands of the clock; and consequently their motion, too, is regulated by the pendulum.

Hence, to regulate a clock when it goes too slow or too fast, the length of the pendulum must be altered. If the clock goes too slow, it is because the pendulum oscillates too slowly, and it must therefore be shortened; if, on the contrary, it goes too fast, it must be lengthened. This shortening or lengthening is usually effected at the top of the pendulum by varying the length of the oscillating portion of the plate to which it is suspended. Clocks are provided

with a simple arrangement for this purpose, which, however, is not represented in the figure.

A pendulum which makes one oscillation in a second is called a *seconds pendulum*. Its length is not the same in different parts of the earth; it is somewhat less at the equator than at the poles. In London it amounts in round numbers to 39·14 inches, and in New York to 39·10 inches.

Seeing that heat expands bodies, the length of the pendulum will be greater in summer, and less in winter. Hence a clock which has been once regulated for the mean temperature, will lose in summer and will gain in winter. How this effect of temperature is counteracted by a self-acting arrangement, will be seen in the chapter on Heat.

Fig. 53.

62. **Metronome.**—This is another application of the isochronism of the oscillations of the pendulum, and is used to mark the time in

practising music. As this time varies in different compositions, it is important to be able to vary the duration of the oscillations, which is effected as follows. The bob of the pendulum, B (fig. 53). is of lead, and it oscillates about an axis, *o*; the rod which is prolonged above this axis is provided with a weight, A, which slides on this rod and can be fixed in any position. This weight obviously acts in opposition to the oscillations of the bob, B, for when this tends to oscillate, for instance, from right to left, the weight tends to move the rod in the opposite direction, and this resistance which it affords to the motion is greater the longer the arm of the lever, A *o*, on which it acts. Hence the higher the weight, A, is raised the slower are the oscillations. At the base of the instrument there is a clockwork motion, which works an escapement with such force that, at each oscillation of the pendulum, a tooth strikes strongly against a pallet fixed to the axis, *o*, thus producing a regular beat which gives the time. In front of the box which contains the mechanism is a scale with numbers, indicating the height at which the weight must be placed to obtain a given number of oscillations in a minute. In the drawing this weight is at the number 92, which indicates that the pendulum makes 92 oscillations in a minute.

CHAPTER VI.

MOLECULAR ATTRACTION.

63. **Cohesion and chemical affinity.**—After having described, under the name of *universal gravitation*, the attraction which exists between the stars and planetary bodies; and under that of *gravity*, the attraction which the earth exerts upon all bodies in making them fall towards it, we have to investigate the attractions which hold together the ultimate particles or molecules of a body. These are—cohesion, affinity, and adhesion.

Cohesion is the force which unites two molecules of the same nature; for example, two molecules of water, or two molecules of iron. Cohesion is strongly exerted in solids, less strongly in liquids, and scarcely at all in gases. Its intensity decreases as the temperature increases, because then the repulsive force due to heat increases. Hence it is, that when solid bodies are heated, they first

expand, then liquefy, and are ultimately converted into the gaseous state, provided that heat produces in them no chemical change.

Cohesion varies not only with the nature of bodies, but also with the arrangement of their molecules; for example, the difference between tempered and untempered steel is due to a difference in the molecular arrangement produced by tempering. Many of the properties of bodies, such as tenacity, hardness, and ductility, are due to the modifications which this force undergoes.

In large masses of liquids, the force of gravity overcomes that of cohesion. Hence liquids acted upon by the former force have no special shape; they take that of the vessel in which they are contained. But in smaller masses cohesion gets the upper hand, and liquids present then the spheroidal form. This is seen in the drops of dew on the leaves of plants; it is also seen when a liquid is placed on a solid which it does not moisten; as, for example, mercury upon wood. The experiment may also be made with water, by sprinkling upon the surface of the wood some light powder such as lycopodium or lampblack, and then dropping some water on it.

Chemical affinity is the force which is exerted between molecules not of the same kind. Thus, in water, which is composed of oxygen and hydrogen, it is affinity which unites these elements, but it is cohesion which binds together two molecules of water. In compound bodies cohesion and affinity operate simultaneously, while in simple bodies cohesion has alone to be considered.

To affinity are due all the phenomena of combustion; when carbon burns it is affinity which causes this body to combine with the oxygen of the air to form the gas known as carbonic acid. Affinity determines the combination of the elements, so that with a small number of them are formed the immense number of organic and mineral substances which serve for our daily uses.

The causes which tend to weaken cohesion are most favourable to affinity; for instance, the action of affinity between substances is facilitated by their division, and still more by converting them to a liquid or gaseous state. It is most powerfully exerted by a body in its *nascent* state, that is, the state in which the body exists at the moment it is disengaged from a compound; the body is then free, and ready to obey the feeblest affinity. An increase of temperature modifies affinity differently under different circumstances. In some cases, by diminishing cohesion, and increasing the distance between the molecules, heat promotes combination. Sulphur and oxygen,

which at the ordinary temperature are without action on each other, combine to form sulphurous acid when the temperature is raised. In other cases heat tends to decompose compounds ; thus many metallic oxides, as for example those of silver and mercury, are decomposed, by the action of heat, into gas and metal.

64. **Adhesion.**—*Adhesion* is the name given to the attraction manifested by two bodies when their surfaces are placed in contact. If two leaden bullets are cut with a penknife so as to form two equal and brightly polished surfaces, and the two faces are turned against each other until they are in the closest contact, they adhere so strongly as to require a force of more than 3 or 4 ounces to separate them. The same experiment may be made with two equal pieces of glass, which are polished and made perfectly plane. When they are pressed one against the other, the adhesion is so powerful that they cannot be separated without breaking. As the experiment succeeds in vacuo, it cannot be due to atmospheric pressure, but must be attributed to a reciprocal action between the two surfaces. The attraction also increases as the contact is prolonged, and is greater in proportion as the contact is closer.

To adhesion is due the resistance experienced in raising a plank placed on water ; and to the same force is ascribed the difficulty met with in walking through thick mud. If we dip a glass rod into water, on withdrawing it a drop will be found to collect at the bottom, and remain suspended there. As the weight of the drop tends to detach it, there must necessarily be some force superior to this weight which maintains it there ; this force is the force of adhesion. On the property of adhesion, depends the operations of gluing and soldering, of cementing, and coating mirrors.

The force of adhesion operates also between solids and gases. If a metal plate be immersed in water bubbles will be found to appear on the surface. As air cannot penetrate into the pores of the plate, the bubbles could not arise from air which had been expelled, but must be due to a layer of air which covered the plate and *moistened* it like a liquid.

CAPILLARITY. ABSORPTION.

65. **Capillary phenomena.**—When solid bodies are placed in contact with liquids, molecular attraction gives rise to a class of phenomena called *capillary phenomena*, because they are best seen in tubes whose diameters are comparable with the diameter of a hair. These phenomena are treated of in physics under the head

of *capillarity* or *capillary attraction* : the latter expression is also applied to the force which produces the phenomena.

The phenomena of capillarity are very various, but may all be referred to the mutual attraction of the liquid molecules for each other, and to the attraction between these molecules and solid bodies. The following are some of these phenomena :—

i. When a glass rod is placed in a liquid which wets it, water for instance, the liquid, as if not subject to the laws of gravity, is raised upwards against the sides of the solid, and its surface, instead of being horizontal, becomes slightly concave (fig. 54).



Fig. 54. Fig 55. Fig. 56.

ii. If instead of a solid rod, a hollow tube be immersed in water (fig. 55), not merely is the liquid raised around the tube, but it rises in the inside to a height which is greater, the narrower the tube ; and at the same time the surface of the liquid inside the tube assumes a concave form.

iii. If the tube is not moistened by the liquid, as is the case with mercury, the liquid is depressed instead of being raised, and the more so the narrower the tubes (fig. 56) ; and the surface, which was previously concave, now becomes convex. The surface of a liquid exhibits the same concavity or convexity against the sides of a vessel in which it is contained, according as the sides are or are not moistened by the liquid.

66. **Laws of capillarity.**—Gay-Lussac has shown experimentally that the elevation and depression of liquids in capillary tubes, the internal diameter of which does not exceed two millimetres, are governed by the following laws :—

I. *When a capillary tube is placed in a liquid, the liquid is raised or depressed according as it does or does not moisten the*

tube, and the elevation varies inversely as the diameter of the tube, that is, it is two or three times as great when this diameter is two or three times as small.

II. *The elevation varies with the nature of the liquid, and with the temperature, but is independent of the nature and thickness of the tube.*

67. **Effects due to capillarity.**—It is from capillarity that sap rises in plants, that oil rises in the wicks of lamps, and melted tallow in the wicks of candles. The interstices which exist between the fibres of the cotton of which the wicks are formed, act as capillary tubes in which the ascent takes place. In very porous bodies, the pores being in communication with each other form a series of capillary tubes, which produces the same effect. If a lump of sugar be placed in a cup in which a little coffee is left, the liquid is seen to rise rapidly and fill the entire piece; and it is even to be remarked that the sugar then dissolves more quickly than if it had been directly immersed in the coffee. This is due to the fact that in the latter case the air which fills the pores not being able to escape so rapidly, as if the piece of sugar is only partially immersed, prevents the liquid from penetrating into the mass of the sugar, and thus retards the solution.

Insects can often move on the surface of water without sinking. This is a capillary phenomenon caused by the fact, that as their feet are not wetted by the water, a depression is produced which keeps them up in spite of their weight. Similarly a sewing needle gently placed on water does not sink, because its surface, being covered with an oily layer, does not become wetted. But if previously washed in alcohol, or in potash, it at once sinks to the bottom.

68. **Absorption and imbibition.**—The words absorption and imbibition are used almost promiscuously in physics; they indicate the penetration of a liquid or a gas into a porous body. Absorption is used both for liquids and gases, while imbibition is restricted to liquids.

Charcoal has a great absorbing power for gases. If a piece of recently heated charcoal be passed into a bell jar full of carbonic acid placed over a mercury trough, the volume of gas is seen to diminish rapidly, and it is found that the gas which has disappeared, in penetrating the charcoal represents a volume thirty-five times that of the solid. There are even gases, such as ammonia, of which charcoal can absorb ninety times its own volume.

Absorption takes place in all parts of plants, but more especially in the rootlets and by the leaves. These organs absorb, in the form of water, carbonic acid, and ammonia, the oxygen, hydrogen, carbon, and nitrogen necessary for the growth of the plants.

Absorption also plays an important part both in the nutrition and respiration of animals. Animal tissues can even absorb solid substances. For instance, in those processes of the arts where the workmen have to handle salts of mercury or of lead, these metals are gradually absorbed into the system and produce serious evils.

69. **Effects due to imbibition.**—Imbibition has been defined as being the penetration of a liquid into the pores of a solid body. It is a capillary effect, for the pores being in intercommunication act like small tubes; thus it is that water rises in wood, sponge, bibulous paper, sugar, sand, and in all bodies which possess pores of a perceptible size.

Owing to imbibition, tobacco soon dries if kept in a wooden box, while it remains fresh if kept in a metal one, for then its moisture is not absorbed by the metal as it is by the wood.

When water is absorbed by animal or vegetable matters their volume increases. Thus if a tolerably large sheet of dry paper be measured and be then moistened, it will be found to have appreciably increased by this process. This property is made use of in stretching paper on drawing boards; the paper is moistened and is then glued or fastened with pins round the edge of the board. In drying, the paper contracts, and is tightly stretched. For the same reason, too, wall papers which have been fastened on cloth along the walls, are frequently liable to be torn.

In bending wood, the side to be bent is heated, and the other side moistened. This being lengthened owing to the water it absorbs, while the other is contracted in consequence of the dryness, a curvature ensues on the heated side.

It is often observed that, owing to the changes of volume which they undergo under the influence of moisture and dryness, the furniture of our rooms is frequently heard to crack when the weather changes.

By the absorption of moisture ropes become shorter; and lengthen when they dry. This may seem opposed to what has been stated about moistened paper, but the explanation is not difficult. Ropes are formed of fibres twisted together, and as these fibres swell owing to the water they absorb, the rope becomes larger, and hence each fibre should make in coiling a longer

circuit; and the rope will become more shortened the more it moistened. For this reason, too, new cloths shrink considera when they are moistened for the first time.

It is related that Pope Sixtus, wishing to raise in a place in Ro an obelisk brought from Heliopolis to Rome under Caligula, fear of disturbing the operation, ordered the spectators to prese profound silence under pain of death. The obelisk was on t point of being placed on its pedestal, when the ropes began stretch, owing to the great traction to which they were expos and the operation was in great danger. A voice from the crowd that of the architect Zapaglia—cried out, 'Wet the ropes,' whi was done, and the operation successfully performed.

CHAPTER VII.

PROPERTIES SPECIAL TO SOLIDS.

70. **Tenacity.**—Besides the general properties which we h hitherto been considering, and which are met with in soli liquids, and gases, there are some special to solids which dese mention, on account of the numerous applications which t present. They are—tenacity, hardness, ductility, and malleabili

Tenacity is the resistance which bodies oppose to being brok when subjected to a greater or less traction. The tenacity of particular body is determined by giving to it the form of a cy drical or prismatic rod, one end of which is then firmly fixed a vertical position to a support. To the lower end is fixed a sc pan, in which weights are successively added until the rod bre The breaking weight represents the limit of the tenacity of a for a given section.

Of all substances iron has the greatest tenacity. A cylindri iron rod with a section of a square centimetre, only breaks wit weight of 13,200 pounds. A rod of boxwood of the same dimensi breaks with a weight of 2,640, and one of oak with 1,540 poun a steel wire supports a load of 39,000 times its own length; l constructed of fine iron wire, the $\frac{1}{25}$th to $\frac{1}{30}$th of an inch in diame can support a load of 60 tons for each square inch of section.

Tenacity is directly proportional to the breaking weight, inversely proportional to the area of a transverse section of the w

Tenacity diminishes with the duration of the traction. A s

force continuously applied for a long time will often break a wire, which would not at once be broken by a larger weight.

Not only does tenacity vary with different substances, but it also varies with the form of the body. Thus, with the same sectional area, a cylinder has greater tenacity than a prism. The quantity of matter being the same, a hollow cylinder has greater tenacity than a solid one.

The shape has also the same influence on the resistance to crushing, as it has on the resistance to traction. A hollow cylinder with the same mass, and the same weight, offers a greater resistance than the solid cylinder. It is for this reason that the bones of animals, the feathers of birds, the stems of corn and other plants, offer greater resistance than if they were solid, the mass remaining the same.

71. **Hardness.**—*Hardness* is the resistance which bodies offer to being scratched or worn by others. It is only a relative property, for a body which is hard in reference to one body, may be soft in reference to others. The relative hardness of two bodies is ascertained by trying which of them will scratch the other. Diamond is the hardest of all bodies, for it scratches all, and is not scratched by any. The hardness of a body is expressed by referring it to a *scale of hardness* : that usually adopted is—

1. Talc	5. Apatite	8. Topaz
2. Rock salt	6. Felspar	9. Corundum
3. Calcspar	7. Quartz	10. Diamond
4. Flourspar		

Thus the hardness of a body which would scratch felspar, but would be scratched by quartz, would be expressed by the number 6·5.

The pure metals are softer than their alloys. Hence, for jewellery and coinage, gold and silver, which are soft metals, are alloyed with copper to increase their hardness.

The hardness of a body has no relation to its resistance to compression. Glass and diamond are much harder than wood, but the latter offers far greater resistance to the blow of a hammer. Hard bodies are often used for polishing powders; for example, emery, pumice, and tripoli. Diamond, being the hardest of all bodies, can only be ground by means of its own powder.

72. **Ductility.**—*Ductility* is the property in virtue of which a great number of bodies change their forms by the action of traction or pressure.

Certain bodies, such as clay, wax, etc., are so ductile that the can be drawn out, flattened, modelled, between the fingers; other such as the resins and glass, require the aid of heat. Glass is the so ductile that it can be drawn out into fine threads, which ar flexible enough to be woven into cloth.

Several metals, such as gold, silver, copper, are ductile, even a ordinary temperatures, but require the use of powerful machine such as the draw-plate or the rolling-mill.

73. **Malleability.**—Malleability is that modification of ductilit which is exhibited when metals are hammered. This propert greatly increases with the temperature; everyone knows, for in stance, that iron is easily forged when hot, and not when cold.

Gold is very malleable even at the ordinary temperature. T make the extremely thin plates of gold, known as *gold leaf*, the gol is first pressed, by means of the rolling mill into long plates fro two to three centimetres in breadth, and about a millimetre, the $\frac{1}{25}$t of an inch in thickness. These plates are then beaten into smal squares by means of a hammer; these are then cut and beaten again and so on. By beating them directly, the operation could not lon be continued, for the metal would be torn: hence the plates to b beaten must be placed between plates of a substance which, whil thin, affords great resistance. Sheets of vellum and parchment ar first used for this purpose, and afterwards *gold beater's skin.*

Leaves of gold are thus obtained, which are so thin, that 20,00 superposed are only an inch thick. Silver and copper may also b worked in the same manner. These leaves are used in the arts fo gilding on wood, paper, and other materials.

The following is the usual order of the metals under the draw plate, the rolling mill, and the hammer, arranged in reference t their decreasing ductility.

Draw-plate	Rolling mill	Hammer
Platinum	Gold	Lead
Silver	Silver	Tin
Iron	Copper	Gold
Copper	Tin	Zinc
Gold	Lead	Silver
Zinc	Zinc	Copper
Tin	Platinum	Platinum
Lead	Iron	Iron

The metals must be pure, if they are alloyed with other meta they are fragile, and have but little ductility.

BOOK II.

HYDROSTATICS.

CHAPTER I.

PRESSURES TRANSMITTED AND EXERTED BY LIQUIDS.

74. **Province of Hydrostatics.**—The science of *hydrostatics*, from two Greek words, signifying *equilibrium of water*, treats of the conditions of the equilibrium of liquids, and of the pressure they exert, whether within their own mass, or on the sides of the vessels in which they are contained.

75. **Special characteristics of liquids.**—One essential character of a liquid is the extreme mobility of its molecules, which are displaced by the slightest force. The fluidity of liquids is due to this property; it, however, is not perfect, there is always a sufficient adherence between the molecules to produce a greater or less viscosity.

Another essential property of liquids, and one by which they are distinguished from gases, is their almost entire incompressibility. We have already seen (5) that their compressibility is so small, that for a long time they were regarded as being quite incompressible. It was not before 1823 that Oersted, a Swedish physicist, first proved in an exact manner that liquids are compressible. The apparatus he used for this purpose is called the *piezometer* (πιέζω, I compress, μέτρον, measure). By its means it has been found that a pressure of one atmosphere compresses distilled water by about the $\frac{1}{20000}$ part of its volume; mercury by the same pressure only undergoes about a tenth as great a diminution, and ether about 2½ times as much.

Liquids are also porous, elastic, and impenetrable, like all other

bodies. The proofs of their porosity have been already given, their elasticity is a necessary consequence of their compressibility. Their impenetrability is manifested whenever a solid is immersed in water. For if a vessel be quite filled with water, and any solid body be placed in it which does not absorb the liquid, it will be observed that a volume of water flows over, which is exactly equal to that of the solid immersed.

76. **Equality of pressures. Pascal's law.**—Liquids have the following remarkable property, which is not possessed by solids. It is often called 'Pascal's law,' for it was first enunciated by that distinguished geometrician.

Pressure exerted anywhere upon a mass of liquid is transmitted undiminished in all directions, and acts with the same force on all equal surfaces, and in a direction at right angles to those surfaces.

To get a clearer idea of the truth of this principle, let us conceive a cylindrical vessel, in the sides of which are placed various cylindrical tubulures, all of the same size, and closed by movable pistons (fig. 57). The vessel being filled with water, or any other liquid, the moment any pressure is applied to the piston A, all the other pistons are pressed outwards, showing that the pressure is not merely transmitted downwards upon the piston D, but laterally upon the pistons E and F, and upwards upon the pistons B and C. If, instead of pressing on the piston A, the pressure be exerted upon B, the same effects are produced; the piston A is then forced upwards.



Fig. 57.

In these different cases, not only is the pressure transmitted in all directions, but for the *same surface* it is transmitted with the same intensity. For instance, if the pressure on the piston A is twenty pounds, and its surface is equal to that of the piston B, the upward pressure on the latter is also twenty pounds; but if the surface of the piston B is only a twentieth that of A, the pressure upon B is only one pound. This is the principle of *the equality of pressure.*

77. **Consequence and verification of Pascal's principle.**—It follows from what has been said, that *the pressure transmitted by a liquid is proportional to the extent of surface*; this is indeed only another enunciation of Pascal's principle.

To verify this, two cylinders are taken of unequal dimensions, joined by a tube (fig. 58). These cylinders contain water, and are provided with pistons which move in them with gentle friction. Now if the surface of the larger one, P, for instance, is twenty times that of the smaller one, p, it will be found that a weight of a pound placed upon p will balance a weight of twenty pounds placed upon P; if these weights are in any other ratio, equilibrium is destroyed.



Fig. 58.

The principle of the equality of pressures forms the basis of the whole science of hydrostatics, and we shall presently find a very important application of it in the *hydraulic press* (83).

78. **Pressures resulting from the weight of liquids.**—In what has been said, we have considered the pressures transmitted towards the sides of the vessel, when some external force is applied. It is not, however, necessary to exert an external pressure on the surface of a liquid in order to produce internal pressures in its mass, and on the sides of the vessel. The mere weight of the liquid itself is sufficient to produce pressures which vary with the depth and with the density of the liquid.

For suppose any vessel filled with liquid; if we conceive the liquid divided into horizontal layers of equal thickness, it is clear that the second layer supports a pressure equal to the weight of the first; that the third supports the weight of the first and second, and so on; so that the pressure increases with the number of layers, which is expressed by saying that *gravity produces in liquids pressures proportional to the depth.*

It is obvious, moreover, that *these pressures are proportional to the density of the liquids*; that is, that for the same depth, a liquid which has two or three times the density of another, will exert twice or thrice as much pressure.

It follows from the principle of the equality of pressure in all directions, that the pressure produced by gravity in liquids is exerted

not merely in the direction of this force, but *horizontally*, and al *upwards*, as will now be demonstrated.

79. **Lateral pressures. Hydraulic tourniquet.**—The existen of lateral pressures which liquids exert upon the sides of the vess in which they are containe may be demonstrated b means of the *hydrau tourniquet* or *Barker's mi* (fig. 59). This consists esse tially of a long glass tube, C with a funnel, D, at th top. The bottom of the tub fits into a hollow bra box, which rests on a pivot in the sides of the box a fitted four brass tubes, a ranged crosswise, and a bent in the same direction the ends.



Fig. 59.

Water descending the lon tube emerges by the ape tures of the bent tubes, whic are soon seen to rotate rapid in the direction indicated b the arrow. This rotation i due to the lateral pressur exerted by the column water in the long tube. F let us consider one of th bent tubes, *a*A, B*b*, repr sented in section on the le (fig. 59), and suppose fir that the orifices, *a* and *b*, a closed. The column of water which then fills the tube C exe upon the portions of the opposite sides, A and *a*, equal and contra pressures which hold each other in equilibrium; this is also the ca at B and *b*, and thus no rotation can be produced in either directio But if the orifices *a* and *b* are open, as is the case when the app ratus is at work, as the water issues by these orifices, the pressur at *a* and *b* no longer exist; while those transmitted to A and continuing to act, produce the rotation.

Rotating fireworks also act on the same principle as Barker's mill; that is, an unbalanced reaction from the heated gases which issue from openings in them gives them motion in the opposite directions.

It is in consequence of the lateral pressure of water that dykes and banks which retain rivers or reservoirs, sometimes give way, by becoming too weak for the pressure they have to support.

80. **Vertical upward pressure.**—The pressure which the upper layers of a liquid exert on the lower layers causes them to exert an equal reaction in an upward direction, a necessary consequence of the principle of transmission of pressure in all directions.

The following experiment (fig. 60) serves to exhibit the upward pressure of liquids. A large open glass tube, one end of which is ground, is fitted with a ground glass disc, *a*, or still better, with a thin card or piece of mica, the weight of which may be neglected. To the disc is fitted a string, *b*, by which it can be held against the bottom of the tube. The whole is then immersed in water, and the disc does not fall, although no longer held by the string; it is consequently kept in its position by the upward pressure of the water. If water be now slowly poured into the tube, the disc will only sink when the height of the water inside the tube is equal to the height outside. It follows thence that the upward pressure on the disc is equal to the pressure of a column of water, the base of which is the internal section of the tube *a*, and the height the distance from the disc to the outer surface of the liquid. Hence *the upward pressure of liquids at any point is governed by the same laws as the downward pressure.*

Fig. 60.

This upward pressure is termed the *buoyancy* of liquids; it is perceived when the hand is plunged into water, and still more distinctly if it is immersed in mercury, which being of greater density produces greater pressure. It is owing to this buoyancy that, if a hole be made in the bottom of a ship, water enters with force.

81. **Pressure is independent of the shape of the vessel.**—The

pressure exerted by a liquid, in virtue of its weight, on any pc of the liquid, or on the sides of the vessel in which it is conta depends on the depth and density of the liquid, but *is indepe of the shape of vessel and of the quantity of the liquid.*

This principle, which follows from the law of the equal pressure, may be experimentally demonstrated by many forn apparatus. The following is one frequently used, and is d Masson. It consists of a large conical vessel, M, screwe a brass tubulure, *c*, fixed to a wooden support (fig. 61). tubulure is closed by a disc, *a*, which does not adhere to it, b



Fig. 61.

simply applied against the edge, and is kept there by a s attached to one end of an ordinary balance, to the other en which is a scale-pan. Weights are placed in the latter, so as to counterbalance the pressure of the water on the disc, whe vessel M is almost full; water is then gradually added unti disc just begins to give way and allows some to escape. A *o*, is then lowered until its point just grazes the surface of liquid. If the vessel M be unscrewed and replaced by the lindrical tube, P, the capacity of which is far less, on grad pouring water in, the moment the level of the liquid just to the point of the rod, *o*, the disc, *a*, begins to allow some wat

escape. The same result ensues if for the straight tube, P, the inclined one Q, be substituted. In these three cases, therefore, provided the height of the liquid is the same, the pressure on the disc, *a*, is the same, whatever be the shape and capacity of the vessels.

Moreover, the weight which has to be put on the scale-pan to establish equilibrium, shows that *the pressure exerted by the liquid is equal to the weight of a column of water, the base of which is the internal section of the tubulure, c, and the height the vertical distance from the disc to the surface of the liquid.*

This principle is sometimes called the *hydrostatical paradox*, for at first sight it seems quite impossible.

82. **Pascal's experiment.** — Pascal made the following experiment, which proves what great pressures may be produced by even small quantities of liquid when contained in vessels of great height. He fixed firmly, in a stout cask, as represented in fig. 62, a very narrow tube about 30 feet in height, and then filled the cask and the tube with water. The effect of this was to burst the cask; for there was a pressure on the bottom of the cask equal to the weight of a column of water whose base was the bottom itself, and whose height was equal to that of the water in the tube (81).

Fig. 62.

83. **Hydraulic press.**—The law of the equality of pressure has received a most important application in the *hydraulic press*, a machine by which enormous pressures may be produced. Its principle is due to Pascal, but it was first constructed by Bramah in 1796.

Fig. 63 represents an elevation, and fig. 64 a section of the instrument; it consists of two iron cylinders or barrels, A and B, of unequal diameters. In the barrel A, which is of very small diameter, is a cylindrical rod, *a*, which acts as piston, and can be moved up and down by the lever, O. In the cylinder, B, the internal diameter of which

is 12 to 15 times that of the barrel, A, is a long cylindrical i ram, C, which also forms a piston, and works water-tight in barrel B. On the top of the ram, C, is an iron slab, K, wl rises and falls with it. Four wrought-iron columns suppo second plate, MN, which is fixed. The objects to be pressed placed between K and MN.

Fig. 62.

When the piston is raised by means of the level, a vacuu produced in the barrel A, and a valve, S, at the bottom opens allows water to pass from a reservoir, P, into the barrel. W *a* re-descends, the valve, S, closes; but another valve, *m*, pl at the bottom of the tube *d*, opens; the water is thus forced this tube into the large cylinder, B. At the next stroke of piston, *a*, a fresh quantity of water is drawn from the reservoi and forced into the barrel B, and so forth.

In consequence of the principle of the equality of pressure, the downward pressure exerted by the small piston, *a*, is transmitted upwards upon the piston C. The pressure which can be obtained depends on the relation of the piston C to that of the piston *a*. If the former has a transverse section fifty or a hundred times as large as the latter, the upward pressure on the large piston will be fifty or a hundred times that exerted upon the small one. By means of the lever, O, an additional advantage is obtained. If the distance from the fulcrum to the point where the power is applied is five times the distance from the fulcrum to the piston, *a*, the pressure on *a* will be five times the power. Thus, if a man acts on O with



Fig. 64.

a force of sixty pounds, the force transmitted by the piston *a* will be 300 pounds, and the force which tends to raise the piston C will be 30,000 pounds, supposing the section of C is a hundred times that of *a*.

The hydraulic press is used in all cases in which great pressures are required. It is used in pressing cloth, in extracting the juice of beet root, in expressing oil from seeds, and in pressing apples in making cider; it also serves to test the strength of cannon, of steam boilers, and of chain cables. The parts composing the tubular bridge which spans the Menai Straits were raised by means of an hydraulic press. The cylinder of this machine, the largest which has ever been constructed, was nine feet long and twenty-two inches in internal diameter; it was capable of raising a weight of two thousand tons.

CHAPTER II.

EQUILIBRIUM OF LIQUIDS.

84. **Conditions of the equilibrium of liquids.**—We have se
that the conditions of the equilibrium of a solid are that its cen
of gravity be supported by a fixed point; all the other parts of t
body then retain the same state of equilibrium in consequence
cohesion, which unite the particles to each other, and to the cen
of gravity. This is by no means the case with liquids; owing
the greater mobility of their molecules, and the facility with whi
they obey the force of gravity, they would flow away and spre
out in a horizontal position, if they were not retained by so
obstacle. Hence a liquid cannot be at rest in any vessel, unless
satisfies the following conditions :—

I. *The free surface of the liquid must be horizontal, that
perpendicular everywhere to the direction of gravity.*

II. *Every molecule of the mass of the liquid must be subject
every direction to equal and contrary pressures.*

The second condition is self-evident; for if, in two opposi
directions, the pressures exerted on any given molecule were n
equal and contrary, the molecule would be moved in the directio
of the greater pressure, and there would be no equilibrium. Th
the second condition follows from the principle of the equality
pressures, and from the reaction whic
all pressure causes on the mass
liquids.



Fig. 65.

To account for the first conditio
relative to the free surface of the liqui
let us observe that in a liquid whos
surface is horizontal, all the molecule
supporting each other, the action o
gravity is destroyed, and the liquid is at rest. But if the surface
is not horizontal, if some parts are higher than others (fig. 65),
the higher part, *ab*, exerts upon any horizontal layer, *bd*, a greater
pressure than the part *cd*, and therefore as a given molecule, *o*,
of the horizontal layer is exposed to a greater pressure in the
direction *bo* than in the direction *do*, equilibrium is impossible.

In saying that in order that a liquid be at rest its surface must be horizontal, we must remark that that presumes the liquid only to be acted upon by gravity, which is usually the case; if it is under the action of other forces, as is the case with the capillary phenomena, where it is attracted by the sides of the vessel, its surface is then inclined so as to be perpendicular to the resultant of the forces which act upon it.

85. **Level of liquids.**—A liquid is said to be *level* when all the points of its surface are in the same horizontal plane. This, however, only applies to surfaces of small extent. For as the direction of the vertical constantly changes from one place to another on the

Fig. 66.

surface of the globe, the direction of the horizontal surfaces changes too; that is to say, that a plane which is horizontal at one part of the earth's surface, is not parallel to a horizontal plane at a small distance; they form an angle with each other. Hence a liquid surface of some extent in a state of equilibrium, being necessarily horizontal in each of its parts, does not form one single perfectly plane surface, but a series of plane surfaces inclined to each other; which of course produces a curved surface. This curvature cannot, however, be perceived on surfaces of small extent, as in water contained in a vessel; for the surface of such a liquid is so perfectly levelled, that it reflects the rays of light like the most per-

fectly polished plane mirror. The curvature is, however, easily observed on large surfaces like those of the sea. For if this surface were perfectly level, a ship in sailing away from the shore would only cease to be visible in consequence of increasing distance, and the less apparent parts, the masts and the cordage, would disappear first. This, however, is not the case ; the hull first sinks below the horizon, then the lower part of the masts, and ultimately the top, as seen in fig. 66, thus proving the curvature of the surface of the sea.

86. **True and apparent level.**—When we consider a great surface of water—the Mediterranean sea, for instance—its surface is said to be level when all points of the surface are equidistant from the centre of the earth. This is the *true level* ; while that level which is defined as having all the points of its surface in the same horizontal plane, is the *apparent level*, the level for the eye. The true level only coincides with the apparent level when the liquid surfaces are very small. If the earth did not rotate about its own axis, the surface of all seas would form a true level ; but owing to the centrifugal force which results from its daily motion, the surface is heaped up at the equator, and the level is higher than at the poles.

87. **Equilibrium of the same liquid in several communicating vessels.**—Not merely do liquids tend to become level



Fig. 67.

when they are placed in the same vessel, but also when they are placed in vessels which communicate with each other. Whatever

: and the dimensions of these vessels, equilibrium will *:n the surfaces of the liquids in all the vessels are in the :zontal plane.*

)rinciple may be demonstrated by means of the apparatus ed in fig. 67. It consists of a series of vessels of different nd capacities connected together by a common horizontal

When water or any other liquid is poured into the ıe level is seen to rise at the same time, and stop at ıe same height in each. Equilibrium is then established. : have seen that the pressures exerted by a liquid do not ıpon its quantity but upon its height (81), when this is for all the vessels above the tube of communication *abc*, ure is necessarily everywhere equal, and therefore, as the ; no more tendency to flow from *b* towards *a* than from uilibrium continues.

quilibrium of different liquids in communicating –In what has been said the communicating vessels all



Fig. 68.

d the same liquid. It may, however, happen that the :ontain liquids of different densities, which do not mix.

The level is then no longer the same; the lighter liquid higher, and equilibrium is only possible *when the heights liquid columns in communication are inversely as their den* that is, that if one of the liquids is twice or thrice as de another, its height will be half or one-third as much.

This principle is demonstrated experimentally by means apparatus represented in fig. 68. It consists of two glass connected at the bottom by a narrow tube. The tubes ar ported by two vertical columns, and on each of them is a graduated on the glass itself. If then mercury is poured in of the tubes, it quickly assumes the same level in each. O pouring water into the tube A, the level of the mercury is s sink in this tube in virtue of the pressure of the water, and i in the other tube. Then, when equilibrium is establishe mercury in B is higher than in the tube A by a quantity, *c* is clear, then, that the pressure of the column of mercury, *cd*, co balances the pressure of the column of water, *ab*. If no heights of *ab* and *cd* be measured by means of the graduated on the two tubes, it will be found that the height *cd* is 1 small as that of *ab*; which demonstrates the above princip we shall presently see that mercury is 13·6 times as hea water.

Fig. 69.

89. **Equilibrium of superi liquids.**—In order that there shou equilibrium when several heteroge liquids which do not mix are super in the same vessel, each of them satisfy the conditions necessary for a liquid; and further, *there will be a equilibrium only when the liquia arranged in the order of their decre densities from the bottom upwards.*

The last condition is experime demonstrated by means of the *pl four elements* (fig. 69). It consists long narrow bottle containing me water saturated with carbonate of p alcohol coloured red, and petro When the phial is shaken the liquid but when it is allowed to rest separate; the mercury sinks to the bottom, then comes the

then the alcohol, and then the petroleum. This is the order of the decreasing densities of the bodies. The water is saturated with carbonate of potass to prevent its mixing with the alcohol.

This separation of the liquids is due to the same causes as that which enables solid bodies to float on the surface of a liquid of greater density than their own. It is also from this principle that fresh water, at the mouths of rivers, floats for a long time on the denser salt water of the sea ; and for the same reason cream, which is lighter than milk, rises to the surface.

APPLICATIONS OF THE PRINCIPLE OF THE EQUILIBRIUM OF LIQUIDS.

90. **Water level.**—In a great number of operations, such as the construction of canals, railways, roads, etc., it is continually necessary to determine the difference in level of two more or less distant places. The simplest apparatus for this purpose is the *water level*

Fig. 70.

which is an application of the conditions of equilibrium in communicating vessels. It consists of a metal tube bent at both ends, in which are fitted glass tubes (fig. 70). It is placed on a tripod, and water poured in the tube until it rises in both limbs. When the liquid is at rest, the level of the water in both tubes is the same—that is, they are both in the same horizontal plane.

This instrument is used in levelling, or ascertaining how much one point is higher than another. If, for example, it is desired to

find the difference between the heights of two places, a *levelling-staff* is fixed on the latter place. This staff consists of a rule formed of two sliding pieces of wood, one of which supports a piece of tin plate, in the centre of which there is a mark. This staff being held vertically, an observer looks at it through the level along the surfaces in the two tubes, and directs the holder to raise or lower the slide until the mark is in the prolongation of the level in the two tubes. The assistant then reads off on the graduated rod the height of the mark upon the ground. If this height exceeds that of the level, the height of the latter is subtracted from that of the former, and the difference gives the difference in the heights of the two places.

91. **Spirit level.**—The *spirit level* is both more delicate and more accurate than the water level. It consists of a glass tube (fig. 71), very slightly curved; it is filled with spirit with the ex-

Fig. 71.

ception of a bubble of air, which tends to occupy the highest part. The tube is placed in a brass case, which is so arranged that when it is in a perfectly horizontal position the bubble of air is exactly between the two points marked in the case. But if the plane on which the instrument rests is ever so little inclined, the air bubble tends to move towards the higher part.

This thus furnishes a ready means of ascertaining whether any article—a table, a stand, or a bookshelf—is quite horizontal.

To take levels with this apparatus, it is fixed on a telescope, which can consequently be placed in a horizontal position.

92. **Jets of water.**—The jets which ornament our gardens and public places depend on the tendency of liquids always to become level. For the water which jets out always comes from a reservoir placed in a higher position than that where the jet is; and its jetting is a consequence of its tendency to form a level. Fig. 72 gives an idea of this phenomenon. On the eminence on the left of the figure is a reservoir containing water, from the bottom of which passes a

h terminates in the centre of the basin. The water then orced by the pressure of a column of water, the height of

Fig. 72.

qual to the difference in level between the reservoir and

y proves that in such a case the water always tends to e level of the reservoir from which it is supplied. It never is height, for the jet experiences three kinds of resistances : iction of the water in the conduit pipe ; 2nd, the resist- he air ; and 3rd the hindrance offered by the particles m the height of the jet upon those ascending.

reams, springs, wells.—The formation of springs upon e of the earth, and in its interior, is also due to the tendency o seek its level. For gravity causes water to flow from lower places. Hence it is that the rain which falls upon , and the water arising from the melting of snow, pass the valleys, where they form brooks, streams, and rivers, w along their beds as along an inclined plane, until they ıto the seas. A very small fall can give rise to a current. mean height of the Seine at Paris is not more than 35 ve the sea-level. The extent of its course between these s is about 224 miles, which scarcely amounts to a fall of

the $\frac{1}{312}$th part of an inch in a yard; and water requires several days to traverse this distance.

All the rain which falls does not flow upon the surface; part of it penetrates into the earth, and gives rise to small subterranean watercourses which are called *springs*. It is in order to procure water from these that *wells* are sunk.

94. **Artesian wells.**—When the spring which feeds a well comes from a place much higher than that where the well is sunk, it may happen that water tends to rise higher than the ground. This is what happens in what are called *Artesian wells*. These wells derive their name from the province of Artois, where it has long been customary to dig them, and from whence their use in other parts of



Fig. 73.

France and Europe was derived. It seems however, that at a very remote period, wells of the same kind were dug in China and Egypt.

To understand the theory of these wells, it must be premised that the strata composing the earth's crust are of two kinds: the one *permeable* to water, such as sand, gravel, etc.; the other *impermeable*, such as clay. Let us suppose, then, a basin of greater or less extent, in which the two impermeable layers AB, CD (fig. 73), enclose between them a permeable layer KK. The rain-water falling on the part of this layer which comes to the surface, which is called the *outcrop*, will filter through it, and, following the natural fall of the ground, will collect in the hollow of the basin, whence it cannot escape, owing to the impermeable strata above and below it. If now a vertical hole, I, be sunk down to the water-bearing stratum, the water striving to regain its level will spout

height which depends on the difference between the levels
ıtcrop and of the point at which the perforation is made.
waters which feed Artesian wells often come from a distance
or seventy miles. The depth varies in different places.
l at Grenelle is 1,800 feet deep; it gives 656 gallons of
a minute, and is one of the deepest and most abundant
as been made. The temperature of the water is 27° C. It
from the law of the increase of temperature with the in-
; depth below the surface of the ground (297), that, if this
'e 210 feet deeper, the water would have all the year round
rature of 32° C., that is, the ordinary temperature of warm

CHAPTER III.

SURES SUPPORTED BY BODIES IMMERSED IN LIQUIDS. SPECIFIC GRAVITIES. AREOMETERS.

Pressure supported by a body immersed in a liquid.—
. solid is immersed in a liquid, it is obvious that the pressures
he sides of the vessel support are also exerted against the
of the body immersed, since liquids transmit pressure in all
ns (76). But it is readily seen that the pressures which the
ed body supports do not neutral-
ıselves, but have a resultant, the
y of which is to move the body
s.

us imagine a cube immersed in
of water (fig. 74), and that four of
s are vertical. The horizontal
:s upon the two opposite faces,
, are clearly of the same inten-
they are exerted at the same
8); and as they are in opposite
ns they will balance one an-
ıd the only effect will be to com-
e body without displacing it.

Fig. 74.

the vertical pressures on the faces *d* and *c* are obviously un-
The first is pressed downwards by a column of water whose

base is the face *d*, and whose height is *dn*, the lower face *c* is pr upwards by the weight of a column of water whose base is th itself, and whose height is *cn*. The cube, therefore, is urge wards by a force equal to the difference between these two pres which latter is manifestly equal to the weight of a column of having the same base and the same height as this cube. B reasoning, therefore, we arrive at the remarkable principle, tha *body immersed in a liquid is pressed upwards by a pressure to the weight of the volume of liquid which it displaces.* We see how this principle can be experimentally verified.

96. **Principle of Archimedes. Hydrostatic balance.** have thus seen that any body immersed in a liquid is submitt the action of two forces—gravity which tends to make it sink

Fig. 75.

the buoyancy of the liquid which tends to raise it with a force to the weight of the liquid displaced. The body weighs less fore than in air, and the diminution of its weight is exactly eq the weight of the displaced liquid. The above principle m

thus enunciated : that *a body immersed in a liquid loses* a *part of its weight equal to the weight of the displaced liquid.* For instance, suppose that a body which in air weighs 1,000 grains, when immersed in water displaces a cubic inch of water ; it will now only weigh 1,000 − 252 = 748 grains (a cubic inch of water = 252 grains).

This principle, which is remarkable for its numerous applications, is called the 'principle of Archimedes,' after the discoverer. It is shown experimentally by means of the *hydrostatic balance* (fig. 75). This is an ordinary balance, each pan of which is provided with a hook; the rod, *c*, slides in the hollow cylinder *d*. The beam is supported on the rod, *c*, which can be fixed in any position by means of a screw, *n*. The beam being raised, a hollow brass cylinder, *b*, is suspended to one of the pans, and below this a solid cylinder, *a*, whose volume is exactly equal to the capacity of the first cylinder ; lastly an equipoise is placed in the other pan. If now the hollow cylinder, *a*, be filled with water, the equilibrium is disturbed, but if at the same time the beam is lowered so that the solid cylinder becomes immersed in a vessel of water placed beneath it, the equilibrium will be restored. By being immersed in water, the cylinder *a* loses a part of its weight equal to that of the water in the cylinder *b*. Now as the capacity of the cylinder *a* is exactly the same as that of the cylinder *b*, the principle which has been laid down is proved.

It is stated that Archimedes discovered this principle on the occasion of a problem which had been propounded to him by Hiero, tyrant of Syracuse. This prince, desiring to offer to Jupiter a gold crown, had furnished a goldsmith with ten pounds of gold as the material for this purpose. The crown when finished was found to weigh ten pounds, but Hiero, suspecting that some of the gold had been replaced by silver, owing to the beauty of its workmanship, demanded from Archimedes a means of detecting the supposed fraud without destroying the crown.

Archimedes pondering over the solution of the problem, was in the bath, when he observed that he could raise his limbs in water more easily than in air. This simple observation was a gleam of light for him ; he discovered the above principle, and this led him to a simple means of calculating the quantity of gold and silver in the crown. It is said that Archimedes was so transported with joy, at his discovery that he ran home from the bath, crying in the streets, Εὕρηκα, εὕρηκα (I have found it).

We have all had occasion to make the observation of Archimedes,

on observing how much lighter our limbs appear in water, and the contrary, how much heavier they seem when lifted out. In li manner, if the body is almost entirely immersed in water, we c walk barefoot on the stones without injuring the feet ; but this not possible when we are out of the water. For in the former ca part of the weight of the body is raised by the liquid, while in t latter the whole weight of the body presses the feet against t sharp projections.

97. **Equilibrium of immersed and floating bodies.**—When body is placed in a liquid, three cases are possible : the body m have the same specific gravity as the liquid, in which case it weig as much as the liquid for an equal volume ; or it may be denser, which case it weighs more ; or it is lighter, and in this case weighs less.

I. If the body immersed is of the same density as the liquid, t weight of the liquid displaced being the same as that of the bod it follows from Archimedes' principle that the buoyancy whi tends to raise it, is exactly equal to the force with which gravi tends to sink it. The two forces are thus in equilibrium, and t body remains in suspension in any position in the liquid.

II. If the body immersed is denser than the liquid, it sinks, f then its weight preponderates over the buoyancy. This is the ca when a stone or a mass of metal is thrown into water.

III. Lastly, if the immersed body is lighter than the liquid, t buoyancy prevails, and the body rises until it only displaces weight of liquid equal to its own. It is then said to *float*. Co wax, wood, and all substances lighter than water, float on surface.

A body which floats on one liquid may sink in another; the bo for this purpose must be lighter than the one liquid, but heav than the other. An egg sinks at once if placed in ordinary wat since it is heavier than an equal volume of water ; but it swim placed in strong brine, which is denser than water. A piece of c floats on water, but sinks in ether, which is lighter than water. It floats on mercury, but sinks at once in water.

Yet a body, though denser than a liquid may float on its surfa For this purpose it must have such a shape as to displace a volu of liquid, the weight of which is greater than its own. Porcelain much heavier than water, yet a porcelain saucer placed on wa floats on the surface ; this arises from its concave shape, ow to which it displaces a weight of water equal to its own, though i

only partially immersed. For the same reason iron ships, even with very thick sides, float freely on water.

98. **Cartesian diver.**—The different effects of suspension, immersion, and floating are reproduced by means of a well-known hydrostatic toy, the *Cartesian diver* (fig. 76). It consists of a glass cylinder, nearly full of water, on the top of which a brass cap, A, provided with a piston, is hermetically fitted. In the liquid there is a little porcelain figure, a fish, *o*, for example, attached to a hollow glass ball, *m*, which contains air and water, and floats on the surface. In the lower part of this figure there is a little hole by which water can enter or escape, according as the air in the interior is more or less compressed. The quantity of water in the globe is such, that very little more is required to make it sink. If the piston be slightly lowered the air is compressed, and this pressure is transmitted to the water of the vessel and to the air in the bulb. The consequence is, that a small quantity of water penetrates into the bulb, which therefore becomes heavier and sinks. If the pressure is relieved, the air in the bulb expands, expels the excess of water which had entered it, and the apparatus being now lighter, rises to the surface. The experiment may also be made, by replacing the brass cap and piston by a cover of sheet india rubber, which is tightly tied over the mouth. When this is pressed by the hand the same effects are produced.

Fig. 76.

99. **Swimming bladder of fishes.**—Most fishes have an air-bladder below the spine, which is called the *swimming bladder*. The fish can compress or dilate this at pleasure by means of a muscular effort, and produce the same effects as those just described—that is, it can either rise or sink in water.

100. **Swimming.**—The human body is lighter, on the whole, than an equal volume of water; it consequently floats on the surface and still better in sea water, which is

heavier than fresh water. The difficulty in swimming consists, no so much in floating, as in keeping the head above water, so as t breathe freely. In man the head is heavier than the lower parts, and consequently tends to sink, and hence swimming is not natural to him, but is an art which requires to be learned. With quadrupeds on the contrary, the head being less heavy than the posterior part of the body, remains above water without any effort, and these animals therefore swim naturally.

If a person who cannot swim, and who falls into the water, retains

Fig. 77.

coolness enough to turn on his back, so that his face is out of water, he can breathe freely, and wait until help arrives. Instead of this however, he generally attempts to raise his arms out of water, as i grasping at some fixed support. This is very dangerous, for as th arms no longer displace a quantity of liquid equal to their own bul their weight is not diminished to that extent, but concurs with the of the head in making them sink.

Weight for weight, fat persons swim more easily than lean one for they displace more water. For the same reason air bladders, c cork girdles, are fastened to persons who are learning to swi (fig. 77), for then, without any considerable increase of weight, the displace more water, which increases the buoyancy and keep them up.

Several kinds of birds, such as ducks, geese, and swans, swim easily on water. They owe this property to a thick coating of a light impervious down which covers the lower part of the body, so that they displace, even with a small immersion, a weight equal to their own.

SPECIFIC GRAVITY. HYDROMETERS.

101. **Specific gravity.**—Daily experience shows us that different ıstances have very unequal weights for one and the same ıme. For instance, we all know that gold weighs more than :r, lead than iron, stone than wood. In order to compare ıl volumes of various substances as to their weights, the weight 'ater has been taken as a standard of comparison—as *unity*. For :r is everywhere met with, and can always be had pure; this :r condition is necessary, for the weight of a given quantity of er differs with the substances it holds in solution. As, more-, the weight varies with the temperature, a constant temperature ıt be adopted. Hence the unit of weight is *distilled* water at a perature of 4 degrees, for at this point, as we shall afterwards (228), water has its greatest density.

Fig. 78.

Thus having agreed to represent by 1 the weight of a certain ıme of distilled water at 4 degrees, *the specific gravity* of a body

is the weight of *the same volume* of it as compared with that of water, or what is the same, the number which expresses how much it weighs as compared with water. Thus, when we say that the specific gravity of gold is 19, and that of lead 11, we mean that the former metal is 19 times, and the latter 11 times as heavy as water.

102. **Determination of the specific gravity of solids.**—Three methods are commonly used in determining the specific gravities of solids and liquids. These are—the method of the hydrostatic balance, that of the hydrometer, and that of the specific gravity flask. All three, however, depend on the same principle, that of first ascertaining the weight of a body, and then that of an equal volume of water. We shall first apply these methods to determining the specific gravity of solids, and then to the specific gravity of liquids.

i. *Hydrostatic balance.* To obtain the specific gravity of a solid, a piece of iron for instance, by the hydrostatic balance (fig. 78), it is first weighed in air by suspending it to the hook of one of the plates. Let us suppose that its weight is 585 grains. It is then weighed while immersed in distilled water, as shown in fig. 78. It will now weigh less ; suppose the weight to be 510 grains, this is in accordance with Archimedes' principle, for it now loses a weight equal to that of the water which it displaces. Hence, subtracting 510 from 585, the difference 75 represents the weight of the displaced water, that is, the weight of a volume of water equal to that of the iron : we need now only calculate how often the weight 75, that of the water, is contained in 585, that of the iron, and the quotient 7·8 is the specific gravity of iron ; it says that, for equal volumes, this substance weighs 7·8 times as much as water.

Nicholson's hydrometer. This apparatus consists of a hollow metallic cylinder (fig. 79), to which is fixed a cone, *d*, loaded with lead. The object of the latter is to depress the centre of gravity so that the cylinder does not upset when in the water. At the top is a stem, *c*, terminated by a pan, *a*, in which is placed the substance whose specific gravity is to be determined. On the stem a standard point, *c*, is marked.

The apparatus stands partly out of the water, and the first step is to ascertain the weight which must be placed in the pan in order to make the hydrometer sink to the standard point *c* (fig. 80). Let this weight be 125 grains, and let sulphur be the substance whose specific gravity is to be determined. The weights are then removed from the pan, and replaced by a piece of sulphur which weighs less

than 125 grains, and weights added until the hydrometer is again depressed to the standard, *c*. If, for instance, it has been necessary



Fig. 79. Fig. 80. Fig. 81.

to add 55 grains, the weight of the sulphur is evidently the difference between 125 and 55 grains, that is, 70 grains.

Having thus determined the weight of the sulphur in air, it is now only necessary to ascertain the weight of an equal volume in water. To do this, the piece of sulphur is placed in the lower pan at *d*, as represented in fig. 81. The whole weight is not changed, nevertheless the hydrometer no longer sinks to the standard ; the sulphur, by immersion, has lost part of its weight equal to that of the water displaced. Weights are added to the upper pan until the hydrometer sinks again to the standard. This weight, 34·4 grains for example, represents the weight of the volume of water displaced ; that is, of the volume of water equal to the volume of the sulphur.

It is only necessary, therefore, to divide 70 grains, the weight in air, by 34·4 grains, and the quotient 2·03 is the specific gravity.

Specific gravity flask. In this method, which is advantageously used for the determination of the specific gravity of bodies in a state of powder, a wide-necked flask is used which can be carefully closed by a ground glass disc (fig. 82). Having filled it with water it is closed with the disc, great care being taken that not a bubble of air is left. After being carefully wiped dry, it is placed in the pan of a balance, and by its side is the substance, *a*, whose

specific gravity is to be determined. The whole is then equi poised by placing weights in the other pan of the balance. Th substance, *a*, is then removed, and weight added in its place, until equilibrium is again established. The weight necessary for this purpose gives the weight of the substance in air.



Fig. 82.

To obtain its weight in water it is placed in the flask, the disc adjusted, and the whole again carefully wiped. In order now to equipoise the tare in the second pan, weights must be added on the side of the flask to make up for the water displaced. The weights necessary for this purpose represent then the weight of a volume of water equal to that of the body.

Dividing, then, the weight of the body in air by the weight of an equal volume of water, we have the specific gravity sought.

103. **Specific gravity of liquids.**—These are determined by the same methods as those of solids.

Hydrostatic balance. In determining the specific gravity of a liquid by this means, a body is suspended to one of the pans of the balance, which is neither dissolved by the liquid whose specific gravity is to be determined, nor by water; for instance, a ball of platinum, which is insoluble in all ordinary liquids. This ball is first weighed in air, then in water, and finally in the liquid in question which we will suppose is alcohol. Let us assume that in air the ball weighs 510 grains, in water 486 grains, and in alcohol 489 grains. The loss of weight in water has thus been 510 less 486, or 24 grains, and in alcohol 510 less 499, or 21 grains; which tells us that if a volume of water equal to that of the ball weighs 24 grains, the same volume of alcohol weighs 21 grains. Hence, to obtain the specific weight of alcohol we must ascertain how many times the number 21 contains 24, which of course is obtained by division. The quotient thus obtained is 0·866, which represents the specific gravity of alcohol as compared with water.

ii. *Fahrenheit's hydrometer.* This instrument (fig. 83) resembles Nicholson's hydrometer, but is made of glass, so as to be used in all liquids. At its lower extremity, instead of a pan, it is loaded with a small bulb containing mercury. There is a standard mark on the stem, at the top of which is a pan.

The weight of the instrument is first accurately determined in air by means of an ordinary balance. Let us suppose that its



Fig. 83.

weight is 618 grains, and that the liquid whose specific gravity is to be determined, is olive oil. The hydrometer is placed in water, and the pan loaded with weights, until the liquid is level with the mark on the stem. Suppose it has been necessary to add 93 grains for this purpose ; these 93 grains, together with the 618 which the instrument weighs, make 711 grains, which represents the weight of water displaced by the instrument (97). The hydrometer is then removed, wiped dry, and immersed in the olive oil. Let us suppose that now only 31 grains need be added to sink the hydrometer to the mark. These together with the 618 grains which the instrument weighs, in all 649, represent the weight of the displaced oil. We thus learn that equal volumes of oil and water weigh respectively 649 and 711. Hence we obtain the specific gravity of the latter as compared with the former by dividing 649 by 711. The quotient is 0·91, which teaches us that if a certain volume of water weighs 100 grammes, the same volume of oil weighs 91 grammes.

Neither Fahrenheit's nor Nicholson's hydrometers, give such accurate results as the hydrostatic balance.

Specific gravity flask. This has been already described. In

determining the specific gravity of a liquid, the flask is first weigl empty, and then, successively, full of water and of the given liq If the weight of the flask be subtracted from the two weights t obtained, the result represents the weights of equal volumes of liquid, and of water, from which the specific gravity is obtained division.

Specific gravities of solids.

Platinum	22·069	Aluminum	
Gold	19·36	Glass	
Lead	11·35	Anthracite	
Silver	10·47	Coal	
Copper	8·87	Amber	
Iron	7·78	Oak	
Zinc	6·86	Yellow pine	
Diamonds	3·53	Common poplar	
Statuary marble	2·83	Cork	

Specific gravities of liquids.

Mercury	13·60	Distilled water at 0° C.	
Bromine	2·96	Claret	
Sulphuric acid	1·84	Olive oil	
Milk	1·03	Oil of turpentine	
Sea water	1·02	Absolute alcohol	
Distilled water at 4° C.	1·00	Ether	

104. **Use of tables of specific gravities.**—Tables of spe gravity admit of numerous applications. In mineralogy the spe gravity of a mineral is often a highly distinctive character. Jewe also use them. By means of tables of specific gravities the we of a body may be calculated when its volume is known, and versely the volume when its weight is known.

With a view to explaining the last-mentioned use of these ta it will be well to explain the connection existing between the Br *units of length, capacity, and weight.* It will be sufficient for purpose to define that which exists between the *yard*, *gallon*, *pound avoirdupois*, since other measures stand to these in known relations. The yard, consisting of 36 inches, ma regarded as the primary unit. Though it is essentially an arbi standard, it is determined by this—that the simple pendulum w makes one oscillation in a second, at London on the sea l is 39·1375 inches long (61). The gallon contains 277·274 c

inches. A gallon of distilled water at the standard temperature weighs 10 lbs. avoirdupois or 70,000 grains troy; or, which comes to the same thing, one cubic inch of water weighs 252·5 grains.

On the French system the *metre* is the primary unit, and is so chosen that 10,000,000 metres are the length of a quadrant of the meridian from either pole to the equator. The metre contains 10 decimetres, or 100 centimetres, or 1,000 millimetres, its length equals 1·0936 yard. The unit of the measure of capacity is the *litre* or cubic decimetre. The unit of weight is the *gramme*, which is the weight of a cubic centimetre of distilled water at 4° C. The kilogramme contains 1,000 grammes, or is the weight of a decimetre of distilled water at 4° C. The gramme equals 15·443 grains.

Suppose it is required to calculate the weight of a cubic foot of coal. A cubic foot contains 1,728 cubic inches; the weight of a cubic foot of water would therefore be 1,728 times 252·5 grains, this being the weight of one cubic inch of water. The product of this multiplication divided by 7,000 grains (the number contained in a pound avoirdupois) gives 62·3 pounds as the weight of a cubic foot of water; and as we learn, from the tables, that coal is 1·32 times as heavy as water, the weight of a cubic foot of coal will be 1·32 times 62·3 or 83·16 pounds.

105. **Hydrometers with variable volume.**—The hydrometers of Nicholson and Fahrenheit are called *hydrometers of constant volume, but variable weight*, because they are always immersed to the same extent, but carry different weights. There are also *hydrometers of variable volume but of constant weight.* These instruments known under the different names of *acidometer, alcoholometer, lactometer*, and *saccharometer*, are not used to determine the specific gravity of the liquids, but to show whether the acids, alcohols, solutions of sugar, etc., are more or less concentrated.

106. **Beaumé's hydrometer.**—This, which was the first of these instruments, may serve as a type of them. It consists of a glass tube, AB (fig. 84), loaded at its lower end with mercury, and with a bulb blown in the middle. The stem, the external diameter of which is as regular as possible, is hollow, and the scale is marked upon it.

The graduation of the instrument differs according as the liquid, for which it is to be used, is heavier or lighter than water. In the first case it is so constructed, that it sinks in water nearly to the

top of the stem, to a point A, which is marked zero. A solution c fifteen parts of salt in eighty-five parts of water is made, and th instrument immersed in it. It sinks to certain point on the stem, B, which i marked 15; the distance between A and B is divided into 15 equal parts, and th graduation continued to the bottom of th stem. Sometimes the graduation is on piece of paper in the interior of the stem.

Fig. 84.

The hydrometer thus graduated only serve for liquids of a greater specific gravity tha water, such as acids and saline solution For liquids lighter than water a differen plan must be adopted. Beaumé took fo zero the point to which the apparatus sank in a solution of 10 parts of salt in 90 o water, and for 10° he took the level i distilled water. This distance he divide into 10°, and continued the division to the top of the scale.

The graduation of these hydrometers is entirely arbitrary, an they give neither the densities of the liquids, nor the quantitie dissolved. But they are very useful in making mixtures or solu tions in given proportions; the results they give being sufficiently near in the majority of cases. For instance, it is found that a well-made syrup marks 35° on Beaumé's hydrometer, from which a manufacturer can readily judge whether a syrup which is being evaporated has reached the proper degree of concentration.

107. **Gay-Lussac's alcoholometer.**—The spirits of wine and brandy, in daily use, are a mixture of pure alcohol and water. The more alcohol they contain the stronger they are; the more water they contain so much the weaker are they. Hence it is important to have a simple means of exactly determining the quantity of water contained in spirituous liquors. This is effected by means of Gay-Lussac's *alcoholometer*, which has the same shape as Beaumé's and only differs in the graduation. This is effected as follows :—

Mixtures of absolute alcohol and distilled water are made, containing 5, 10, 20, 30, etc., per cent. of the former. The alcoholometer is so constructed that when placed in pure distilled water the bottom of its stem is level with the water, and this point is zero. It is next placed in absolute alcohol, which marks 100°, and then successively in mixtures of different strengths, containing 10, 20

30, etc., per cent. Ths divisions thus obtained are not exactly equal, but their difference is not great, and they are subdivided into ten divisions, each of which marks *one* per cent. of absolute alcohol in a liquid. Thus a brandy in which the alcoholometer stood at 48, would contain 48 per cent. of absolute alcohol, and the rest would be water.



Fig. 85.

All these determinations are made at 15° C., and for that temperature only are the indications correct. For, other things being the same, if the temperature rises the liquid expands, and the alcoholometer will sink, and the contrary, if the temperature falls. To obviate this error Gay-Lussac constructed a table which for each percentage of alcohol gives the reading of the instrument for each degree of temperature from 0° up to 30°. When the exact analysis of an alcoholic mixture is to be made, the temperature of the liquid is first determined, and then the point to which the alcoholometer sinks in it. The number in the table corresponding to these data indicates the percentage of alcohol. From its giving the percentage of alcohol, this is often called the *centesimal alcoholometer*.

108. **Lactometer.** — The lactometer is a hydrometer like Beaumé's, specially graduated for the purpose of ascertaining the quality of milk (fig. 86). This is accomplished in the following manner:—The instrument is immersed in a vessel containing pure milk, and the point to which it sinks is marked zero on a paper strip affixed to the stem. Mixtures are then made of $\frac{9}{10}$ of milk and $\frac{1}{10}$ of water; of $\frac{8}{10}$ and $\frac{2}{10}$, and so on to $\frac{1}{10}$ of milk and $\frac{5}{10}$ of water. The lactometer is successively immersed in these, and sinks to different depths; the point at which it stops in each case is marked by a number on the stem, and thus indicates a milk of a particular strength, that is, one containing a certain quantity of admixed water.



Fig. 86.

The lactometer is, however, no infallible test for the adulteration of milk; for the density of natural milk is subject to variation, and an apparent fraud may really be due to a bad natural quality of milk.

BOOK III.

ON GASES.

CHAPTER I.

PROPERTIES OF GASES. ATMOSPHERE. BAROMETERS.

109. **Physical properties of gases.**—Gases, as we have alrea seen, are bodies whose molecules are in a constant state of rep sion in virtue of which they possess the most perfect mobility, a are continually tending to occupy a greater space. This prope of gases is known by the names *expansibility*, *tension*, or *elas force*, from which they are often called *elastic fluids*.

The number of gases with which chemistry makes us acquaint is very considerable; but only four are elementary; these are oxyg hydrogen, nitrogen, and chlorine. Some gases are coloured, l most of them are colourless. Some have a disagreeable odo others are quite inodorous. Some are noxious, acting as pois to men and animals which breathe them; such are carbonic oxi which is produced by the combustion of charcoal; sulphuret hydrogen, which is given off from drains. Others are inoffensi such as nitrogen and hydrogen; yet an animal cannot live in the They are not deleterious, in the sense of being poisonous; but th do not support life. The only gas which has this property is o gen; an animal deprived of this gas, even for a few seconds, soon di

Gases and liquids have several properties in common, and so in which they seem to differ are in reality only different degr of the same property. Thus, in both, the particles are capable moving; in gases quite freely; in liquids not quite freely, ow to a certain degree of viscosity. Both are compressible, thou in very different degrees; if a liquid and a gas both exist un a pressure of one atmosphere, and then the pressure be doubl the water is compressed by about the $\frac{1}{20000}$th part (75), while gas is compressed by one-half. In density there is a great differenc water, which is the type of liquids, is about 770 times as heavy

air, the type of gaseous bodies, while under a pressure of one atmosphere. The property by which gases are distinguished from liquids is their tendency to indefinite expansion.

Matter assumes the solid, liquid, or gaseous form according to the relative strength of the cohesive and repulsive forces exerted between their particles. In liquids these forces balance; in gases repulsion preponderates.

By the aid of pressure and of very low temperatures, the force of cohesion may be so far increased in many gases that they are converted into liquids; and there is reason for believing that, with a sufficient degree of pressure and cold, they might all be liquefied. On the other hand, heat, which increases the force of repulsion, converts liquids, such as water, alcohol, and ether, into the aëriform state in which they obey all the laws of gases. This aëriform state of liquids is known by the name of *vapour*, while gases are bodies which under ordinary temperature and pressure, remain in the aëriform state.

In describing the properties of gases we shall for obvious reasons, have exclusive reference to atmospheric air as their type.

110. **Atmospheric air.**—Air is the gaseous fluid in which we live. It was regarded by the ancients as one of the four elements. Modern chemistry, however, has shown that it is a mixture of oxygen and nitrogen gases in the proportion of 20·8 volumes of the former to 79·2 volumes of the latter. By weight it consists of 23 parts of oxygen to 77 parts of nitrogen.

The oxygen feeds all the combustions, which are produced round about us; and it also supports animal life. If it alone were present, or even if it were present in a larger proportion, the combustions would be too brisk, and life too active. The coal of our fireplaces would burn almost instantaneously, and even the grates in which it is contained would take fire. Life would be promptly destroyed by so active an agent. The function of the nitrogen is to attenuate the too powerful effects of the oxygen.

Air is inodorous, transparent, and colourless, at any rate in small masses. In larger masses it is blue; thus arises the blue colour of the sky. Without air the celestial vault would appear black; it appears almost so when viewed from the tops of very high mountains, and from balloons; for then the air above is very highly rarefied.

Air too, in virtue of its elasticity, is the medium for transmitting sounds; so that, if we were without it, the use of speech and of music would be lost.

111. **Expansibility of gases.**—This property of gases, the tendency to assume continually a greater volume, is exhibited by means of the following experiment. A bladder closed by a stop-cock, moistened so as to render it more flexible, and about half full of air, is placed under the receiver of the air-pump (fig. 87), and a partial vacuum is produced, on which the bladder immediately distends. This arises from the fact that the molecules of air repel each other, and press against the sides of the bladder. Under ordinary conditions this internal pressure is counterbalanced by the air in the receiver, which exerts an equal and contrary pressure. But when this pressure is removed by exhausting the receiver, the internal pressure becomes evident. When air is again admitted into the receiver the bladder resumes its original form.

Fig. 87.

The same effects would be produced whatever gases were contained in the bladder, thus showing that all are expansible.

112. **Weight of gases.**—From their extreme fluidity and expansibility, gases seem to be uninfluenced by the force of gravity; they nevertheless possess weight, like solids and liquids. To show this, a glass globe of 3 or 4 quarts capacity is taken (fig. 88), the neck of which is provided with a stop-cock, which hermetically closes it, and by which it can be screwed to the plate of the air-pump. The globe is then completely exhausted, and its weight determined by means of a delicate balance. Air is now allowed to enter, and the globe again weighed. The weight in the second case will be found to be greater than before, and if the capacity of the vessel is known, the increase will obviously be the weight of that volume of air.

Fig. 88.

By a modification of this method, and with the adoption of certain precautions, the weight of air and of other gases has been determined: 100 cubic inches of dry air under the ordinary atmospheric pressure of 30 in. and at the temperature of 16° C., weigh 31 grains; the same volume of carbonic acid gas under the same circumstances weigh

47·25 grains; 100 cubic inches of hydrogen, the lightest of all gases, weigh 2·14 grains; and 100 cubic inches of hydriodic acid gas weigh 146 grains.

The ratio of the destiny of air at 0° C. and 30 inches pressure to that of water at 0° C. is found to be 0·001296. In other words, the latter is about 770 times as heavy as the former.

113. **The atmosphere. Experiments proving its weight.**—The *atmosphere* is the name given to the layer of air which, like a light coating, surrounds our globe in every part. It shares the rotatory motion of the globe, and would remain fixed relatively to terrestrial objects, but for local circumstances, which produce winds, and are constantly disturbing its equilibrium.

The existence of this gaseous mass is proved by the winds, which incessantly blow on the surface of the earth; by the flight of birds, and the suspension of clouds.

Besides the oxygen and nitrogen of which the air is composed, it also contains a quantity of aqueous vapour, which varies with the temperature, the season, the locality, and the direction of the winds. The mean amount of this in London is from 5 to 6 grains in a cubic foot of air.

It further contains from 3 to 6 parts in 10,000 of carbonic acid. This arises from the respiration of man and animals, from the decay of organic matter, and from the combustion of wood and coal. This latter cause of the production of carbonic acid increases every year. It has been calculated that in Europe alone about 104 milliards of cubic yards of carbonic acid are every year sent into the atmosphere from this source. This mass of gas is equal to what would be produced by 509 millions of individuals, each by the act of respiration converting 154 grains of carbon in the system into carbonic acid every hour.

Notwithstanding this enormous continual production of carbonic acid on the surface of the globe, the composition of the atmosphere does not vary; for plants in the process of vegetation decompose the carbonic acid, assimilating the carbon, and restoring to the atmosphere the oxygen which is being continually consumed in the processes of respiration and combustion.

Thus, by a natural harmony, the atmosphere retains an almost uniform quantity of this gas, so that there is no fear of its accumulating to such an extent as to be injurious to the human species.

114. **Atmospheric pressure.**—Having seen that air has weight, it is easy to conceive that the great mass of air which constitutes

the atmosphere must exert a great pressure on the surface o earth, and on all bodies found there. This pressure is c the *atmospheric pressure.* It necessarily decreases as we asce the atmosphere; for if we conceive the atmosphere resolved horizontal layers superposed on each other, it is clear tha lower layers which support the weight of the whole atmospher the most compressed, and the most dense; while the higher l are less and less compressed, and therefore less and less d This is expressed by saying that they are more *rarefied* or *rare.* In saying that 100 cubic inches of air weighed 31 grai was understood that air at the sea level was referred to; at greater height this volume of air would weigh less.

The pressure of the atmosphere may be demonstrated number of experiments, among which are the following:

115. **Crushing force of the atmosphere.**—On one end stout glass cylinder, about 5 inches high, and open at both en

Fig. 89.

Fig. 90.

piece of bladder is tied quite air-tight. The other end, the ed which is ground and well greased, is pressed on the plate of th pump (fig. 89). The bladder is pressed downwards by the w of the atmosphere, and is pressed upwards by the expansive for the air in the cylinder. These two pressures at first counterbal each other; the bladder is not pressed in either direction, b soon as the internal air is removed from the vessel, by wo the air-pump, the bladder is depressed by the weight of the a

sphere above it, and finally bursts with a loud report caused by the sudden entrance of the air.

116. **Magdeburg hemispheres.**—The preceding experiment only serves to illustrate the downward pressure of the atmosphere. By means of the *Magdeburg hemispheres* (fig. 90), the invention of which is due to Otto von Guericke, burgomaster of Magdeburg, it can be shown that the pressure acts in all directions. This apparatus consists of two hollow brass hemispheres of 4 to 4½ inches

Fig. 91.

diameter, the edges of which are made to fit tightly, and are well greased. One of the hemispheres is provided with a stopcock, by which it can be screwed on the air-pump, and on the other there is a handle. As long as the hemispheres contain air they can be separated without any difficulty, for the external pressure of the atmosphere is counterbalanced by the elastic force of the air in the interior. But when the air in the interior is pumped out by means of the air-pump, the hemispheres cannot be separated without a powerful effort, fig. 91; and as this is the case in whatever position they are held, it follows that the atmospheric pressure is transmitted in all directions.

We shall presently see (119) that the pressure of the atmosphere

on a square inch is about 15 lbs. Hence if in the above experiment, the area, not of each of the hemispheres, but of the circle along which they are pressed, is 10 square inches, the force by which they are pressed together is 150 lbs. and this force would be required to separate them.

It is related that Otto von Guericke, the inventor of this apparatus, constructed hemispheres the internal diameter of which was about 2 feet; when applied against each other and exhausted, twelve horses, six pulling at each hemisphere, were required to separate them.

DETERMINATION OF THE ATMOSPHERIC PRESSURE. BAROMETERS.



Fig. 92.

117. **Torricelli's experiment.**—The above experiments demonstrate the existence of the atmospheric pressure, but they give no indications as to its amount. The following experiment, which was first made in 1643 by Torricelli, a pupil of Galileo, not merely proves the pressure of the atmosphere, but also gives an exact measure of its weight.

A glass tube is taken, about a yard long, and a quarter of an inch internal diameter (fig. 92). It is sealed at one end, and is quite filled with mercury. The aperture C being closed by the thumb, the tube is inverted, the open end placed in a small mercury trough, and the thumb removed. The tube being in a vertical position, the column of mercury sinks, and after oscillating some time, it finally comes to rest at a height A, which at the level of the sea is about thirty inches above the mercury in the trough. The mercury is raised in the tube by the pressure of

the atmosphere on the mercury in the trough. There is no contrary pressure on the mercury in the tube, because it is closed. But if the end of the tube be opened, the atmosphere will press equally inside and outside the tube, and the mercury will sink to the level of that in the trough. It has been shown in hydrostatics (88) that the heights of two columns of liquid in communication with each other are inversely as their densities ; and hence it follows, that the pressure of the atmosphere is equal to that of a column of mercury, the height of which is thirty inches. That the mercury sank in the first case was due to its weight being greater than the pressure of the atmosphere. If, however, the weight of the atmosphere diminishes, the height of the column which it can sustain must also diminish.

118. **Pascal's experiments.**—Pascal, who wished to prove that the force which sustained the mercury in the tube was really the pressure of the atmosphere, made the following experiments :—i. If it were the case, the column of mercury ought to descend in proportion as we ascend in the atmosphere (114). He accordingly requested one of his relations to repeat Torricelli's experiment on the summit of the Puy de Dôme in Auvergne. This was done, and it was found that the mercurial column was about three inches lower, thus proving that it is really the weight of the atmosphere which supports the mercury, since, when this weight diminishes, the height of the column also diminishes. ii. Pascal repeated Torricelli's experiment at Rouen, in 1646, with other liquids. He took a tube closed at one end, nearly 40 feet long, and having filled it with water, placed it vertically in a vessel of water, and found that the water stood in the tube at a height of 34 feet ; that is, 13·6 times as high as mercury. But since mercury is 13·6 times as heavy as water, the weight of the column of water was exactly equal to that of the column of mercury in Torricelli's experiment, and it was consequently the same force, the pressure of the atmosphere, which successively supported the two liquids. Pascal's other experiments with oil and with wine gave similar results. He found, for instance that a column of oil stood at a height of about 37 feet.

119. **Amount of the atmospheric pressure.**—Let us assume that the tube in the above experiment is a cylinder, the cross-section of which is equal to a square inch, then, since the height of the mercurial column in round numbers is 30 inches, the column will contain 30 cubic inches, and as a cubic inch of mercury weighs 3433·5 grains = 0·49 of a pound, the pressure of such a column on a

square inch of surface is equal to 14·7 pounds. In round numbers the pressure of the atmosphere is taken at 15 pounds on the square inch. A surface of a foot square contains 144 square inches, and therefore the pressure upon it is equal to 2,160 pounds, or nearly a ton.

Fig. 93.

A gas or a liquid which acts in such a manner that a square inch of surface is exposed to a pressure, 15 pounds, is said to exert a pressure of *one atmosphere*. If, for instance, the elastic force of the steam of a boiler is so great that each square inch of the internal surface is exposed to a pressure of 90 pounds ($=6\times15$), we say it was under a pressure of six atmospheres.

120. **Different kinds of barometers.** — The instruments used for measuring the atmospheric pressure are called *barometers*, from two Greek words which signify *measure of weight* (air, of course being understood). In ordinary barometers, the pressure is measured by the height of a column of mercury, as in Torricelli's experiment the barometers which we are about to describe are of this kind. But there are barometers without *mercury*, one of which, the aneroid (135) is remarkable for its simplicity and portability.

121. **Cistern barometer.**—Ordinary barometers are classed as *syphon* and *cistern* barometers. Fig. 93 represents the usual form of the cistern barometer. It consists of a glass tube *ai*, closed at one end, about thirty-three inches long and about half an inch in diameter. The tube is filled with mercury, and then its open end is inverted

n mercury contained in a glass vessel, A, of a peculiar shape ; nly the front half of this is visible, the other being fixed in a nahogany board which supports the whole barometer. The bottom f the cistern forms a spherical well, which is filled with mercury, nd in which the tube *ai* is immersed. The tube is not fixed tightly n the neck, so that the atmospheric pressure can be freely transmitted to the mercury of the bath, and thus supports the column of mercury *ai*. If the pressure increases the mercury rises, if it decreases the mercury sinks.

At the top of the tube on the right is a scale divided in inches to measure the height of the mercury in the tube. The graduation starts from the zero which is level with the mercury in the bath. Hence, if the top of the mercury at *a* stands at thirty inches, for instance, this signifies that the height of the column of mercury is thirty inches. Only a portion of the scale is given, since, for ordinary purposes, the variations of the atmospheric pressure are within a few inches. Where greater variations occur, as in the use of the barometer for measuring heights, the graduated part must be longer.

It will be observed that the starting-point of the graduation, the zero, is at the level of the mercury in the cistern. But the zero of the scale does not always correspond to the level of the mercury in the cistern. For as the atmospheric pressure is not always the same, the height of the mercurial column varies ; sometimes mercury is forced from the cistern into the tube, and sometimes from the tube into the cistern, so that, in the majority of cases, the graduation of the barometer does not indicate the true height. To diminish this source of error, the cistern has the form represented in fig. 93. Its upper part, that corresponding to the level of the mercury, is about four inches in diameter ; so that, whether the mercury passes from the cistern into the tube, or from the tube into the cistern, as it is spread over a large surface the variations in the level are very small and may be neglected.

To complete this description it may be added, that on the scale is a small index, *c*, sliding along a vertical rod. When made level with the mercury this index points on the one side to the divisions on the graduated scale, and, on the other side, to certain inscriptions, the use of which will be afterwards stated (127). Lastly, in the middle of the tube are two thermometers, one with a Fahrenheit and the other with a Centigrade graduation.

122. **Fortin's barometer.**—*Fortin's barometer* (fig. 94) differs

from that just described, in the shape of the cistern. The of the cistern is made of leather, and can be raised or lo by means of a screw; this has the advantage, that a co level can be obtained, and also that the instrument is made portable. For, in travelling, it is only necessary to raise the leather until the mercury, which rises with it, quite fills the cistern; the barometer may then be inclined, and even inverted, without any fear that a bubble of air may enter, or that the shock of the mercury may crack the tube.

Fig. 94.

Fig. 95 shows the construction of the cistern. It consists of a glass cylinder, *b*, which allows the mercury to be seen; the bottom of the cylinder is cemented to a box-wood cylinder, *zz*, on which is firmly fixed at *ii* the chamois leather, *mn*, which is the base of the cistern. At the bottom of this leather is a small wooden button, *x*, against which the screw C works, by which it is raised or lowered. This screw works in the bottom of a brass cylinder, G, which is fastened on the glass cylinder. At the top of the cistern there is a small ivory pointer, *a*, the point of which exactly corresponds to the zero on the scale. The upper part of the cistern is closed by buckskin, *ce*, which is fastened to the bar tube, E, and to a tubulure in the wooden disc, covers the cistern. The barometer tube is dra at the open end, which is immersed in the mercury. The spheric pressure is transmitted through the pores of the l In using this barometer, the mercury is first made leve the point *a*, which is effected by turning the screw C ei one direction or the other. In this manner the distance top, B, of the column of mercury from the ivory point *a*

Fig. 95

the height of the barometer. For the graduation is
l from the point *a*. Lastly, the lower part of the cistern
ed in a brass case, which is connected with the lid by
ews *k*, *k*, *k*. To the cistern is screwed a long brass case,
closes the whole of the tube, as seen in figure. At the top
case there are two longitudinal slits, on opposite sides,
the level of the mercury, B, is seen. The scale on the
graduated in millimetres or in inches. An index, A,
y the hand, gives, by
f a vernier, the height
ercury to $\frac{1}{10}$ of a milli-
At the bottom of the
ffixed a thermometer to
the temperature.

Gay-Lussac's syphon
er.—The syphon baro-
s no cistern, but con-
a bent glass tube (fig.
f the branches of which
longer than the other.
ger branch, which is
the top, is filled with
as in the cistern baro-
bile the shorter branch,
s open, serves as a
The difference between
levels is the height of
neter.



Fig. 96. Fig. 97. Fig. 98.

6 represents the syphon
r as modified by Gay-
In order to render it
ilable for travelling, by
ig the entrance of air,
the two branches by a
tube; when the instrument is inverted (fig. 97), the tube
mains full in virtue of its capillarity, and air cannot pene-
the longer branch, which, of course, is absolutely necessary.
shock, however, might separate the mercury and admit
To avoid this M. Bunten has introduced an ingenious
ion into the apparatus. The longer branch, A, is drawn
fine point, and is joined to a tube, B, of the form repre-

sented in fig. 98. By this arrangement, if air passes through the capillary tube, it cannot penetrate the drawn-out extremity of the longer branch, but lodges in the upper part of the enlargement B. In this position it does not affect the observations, since the vacuum is always at the upper part of the tube; it is, moreover, easily removed.



Fig. 99.

In Gay-Lussac's barometer the shorter branch is closed, but there is a lateral capillary aperture *i*, through which the atmospheric pressure is transmitted.

The barometric height is determined by means of two scales, which have a common zero at the middle of the longer branch, and are graduated in contrary directions, the one from the middle to *a*, and the other from the middle to *b*, either on the tube itself, or on brass rules fixed parallel to the tube. Two sliding indexes are moved until they correspond to the level of the mercury in *a* and *b*. The total height of the barometer *ab* is the sum of the distances from the middle to *a* and *b* respectively.

124. **Precautions in reference to barometers.**—In constructing barometers, mercury is chosen in preference to any other liquid. For being the densest of all liquids it stands at the least height. When the mercurial barometer stands at thirty inches, the water barometer would stand at about thirty-four feet. It also deserves preference because it does not moisten the glass. It is necessary that the mercury be pure and free from oxide; otherwise it adheres to the glass and tarnishes it. Moreover, if it is impure its density is changed, and the height of the barometer is too great or too small. Mercury is purified, before being used for barometers, by treatment with dilute nitric acid, and by distillation.

The space at the top of the tube (figs. 96 and 99), which is called the *Torricellian vacuum*, must be quite free from air and from

aqueous vapour, for otherwise either would depress the mercurial column. Now, glass tubes always condense aqueous vapour on their surface. Under the ordinary pressure of the atmosphere this layer of moisture adheres to the glass; but in a vacuum where there is no pressure it escapes, and there is formed a mixture of air and aqueous vapour which depresses the mercurial column.

The air and moisture can only be got rid of by boiling the mercury in the tube. To obtain this result, a small quantity of pure mercury is placed in the tube and boiled for some time, fig. 100.



Fig. 100.

It is then allowed to cool, and a further quantity, previously warmed added, which is boiled, and so on, until the tube is quite full; in this manner the moisture and the air which adhere to the sides of the tube pass off with the mercurial vapour. The bulb at the end is placed there to collect the mercury which may distil over. It is afterwards removed.

A barometer is free from air and moisture if, when it is inclined, the mercury strikes with a sharp metallic sound against the top of the tube. If there is air or moisture in it, the sound is deadened.

125. **Variations in the height of the barometer.**—When the barometer is observed for several days, its height is found to vary in the same place, not only from one day to another, but also during the same day.

The extent of these variations, that is, the difference between the greatest and the least height, is different in different places. It increases from the equator towards the poles. The greatest variations are observed in winter.

The *mean daily height* is the height obtained by dividing the sum of 24 successive hourly observations by 24. In our latitudes, the barometric height at noon corresponds to the mean daily height.

The *mean monthly height* is obtained by adding together the mean daily heights for a month, and dividing by 30.

The *mean yearly height* is similarly obtained.

Under the equator, the mean annual height at the level of the sea is $0^m{\cdot}758$, or 29·14 inches. It increases from the equator, and between the latitudes 30° and 40°, it attains a maximum of $0^m{\cdot}763$, or 30·04 inches. In lower latitudes it decreases, and in Paris it does not exceed $0^m{\cdot}7568$.

The general mean at the level of the sea is $0^m{\cdot}761$ or 29·96 inches.

The mean monthly height is greater in winter than in summer, in consequence of the cooler atmosphere.

Two kinds of variations are observed in the barometer: 1st, the *accidental variations*, which present no regularity; they depend on the seasons, the direction of the winds, and the geographical position, and are common in our climates: 2nd, the *daily variations*, which are produced periodically at certain hours of the day.

At the equator, and between the tropics, no accidental variations are observed; but the daily variations take place with such regularity that a barometer may serve to a certain extent as a clock. The barometer sinks from midday till towards four o'clock; it then rises, and reaches its maximum at about ten o'clock in the evening. It then again sinks, and reaches a second minimum towards four o'clock in the morning, and a second maximum at ten o'clock.

In the temperate zones there are also daily variations, but they are detected with difficulty, since they occur in conjunction with accidental variations.

The hours of the maxima and minima appear to be the same in all climates, whatever be the latitude; they merely vary a little with the seasons.

126. **Causes of barometric variations.**—It is observed that the course of the barometer is generally in the opposite direction to that of the thermometer; that is that when the temperature rises the barometer falls, and *vice versâ*; which indicates that the barometric variations at any given place are produced by the expansion or contraction of the air, and therefore by its change in density. If the temperature were the same throughout the whole extent of the atmosphere, no currents would be produced, and at

the same height, the atmospheric pressure would be everywhere the same. But when any portion of the atmosphere becomes warmer than the neighbouring parts, its specific gravity is diminished, and it rises and passes away through the upper regions of the atmosphere; whence it follows that the pressure is diminished, and the barometer falls. If any portion of the atmosphere retains its temperature, while the neighbouring parts become cooler, the same effect is produced; for in this case, too, the density of the first-mentioned portion is less than that of the others. Hence, also, it usually happens, that an extraordinary fall of the barometer at one place is counterbalanced by an extraordinary rise at another place. The daily variations appear to result from the expansions and contractions which are periodically produced in the atmosphere by the heat of the sun during the rotation of the earth.

127. **Relation of barometric variations to the state of the weather.**—It has been observed that, in our climate, the barometer in fine weather is generally above 30 inches, and is below this point when there is rain, snow, wind, or storm, and also, that for any given number of days on which the barometer stands at 30 inches, there are as many fine as rainy days. From this coincidence between the height of the barometer and the state of the weather, the following indications have been marked on the barometer, counting by thirds of an inch above and below 30 inches:

Height	State of the weather
31 inches	Very dry.
30⅔ „	Settled weather.
30⅓ „	Fine weather.
30 „	Variable.
29⅔ „	Rain or wind.
29⅓ „	Much rain.
29 „	Tempest.

In using the barometer as an indicator of the state of the weather, we must not forget that it really only serves to measure the weight of the atmosphere and that it only rises or falls as this weight increases or diminishes; and although a change of weather frequently coincides with a change in the pressure, they are not necessarily connected. This coincidence arises from meteorological conditions peculiar to our climate, and does not always occur. That a fall in the barometer usually precedes rain in our latitudes, is caused by the position of Europe. The south-west winds, which

are hot, and consequently light, make the barometer sink; but the same time as they become charged with aqueous vapour crossing the ocean, they bring us rain. The winds of the nor and north-east, on the contrary, being colder and denser, make t



Fig. 101. Fig. 102.

barometer rise ; and, as they only reach us after having passed ov vast continents, they are generally dry.

When the barometer rises or sinks slowly, that is, for two

ee days, towards fine weather or towards rain, it has been found, m a great number of observations, that the indications are then remely probable. Sudden variations in either direction indicate d weather or wind.

128. **Wheel barometer.**—The *wheel barometer*, which was inted by Hooke, is a syphon barometer, and is especially intended indicate good and bad weather (fig. 101). In the shorter leg of e syphon there is a float *a*, which rises and falls with the mercury g. 102). A string attached to this float passes round a pulley, d at the other end there is another and somewhat lighter weight. needle fixed to the pulley moves round a graduated circle, on ich is marked *variable*, *rain*, *fine weather*, etc. When the essure varies the float sinks or rises, and moves the needle round the corresponding points on the scale.

The barometers ordinarily met with in houses, and which are lled *weather glasses*, are of this kind. They are, however, of le use, for two reasons. The first is, that they are neither very licate nor precise in their indications. The second, which applies ually to all barometers, is, that those commonly in use in this untry are made in London, and the indications, if they are of any lue, are only so for a place at the same level and of the same matic conditions as London. Thus a barometer standing at a rtain height in London would indicate a certain state of weather, t if removed to Shooter's Hill it would stand half an inch lower, d would indicate a different state of weather. As the pressure fers with the level and with geographical conditions, it is necesry to take these into account if exact data are wanted.

129. **Determination of the heights of places by the barometer.**—One of the most important of the uses of the barometer s been its application to the measurement of the heights of aces above the sea level. For, if we suppose the atmosphere vided into horizontal layers of equal thickness, a hundred for stance, a barometer at the sea level would support the weight of hundred of these layers ; and, as we have seen (117), would be at st when its height was thirty inches. If it were raised in the atmohere to the height of ten such layers, it would now only support e weight of ninety such layers, and the mercury would therefore cessarily sink. It would sink still further if it were raised to the entieth layer, and so on to the limit of the atmosphere if that re possible. There it would be under no pressure, and the level the mercury in the tube and in the cistern would be the same.

As the mercury sinks in proportion as we rise in the atmosphere, we might, from the amount by which it is lower, deduce the height above the sea level. If air had everywhere the same density up to the extreme limit of the atmosphere, the calculation would be very simple; for as mercury is about 10,500 times as heavy as air, an inch of the barometer would correspond to a column of air about 875 feet; hence, in ascending a mountain, a diminution of an inch in the height of the barometer would correspond to an ascent of about 875 feet. But the density of the air decreases as we ascend, for the layers of air necessarily support a less weight; hence, the measurement of the heights by the barometer is not so simple as we have supposed. Very complete tables have, however, been constructed, by which the difference in height between any two places may be readily ascertained, if we know the corresponding heights of the barometer. For small elevations we may assume that an ascent of 900 feet produces a depression of an inch in the height of the barometer. For measuring heights by the barometer the aneroid (135) is extremely convenient.

130. **Height of the atmosphere.**—In virtue of the expansive force of the air, it might be supposed that the molecules would expand indefinitely into the planetary spaces. But, in proportion as the air expands, its expansive force decreases, and is further weakened by the low temperature of the upper regions of the atmosphere, so that, at a certain height, an equilibrium is established between the expansive force which separates the molecules, and the action of gravity which draws them towards the centre of the earth. It is therefore concluded that the atmosphere is limited.

From the weight of the atmosphere, and its decrease in density, and from the observation of certain phenomena of twilight, its height has been estimated at from 30 to 40 miles. Above that height the air is extremely rarefied, and at a height of 60 miles it is assumed that there is a perfect vacuum. From certain observations recently made in the tropical zone, and particularly at Rio Janeiro, on the twilight arc, M. Liais estimates the height of the atmosphere at between 198 and 212 miles, considerably higher, therefore, than what has hitherto been believed.

ILLUSTRATIONS OF ATMOSPHERIC PRESSURE.

131. **The pressure of the atmosphere is transmitted in all directions.**—The atmosphere, like any other mass of fluid (76),

must necessarily transmit its pressure in all directions, upwards and laterally as well as downwards. We have already seen a striking instance of this in the Magdeburg hemispheres (116), and the following experiment furnishes another illustration of this point.

A tumbler full of water is carefully covered with a sheet of paper, which is kept in position by one hand, while with the other the tumbler is inverted. Removing then the hand which held the paper, the water does not fall out, both water and paper being kept in position by the upward pressure (fig. 103). The object of the paper is to present a flat surface of water, for otherwise the water would divide and would allow air to enter, and then the experiment would fail.

The use of the *wine-tester* also depends on the pressure of the

Fig. 103.



Fig. 104.

atmosphere. It consists of a tin tube (fig. 104), terminating at the bottom in a small cone, the end of which, *o*, is open; at the top there is a small aperture, which is closed by the thumb. The two ends being open, the tube is immersed in the liquid to be tested; closing then the upper end by the thumb, as shown in the figure, the tube is withdrawn, and remains filled in consequence of the pressure at *o*. But if the thumb be withdrawn the pressure is transmitted both upwards and downwards, and the liquid flows out in obedience to the action of gravity.

132. **Pressure supported by the human body.**—The surface of the body of a man of middle size is about 16 square feet; the pressure, therefore, which a man supports on the surface of his body is 37,560 pounds, or upwards of 16 tons. Such an enormous pressure might seem impossible to be borne; but it must be remembered that in all directions there are equal and contrary pressures which counterbalance one another. It might also be supposed

that the effect of this force, acting in all directions, press the body together and crush it. But the solid skeleton could resist a far greater pressure ; and as to contained in the organs and vessels, from what has been liquids (75), it is clear that they are virtually incompres

Fig. 105.

gases, too, are compressed by of the atmosphere, but they virtue of their elasticity. T short, like a bottle full of air. of the latter are pressed in by of the atmosphere ; but they ca however thin their walls, for of the gas from within qu balances that which presses side.

The following experimen illustrates the effect of pressure on the human body vessel open at both ends, b on the plate of the air-pump end of the cylinder is closed and a vacuum is made. The hand then becomes pre weight of the atmosphere, and can only be taken awa effort. And as the elasticity of the gas contained in t not counterbalanced by the weight of the atmosphere, the hand swells, and blood tends to escape from the po

The operation of *cupping* in medicine is an applic effect of removing the atmospheric pressure from the h The human mouth applied upon any part, in the actior is a kind of cupping apparatus. The mouth of the leec apparatus with one lancet.

CHAPTER II.

MEASUREMENT OF THE ELASTIC FORCE OF GA

153. **Boyle's law.**—The law of the compressibility o discovered by Boyle, and subsequently, though indepe Mariotte. In consequence it is in England comm Boyle's law, and on the Continent Mariotte's law. It is

temperature remaining the same, the volume of a given ity of gas is inversely as the pressure which it bears.

ıis law is verified by means of an apparatus called *Mariotte's* fig. 106). It consists of a long glass tube fixed to a vertical



Fig. 106.

Fig. 107.

ort: it is open at the top; and the other end, which is bent ı short vertical leg, is closed. On the shorter leg there is a which indicates equal capacities; the scale against the long ves the heights. The zero in both scales is in the same hori- l line.

small quantity ot mercury is poured into the tube, so that its in both branches is at zero, which is effected without much

difficulty. The air in the short leg is thus under the ordinary atmospheric pressure. If mercury is then poured into the longer tube the volume of the air in the smaller tube is gradually reduced. If this be continued until it is only one-half, that is, until it is reduced from 10 to 5, as shown in figure 107, and if the height of the mercurial column, CA, be now measured, it will be found exactly equal to the height of the barometer at the time of the experiment. The pressure of the column CA is therefore equal to an atmosphere, which, with the atmospheric pressure acting on the surface of the column at C, makes two atmospheres. Accordingly, by doubling the pressure, the volume of the gas has been diminished to one-half.



Fig. 108.

Fig. 109.

If mercury be poured into the longer branch until the volume of the air is reduced to one-third its original volume, it will be found that the distance between the level of the two tubes is equal to two barometric columns. The pressure is now three atmospheres, while the volume is reduced to one-third. Dulong and Petit have verified the law for air up to 27 atmospheres, by means of an apparatus analogous to that which has been described.

The law also holds good in the case of pressures of less than one atmosphere. To demonstrate this, mercury is poured into a graduated tube, until it is about two-thirds full, the rest being air. It is then inverted in a deep trough containing mercury (fig. 108), and lowered until the levels of the mercury inside and outside the tube are the same, and the volume AB, which is then under a pressure of one atmosphere, is noted. The tube is then raised, as represented in fig. 109, until the volume of the air, AC, is doubled. The height of the mercury in the tube, above the mercury in the trough, is then

and to be exactly half the height of the barometer at the time of the experiment. Accordingly, for half the pressure the volume has been doubled.

In the experiment with Mariotte's tube, as the quantity of air remains the same, its density must obviously increase as its volume diminishes, and *vice versâ*. The law may thus be enunciated: *For the same temperature the density of a gas is proportional to its pressure.*' Hence, as water is 773 times as heavy as air, under a pressure of 773 atmospheres air would be as dense as water.

Until within the last few years Boyle's law was supposed to be absolutely true for all gases at all pressures; but several physicists have since observed that the gas is not rigorously exact, especially in the case of those gases which can be liquefied. They are more compressed than is required by the law. For air, Dulong and Arago investigated the pressure up to 27 atmospheres, and observed that the volume of air always diminished a little more than is required by Boyle's law. But, as these differences were very small, they attributed them to errors of observation, and concluded that the law was perfectly exact, at any rate up to 27 atmospheres.

For ordinary pressures Boyle's law may be assumed to be exact for all gases.

134. **Manometers.**—*Manometers* are instruments for measuring the elastic force of gases or vapours. In all manometers the unit chosen is the pressure of one atmosphere, or 30 inches of mercury at the standard temperature, which, as we have seen, is nearly 15 lbs. to the square inch. The open air *manometer* is represented in fig. 110 fixed against a board fastened to a wall, and connected with a steam boiler. It consists of a glass tube about 20 feet in height open at the top, and fixed at the other end to a glass bath C, containing mercury. A long tube connects this with the boiler.

When the elastic force of the vapour in the boiler is equal to the pressure of the atmosphere, it will counterpoise the weight of the atmosphere which is transmitted through the tube, and the level of the mercury is then the same in the tube and in the bath. At this level the number 1 is marked on the board. Then since a column of mercury 30 inches in height represents a pressure of an atmosphere, the number 2 is marked at this height above 1; at a height of 30 inches above this the number 3 is marked, and so on, each interval of 30 inches representing an atmosphere. Thus, for instance, if the mercury had been forced up to $3\frac{1}{2}$, as represented in the drawing that would indicate that the tension of the vapour in

the boiler is $3\frac{1}{2}$ atmospheres; so that, on each square incl
internal surface of the boiler, there is a pressure of $3\frac{1}{2} + 15$
or $52\frac{1}{2}$ pounds.

The manometer with *compressed air* is founded on M



Fig. 110.

law: it consists of a glass tube closed at the top (fig. 1
filled with dry air. It is firmly cemented in a small bath co
mercury. By a tubulure, this bath is connected with the
vessel containing all the gas or vapour whose elastic force
measured.

In the graduation of this manometer, the quantity of air contained in the tube is such, that when the aperture communicates freely with the atmosphere, the level of the mercury is the same in the tube and in the bath. Consequently, at this level, the number 1 is marked on the scale to which the tube is affixed. As the pressure acting through the tubulure A increases, the mercury rises in the tube, until its weight added to the elastic force of the compressed air, is equal to the external pressure. It would consequently be incorrect to mark two atmospheres in the middle of the tube;



Fig. 111.

Fig. 112

for since the volume of the air is reduced to one-half, its elastic force is equal to two atmospheres, and, together with the weight of the mercury raised in the tube, is therefore more than two atmospheres. The position of the number is a little below the middle, at such a height that the elastic force of the compressed air, together with the weight of the mercury in the tube, is equal to two atmospheres. The exact position of the numbers 2, 3, 4, etc., on the manometer scale can only be determined by calculation.

135. **Aneroid barometer.**—This instrument derives its name

from the circumstance that no liquid is used in its construction (*ἀ*, without, *νηρὸς*, moist). Fig. 112 represents one of the forms of these instruments constructed by Mr. Casella ; it consists of a cylindrical metal box, exhausted of air, the top of which is made of thin corrugated metal, so elastic that it readily yields to alterations in the pressure of the atmosphere.

When the pressure increases, the top is pressed inwards; when on the contrary it decreases, the elasticity of the lid, aided by a spring, tends to move it in the opposite direction. These motions are transmitted by delicate multiplying levers to an index which moves on a scale. The instrument is graduated empirically by comparing its indications under different pressures with those of an ordinary mercurial barometer.

The aneroid has the advantage of being portable, and can be constructed of such delicacy as to indicate the difference in pressure between the height of an ordinary table and the ground. It is hence much used in surveying and in determining heights in mountain ascents. But it is somewhat liable to get out of repair, especially when it has been subjected to great variations of pressure : and its indications must from time to time be compared by means of a standard barometer.

MIXTURE AND SOLUTION OF GASES.

136. **Laws of the mixture of gases.**—We have seen that liquids, when they do not act chemically on each other, tend continually to separate, and to become superposed in the order of their densities. This is not the case with gases ; being under a continual tendency to expand, when they mix, their mixture is found to be subject to the following laws :

I. *Whatever their densities, gases mix in equal proportions in all parts of the vessel in which they are contained.*

II. *The elastic force of the mixture is equal to the sum of the elastic forces of the constituents.*

The first law was shown experimentally by Berthollet, by means of an apparatus represented in fig. 113. It consisted of two glass globes provided with stopcocks, which could be screwed one on the other. The upper globe was filled with hydrogen, and the lower one with carbonic acid, which has 22 times the density of hydrogen. The globes having been fixed together were placed in the cellars of the Paris Observatory, and the stopcocks then opened, the globe

ntaining hydrogen being uppermost. Berthollet found, after ne time, that the pressure had not changed, and that, in spite the difference in density, the two ses had become uniformly mixed in e two globes. Experiments made the same manner with other gases ve the same results, and it was found at the diffusion was more rapid in oportion as the difference between e densities was greater.



Fig. 113.

In accordance with this law, air ing a mixture of nitrogen and oxy-n, which are different in density, its mposition should be the same all parts of the atmosphere, ich in fact is what has been ob-rved.

Gaseous mixtures follow Boyle's w, like simple gases, as has been oved for air (133), which is a mix-re of nitrogen and oxygen.

137. **Mixture of gases and liquids. Absorption.**—Water and ny liquids possess the property of absorbing gases. Under the ne conditions of pressure and temperature a liquid does not sorb equal quantities of different gases. At the ordinary tem-rature and pressure water dissolves $\frac{25}{1000}$ its volume of nitrogen, $\frac{1}{3}$ its volume of oxygen, its own volume of carbonic acid, and 430 es its volume of ammoniacal gas.

The general laws of gas-absorption are the following :

I. *For the same gas, the same liquid, and the same temperature, weight of gas absorbed is proportional to the pressure.* This y also be expressed by saying that at all pressures the volume solved is the same ; or that the density of the gas absorbed is in onstant relation with that of the external gas which is not ab-bed.

Accordingly, when the pressure diminishes, the quantity of dis-ved gas decreases. If a solution of a gas be placed under the pump and a vacuum created, the gas obeys its expansive force l escapes with effervescence.

The manufacture of aerated water is a practical application of i law. By means of force-pumps an excess of carbonic acid is

dissolved in the water, and the solution is then preserved in carefully closed vessels.

It is the carbonic acid dissolved in beer, in champagne, and in all effervescing liquids, which, rapidly escaping when the bottles are uncorked, produces the well-known report, and carries with it a greater or less quantity of the liquid.

II. *The quantity of gas absorbed is greater when the temperature is lower;* that is to say, when the elastic force of the gas is less.

III. *The quantity of gas which a liquid can dissolve is independent of the nature and of the quantity of other gases which it may already hold in solution.*

CHAPTER III.

APPARATUS FOUNDED ON THE PROPERTIES OF AIR.

138. **Air-pump.**—The air-pump is an instrument by which a vacuum can be produced in a given space, or rather by which air can be greatly rarefied, for an absolute vacuum cannot be produced by its means. It was invented by Otto von Guericke in 1650, a few years after the invention of the barometer.

Fig. 114 gives a perspective view of the pump, fig. 115 gives a detailed longitudinal section, and fig. 116 gives a cross section.

The pump consists of two stout glass barrels in which two pistons, P and Q, made of leather well soaked with oil, move up and down, and close the barrels air-tight. The pistons are fixed to two racks, A and B, working with a pinion (K, fig. 116), which is moved by a handle MN, so that, when one piston rises, the other descends.

The two barrels are firmly cemented on the base, H, which is of brass; on this plate is a column, I, terminated by a plate G. On this plate is a glass bell jar which is called the *receiver*. In the interior of the column is a conduit, which is prolonged below the base to between the two barrels. It there branches in the shape of a T, terminating in two apertures, *a* and *b*, in the bottom of the cylinders. These apertures are conical, and are closed by two small conical valves; these latter are fixed to metal rods which work air-tight, but with gentle friction in the pistons. In the pistons is a cylindrical cavity communicating with the lower part of the pump by two apertures, *s* and *t* (fig. 116). These apertures are closed

by small clack valves, kept in position by springs which surround the rods themselves. The four valves, *a*, *b*, *s*, *t*, it may be remarked, open upwards.

These details being known, the working of the machine is readily

Fig. 114.

understood. It is sufficient to consider what takes place in a single piston (fig. 114). The piston P being first at the bottom of its stroke, on rising it raises the rod which traverses it, and therewith the valve *a*, which remains open during the ascent. The valve, *t*, which is in the piston, remains closed by the action of the spring

and the pressure of the atmosphere, which acts in the barrel through an aperture, *r*, in the cover. From this position of the two valves, it will be seen that, as the piston rises, the external pressure of the atmosphere cannot act in the bottom of the barrel, but the air of the receiver, in virtue of its elasticity, expands and passes by the conduit, I and H, into the barrel. The receiver is still full of air, but it is more rarefied ; it is less dense.

When the piston descends, the rod which bears the valve, *d*,



Fig. 115.

descending with it, communication between the receiver and the barrel is cut off. The air in the barrel becomes more and more compressed, its elastic force increases, and finally overcomes the atmospheric pressure ; so that the valve *t*, being pressed upwards by the elastic force of the air in the interior more strongly than it is pressed downwards by the atmosphere, is raised, and allows the air of the barrel to escape into the upper part of the barrel, and thence into the atmosphere. Thus a certain quantity of air has

en removed. A fresh quantity is removed at a second stroke of e piston, another at the third, and so on. The air in the receiver thus gradually more and more rarefied; yet all the air cannot be ıtirely extracted, for it ultimately becomes so rarefied both in the :eiver and in the barrel, that when the piston P is at the bottom f its stroke, the compressed gas below the piston has no longer ıfficient force to overcome the resistance of the atmosphere and ırce open the valve, *t*. The limit of rarefaction has then been ttained, and it is useless to work ıe pump any longer.

What has been said in refer- nce to one barrel applies also) the other. The machine 'orks with one; and the first ir-pumps had but one. The dvantage of having two is ıat the vacuum is more rapidly roduced. The use of double- ction air-pumps was first intro- uced by Hawksbee.



Fig. 116.

139. **Measurement of the degree of rarefaction in the receiver.** — Since a perfect acuum cannot be obtained in ıe receiver, it is useful to have means of ascertaining the de- ree of rarefaction at any par- cular time. This is effected by ıeans of a glass cylinder, E, ınnected by a brass cap with ıe conduit in the column I g. 114). In this cylinder is placed a bent glass tube, closed one end and open at the other. This is called the *air-pump uge*. It is fixed against a plate, on which is a graduated scale. he closed branch being at first full of mercury, so long as the r in the receiver P and in the cylinder E has sufficient tension, sustains the mercury in the tube; the height of which is from t to eight inches. But as the pump is worked the air becomes ore and more rarefied, and has no longer the elastic force suffi- nt for retaining the column of mercury in the closed limb. It cordingly sinks in this limb and rises in the other. The greater

the rarefaction, the smaller the difference of the level in the t
They are, however, never exactly equal; that would corr
a perfect vacuum. The mercury is always at least the $\frac{1}{20}$
inch higher in the closed branch. This is expressed by sa
a vacuum has been created within $\frac{1}{20}$ th of an inch.

140. **Uses of the air-pump.**—A great many experim
the air-pump have been already described. Such are the
rain (fig. 1), the fall of l
vacuo (fig. 37), the bladder
the bursting of a bladder (fi
Magdeburg hemispheres (fig
the baroscope (fig. 134).



Fig. 117.

The *fountain in vacuo* (fi
an experiment made with
pump, and shows well th
force of the air. It is a f
taining water and air; the
closed by a cork, through whi
a tube dipping in the liquid.
being placed under the recei
of water issues from the t
tube as soon as the air is s
rarefied. This is due to t
force of the air enclosed in t

By means of the air-pum
be shown that air, by reas
oxygen it contains, is nece
the support of combustion a
For if we place a lighted ta
the receiver and begin to ex
air, the flame becomes weake
faction proceeds, and is fina
guished. Similarly an anin
and dies, if a vacuum is fo
receiver under which it is placed. Mammalia and bi
die in vacuo. Fishes and reptiles support the loss of air f
longer time. Insects can live several days in vacuo.

141. **Application of the vacuum to the preserv
food.**—An important application has been made of the v
preserving food. In air, under the influence of heat, mois
oxygen, animal and vegetable matters rapidly ferment and

but if the oxygen be removed, either by exhausting or by other means, they may be kept fresh for many years.

Appert of Paris was the first in 1809 to devise a means of preserving food in vacuo; or rather in a space deprived of oxygen, which practically amounts to the same. This method consists in placing the substances to be preserved in tin vessels, which are closed hermetically, and then heated in boiling water for some time; under the influence of heat the small quantity of oxygen left in the vessel is absorbed by the substance placed there, so that only nitrogen is present in the free state, a gas which cannot induce fermentation. Substances properly prepared in this manner may be kept for years without alteration.

Appert's method is modified in England in the following manner. Instead of boiling the food while contained in the closed vessel, a small hole is left in the lid, through which escape the air and vapours produced during ebullition. When it is supposed that all the air has been expelled, a drop of melted lead is allowed to fall on the small hole in the cover which completely closes it. This method is practised on the large scale in preserving food and vegetables for the use of sailors, and also in preserving Australian meat, which is now consumed in large quantities.



Fig. 118.

Fig. 119.

142. **Condensing pump.**—The condensing pump is an apparatus for compressing air or any other gas. The form usually adopted is the following: In a cylinder, A, of small diameter (fig. 118), there is a solid piston, the rod of which is worked by the hand. The cylinder is provided with a screw which fits into the receiver, K. Fig. 119 shows the arrangement of the valves, which are so constructed

that the lateral valve, *o*, opens from the outside, and the lower valve, *s*, from the inside.

When the piston descends, the valve *o* closes, and the elastic force of the compressed air opens the valve *s*, which thus allows the compressed air to pass into the receiver. When the piston ascends, *s* closes and *o* opens, and permits the entrance of fresh air, which in turn becomes compressed by the descent of the piston, and so on.

This apparatus is chiefly used for charging liquids with gases. For this purpose the stopcock B is connected with a reservoir of the gas, by means of the tube D. The pump exhausts this gas, and forces it into the vessel K, in which the liquid is contained. This can be drawn off by the stopcock E. The artificial aerated waters are made by means of analogous apparatus.

143. **Hero's fountain.**—Hero's fountain is an arrangement by which a jet may be obtained, which lasts for some time. It derives its name from its inventor, Hero, who lived at Alexandria. 120 B.C., and depends on the elasticity of the air. It consists of a brass dish (fig. 120), and of two glass globes. The dish communicates with the lower part of the globe by a long tube; and another tube connects the two globes. A third tube passes through the dish to the lower part of the upper globe. This tube having been taken out, the upper globe is partially filled with water, the tube is then replaced, and water is poured into the dish. The water flows through the long tube into the lower globe, and expels the air, which is forced into the upper globe; the air thus compressed, acts upon the water, and makes it jet out as represented in the figure. If it were not for the resistance of the atmosphere, and friction, the liquid would rise to a height above the water in the dish equal to the difference of the level in the two globes.

144. **Intermittent fountain.**—The *intermittent fountain* depends partly on the elastic force of the air and partly on the atmospheric pressure. It consists of a stoppered glass globe *a* (fig. 121), provided with two or three capillary tubulures. A glass tube, *d*, open at both ends, reaches at one end to the upper part of the globe, *a*; the other end is fitted in a support, *c*, placed in the middle of the dish, *m*, which supports the whole apparatus. The support, *c*, is perforated with small holes, which allow air to pass into the tube just above a little aperture in the dish, *m*.

The water, with which the globe, *a*, is nearly two-thirds filled.

ns out by the tubes, as shown in the figure; the internal pres-
ıre being equal to the atmospheric pressure, together with the
eight of the column of water, while the external pressure at that
oint is only that of the atmosphere. These conditions prevail so
ng as the lower end of the glass tube is open, that is, so long as

Fig. 120.

r can enter and keep the air in *a* at the same density as the ex-
rnal air; but the apparatus is arranged so that the orifice in the
ish does not allow so much water to flow out as it receives from
e upper tubes, in consequence of which the level gradually rises in

the dish, and then closes the lower end of the glass tube. As the external air cannot now enter the globe, *a*, the air becomes rarefied in proportion as the flow continues, until the pressure of the column of water, together with the elastic force of the air contained in the globe, is equal to this external pressure ; the flow consequently

Fig. 121.

stops. But as water continues to flow out of the dish at *m*, the tube opens again, air enters, and the flow recommences, and so on, as long as there is water in the globe *a*.

145. **Syphon inkstand.**—This instrument, the object of which is to protect ink from too rapid evaporation is an interesting illustration of the pressure of the atmosphere, and of the elasticity of

air. It consists of a glass vessel of the shape of a truncated pyramid (fig. 122), closed everywhere except at the bottom, where there is a tubulure, which is always open. The inkstand is partially full of ink, while there is air at the top. The level of the ink inside being higher than in the tubulure, the elastic force of the air inside is a little less than the pressure of the atmosphere on the ink in the tubulure. As the ink there is used, its level sinks, and is finally lower than the point *o*. At this moment a bubble of air passes into the interior, and the elastic force being thereby increased, the level of the ink descends in the inside and rises in the tubulure. This goes on until the internal level is at the point

Fig. 122.

More ink must then be added, which is effected by pouring into the tubulure, care being taken to incline the inkstand in the opposite direction. The fountains in birdcages are on a similar principle.

PUMPS.

146. **Suction-pump.**—Pumps are machines for raising liquids. Their invention, which is of great antiquity, is attributed to Ctesibius, a celebrated mechanician, who flourished at Alexandria, 300 B.C. There are many modifications of pumps, but they may all be referred to three types, *the suction or lift-pump, the forcing pump, and the suction and forcing pump.*

The suction or lifting pump, represented in fig. 123, consists of a cast-iron cylinder called the *barrel*, at the bottom of which is a pipe of a smaller diameter, which dips in the well. At the top of this pipe is a clack valve, which is represented in the drawing as being open. It moves easily up and down, and it establishes a communication between the cylinder and the body of the pump when it is open, and breaks it when closed. The piston in the barrel consists of a thick disc of metal or of leather, coated with tow or with leather. The piston is perforated by a small hole, which is closed by a valve; the valve is like that in the barrel, and, like it, opens upwards. The piston is worked by means of

a long lever, which is the ***handle***. This is joined at one
forked rod, *a*, which is connected with the piston rod, *b*.
important that the piston move in a straight line, it is gu
passing through a hole in a fixed piece, *o*.

Fig. 123.

The manner in which the water is raised will be un
from an inspection of figs. 124, 125, and 126, which repre
piston and the valves in three different positions. W
pump has not been worked, the barrel and the pipe are fu
under the ordinary atmospheric pressure, which counterl
the external atmospheric pressure on the well. Hence it

that the level of the water inside and outside is the same. When the piston rises (fig. 124), as it is pressed down by its own weight and by that of the atmosphere, a vacuum is created below the piston; but, in virtue of its elastic force, the air which fills the pipe B quickly opens the valve, *a*, and passes into the barrel. The air in the pipe B losing then in elastic force what it gains in volume (133), its pressure is no longer equal to the external pressure on the

Fig. 124.



Fig. 125.



Fig. 126.

water in the well. Hence water rises in the pipe, as represented in the diagram. If now the piston sinks (fig. 125), the valve *a* closes; and as the air thus enclosed in the barrel becomes more and more compressed, a moment arrives when its elastic force exceeding the pressure of the atmosphere, the valve *c* is raised, and air escapes into the top of the barrel, and thence into the atmosphere. With a second ascending stroke of the piston, the same phenomena are reproduced; that is, *c* falls and the valve *a* opens, the water being thus raised in the pipe, ultimately passes beyond the valve *a*, and completely fills the barrel. From this time, when the piston re-descends, and the valve *a* closes, the

pressure exerted on the water raises the valve *c*, and the water passes above the piston (fig. 125). Once this effect is produced, when the piston ascends, the valve *c* closes, and the water which has passed above the piston being raised with it, ultimately flows out by a lateral tubulure in the barrel (fig. 126).

Since it is the atmospheric pressure which raises the water in the pipe, the height of the valve *a*, above the level in the vessel, cannot exceed a certain limit. A column of water, 34 feet in height, balances, as we have seen, the pressure of the atmosphere (118). Hence if the pipe had a greater length than this, when once water had reached this height, the column of water in the pipe would balance the pressure of the atmosphere on the water of the well, and it could not be raised any higher. This, therefore, would be the extreme theoretical limit which the pipe could have; but in practice the height of the tube A does not exceed 26 to 28 feet; for, although the atmospheric pressure can support a higher column, the vacuum produced in the barrel is never perfect, owing to the fact that the piston does not fit exactly on the bottom of the barrel. But when the water has passed the piston, it is the lifting force of the latter which raises it, and the height to which it can be brought depends on the force which works the piston.



Fig. 127.

147. **Force-pump.** — In these water is not raised by the pressure of the atmosphere, but by the pressure of the piston on the water during its descent. For this purpose the piston is solid, that is, has no valve, and there is no lifting pipe, the barrel being immersed in the liquid to be raised (figs. 127 and 128). There are two valves in the barrel; one *a*, in the bottom, opens upwards; the other, *b*, is placed in the orifice of a long tube in the side of the pump.

When the piston rises (fig. 127), a vacuum being produced below it, the atmospheric pressure acts on *c*, and closes it; while the water

in which the pump is immersed being forced by its own weight and that of the atmosphere, raises the valve *a*, and passes into the barrel which it fills completely. The motion of the pistons is just reversed when the piston descends (fig. 128). By its own weight and by the pressure upon it, the valve *a* closes, while the valve *c* opens and gives exit to the water in the barrel, which then rises to a height depending on the pressure exerted by the piston. If this amounts to a pressure of one atmosphere, water rises 34 feet in the pipe H (118); if it is two atmospheres water rises to 68 feet, and so on; that is, always to a height of 34 feet for a pressure of one atmosphere. The height, therefore, to which water can be raised in these pumps is not limited as it is in the suction-pump.



Fig. 128.

From what has been said, it will be seen that water only rises in the pipe H when the piston descends; there is, therefore, an intermittent flow at the end of the pipe. A more regular flow is obtained by arranging two pumps, both forcing water into the same pipe, and in such a manner that, when one piston rises, the other sinks. It is by means of such an arrangement of two pumps, that air is raised to the wicks in Carcel's lamp. At the base of these lamps, and immersed in the oil itself, are two small pumps worked by a clock-work motion, which is wound up like a clock. Such a system is also applied in fire-engines.

148. **Fire-engines.**—In a *fire-engine* water has to be forced to a great height in a continuous stream. Fig. 129 represents a section of such a pump. To the handles PQ are fixed, by means of a joint, two rods which work the pistons *m* and *n* in two brass barrels. These pumps are placed in a trough, MN, of the same metal, which is called the tank, and which is fed with water while the pump is at work. Between these two is an air-chamber R, with a lateral aperture Z, to which can be attached a long leather tube. This

tube is provided at the end with a long conical copper tube, and which has an aperture only about three-fifths of an inch diameter.

The use of the air-chamber is as follows : Although the pistons work alternately there would necessarily be some intermittence in the jet when they are at the top or at the bottom of their course. But the water, instead of being forced by the pumps directly into the ascending pipe, first passes into the reservoir R, as shown in fig. 129. Owing to the resistance in the tube and on the jet, it



Fig. 129.

flows out of the reservoir more slowly than it enters. Its level rises in the reservoir, and as the air is thereby reduced in volume, its pressure increases, so that the compressed air, reacting on the water when the pistons stop, forces out the water and thus keeps up the continuity of the jet. A good fire-engine worked by eight men will raise water to a height of 100 feet.

149. **The syphon.**—The syphon is a bent tube open at both ends and with unequal legs (fig. 130). It is used in transferring liquids, especially in cases in which they are to be removed without disturbing any sediment they contain. It is worked in the following manner : The syphon is filled with some liquid, and the two ends being closed, the shorter leg is dipped in the liquid as represented

30; or the shorter leg having been dipped in the liquid, the xhausted by applying the mouth at *b*. A vacuum is thus :d, the liquid in *d* rises and fills the tube in consequence of ıospheric pressure. It will then run out through the syphon as the shorter end dips in the liquid.

'phon of the form represented in fig. 131 is used where the e of the liquid in the mouth would be objectionable. A is attached to the longer branch, and it is filled by closing of the longer limb, and sucking at the end of *a*.



Fig. 130. Fig. 131.

xplain this flow of water from the syphon, let us suppose it d the short leg immersed in the liquid. The pressure then n *d*, and tending to raise the liquid in the tube, is the at- ric pressure minus the height of the column of liquid, *cd*. nanner, the pressure on the end of the tube *b* is the weight ıtmosphere less the pressure of the column of liquid, *ab*. his latter column is longer than *cd*, the force acting at *b* is ı the force acting at *d*, and consequently a flow takes place onal to the difference between these two forces. The flow efore be more rapid in proportion as the difference of level the aperture *b* and the surface of the liquid in *d* is

150. **Intermittent springs. Tantalus' cup.**—In nature, springs are met with whose flow is spontaneously interrupted, and which begins again after a longer or shorter interval. This phenomenon

Fig. 132.

depends on the action of the syphon, and is readily understood by reference to fig. 132, which represents a subterranean reservoir fed by a series of fissures in the earth; the channel by which the water flows out is on the left of the figure, and on coming to the surface it forms a spring. In the figure the reservoir is represented as just being filled, and when the water rises to the height of the bend the syphon begins to act. If the fissures by which water is supplied furnish a smaller quantity than that which flows out, the reservoir together with the channel is gradually emptied, and the flow then ceases. The reservoir gradually fills again, but the water cannot flow out until it has risen to the height represented by the dotted line, and the syphon has begun to work again.



Fig. 133.

The action of Tantalus' cup which is represented in fig. 133 will be at once understood; and the same principle is applied in an arrangement frequently used by photographers for washing prints.

CHAPTER IV.

PRESSURE ON BODIES IN AIR. BALLOONS.

151. **Archimedes' principle applied to gases.**—The pressure exerted by gases on bodies immersed in them, is transmitted equally in all directions, as has been shown by the experiment with the Magdeburg hemispheres. It therefore follows, that all which has been said about the equilibrium of bodies in liquids, applies to bodies in air; they lose a part of their weight equal to that of the air which they displace.

Fig. 134.

This loss of weight in air is demonstrated by means of the *baroscope*, which consists of a scalebeam, at one of whose ends a small leaden weight is supported, and at the other there is a hollow copper sphere (fig. 132). They are so constructed that in air they exactly balance one another, but when they are placed under the receiver of the air-pump and a vacuum is produced, the sphere sinks; thereby showing that in reality it is heavier than the small leaden weight. Before the air is exhausted each body is buoyed up by the weight of the air which it displaces. But as the sphere is much the larger of the two, its weight undergoes most apparent diminution; and thus, though in reality the heavier body, it is balanced by the small leaden weight. It may be proved by means of the same apparatus that this loss is equal to the weight of the displaced air, and we may thus generalise Archimedes' principle and say, that any body plunged in any fluid, whether it be a liquid or a gas, loses part of its weight equal to the weight of the displaced fluid. Hence bodies weighed in air usually indicate too small a weight. To have an exact weight the volume of the weights and of the displaced fluid should be exactly the same, which is seldom the case. The true weight of bodies is obtained by weighing them in a vacuum.

The principle of Archimedes being thus true for bodies in air, all that has been said about bodies immersed in liquids applies to them, that is, that when a body is heavier than air it will sink, owing to the excess of its weight over the buoyancy. If it is as heavy as air, its weight will exactly counterbalance the buoyancy, and the body will float in the atmosphere. If the body is lighter than air, the buoyancy of the air will prevail, and the body will rise in the atmosphere until it reaches a layer of the same density as its own. The force of the ascent is equal to the excess of the buoyancy over the weight of the body. This is the reason why smoke, vapours, clouds, and air balloons rise in the air.

152. **Air balloons.**—*Air balloons* are hollow spheres made of some light impermeable material, which, when filled with heated air, with hydrogen gas, or with coal gas, rise in the air in virtue of their relative lightness.

They were invented by the brothers Montgolfier, of Annonay, and the first experiment was made at that place in June 1783. Their balloon was a sphere of 40 yards in circumference, and weighed 500 pounds. At the lower part there was an aperture, and a sort of boat was suspended, in which was burnt paper and straw. The heated air thus produced gradually inflated the balloon, and when it was full of expanded air, which was thus lighter than the external air, the weight of the balloon and its hot air being less than that of the air which it displaced, it soon rose to a height of more than 2,000 yards, to the great astonishment of the assembled spectators. It rapidly descended, however, for the hot air it contained soon became cooled in the higher regions of the atmosphere.

The experiment at Annonay excited great interest all over France, and pending the repetition on a larger scale at the expense of the government, Charles, a professor of physics, constructed a smaller balloon, about 13 feet in diameter, which was filled with hydrogen instead of heated air. The use of hydrogen is very advantageous, for as it is almost 14 times less dense than air, its ascensional force is far greater than that of hot air, and it is also less dangerous, for in heating the air there is a great risk of setting fire to the balloon. Charles made an ascent in 1783 in a balloon inflated by hydrogen.

Since then, the art of ballooning has been greatly extended, and many ascents have been made. That which Gay-Lussac made in 1804 was the most remarkable for the facts with which it has enriched science, and for the height which he attained—23,000 feet

ve the sea level. At this height the barometer stood at 12·6 hes, and the thermometer, which was 31° C. on the ground was legrees below zero.

In these high regions, the dryness was such on the day of Gay-ssac's ascent, that hygrometric substances, such as paper, parch-nt, &c.. became dried and crumpled as if they had been placed ar the fire. The respiration and circulation of the blood were celerated in consequence of the great rarefaction of the air. Gay-ssac's pulse made 120 pulsations in a minute, instead of 66, the rmal number. At this great height the sky had a very dark ue tint, and an absolute silence prevailed.

One of the most remarkable recent ascents was made by Mr. laisher and Mr. Coxwell, in a large balloon belonging to the ter. This was filled with 90,000 cubic feet of coal gas (sp. gr. 37 to 0·33) : the weight of the load was 600 pounds. The ascent ok place at 1 P.M. on September 5, 1861 ; at 1° 28′ they had ached a height of 15,750 feet, and in eleven minutes afterwards a ight of 21,000 feet, the temperature being – 10·4° ; at 1° 50′ they ere at 26,200 feet with the thermometer at – 15·2°. At 1° 52′ the ight attained was 39,000 feet, and the temperature – 16·0 C. At is height the rarefaction of the air was so great and the cold so tense that Mr. Glaisher fainted, and could no longer observe. ccording to an approximate estimation the lowest barometric eight they attained was 7 inches, which would correspond to a eight of 36,000 to 37,000 feet.

153. **Construction and management of balloons.**—A balloon ig. 135) is made of long bands of silk sewed together and covered ith caoutchouc varnish, which renders it air-tight. At the top iere is a safety-valve closed by a spring, which the aëronaut can pen at pleasure by means of a cord. A light wicker-work boat suspended by means of cords to a net-work, which entirely covers ie balloon.

A balloon of the ordinary dimensions, which can carry three ersons, is about 16 yards high, 12 yards in diameter, and its olume when it is quite full is about 680 cubic yards. The balloon self weighs 200 pounds ; the accessories, such as rope and boat, 00 pounds.

The balloon is filled either with hydrogen or with coal gas. Al-ough the latter is heavier than the former, it is generally pre-rred, because it is cheaper and more easily obtained. It is passed to the balloon from the gas reservoir by means of a flexible pipe

(fig. 135). It is important not to fill the balloon quite fi
atmospheric pressure diminishes as it rises, and the
expanding in consequence of its elastic force, tends t
It is sufficient for the ascent if the weight of the dis
exceeds that of the balloon by 8 or 10 pounds. The

Fig. 135.

due to this excess of weight is constant so long as the bal
quite distended by the dilatation of the air in the interi
atmospheric pressure, for example, has diminished to on
gas in the balloon, according to Boyle's law, has doubled i
The volume of the air displaced is therefore twice as great
its density has become only one-half, the weight, and co

the upward buoyancy, are the same. When once the balloon is completely dilated, if it continue to rise, the force of the ascent decreases, for the volume of the displaced air remains the same, but its density diminishes, and a time arrives at which the buoyancy is only equal to the weight of the balloon. The balloon can now only take a horizontal direction, carried by the currents of air which prevail in the atmosphere. The aëronaut knows by the barometer whether he is ascending or descending; and by the same means he determines the height which he has reached. A long flag fixed to the boat would indicate, by the position it takes either above or below, whether the balloon is descending or ascending.

When the aëronaut wishes to descend, he opens the valve at the top of the balloon by means of the cord, which allows gas to escape, and the balloon sinks. If he wants to descend more slowly, or to rise again, he empties out bags of sand, of which there is an ample supply in the car. The descent is facilitated by means of a grappling iron fixed to the boat. When once this is fixed to any obstacle, the balloon is lowered by pulling the cord.



Fig. 136.

The only practical applications which air balloons have hitherto had, have been in military reconnoitring. At the battle of Fleurus in 1794, a captive balloon, that is, one held by a cord, was used, in which there was an observer who reported the movements of the enemy by means of signals. At the battle of Solferino the move-

ments and dispositions of the Austrian troops were watched by a captive balloon; and in the war in America balloons were frequently used; while the part which they played in the siege of Paris is still fresh in all memories. Many ascents have recently been made by Mr. Glaisher for the purpose of making meteorological observations in the higher regions of the atmosphere (152). Air balloons can only be truly useful when they can be guided, and as yet all attempts made with this view have completely failed. There is no other course at present than to rise in the air until there is a current which has more or less the desired direction.

154. **Parachute.**—The object of the parachute is to allow an aëronaut to leave the balloon, by giving him the means of lessening

Fig. 137.

the rapidity of his descent. It consists of a large circular piece cloth (fig. 137) about 16 feet in diameter, and which by the resi ance of the air spreads out like a gigantic umbrella. In t centre there is an aperture, through which the air, compressed

e rapidity of the descent, makes its escape ; for otherwise oscilla-ıns might be produced, which, when communicated to the boat, ɔuld be dangerous.

In fig. 136 there is a parachute attached to the network of the lloon by means of a cord, which passes round a pulley, and is ed at the other end to the boat. When the cord is cut, the para-ute sinks, at first very rapidly, but more slowly as it becomes stended, as represented in the figure.

155. **Bellows.**—Fig. 138 represents a simple form of bellows, e action of which depends on the compression of air. Between o round wooden boards provided with handles, one of which has valve *k*, while the other works on a hinge, a folded leathern

Fig. 138.

ag is fastened. The inner space terminates in front in a shorter ron or brass pipe *d*, which is called the *nozzle*. If now the upper id is raised, the valve is open, the space is quite filled with air, nd when it is compressed it flows out through the nozzle. Thus his arrangement, like that of the force pump, produces an inter-mittent flow of air.

BOOK IV.

ACOUSTICS.

CHAPTER I.

PRODUCTION, PROPAGATION, AND REFLECTION OF SOUND.

156. **Province of acoustics.**—The study of sounds, and that of the vibrations of elastic bodies, form the province of *acoustics*.

Music considers sounds with reference to the pleasurable feelings they are calculated to excite. Acoustics is concerned with the questions of the production, transmission, and comparison of sounds. To this may be added the physiological question of the perception of sounds.

Sound is a peculiar sensation excited in the organ of hearing by the vibratory motion of bodies, when this motion is transmitted to the ear through an elastic medium.

Take for instance the string of a musical instrument, when it is pulled or sounded by a bow (fig. 139). When this is pulled aside from the position *acb*, where it is at rest, to the position *adb*, all the



Fig. 139.

points being more or less out of their position of equilibrium, when the string is left to itself, it tends to revert to its original position *acb*, owing to its elasticity. In virtue, however, of its acquired velocity, it passes beyond it as far as *aeb*, all the points being then virtually as far out of their position of rest as they were at *adb*. But as the elasticity still continues to act, not merely does the string revert to its original position, but it again passes beyond it, and so

on, the amplitude of its path becoming smaller and smaller, as represented by the dotted lines in the figure, until it ultimately reverts to its original state of equilibrium. Hence each point of the string makes a backward and forward, or vibratory motion, like that of the pendulum. The passage from the position *adb* to *aeb*, and back to *adb*, is called a complete *vibration* or *oscillation*; the passage from *adb* to *aeb*, or from *aeb* to *adb*, is a *semi-vibration* or *semi-oscillation*.

Any body which vibrates or yields a sound, is called a *sonorous* or *sounding body*. The vibrations of sounding bodies are generally too rapid to be counted or even distinctly seen. Yet they may be rendered evident in a variety of ways. Thus, if a tolerably large bell jar be made to sound by striking it with the finger, and a small ivory bell suspended by a thread be approached to it, the ball will be observed to receive a series of rapid shocks from the sides of the bell, showing that it is in a state of vibration. Or, if a plate of metal be fixed horizontally at one end, and sand be strewed over it, when the plate is made to vibrate by briskly moving a violin bow against the edge, the sand becomes violently agitated, which is obviously due to the vibrations of the plate.

157. **Propagation of sound in the air. Sound waves.**— After having ascertained that when a body emits a sound, its molecules are in a state of vibration, it remains to explain how these are transmitted to the ear to produce the sensation of sound. Sound always requires for its transmission an elastic medium, which at one end is in contact with the sounding body, and at the other with the organ of hearing. Air is the ordinary medium through which sound is transmitted. As air is very mobile, compressible, and elastic, its molecules being in contact with different points of the sounding body acquire movements which are similar to those of these points; they go and come with these points, so that each molecule of air in contact with the body is pushed forward by it in the direction of the sound, and returns, having communicated its motion to the next molecule; this then acts in the same manner on the next molecule, and so on to the molecules in contact with the *tympanum* or *drum*. This is the name given to a membrane placed at the end of the auditory canal of the ear; it receives the vibrations of the air, which it transmits by a series of small bones and liquids to the acoustic nerve, and thence to the brain, which finally perceives the sensation of sound.

At each impulse imparted by a sounding body to the molecules of air in contact with it, these molecules pressing in turn upon the

succeeding ones, a condensed part is produced in the air to a certain distance which is called the *condensed wave*; then, when the vibrating body reverts to its original position, the molecules nearest to it follow it in its motion, so that there is formed in the air a rarefied part which follows the condensed wave, and which is called the *rarefied wave*. A condensed and a rarefied wave together form a sound wave. A sounding body is a centre from which these waves are emitted all round it in the form of continually increasing spheres, and thus it is that sound is propagated by a body in all directions. Fig. 140 furnishes a rough illustration of this process. If a stone is thrown into still water, there are formed round the point where it



Fig. 140.

falls a series of concentric waves, which continually increase, and which give an idea of the propagation of sound waves in the air.

In the case of very intense sounds, the disturbance communicated to the air in the form of sound waves may be very considerable. Thus the waves produced by thunder, by the report of cannon, and by gunpowder explosion, are frequently powerful enough to break whole panes of glass.

158. **Coexistence of sound waves.**—It is to be observed that several sounds may be propagated in air without destroying each other. Thus in the most complicated orchestral music, a person with a practised ear can readily follow the sound of each instrument. Yet a loud sound interferes with a weak one; thus the sound of a drum overpowers the human voice. Sounds also which are too weak to be distinctly heard, accumulate upon each other, and produce a confused sound, which becomes perceptible to the ear.

ch is the cause of the murmuring of water, the rustling of leaves woods, and the dashing of waves against the shores.

159. **Sound is not propagated in vacuo.**—The vibrations of stic bodies can only produce the sensation of sound in us, by the ervention of a medium interposed between the ear and the so- rous body, and vibrating with it. This medium is usually the , but all gases, vapours, liquids, and solids also transmit sound.

The following experiment shows that the presence of a ponder- le medium is necessary for the propagation of sound. A tolerably ge glass globe (fig. 141), provided with a stop- :k, has a small bell suspended in the interior a thread. A vacuum having been created in : globe by means of the air-pump, no sound is iitted when the globe is shaken, though the ipper may be seen to strike against the bell; t if air, or any other gas or vapour, be admitted, und is distinctly heard each time the globe is itated.



Fig. 141.

The experiment may also be made by placing small metallic bell, which is continually struck a small hammer by means of clockwork, or an ordinary musi- box, under the receiver of the air-pump. As long as the re- ver is full of air at the ordinary pressure, the sound is trans- tted; but, in proportion as the air is exhausted, the sound :omes feebler, and is imperceptible in a vacuum.

To ensure the success of the experiment, the bellwork or musical t must be placed on wadding; for otherwise the vibrations uld be transmitted to the air through the plate of the machine.

160. **Propagation of sound in liquids and solids.**—Sound is o propagated in liquids. When two bodies strike against each er under water, the shock is distinctly heard; and a diver at the tom of the water can hear the sound of voices on the bank.

The conductibility of solids is such, that the scratching of a pen the end of a long wooden rod is heard at the other end. In like nner if a person speaks with a low voice at the end of a pine rod, to 30 yards long, he is heard by a person whose ear is applied inst the other end, while a person who is near, hears nothing. e earth conducts sound so well, that at night, when the ear is plied to the ground, the steps of horses or any other noise at great itances is heard.

161. **Velocity of sound in air.**—Numerous phenomena show

that sound requires a certain time to pass from one place to another. Thus, if we pay attention to a woodmen felling trees at a distance, we see the axe fall in silence, and only hear the sound a moment afterwards. In like manner, when a gun is fired, the report is heard after the flash of light. Thunder, too, is only heard some time after lightning, although in the cloud both thunder and lightning are produced simultaneously.

The velocity of sound was determined experimentally by the members of the Bureau of Longitude of Paris in June 1822, during the night. A cannon was placed on a hill at Montlhéry near Paris, and another on a plateau near Villejuif. The distance of the two places was carefully measured, and was found to be 61,045 feet, and a gun was fired at each station twelve successive times at intervals of 10 minutes (fig. 142). Observers placed near the guns noted

Fig. 142.

by means of accurate and delicate watches, the time which elapsed between the appearance of the flash and the hearing the sound at the opposite station; and the mean of the observations gave the number 54·6 seconds. This was just the time which the sound required to travel from one station to the other; for we shall afterwards see (308) that the velocity of light is such that the time it requires to traverse the above distance is inappreciable. Hence by a simple calculation we find that sound travels 1,118 feet in a second.

above observations were made when the air was at a tem-
: of 16°. At a lower temperature the velocity of sound is

n some accurate experiments made by the above method
nsterdam, the velocity of sound is taken at 1,093 feet per
in dry air at zero. Its velocity increases about 2 feet per
for every degree centigrade. So that at 15° C., which is
inary temperature, the velocity of sound is 1,120 feet per

nowledge of the velocity of sound enables us to measure
:s. Thus, suppose we want to known the distance at which
s fired, of which we only hear the report 15 seconds after
the flash. As sound travels at 1,120 feet in a second, it
iverse 16,800 feet in the time mentioned, and this would be
ance at which the gun was fired. In the same manner we
lculate the depth of a well from the number of seconds
lapses between the moment at which a stone falls into it and
which the sound is produced. The calculation is, however,
mplicated, for the time which the body requires in falling
e taken into account.

velocity of sound is not the same in different gases; it is
in those which are less dense. Dulong found the velocity
to be 846 feet per second for carbonic acid, 1,040 feet in
and 1,093 in air, 1,106 in carbonic oxide, and 4,163 feet in
n.

velocity of sound is the same in air for all sounds, whether
r weak, grave or acute.

this reason the tune played by a band is heard at a great
: without alteration, except in intensity, which could not be
: if some sounds travelled more rapidly than others.

Velocity of sound in liquids and in solids.—We have seen that liquids conduct sound; they even conduct it han gases. The velocity of sound in water was investi- n 1827 by Colladon and Sturm. They moored two boats, at a known distance in the Lake of Geneva. The first, orted a bell C immersed in water, and a bent lever provided end with a hammer *b* which struck the bell, and at the ith a lighted wick *e*, so arranged that it ignited some *m*, the moment the hammer struck the bell. To the second is affixed an ear-trumpet, the bell, *gfk*, of which was in while the mouth *o*, was applied to the ear of the observer,

so that he could measure the time between the flash of lig
the arrival of sound by the water. By this method the velo
found to be 4,708 feet in a second at the temperature 8°,
times as great as in air.



Fig. 143.

That sound travels more rapidly in solids than in air
shown. If a person holds his ear against one end of a t
long iron bar, while another person gives a hard blow at t
end, two distinct sounds are heard ; the first transmitte
metal, and the other transmitted by the air. The velocity
in iron is 16,800 feet in a second ; in copper, 11,600 ;
10,900 ; and in fir, 15,220 feet.

163. **Reflection of sound.**—We have seen that sound i
gated in air by means of spherical waves, alternately co
and rarefied, and which are developed about it in all di
So long as these sound waves are not obstructed in their
they are propagated in the form of concentric spheres ; t
they meet with an obstacle, they follow the general law
bodies ; that is, they are repelled like an ivory ball, whic
against a wall ; they return upon themselves, forming new c
waves, which seem to emanate from a second centre on
side of the obstacle. This phenomena constitutes the *re*
sound.

The reflection of sound, or rather of sound waves, fo

same laws as the reflection of heat and of light, which we shall subsequently have to explain.

The reflection of sound may be demonstrated by means of the arrangement represented in fig. 144, which are two parabolic mirrors placed at some distance opposite each other. At a certain position in front of one of them, called the *focus*, is placed a watch or other convenient sounding body. It is a property of this posi-



Fig. 144.

tion, the focus, that all sound waves emanating from it which fall on the adjacent mirror are thrown back in parallel rays. If these parallel rays fall on the second mirror they are reflected to *its* focus, so that if an ear be placed there the sound waves are concentrated in the ear, and the ticking of the watch is distinctly heard, which is not the case if the ear is not in this position.

164. **Echoes and resonances.**—An *echo* is the repetition of a sound in the air, caused by its reflection from some more or less distant obstacle. Thus, if a few words are loudly spoken at a certain distance from a wood, a rock, or a building, it usually happens that, after a brief interval, the same phrase is heard repeated, as if spoken in the distance by another person; these are the sound waves, which are reflected by the obstacle. There must, however, be a certain distance between the place at which the sound is produced and that at which it is heard.

A very sharp quick sound can produce an echo when the reflecting surface is 55 feet distant; but for articulate sounds at least double that distance is necessary, for it may be easily shown that no one can pronounce or hear distinctly more than five syllables in a second. Now, as the velocity of sound at ordinary temperatures

may be taken at 1,120 feet in a second, in a fifth of that time sound would travel 224 feet. If the reflecting surface is 112 feet distant, sound would travel through 224 feet in going and returning. The time which elapses between the articulated and the reflected sound would, therefore, be a fifth of a second, the two sounds would not interfere, and the reflected sound would be distinctly heard. A person speaking with a loud voice in front of a reflecting surface at the distance of 112 feet can only distinguish the last reflected syllable : such an echo is said to be *monosyllabic*. If the reflector were at a distance of two or three times 112 feet, the echo would be *dissyllabic*, *trisyllabic*, and so on.

Multiple echoes are those which repeat the same sound several times; this is the case when two opposite surfaces (for example, two parallel walls) successively reflect sound. There are echoes which repeat the same sound 20 or 30 times. An echo in the château of Simonetta in Italy, repeats a sound 30 times. At Woodstock there is one which repeats from 17 to 20 syllables. Near Verdun is an echo formed by two parallel towers, at a distance from each other of about 164 feet. A person placing himself between them, and speaking a word with a loud voice, hears it repeated a dozen times. Echoes usually modify sound ; some repeat it with noise ; others with a mocking, laughing tone, or a plaintive accent.

We have seen that when the distance at which a sound is reflected is 112 feet an echo is produced ; and the question may be asked, what happens when the distance is less than this ? As the sound has then a smaller distance to traverse, both in going and coming, than 112 feet, it follows that the reflected sound is added to the directly spoken one. They cannot be heard separately, but the sound is strengthened. This is what is called *resonance*, and its effects are so much the more marked the more elastic are the surfaces from which the sound is reflected. In racket courts and in uninhabited houses, where there is no furniture, the walls, the flooring, and the ceiling readily vibrate, and we all know how the noise of footsteps and the sound of the voice then resound. Tapestry and hangings, which are not elastic, *deaden* the sound.

As the laws of the reflection of sound are the same as those of light and heat, curved surfaces of natural occurrence often produce *acoustic foci*, like the luminous and calorific foci produced by mirrors. If a person standing under the arch of a bridge speaks with his face turned towards one of the piers, the sound is repro-

uced near the other pier with such distinctness that a conversation an be kept up in a low tone, which is not heard by any one tanding in the intermediate spaces.

There is a square room with an elliptical ceiling, on the ground-oor of the Conservatoire des Arts et Métiers, in Paris, which pre-ents this phenomenon in a remarkable degree when persons stand n the two foci of the ellipse. So also bellying sails act as mirrors n sound.

It is not merely by solid surfaces, such as walls, rocks, etc., hat sound is reflected. It is also reflected by clouds, and on assing into a layer of air of greater density than its own; and is aid to be reflected by the vesicles of mist.

Whispering galleries are formed of smooth walls, having a con-inuous curved form. The mouth of the speaker is presented at ne point, and the ear of the hearer at another and distant point. n this case, the sound is successively reflected from one point to he other until it reaches the ear.

Different parts of the earth's surface are unequally heated by he sun, owing to the shadows of trees, evaporation of water, and ther causes, so that in the atmosphere there are numerous ascend-ng and descending currents of air of different densities. Whenever sound wave passes from a medium of one density into another it ndergoes partial reflection; in some cases is strong enough to orm an echo, and always distinctly weakens the direct sound. This is doubtless the reason, as Humboldt remarks, why sound ravels further at night than at daytime; even in the South Ameri-an forests, where the animals, which are silent by day, fill the tmosphere in the night with thousands of confused sounds.

165. **Causes which influence the intensity of sound.**—Many auses modify the force or the *intensity* of the sound. These are, he distance of the sonorous body, the amplitude of the vibrations, he density of the air at the place where the sound is produced, he direction of the currents of air, and, lastly, the nearness of other odies which can enter into a state of vibration.

1. *The intensity of sound is inversely as the square of the distance f the sounding body from the ear.* This law has been deduced by alculation, but it may be also demonstrated experimentally. Let s suppose several sounds of equal intensity, for instance, bells of he same kind, struck by hammers of the same weight, falling from qual heights. If four of these bells are placed at a distance of o yards from the ear, and one at a distance of 10 yards, it is

found that the single bell produces a sound of the same intensity as the four bells struck simultaneously. Consequently, for double the distance, the intensity of the sound is only one-fourth.

The distance at which sounds can be heard depends on their intensity. The report of a volcano at St. Vincent was heard at Demerara, 300 miles off, and the firing at Waterloo was heard at Dover.

ii. *The intensity of the sound increases with the amplitude of the vibrations of the sounding body.* The connection between the intensity of the sound and the amplitude of the vibrations, is readily observed by means of vibrating cords. For if the cords are somewhat long the oscillations are perceptible to the eye, and it is seen that the sound is feebler in proportion as the amplitude of the oscillations decreases.

For the same reason the dying sound of the last blows of a bell become gradually feebler, until they are ultimately extinguished.

iii. *The intensity of sound depends on the density of the air in the place in which it is produced.* As we have already seen (159), when an alarum moved by clockwork is placed under the bell-jar of the air-pump, the sound becomes weaker in proportion as the air is rarefied.

In hydrogen, which has about $\frac{1}{14}$th the density of air, sounds are much feebler, although the pressure is the same. In carbonic acid, on the contrary, which is half as heavy again as air, sounds are more intense. On high mountains, where the air is much rarefied, it is necessary to speak with some effort in order to be heard, and the discharge of a gun produces only a feeble sound. During a severe frost, sounds are heard at a greater distance, because air is then more dense and more homogeneous; and country people will often predict the weather from the sound of the village bell. For the propagation of the sound is modified by the presence of moisture, which alters the elasticity and the density.

iv. *The intensity of sound is modified by the motion of the atmosphere and the direction of the wind.* In calm weather sound is always better propagated than when there is wind; in the latter case, for an equal distance, sound is more intense in the direction of the wind than in the contrary direction.

v. Lastly, *sound is strengthened by the nearness of a sounding body.* A string made to vibrate in free air and not near a sounding body has but a very feeble sound; but when it vibrates above a

unding-box, as in the case of the violin, guitar, or violoncello, sound is much more intense. This arises from the fact that e box and the air which it contains vibrate in unison with the ring. Hence the use of sounding-boxes in stringed instruments.

166. **Influence of tubes on the transmission of sound.**—The minution in the intensity of sound with the distance is due to the ct, that the sound waves are propagated in the form of continually creasing spheres ; and it may indeed be proved geometrically, at since sound is thus transmitted, its intensity must be inversely

Fig. 145.

the square of the distance. If, however, the sound is sent rough a long tube, the waves are propagated in only one direction, nd sound can be transmitted to great distances without appreci- ble alteration. M. Biot found that in one of the Paris water-pipes, 040 yards long, the voice lost so little of its intensity, that a nversation could be kept up at the ends of the tube in a very w tone ; so much so, that in order not to be heard, it was necessary, Biot expressed it, *not to speak at all.* The weakening of sound comes, however, perceptible in tubes of large diameter, or where e sides are rough.

This property of transmitting sounds was first applied in Eng-

land for *speaking tubes*, which are used in hotels and large lishments for transmitting orders. They consist of caou tubes of small diameter, provided at each end with an i bone mouthpiece, and passing from one room to another. person speaks at one end of the tube, he is distinctly hea person applying his ear (fig. 145) at the other end.

One of the most important applications of acoustical pri is the *Stethoscope.* It consists of a cylinder of hard wood foot long and $1\frac{1}{4}$ inch broad at one end, and in which a longi passage is bored. One end of the stethoscope is held agai diseased part of the body, and the ear is held against the othe practised physician can detect the existence of internal by the peculiar sound emitted, and which is strengthened sonance.

167. **Speaking trumpet.**—These instruments are based the reflection of sound, and on its conductibility in tubes.



Fig. 146.

The *speaking trumpet* as its name implies, is used to the voice audible at great distances. It consists of a conical tin or brass tube (fig. 146), very much wider at o (which is called the *bell*), and provided with a mouthpiece other. The larger the dimensions of this instrument the is the distance at which the voice is heard. Its action is ascribed to the successive reflections of sound waves fr

sides of the tube, by which the waves tend more and more to pass in a direction parallel to the axis of the instrument. By means of the speaking trumpet, the word of command can be heard on board ship above the noise of the waves.

168. **Ear trumpet.**—The *ear trumpet* is used by persons who are hard of hearing. It is essentially an inverted speaking trumpet, and consists of a conical metallic tube, one of whose extremities, terminating in a *bell*, receives the sound, while the other end is introduced into the ear (fig. 147). The action of this instrument is the reverse of that of the speaking trumpet. The bell serves as mouthpiece ; that is, it receives the sounds coming from the mouth of the person who speaks. These sounds are transmitted by a series



Fig. 147.

of reflections to the interior of the trumpet, so that the waves which would become greatly developed, are concentrated on the hearing apparatus, and produce a far greater effect than divergent waves would have done.

In man and many animals the outer ear is a trumpet which receives the sound waves. In some animals this part of the auditory apparatus is long and flexible, so that the animal can thus easily recognise the direction from which the sound proceeds.

CHAPTER II.

MUSICAL SOUND. PHYSICAL THEORY OF MUSIC.

169. **Difference between musical sounds and noise.**—Sounds are distinguished from *noises*. Sound properly so called, or *musical sound*, is that which produces a continuous sensation, and the musical value of which can be determined. The only condition necessary for producing a musical sound is that the individual impulses shall succeed each other with sufficient rapidity at equal

intervals of time. Whatever be its origin, whether it be the *ticks* of a watch, or the puffs of a locomotive, if this condition be fulfilled, the coalescence of the separate impressions produces a musical sound.

On the other hand, noise is either a sound of too short a duration to be determined, like the report of a cannon, or else it is a confused mixture of many discordant sounds, like the rolling of thunder, the rattling of a box of nails, or the noise of the waves. Nevertheless, the difference between sound and noise is by no means precise. Savart has shown that there are relations of height in the case of noise, as well as in that of sound, and there are said to be certain ears sufficiently well organised to determine the musical value of the sound produced by a carriage rolling on the pavement.

The action of a noise upon the ear has been compared to that of a flickering light upon the eye; both are painful, in consequence of the sudden and abrupt changes which they impose upon their respective nerves.

170. **Characteristics of musical sounds.**—Musical tones have three leading qualities, namely *pitch*, *intensity*, and *timbre* or *colour*.

i. The *pitch* or *height* of a musical tone is determined by the number of vibrations in a second yielded by the body producing the tone.

ii. The *intensity* or *loudness* of the tone depends on the *extent* of the vibrations. It is greater when the extent is greater, and less when it is less. It is, in fact, nearly or exactly proportional to the square of the extent or amplitude of the vibrations which produce the tone.

iii. The *timbre* is that peculiar quality of tone which distinguishes a note when sounded on one instrument from the same note when sounded on another. Thus when the C of the treble stave is sounded on a violin and on a flute, the two notes will have the same pitch, that is, are produced by the same number of vibrations per second, and they may have the same intensity, and yet the two tones will have very distinct qualities, that is, their timbre is different (179).

171. **Syren.**—The vibrations of any sounding body are so numerous that they cannot be followed by the eye and counted. Various forms of apparatus have been invented for the purpose of determining the number of vibrations corresponding to particular notes. Of these, the one represented in fig. 148, is given as being the simplest and most intelligible. It consists of a circular disc of

ɔoard or of sheet metal about a foot in diameter. This
ɔrated by four concentric series of small equidistant holes.
:ity's sake the inner of
resented as having 12,
15, the third 18, and
24 holes; but a mul-
:se ratios, say 48, 60,
, is more convenient.
sc is made to rotate
d the most convenient
x it on a turning table
n the place of AB.
ıeans of a glass tube,
at one end so as to be
ın the diameter of the
rrent of air is directed



Fig. 148.

: of the series of holes in the rotating disc. A tone is now
:h is tolerably pure when the rotations are sufficiently
the number of vibrations of which can be readily deter-
ıppose, for instance, that there are 48 in the inner series
Then each time a hole passes in front of the glass tube a
wave is produced which reaches the ear in the ordinary
If, for example, the disc makes 16 turns in a second, in
d 16 times 48 or 768 holes, pass in front of the tube, and
ɔroduced 768 waves, which fall upon the ear within a
equal intervals of time. If in like manner the tube were
he second series of holes, while the rotation goes on at
ate, we should hear the tones corresponding to 16 times
vibrations in a second. Thus proceeding in like manner,
g the tube successively from the central to the circum-
ries of holes we hear successively, the fundamental note,
:hird, the fifth, and the octave (173).

mit of perceptible sounds.—Savart, a French physicist,
st to determine the limit of the number of vibrations
ear could perceive. He invented an apparatus for this
ıich is known as *Savart's toothed wheel.* It consists
of a metal wheel with a series of equidistant sharp teeth
ɔhery. This is made to rotate at a uniform rate, and a
ll better, a thin elastic steel plate is held so that in the
the wheel each of the teeth strikes against the plate, and
produces a sound. If, for instance, the rim of the wheel

has 6co teeth, and it is made to rotate 4 times in a second, 2400 impulses are given in a second. The number of impulses depends thus on the velocity of rotation and the sounds produced are pure and continuous.

Thus to determine the number of vibrations corresponding to any particular note, it is simply necessary to turn the wheel at a uniform rate until it produces a note in unison (173) with the one in question. Knowing then the number of teeth on the wheel and the rate of rotation, the number of vibrations can be at once calculated. By means of this apparatus Savart ascertained that the deepest sounds are produced by 16 vibrations in a second. If the number of vibrations is less, no sound is heard. The same physicist found that the highest sound which the ear can perceive corresponds to 48,000 vibrations in a second. Between these two limits it will be seen what an enormous quantity of sounds may be produced and perceived. Yet the sounds used in music, and more especially in singing, are comprised within much narrower limits. Thus the number of vibrations produced by the human voice has been ascertained; and it has been found that the lowest notes of a man's voice are made by 190 vibrations in a second, and the highest notes by 678. The lowest note of a woman's voice corresponds to 572 vibrations, and the highest to 1,606.

173. **Musical scale. Gamut.**—The human ear can distinguish among several sounds not merely which is the highest, or the lowest, but it can also estimate the relations which exist between the numbers of vibrations corresponding to each of these sounds. Not, indeed, that we can say whether one sound produces two or three times as many vibrations as another; but whenever the number of vibrations of two successive or simultaneous sounds are in a simple ratio, these sounds excite in us an agreeable sensation, which varies with the ratio of the vibrations of the two sounds, and which the ear can readily estimate. Hence results a series of sounds characterised by relations which have their origin in the nature of our organisation, and which constitute what is called the *musical scale.*

In this series the sounds are reproduced in the same order, in periods of seven, each period constituting a *gamut*; and the seven sounds or *notes* of each gamut are designated by the names C, D, E, F, G, A, B, or by *ut* or *do*, *re*, *mi*, *fa*, *sol*, *la*, *si*. The first six of these letters are the first syllables of the lines of a hymn which

by the chorister children to St. John, their patron saint, y prayed to be freed from hoarseness; and the word *si* is the first letters of St. John's name.

Ut queant laxis	**re**sonare fibris
Mira gestorum	**fa**muli tuorum
Solve polluti	**la**bii reatum
S ancte	I oannes

ord gamut is derived from gamma, the third letter of the habet, because Guido d'Arezzo, who first (in the eleventh represented notes by points placed on parallel lines, hese lines by letters, and chose the letter gamma to desig- irst line.

agree to represent by 1 the number of vibrations of the ital note C or *do* of the gamut, that is to say, of the ote, experiment shows that the numbers of vibrations of notes of the scale are those given in this table :—

D	E	F	G	A	B	*c*
re	*mi*	*fa*	*sol*	*la*	*si*	*do*
$\frac{9}{8}$	$\frac{5}{4}$	$\frac{4}{3}$	$\frac{3}{2}$	$\frac{5}{3}$	$\frac{15}{8}$	2

able does not give the absolute numbers of the vibrations arious notes, but only their relative numbers. Knowing ute number of vibrations of the fundamental C, we may ose of the other notes by multiplying them by $\frac{9}{8}, \frac{5}{4}, \frac{4}{3}, \ldots$ ectively; and we thus find that at the octave (174), the f vibrations is double that of the fundamental note.

cale may be continued by taking the octaves of these notes , *d*, *e*, *f*, *g*, *a*, *b*, and again the octaves of these last, and

Intervals.—An *interval* is the ratio of one sound to another, ie relation between the numbers of vibrations which pro- ie sounds.

interval between two consecutive notes of the gamut is *second*; such as the interval from *do* to *re*, from *re* to *mi*, to *fa*, and so on.

:ween any two notes which are compared, there are one, e, four, five, or six intermediate notes, these intervals are spectively, a *third*, a *fourth*, *fifth*, *sixth*, *seventh*, and Thus the interval from C to E is a third, that from C to h, from C to G a fifth, from C to A a sixth, and from C to nth, and from C to *c* an octave.

Although two or more notes may be separately musical, it does not follow that, when sounded together, they produce a pleasant sensation. When the ear can distinguish without fatigue the ratio between two sounds, which is the case when the ratio is simple, the accord or co-existence of these two sounds forms a *consonance*; but if the number of vibrations is in a complicated ratio the ear is unpleasantly affected and we have *dissonance.*

The simplest concord is *unison*, in which the numbers of vibrations are equal; then comes the octave, in which the number of vibrations of one sound is double that of the other; then the fifth, where the ratio of the sounds is as 3 to 2; the fourth, of which the ratio is 4 to 3; and lastly, the third, where the ratio is 5 to 4.

If three notes are sounded together they are concordant, when the number of their vibrations are as 4 : 5 : 6. Three such notes form a *harmonic triad*, and if sounded with a fourth note, which is the octave of the lowest, they constitute what is called a *major chord.* Thus C, E, G, form a major triad, G, B, *d* form a major triad, and F, A, *c* form a major triad. C, G, and F have, for this reason, special names, being called respectively, the *tonic, dominant*, and *sub-dominant*, and the three triads the *tonic, dominant*, and *sub-dominant* triads or chords respectively.

If, however, the ratio of any three notes is as 10 : 12 : 15, the three sounds are slightly dissonant, but not so much as to disqualify them from producing a pleasant sensation, at least under certain circumstances. When these three notes and the octave to the lower are sounded together they constitute what in music is called a *minor chord.*

The intervals between the notes in the scale are—

C to D $\frac{9}{8}$.	G to A $\frac{10}{9}$.
D to E $\frac{10}{9}$.	A to B $\frac{9}{8}$.
E to F $\frac{16}{15}$.	B to C $\frac{16}{15}$.
F to G $\frac{9}{8}$.	

It will be seen that there are here three kinds of intervals; the interval $\frac{9}{8}$ is called a *major tone*, and that of $\frac{10}{9}$ a *minor tone*; the relation between the major and the minor tone is $\frac{9}{8} : \frac{10}{9} = \frac{81}{80}$, and is called a *comma.* The interval $\frac{16}{15}$ is called a *major semitone.* The major scale is formed of the following succession of intervals: a major tone, a minor tone, a major semitone, a major tone, a minor tone, a major tone, and a major semitone. It is this succession

ıich constitutes the scale; the key note, or the tonic, may have ıy number of vibrations; but once its height is fixed, that of the her notes are always in the above ratio.

175. **On semitones and on scales with different key notes.**— : is found convenient for the purpose of music to introduce notes ıtermediate to the seven notes of the gamut; this is done by in-reasing or diminishing those notes by an interval of $\frac{25}{24}$, which is alled a *minor semitone.* When a note (say C) is increased by his interval, it is said to be sharpened, and is denoted by the ymbol C♯, called 'C sharp;' that is $C♯ \div C = \frac{25}{24}$. When it is de-reased by the same interval, it is said to be flattened, and is epresented thus—B♭, called 'B flat;' that is, $B \div B♭ = \frac{25}{24}$. If the ffect of this be examined, it will be found that the number of notes ı the scale from C up to *c* has been increased from seven to wenty-one notes, all of which can be easily distinguished by the ar. Thus, reckoning C to equal 1, we have—

C	C♯	D♭	D	D♯	E♭	E	etc.
1	$\frac{25}{24}$	$\frac{27}{25}$	$\frac{9}{8}$	$\frac{75}{64}$	$\frac{6}{5}$	$\frac{5}{4}$	etc.

Hitherto we have made the note C the tonic or *key note.* Any ther of the twenty-one distinct notes above-mentioned, for instance, ♯, or F, or C♯, etc, may be made the key note, and a scale of notes onstructed with reference to it. This will be found to give rise in ach case to a series of notes, some of which are identical with ıose contained in the series of which C is the key note, but most f them different. And of course the same would be true for the ıinor scale as well as for the major scale, and indeed for other ·ales, which may be constructed by means of the fundamental iad.

176. **On musical temperament.**—The number of notes that ·ise from the construction of the scales described in the last ticle is enormous; so much so as to prove quite unmanageable the practice of music; and particularly for music designed for struments with fixed notes such as the pianoforte. Accordingly becomes practically important to reduce the number of notes, hich is done by slightly altering their just proportions. This ·ocess is called *temperament.* By tempering the notes, however, ore or less dissonance is introduced, and accordingly several dif-rent systems of temperament have been devised for rendering is dissonance as slight as possible. The system usually adopted called the system of *equal temperament.* It consists in the sub-

stitution between C and *c* of eleven notes at equal inte
interval being the twelfth root of 2, or 1·05946. By this
distinction between the semitones is abolished, so that, fo
C♯ and D♭ become the same note. The scale of tw
thus formed is called the *chromatic scale.* It of course f
the major triad becomes slightly dissonant. Thus in t
scale, if we reckon C to be 1, E is denoted by 1·25000,
1·50000. On the system of equal temperament if C is
1, E is denoted by 1·25992 and G by 1·49831.

177. **The number of vibrations producing each n
tuning fork.**—Hitherto we have not assigned any num
to that symbol the note C. In the theory of music it
to assign 256 double vibrations to the middle C. Thi
is arbitrary; its justification is the facility with which t
may be subdivided. An instrument is in tune provi
tervals between the notes are correct, when C is yield
number of vibrations per second not differing much
Moreover, two instruments are in tune with one anoth
separately in tune, they have any one note, for instance,
by the same number of vibrations. Consequently, if
ments have one note (say C) in common, they can then
into tune jointly, by having their remaining notes sep
justed with reference to that fundamental note. A *tun
diapason* is an instrument yielding a constant sound, an
a standard for tuning musical instruments. It consists o
steel rod, bent as represented in fig. 149. It is made
either by drawing a bow across the ends, as shown in
or by striking one of the legs against a hard body, or
separating the two legs by means of a steel rod. The vi
duces a note which is always the same for the same tun

The note is strengthened by fixing the tuning fork
open at one end called a *resonance box* (178).

It has been remarked for some years that not only h
of the tuning fork, that is, *concert pitch*, been getting hi
larger theatres of Europe, but also that it is not the same
Paris, Vienna, Milan, etc. This is a source of great inc
both to composers and singers, and a commission wa
to establish in France a tuning fork of uniform pitch, an
a standard which would serve as an invariable type.
ance with the recommendations of that body, a *normal*

has been established, which is compulsory on all musical establishments in France, and a standard has been deposited in the Conservatory of Music in Paris.

It makes 870 single or 435 double vibrations in a second and yields the note *la* of the treble stave ; the *do* or C of the same stave makes thus 261 double vibrations in a second.

The standard tuning fork adopted by the Society of Art in London, on the recommendation of a committee of eminent musicians, makes 264 double vibrations in a second, and gives the middle C

Fig. 149.

of the treble stave. The corresponding a or *la* gives therefore 440 vibrations in a second.

The middle C is the note sounded by the white key immediately on the left of the two black keys which are near the middle of the keyboard of a pianoforte. It is designated in musical notation as . For purposes of comparison it is convenient to call this note $c_{,}$, and the next lower octave c ; the octave lower than this C, and the still lower one $C_{,}$, and so on. The lowest note of grand pianos is $A_{,,}$ which gives 27·2 vibrations in a second.

In like manner the higher octaves are distinguished by affixes,

thus c'' c''' c^{iv} and so forth. In height the pianoforte reaches to a^{iv} with 3,520, or c^{v} with 4,224 vibrations in a second.

The practical range of musical sounds is comprised within 40 and about 4,000 vibrations in a second; or a range or 7 octaves.

178. **Resonance of air.**—The action of the resonance-box in strengthening sound (fig. 149) may be illustrated by the following experiment (fig. 150). AB is a glass cylinder about 8 inches in height, and 1 to 1½ in diameter. If now an ordinary tuning fork be made to vibrate, its sound is very faint, and if it is held

Fig. 150.

over the empty cylinder probably no alteration will be experienced. When, however, water is slowly and noiselessly poured into the cylinder, on reaching a certain height, the previously faint sound is far louder. Any other tuning fork, which yields a different note, if held over the cylinder will not have its note strengthened. Reverting now to the original tuning fork, if while it is still sounding and its sound is being strengthened by its nearness to the cylinder, we continue to pour in water, the sound becomes as faint as it was originally. If now the excess of water be again removed until the tone of the fork is once more strengthened, and if, removing the

fork, we sound the column again by blowing into it, we find that the column of air emits the same note as the tuning fork. Hence when the tuning fork could set a column of air of a particular length in vibration so as to produce the same note; and this adding itself to the original note strengthened it.

179. **Compound musical tones. Harmonics. Overtones.**—We have already seen that there is a peculiar quality or timbre, as it is called, by which the notes of different instruments are characterised. Thus we readily distinguish between the note C when sounded on a pianoforte and the same note sounded on an organ or a trumpet. This peculiarity of the tone is due to the fact that only in very few cases does an instrument give a pure note but that in most cases it is accompanied by a series of upper notes or *harmonics*. To understand what these are we may refer to 191, in which it is stated that by successively intensifying the current of air, we get in a stopped pipe a succession of notes the numbers of whose vibrations are as the series of odd numbers, 1, 3, 5, 7, etc. So too if we similarly sound an open pipe we get the series of notes whose numbers of vibrations are represented by the series of even numbers, 1, 2, 3, 4, 5, etc. These are called respectively the *odd* and *even harmonics* of the primary note.

Now if we sound a particular note on the piano, by a little attention a practised ear can discover that the primary note is accompanied by a series of higher notes each of which gradually gets fainter. These upper notes may be detected, and the compound nature of the primary sound analysed even by an unpractised ear by the use of *resonance globes* which Helmholtz devised for this purpose. These instruments, one of which is represented in fig. 151, are an application of the principle explained in the foregoing paragraph. They are small hollow spheres, the projection *b*, which has a small hole, is placed in the ear while the wider aperture *a* is directed towards the source of sound. Each of these resonators is constructed or tuned for a particular note; so that if having sounded the string of a pianoforte, we hold near it a resonator tuned for a particular note, this note if present will be intensified. Thus, if we depress the key *c*,

Fig. 151.

we hear no particular strengthening if a resonator sounded for be held near the ear; but when the resonators sounded for $c_,g$ $c_{,,}$ are used we hear them powerfully respond when held to the ea Hence the notes $c_,, g_,, c_{,,}$ are contained in the mass of sound whic is produced when the key $c_,$ is depressed.

Helmholtz's researches show that the different timbre o quality of the sounds yielded by different instruments is due to th fact that they are accompanied in each case by special harmonics or overtones in varying intensity.

Helmholtz's principal results are as follows :—

Simple tones—those, that is to say, without any admixture of overtones—are most easily produced when a tuning fork is held near a resonance-box of suitable length. These notes are soft and are free from all sharpness and roughness.

Flute notes are also nearly pure, for their overtones are very feeble. Wide-stopped organ pipes give the fundamental note almost perfectly pure, narrower ones give along with it the fifth of the octave.

Wide open pipes give the octave along with the fundamental note ; and narrow ones give a series of overtones.

The overtones present in the sound of stretched strings depend on their substance and on the manner in which they are made to sound. In good *pianos* the overtones are powerful up to the sixth. *In stringed instruments* the fundamental note is comparatively stronger than in pianos ; the first overtones are feebler, the higher, from the sixth to the tenth, on the contrary, are far more distinct, and produce the penetrating character of the sound of stringed instruments.

Metallic rods and *plates* produce, along with the fundamental note, a series of very high overtones which are discordant with each other, but are continuous and of equal strength with the primary note. Thus is produced that peculiarity known as a metallic sound.

By the occurrence of the lower harmonics along with the primary note the tone is more sonorous, richer and deeper than the primary note; by the occurrence of the higher overtones, the clang acquires its penetrating character.

CHAPTER III.

TRANSVERSE VIBRATIONS OF STRINGS. STRINGED INSTRUMENTS.

180. **Transverse vibrations of strings.**—We have already seen (156), that when an elastic string, stretched at the ends, is removed from its position of equilibrium, it reverts to it as soon as it is let go, making a series of vibrations which produce a sound. The strings used in music are commonly of catgut or metallic wire. The vibrations which strings experience may be either *transversal* or *longitudinal*, but practically the former are alone important. *Transversal vibrations* may be produced by drawing a bow across, the string, as in the case of the violin; or by striking the string, as in the case of the pianoforte; or by pulling them transversely and then letting them go suddenly, as in the case of the guitar and the harp.

181. **Laws of the transverse vibrations of strings.**—The number of transverse vibrations which a string can give in a certain time, that is, the sound it yields, vary with its length, its diameter, its tension, and with its specific gravity in the following manner:

The tension being constant, the number of vibrations in a second is inversely as the length; that is, that if a string makes 18 vibrations in a second for instance, it will make 36 if its length is halved, 54 if its length is one-third, and so on. On this property depends the violin, the contre basso, etc., for in these instruments by pressing the string with a finger, the length is reduced or increased at pleasure, and the number of vibrations, and therewith the note is regulated.

With strings of the same length and tension *the number of vibrations in a second is inversely as the diameter of the string*; that is, the thinner a string, the greater its number of vibrations, and the higher its pitch. In the violin, the treble string, which is the thinnest, makes double the number of vibrations of that which would be made by a string twice its size, that is to say, the diameter of which is twice as great.

The number of vibrations in a second is directly a root of the stretching weight or tension; that is, th tension of a string is four times as great, the number is doubled; when the tension is nine times as great, th trebled, and so on. This, then, furnishes a means of character of a note by stretching, as is done in stri ments.

Other things being equal, *the number of vibrations of a string is inversely as the square root of its dens* the greater the density of the materials of which strin the less easily they vibrate, and the deeper are the yield.

From the preceding laws it will be seen how easy the number of the vibrations of strings and make tl extreme variety of sounds, from the deepest, to the hig music.

182. **Verification of the laws of the vibration: Sonometer.**—This may be effected by means of an called the *sonometer* or *monochord*. It consists of a box to strengthen the sound. On this there are two A and B (fig. 152), over which pass the strings AB,



Fig. 152.

are commonly metal wires. These are fastened at o stretched at the other by a weight P, which can be will. By means of a third movable bridge D, the le portion of the wire which is to be put in vibration ca at pleasure

If two strings are taken, which are identical in all r are stretched by equal weights, they will be found, on t to yield the same sound. If now one of them be div

movable bridge D into two equal parts, the sound yielded by CD will be the higher octave of that yielded by the entire string AB, which shows that the number of vibrations is doubled, and thus verifies the law.

To verify the second law, the bridge D is removed. If the string AB is taken so that it has double the diameter of the other, but both stretched by the same weight, it will be found that the sound which the thinnest string yields is the next higher octave of that yielded by AB; proving thus that the number of vibrations is doubled.

The two strings being of the same diameter, and the same length, if the weight which stretches the one be four times that which stretches the other, the sound yielded by the first is the higher octave of that of the second, which shows that the number of vibrations is doubled; when the weight is nine times as great, the sound is the higher octave of the fifth of the former.

The fourth law is established by using strings of different densities, but of the same dimensions, and stretched to the same extent.

183. **Stringed instruments.**—Stringed musical instruments depend on the production of transverse vibrations. In some, such as the piano, the sounds are *constant*, and each note requires a separate string: in others, such as the violin and guitar, the sounds are *varied* by the fingering, and can be produced by fewer strings.

In the piano the vibrations of the strings are produced by the stroke of the *hammer*, which is moved by a series of bent levers communicating with the keys. The sound is strengthened by the vibrations of the air in the *sounding board* on which the strings are stretched. Whenever a key is struck, a *damper* is raised, which falls when the finger is removed from the key and stops the vibrations of the corresponding string. By means of a *pedal* all the dampers can be simultaneously raised, and the vibrations then last for some time.

The harp is a sort of transition from the instruments with constant to those with variable sounds. Its strings correspond to the natural notes of the scale; by means of the pedals the lengths of the vibrating parts can be changed, so as to produce sharps and flats. The sound is strengthened by the sounding box, and by the vibrations of all the strings harmonic with those played.

In the violin and guitar each string can give a great number of sounds according to the length of the vibrating part, which is de-

termined by the pressure of the fingers of the left ha
right hand plays the bow, or the strings themselves. I
instruments the vibrations are communicated to the t
the sounding box, by means of the bridge over whic
pass. These vibrations are communicated from the
lower face of the box, either by the sides, or by an
piece called the *sound post.* The air in the interior is
tion by both faces, and the strengthening of the sound
by all these simultaneous vibrations. The value of th
consists in the perfection with which all possible so
tensified, which depends essentially on the quality c
and the relative arrangement of the parts.



Fig. 153.

Instruments
of the violin are
to play, and re
delicate ear; but
of skilful artists,
marvellous effec
the very soul of
and the most be
of music have be
for them.

184. **Longitu
tions of strings**
When a violin b
over the string o
chord at a very
an unpleasant
tone is heard. I
of the string be
is no change in
the string be to
middle it yields
when the bow is
it. These ton
duced by longit
tions, their pitc
versely as the l
string, but is in
the thickness and tension. In like manner if a gl
grasped in the middle, and rubbed lengthwise with a

penetrating but not unpleasant tone is produced. It grasped at a quarter of its length and if the shorter part be made to vibrate, the octave of the former tone is obtained.

Marloye's harp, fig. 153, is an arrangement which illustrates the sounds produced by the longitudinal vibration of rods. It consists of a series of deal rods of different lengths and thicknesses. They are sounded by rubbing the rods lengthwise with resined fingers. A series of notes of varying pitch is thus produced, which by a skilful artist is far from unpleasing.

The *tuning-fork*, the *triangle*, and *musical boxes* are examples of the transverse vibration of rods. In musical boxes small plates of steel of different dimensions are fixed on a rod, like the teeth of a comb. A cylinder whose axis is parallel to this rod, and whose surface is studded with steel teeth, arranged in a certain order, is placed near the plates. By means of a clockwork motion the cylinder rotates, and the teeth striking the steel plates set them in vibration, producing a tune, which depends on the arrangement of the teeth on the cylinder.

CHAPTER IV.

SOUND PIPES AND WIND INSTRUMENTS.

185. **Production of sound in pipes.**—Sound pipes are hollow pipes or tubes in which sounds are produced by making the enclosed column of air vibrate. In the cases hitherto considered the sound results from the vibrations of solid bodies, and the air only serves as a vehicle for transmitting them. In wind instruments, on the contrary, when the sides of the tube are of adequate thickness, the enclosed column of air is the sounding body. In fact, the substance of the tubes is without influence on the primary tone; with equal dimensions it is the same whether the tubes are of glass, of wood, or of metal. These different materials simply do no more than give rise to different harmonics, and impart a different timbre to the compound tone produced.

If tubes were simply blown into, there could be no sound; there would merely be a continuous progressive motion of the air. To produce a sound, by some means or other a rapid succession of

condensations and rarefactions must be produced, which are then transmitted to the whole column of air in the tube. Hence the necessity of having a *mouthpiece*, that is, the end by which air enters, so shaped that the air enters in an intermittent, and not a continuous manner. From the arrangement made use of to set the enclosed air in vibration, wind instruments are divided into *mouth* instruments and *reed* instruments.

186. **Mouth instruments.**—In mouth instruments all parts of the mouthpiece are fixed. The pipes are either of wood or metal,



Fig. 154. Fig. 155. Fig. 156. Fig. 157. Fig. 158.

rectangular or cylindrical, and are always long as compared wit the diameter. Fig. 154 represents a wooden rectangular orga pipe; fig. 155 gives a longitudinal section by which the interna details are seen. The lower part P, by which air enters, is calle the *foot*; it emerges through a narrow slit *i*, and, on the opposi

side, is a transverse aperture called the *mouth*; *a* and *b* are the *lips*, the upper one of which is bevelled.

The current of air arriving by the mouth, strikes against the upper lip, is compressed, and by its elasticity reacts upon the current and stops it. This, however, only lasts for an instant, for, as the air escapes at *ab*, the current from the foot continues, and so on for the whole time.

In this way, pulsations are produced, which, transmitted to the air in the pipe, make it vibrate, and a sound is the result. In order that a pure note may be produced, there must be a certain relation between the form of the lips and the magnitude of the mouth; the tube also ought to have a great length in comparison with its diameter. The number of vibrations depends in general on the dimensions of the pipe and the velocity of the current of air.

The mouthpiece we have described is used in organs. Fig. 156 represents another modification much in use in organ playing, and fig. 157 gives a longitudinal section. The letters indicate the same parts as in fig. 155. Fig. 158 shows the mouthpiece of a flageolet and whistle. In the German flute the mouthpiece consists of a small lateral circular aperture in the pipe. By means of his lips the player causes the current of air to graze against the edge of this aperture.

187. **Reed instruments.**—In reed instruments the air is set in vibration by means of elastic tongues or plates, which are called *reeds*, and which are divided into free reeds and beating reeds.

Beating reed. This consists of a piece of wood or metal, *a* (fig. 160), which is grooved like a spoon. It is fixed to a kind of stopper, K, perforated by a hole, which connects the cavity with a long pipe, T. The groove is covered by a brass plate, *l*, which is called the *tongue*. In its ordinary position this is slightly away from the edges of the groove, but being very flexible, readily approaches, and closes it. Lastly, a curved wire *br*, presses against the tongue, and can be moved up and down.

The vibrating part of the tongue can thereby be shortened or lengthened at will, and the number of vibrations thus regulated. By means of this wire, reed pipes are tuned.

The reed is fitted to the top of a rectangular pipe KN, called the *wind channel*. This is closed everywhere, except at the bottom, where it can be fitted on a bellows. In models of reed pipes used in illustrating lectures, the sides of the upper part of

the tube are made of glass, so as to show the construction of the reed. This arrangement is represented in fig. 159.

When air arrives in the wind channel, it first passes between the tongue and the groove, and escapes by the pipe T ; but as the velocity increases, the tongue strikes against the edge of the groove, and closing it completely, the current is stopped. But, in virtue of its elasticity, the tongue reverts to its original position,



Fig. 159.

Fig. 160.



Fig. 161.

and thus by a series of alternate openings and closings, the same series of pulsations are produced as in mouth instruments ; hence is formed a sound which is higher the more rapid the current air.

Free reed. Grenié invented in 1810 a kind of reed called a *free reed*, because the tongue, instead of striking against the edges of the groove, like the reed described above, grazes them so as to oscillate backwards and forwards. The groove consists, in this case

of a small wooden box, *ac*, fig. 161, the front of which is of brass plate. In the middle of this is a longitudinal slit, in which is applied the tongue, which can oscillate freely backwards and forwards so as to allow air to pass, which it closes each time it grazes the edges of the slit. In this case also a wire, *r*, regulates the length of the vibrating part of the tongue.

A reed can be very simply made from a piece of straw. About an inch from a knot an incision is made at *r*, (fig. 162), with a

Fig. 162.

sharp penknife, which is about a quarter as deep as the diameter of the straw ; and then by laying the knife flat the straw is slit as far as the knot ; the strip *r r*, thus produced forms a reed joined with the pipe *s r*. The note of this pipe depends on the length of the tube *s r* and is higher the shorter the tube is made. In order to sound the pipe, the whole length of the reed is placed in the mouth and the lips firmly closed.

188. **Bellows.**—In acoustics a *bellows* is an apparatus by which wind instruments, such as the syren and organ pipes, are worked. Between the four legs of a table there is a pair of bellows, S (fig. 163), which is worked by means of a pedal, P. D is a reservoir of flexible leather, in which is stored the air forced in by the bellows. If this reservoir is pressed by means of weights on a rod, T, moved by the hand, the air is driven through a pipe, A, into a *wind* chest, *mn*, fixed on the table. In this chest there are small holes closed by leather valves *s* (fig. 164). These can be opened by pressing on keys, *a*, in front of the box. Below the valve is a spring, *r*, which raises the valve when the key is not depressed. The sound pipe is placed in one of these holes.

189. **Nodes and loops.**—Experiment shows, that when a pipe is sounded, the column of air is subdivided into equal parts, vibrating in unison, and separated by surfaces where the velocity of air is null. These fixed parts are called *nodes* : and the parts between the nodes where the column of air is in a state of vibration is called a *loop*, or a *ventral* segment.

It will be seen afterwards, that one and the same pipe may be made to yield several sounds, and that the nodes and ventral segments then alter their position. When a pipe closed at one end, *a*

stopped pipe, is made to yield its fundamental sound, that is, the deepest one, the bottom is always a node, and the mouthpieces a ventral segment. An open pipe when sounded has a ventral segment at each end ; and if it yields the fundamental sound, there is a single node in the middle.



Fig. 163.

Fig. 164.

When an aperture is opened in the side of a sounding pipe, the sound does not change if the aperture corresponds to a loop ; but if it corresponds to a node. the sound is altered, for this node then becomes a loop. This property is used in wind instruments like the flute, the clarionet, along which holes are made which can be closed by the fingers, or by the aid of keys.

The formation of nodes and loops is far from being restricted to sounding tubes. Strings, plates and membranes, when they vibrate, exhibit parts which are fixed, and parts which are very mobile, that is to say, nodes and loops.

90. **Laws of the vibration of air in pipes.**—The vibrations ir in pipes present two cases according as they are *open* or *ed.*

Laws of stopped pipes. When having placed a stopped pipe on ellows, air is slowly passed, the deepest note, the fundamental d, is produced. If, then, we denote by 1 the corresponding ber of vibrations, when the current of air is forced, we suddenly the sound corresponding to 3; and if the wind be still more ed, we have successively the sounds 5, 7, etc.; that is to say, nds which by their pitch correspond to vibrations 3, 5, 7, etc. s as numerous as those of the fundamental sound. Hence *d pipes, when the air is forced, give successively sounds re-ented by the series of odd numbers.*

The sounds 3, 5, 7, etc., are called the *harmonics* of fundamental note 1.

2. *With pipes of different lengths, the number of rations corresponding to the fundamental note are in-ely as the lengths;* that is to say, that a pipe, which alf as long as another, will yield a sound which is the ve of that yielded by this pipe.

Fig. 165.

Laws of open pipes. The fundamental note being represented by unity, the harmonics obtained by ng the wind are successively represented by 2, 3, 4, etc., that is, *by the natural series of numbers.*

The fundamental note of an open pipe is always an e higher than the fundamental note of a closed pipe e same length.

These laws are known as Bernouilli's laws from the e of their discoverer, Daniel Bernouilli.

91. **Pitch pipe.**—Instead of organ pipes of various ths and bellows, these laws may be conveniently onstrated by means of a *pitch* pipe, fig. 165, which small sound pipe with a movable graduated stopper. aving closed the pipe at its full length, we blow into e get the fundamental note of the stopped pipe, say f now we blow into it more strongly we get the note hich is the major fifth of the higher octave of c, and e strongly still the note $e_{,,}$ which is the major third of its nd octave, and so on for the others.

n like manner having just closed the pipe, if we push in the per until its length is one half and sound it, we get the higher

octave of the fundamental note, by making it $\frac{1}{3}$ its original length we get the major third of c, and so for any other aliquot part.

By removing the stopper altogether we have an open pipe, and the note c which it yields is the octave of the stopped one, and this sounded by increasingly powerful currents of air gives the following series of notes, $c_{,}$ $c_{,,}$ $g_{,,}$ $c_{,,,}$ $e_{,,,}$ and so forth.

192. **Wind Instruments.**—Wind instruments are straight or curved tubes, which are sounded by means of a current of air forced into them. They have all an aperture by which air is forced into them, and, according to the form of this aperture, they are divided into mouth instruments and reed instruments; in some, such as the organ, the notes are *fixed*, and require a separate pipe for each note; in others the notes are *variable*, and are produced by only one tube; the flute, horn, etc., are of this class.



Fig. 166.

The Pandæan pipe, the flageolet, and the German flute are mouth instruments. The principal reed instruments are the clarionet, the oboe, the cornopean, and the bassoon.

The *Pandæan pipe*, fig. 166, consists of tubes of different sizes corresponding to the different notes of the gamut.

In the *organ* the pipes are of various kinds, namely, mouth pipes, open and stopped, and reed pipes with apertures of various shapes. The air is furnished by means of bellows, from which it passes into the wind chest, and thence into any pipe which is desired; this is effected by means of valves which are opened by depressing keys like those of the piano. In the larger and richer organs there are several rows of key-boards arranged at different heights.

In the *flute*, the mouthpiece consists of a simple lateral circular aperture; the current of air is directed by means of the lips, so that it grazes the edge of the aperture. The holes at different distances are closed either by the fingers or by keys; when one of

ıed, a loop is produced in the corresponding layer
ɔdifies the distribution of nodes and loops in the
ıs alters the note. The whistling of a key is
ed.

ıments. In the trumpet, the horn, the trombone, and ophicleide, the lips form the reed, and vibrate
ːe (fig. 167), which terminates in a
ˈ which it can be affixed to the
the *horn*, different tones are pre-
g the distance of the lips. In the
rt of the tube slides within the other,
er can alter at will the length of the
produce higher or lower notes. In
'on, the tube forms several convo-
placed at different distances can,
ut off communications with other
ː, and thus alter the length of the
ı of air.

Fig. 167.

ıman Voice.—If we bevel off the
ː of gutta-percha or of wooden tubing, so that two
, and if now two pieces of thin vulcanised india-
er be stretched and tied between them so as to
slit, we have then a sort of membranous reed pipe
if we blow into the tube we get a note which is
r the lips are stretched;
ɔns of the lips which
be distinctly seen.
experiment well illus-
ɛr in which the sound
ıice is produced in the
ˌ of the windpipe. The
es narrow towards the
ılit, formed by elastic
chords.
oined back and front

Fig. 168.

ɔf the windpipe, and can be more or less tightly
ıeans of various muscles. The human voice
egarded as a reed pipe formed by two elastic

l sonorous part of the human voice is formed by the
acquire their special sound by the fact that to pro-

duce them in each case, the cavity of the mouth spontaneously alters its shape and thus acts as a special resonator to each sound. The consonants are noises which formed by the lips, tongue, and teeth accompany the vowels at their commencement and cessation.

The sounds by which the consonants are produced are much less intense than the vowel sounds. Hence they are inaudible at distances at which the vowel sounds can be distinctly heard. Therefore, in speaking with people hard of hearing, it is by no means necessary to speak louder, but it is sufficient to intensify the consonants. Indeed, distinctness of speech does not depend on loud screaming, but is produced by careful articulation.

BOOK V.

HEAT.

CHAPTER I.

GENERAL EFFECTS OF HEAT. THERMOMETERS.

194. **Heat. Hypothesis as to its nature.**—The sensations of heat and cold are familiar to all of us. In ordinary language the term *heat* is not only used to express a particular sensation, but also to describe that particular state or condition of matter which produces this sensation. Besides this effect, heat acts variously upon bodies; it melts ice, boils water, makes metals red-hot, and so forth.

Two theories as to the cause of heat are current at the present time; these are the *theory of emission*, and the theory of *undulation*.

On the first theory, heat is caused by a subtle imponderable fluid, which surrounds the molecules of bodies, and which can pass from one body to another. These *heat atmospheres*, which thus surround the molecules, exert a repelling influence on each other, in consequence of which heat acts in opposition to the force of cohesion. The entrance of this substance into our bodies produces the sensation of warmth, its egress the sensation of cold.

On the second hypothesis the heat of a body is caused by an oscillating or vibratory motion of its material particles, and the hottest bodies are those in which the vibrations have the greatest velocity and the greatest amplitude. Hence, on this view, heat is not a *substance*, but a *condition of matter*, and a condition which can be transferred from one body to another. It is also assumed that there is an imponderable elastic ether, which pervades all bodies and infinite space, and is capable of transmitting a vibratory motion with great velocity. A rapid vibratory motion of this ether produces heat, just as sound is produced by a vibratory motion of

atmospheric air, and the transference of heat from on another is effected by the intervention of this ether.

This hypothesis is now admitted by the most dis physicists; it affords a better explanation of the phe heat than any other theory, and it reveals an intimate between heat and light. In accordance with it, heat *of motion*; and it will hereafter be shown that heat m verted into motion, and, conversely, motion may be con heat.

Although the undulatory theory of heat is the correc one, that is, which bests explains and accounts for th number of facts, yet it may be sometimes convenie language which is based on the older hypothesis. Thus, ir of a body becoming heated or cooled, we say that it gai heat: in reality, the motion of the particles is inc diminished.

In what follows, however, the phenomena of heat w sidered, as far as possible, independently of either hypot

195. **General effects of heat.**—The general action of bodies is to develope a repulsive force between their which is continually struggling with molecular attractio its influence, therefore, bodies tend to *expand*—that is, tc greater volume.

All bodies expand by the action of heat. As a ge gases are the most expansible, then liquids, and, lastly, so expansion of bodies by heat is thus a new general pro added to those already studied.

The action of heat upon bodies is not merely to exp when accumulated in sufficient quantity, bodies first solidity and become somewhat softer; then, as the he creases, the force of repulsion balances molecular attra then bodies liquefy. Wax, resin, sulphur thus pass re the solid to the liquid state; heat thus produces in solids of state of aggregation. But in liquids it also produces change. When bodies are heated they first expand; h more their molecular attraction is again overcome by th repulsion, and bodies are then changed into aëriform liqu vapours.

If, instead of becoming accumulated in bodies, heat is that is, if bodies are cooled instead of being heated, the phenomena are produced: the molecules come nearer e

ıe volume of the pores diminishes, and hence that of the body, hich is expressed by saying that the body *contracts.* By cooling, apours, losing their elastic force, revert to the liquid state; and quids themselves, by the same process, gradually return to the olid state. Thus water changes into ice, and mercury becomes as ard as lead.

Thus, according as heat accumulates in, or is dissipated by, odies, two physical effects may be produced: 1, Changes in volume, onsisting in expansions and contractions. 2. Changes of condiion, that is, the change of solids into liquids, of liquids into vapours, nd conversely. We shall first discuss the expansion of bodies, and fterwards their changes of state.

196. **Expansion.**—All bodies are expanded by heat, but to very lifferent extents. Gases are most expansible, then liquids, and ıfter them solids.

In solids which have definite figures, we can either consider the :xpansion in one dimension, or the *linear* expansion; in two dimenions, the *superficial* expansion, or in three dimensions, the *cubical* :xpansion or the expansion of volume, although one of these never akes place without the other. As liquids and gases have no lefinite shapes, we can only consider the alterations of volume, which hey undergo.



Fig. 169.

To show the linear expansion of solids, the apparatus represented in fig. 169 may be used. A metal rod, A, is fixed at one end by

a screw, B, while the other end presses against the s
of an index, D, which moves on a scale. Below the ro
a sort of cylindrical lamp in which spirit is burned.
D, is at first at the zero point, but, as the rod becc
the needle moves along the scale, which shows that tl
C, of the lever is slightly displaced, pushed by the r
expands.

It will be observed that if rods of different metals
index will be moved to different extents, showing that
sibility differs. Thus it will be found that brass is mo
than iron, or steel.

The cubical expansion of solids is shown by a
ring. It consists of
a (fig. 170), which
ary temperature p
through a ring, *m*,
same diameter. B
ball has been heate
and no longer pas
the ring. It does
on reverting to its
perature. The exp
liquids and gases,
greater than that
easily shown. Fo
glass tube with a
end may be used
which is filled with
coloured alcohol or



Fig. 170.

instance. When the bulb is gently heated, by placin
water, for example, the column of liquid is seen to ri
ably in the tube ; thus from *a* to *b*.

The experiment may be made in a similar manner
yet as they are far more expansible than liquids, a lon
twice may be fused to the bulb tube, as represented
An index of mercury, *m*, is introduced in the tube, whic
by gently heating the bulb so as to expel some of the
of mercury being then placed in the funnel, *a*, on co
in the bulb and the tube contracts, and the pressure
sphere forces the droplet to *m* for instance. The app
thus arranged, if the bulb is held in the hand for a fe

sed air expands sufficiently to force the index from *m* to
ansion which is far greater than in the case of liquids.
thus be seen that the general
heat upon bodies is to expand
et this only applies to bodies
:e the metals, glass, etc. do not
ıoisture. Bodies which absorb
such as wood, paper, clay,
a contraction when heated,
the increase of temperature ex-
oisture from their pores. Thus
heet of paper placed before the
ıp on the heated side. Coopers,
rve the staves of barrels, heat
one side, by lighting a fire in
: of the barrel when the staves
ed close together. The part
wards the fire contracts in dry-
curves on the side exposed to
n of heat.

Fig. 171. Fig. 172.

REMENT OF TEMPERATURES.
THERMOMETRY.

Temperature. — The *tempe-*
hotness of a body may be de-
ɔeing the greater or less extent
it tends to impart sensible heat
ɔodies. The temperature of any particular body is varied,
g to it or withdrawing from it a certain amount of sensible
he temperature of a body must not be confounded with
tity of heat it possesses ; a body may have a high tempe-
ıd yet have a very small quantity of heat, and conversely
nperature may yet possess a large amount of heat. If a
ıter be taken from a bucketful, both will indicate the same
ure, yet the quantities of heat they possess will be different.
ject of the quantity of heat will be afterwards more fully
l in the chapter on SPECIFIC HEAT.

Thermometers.—*Thermometers* are instruments for mea-
mperatures. Owing to the imperfections of our senses we
ıle to measure temperatures by the sensations of heat or

cold which they produce in us, and for this purpose recourse must be had to the physical effects of heat upon bodies. The most accurate and the most convenient are the expansive effects. Solids, having but little expansibility, can only be used to examine large intervals of temperature; gases, on the other hand, are very expansible, and only serve to measure small alterations of temperature. They are, moreover, affected by changes of atmospheric pressure. For these reasons, liquids are best suited for the construction of thermometers. Mercury and alcohol are the only ones used—the former because its expansion is regular, and it only boils at a very high temperature, and the latter because it does not solidify at the greatest known cold.

Fig. 173.

Fig. 174.

The mercurial thermometer is the most extensively used. It consists of a capillary glass tube, at the end of which is blown the *bulb*, a cylindrical or spherical reservoir (fig. 173). Both the bulb and a part of the stem are filled with mercury, and the expansion is measured by a scale graduated either on the stem itself (fig. 178), or on a frame to which it is attached (fig. 177).

The filling of the tube with mercury is effected by fusing to the tube a small funnel as shown in fig. 173. In this is placed a small quantity of mercury, and the bulb is then gently heated by a spirit lamp. The expanded air partially escapes by the funnel, and on cooling, the air which remains contracts, and a portion of the mercury passes into the bulb. The bulb is then again warmed, and allowed to cool, a fresh quantity of mercury enters, and so on, until the bulb and part of the tube are full of mercury. The mercury is then heated to boiling; the mercurial vapours in escaping carry with them the air and moisture which remain in the tube. The tube being full of the expanded mercury and of mercurial vapour, is hermetically sealed

at one end. When the thermometer is cold the mercury ought to fill the bulb and a portion of the stem.

199. **Graduation of the thermometer.**—The thermometer having been filled, as has just been described, whenever the temperature rises or sinks, the mercury rises or sinks in the stem, and these variations furnish a means of measuring temperatures. For this purpose a graduated scale must be constructed along the stem. In graduating the scale two points must be fixed, which represent identical temperatures and which can always be easily produced.

Experiment has shown that ice always melts at the same point whatever be the degree of heat, and that distilled water under the same pressure, and in a vessel of the same kind, always boils at the same temperature. Consequently, for the first fixed point, or *zero*, the temperature of melting ice has been taken; and, for a second fixed point, the temperature of boiling water in a metallic vessel under the normal atmospheric pressure of 30 inches.

This interval of temperature, that is, the range from zero to the boiling point, is taken as the unit for comparing temperatures; just as a certain length, a foot or a yard for instance, is used as a basis for comparing lengths.

Fig. 175.

To obtain zero, snow or pounded ice is placed in a vessel, in the bottom of which is an aperture by which water escapes (fig. 175). The bulb and a part of the stem of the thermometer are immersed in this for about a quarter of an hour; the mercury sinks, and the level at which it finally rests, *t* for instance, is marked by tying a piece of thread round the stem.

The second fixed point is determined by means of tl
represented in fig. 176. It consists of a tin-plate vesse

Fig. 176.

Fig. 177.

distilled water, in the lid of which is a long tube. T
meter is placed in this by means of a cork, and the wa

to boiling. The thermometer is thus surrounded by steam, which, liberated from the liquid escapes by the lateral apertures. This steam is at the same temperature as the water from which it is liberated, and, when the mercury is stationary, a second mark is made upon the stem.

200. **Construction of the scale.**—Just as the foot-rule which is adopted as the unit of comparison for length is divided into a number of equal divisions called inches, for the purpose of having a smaller unit of comparison, so likewise the unit of comparison of temperatures, the range from zero to the boiling point, must be divided into a number of parts of equal capacity called *degrees*. There are three modes in which this is done. On the Continent, and more especially in France, this space is divided into 100 parts, and this division is called the *Centigrade* or *Celsius* scale; the latter being the name of the inventor. The Centigrade thermometer is almost exclusively adopted in foreign scientific works, and as its use is gradually extending in this country, it has been and will be adopted in this book.



Fig. 178.

The degrees are designated by a small cipher placed a little above on the right of the number which marks the temperature, and to indicate temperatures below zero the minus sign is placed before them. Thus -15° signifies 15 degrees below zero.

In accurate thermometers the scale is marked on the stem itself (fig. 178). It cannot be displaced, and its length remains fixed, as glass has very little expansibility. This is effected by covering the stem with a thin layer of wax, and then marking the divisions of the scale, as well as the corresponding numbers, with a steel point. The thermometer is then exposed for about ten minutes to the vapours of a substance called *hydrofluoric acid*, which attacks the glass where the wax has been removed. The rest of the wax is then removed, and the stem is found to be permanently etched.

Scales are also constructed on plates of ivory, wood, or metal, against which the stem is placed. Fig. 177, represents a mercury thermometer mounted on ivory; its scale extends from 20 degrees below zero to 110 degrees above.

Besides the *Centigrade* scale two others are frequently used—*Fahrenheit's scale* and *Réaumur's scale*.

In Réaumur's scale the fixed points are the same as on the Centigrade scale, but the distance between them is divided into 80 degrees instead of into 100. That is to say, 80 degrees Réaumur are equal to 100 degrees Centigrade; one degree Réaumur is equal to $\frac{100}{80}$ or $\frac{5}{4}$ of a degree Centigrade, and one degree Centigrade equals $\frac{80}{100}$ or $\frac{4}{5}$ degree Réaumur. Consequently to convert any number of Réaumur degrees into Centigrade degrees (20 for example), it is merely necessary to multiply them by $\frac{5}{4}$ (which gives 25). Similarly, Centigrade degrees are converted into Réaumur's by multiplying them by $\frac{4}{5}$.

The thermometric scale invented by Fahrenheit in 1714 is still much used in England, and also in Holland and North America. The higher fixed point is like that of the other scales, the temperature of boiling water, but the null-point or zero is the temperature obtained by mixing equal weights of sal-ammoniac and snow, and the interval between the two points is divided into 212 degrees. The zero was selected because the temperature was the lowest then known, and was erroneously thought to represent *absolute cold.* When Fahrenheit's thermometer is placed in melting ice it stands at 32 degrees, and, therefore, 100 degrees on the Centigrade scale are equal to 180 degrees on the Fahrenheit scale, and thus 1 degree Centigrade is equal to $\frac{9}{5}$ degree Fahrenheit, and conversely 1 degree Fahrenheit is equal to $\frac{5}{9}$ of a degree Centigrade.

If it be required to convert a certain number of Fahrenheit degrees (95 for example) into Centigrade degrees, the number 32 must be first substracted, in order that the degrees may count from the same point of the scale. The remainder in the example is thus 63, and as 1 degree Fahrenheit is equal to $\frac{5}{9}$ of a degree Centigrade, 63 degrees are equal to $63 \times \frac{5}{9}$ or 35 degrees Centigrade.

If F be the given temperature in Fahrenheit's degrees and C the corresponding temperature in Centigrade degrees, the former may be converted into the latter by means of the formula

$$(F - 32)\ \tfrac{5}{9} = C,$$

and conversely, Centigrade degrees may be converted into Fahrenheit by means of the formula

$$\tfrac{9}{5}C + 32 = F.$$

These formulæ are applicable to all temperatures of the two scales, provided the signs are taken into account. Thus, to convert the

nperature of 5 degrees Fahrenheit into Centigrade degrees we ıve

$$(5-32)\tfrac{5}{9} = \frac{-27\times 5}{9} = -15\text{C.}$$

In like manner we have for converting Réaumur's into Fahrenheit's degrees the formula

$$\tfrac{4}{9}\text{R} + 32 = \text{F.},$$

nd conversely, for changing Fahrenheit's into Réaumur's degrees ıe formula

$$(\text{F}-32)\tfrac{4}{9} = \text{R.}$$

201. **Alcohol thermometer.**—The *alcohol thermometer* differs ·om the mercurial thermometer in being filled with coloured lcohol. But as the expansion of liquids is less regular in proporion as they are near the boiling point, alcohol, which boils at 78° C., xpands very irregularly. Hence, alcohol thermometers are usually raduated by placing them in baths at different temperatures toether with a standard ıercurial thermometer.

The filling is effected y gently heating the bulb, o as to expel a certain uantity of air, then inerting it and plunging the pen end into alcohol (fig. 79). The interior air ontracts on cooling, and ıe atmospheric pressure iises the alcohol in the ibe and in the bulb. It ›es not at first fill it ›mpletely, for some air mains; but the alcohol is then boiled, and its vapours expel l the air; the tube is then again inverted and placed in alcohol, ıd now the instrument fills completely. The further construction sembles that of a mercurial thermometer.



Fig. 179.

202. **Limits to the employment of mercurial thermometers.** ·Of all thermometers in which liquids are used, the one with ercury is the most useful, because this liquid expands most reılarly, and is easily obtained pure, and because its expansion beveen −36° and 100° is *regular*, that is, proportional to the degree

of heat. It also has the advantage of having a very low specific heat. But for temperatures below $-36°$ C. the alcohol thermometer must be used, for mercury solidifies at $-40°$ C. to a mass like lead. Above 100 degrees the coefficient of expansion increases and the indications of the mercurial thermometers are only approximate, the error amounting sometimes to several degrees. Mercurial thermometers also cannot be used for temperatures above 350°, for this is the boiling point of mercury.

Observations by means of the thermometer. In taking the temperature of a room, the thermometer is usually suspended against the wall. This may, however, give rise to an error of several degrees; for if the wall communicates with the outside, and especially if it has a northern aspect, it will, generally speaking, be colder than the air in the room, and will communicate to the thermometer too low a temperature. On the other hand it may happen that the wall becomes too much heated by the sun's rays, or by chimney flues, and then the thermometer will be too high. The only way to obtain with accuracy the temperature of the air in a room is to suspend the thermometer by a string in the centre at a distance from any object which might raise or lower its temperature. The same remark applies to the determination of the temperature of the atmosphere; the thermometer must be suspended in the open air, in the shade, and not against a wall.



Fig. 180.

203. **Leslie's differential thermometer.**—Sir John Leslie constructed a thermometer for showing the difference in temperature of two neighbouring places, from which it has received the name *differential thermometer.* It consists of two glass bulbs containing air, and joined by a bent glass tube of small diameter fixed on a frame (fig. 180). Before the apparatus is sealed, a coloured liquid is introduced in sufficient quantity to fill the horizontal part of the tube and about half the vertical legs. It is important to use a liquid which does not give off vapours at ordinary temperatures, and dilute sulphuric acid coloured with litmus is generally preferred. The apparatus being closed, the air is passed

n one bulb into the other, by heating them unequally, until the el of the liquid is the same in both branches. A zero is marked each end of the liquid column. To graduate the apparatus, of the bulbs is raised to a temperature 10° higher than the er. The air of the first is expanded and causes the column of uid, *ba*, to rise in the other leg. When the column is stationary number 10 is marked on each side at the level of the liquid, the tance between zero and 10 being divided into 10 equal parts, h above and below zero, on each leg.

204. **Rutherford's maximum and minimum thermometers.**— is necessary, in meteorological observations, to know the highest nperature of the day, and the lowest temperature of the night. dinary thermometers could only give these indications by a con- uous observation, which would be impracticable. Several in- uments have accordingly been invented for this purpose, the nplest of which is Rutherford's. On a rectangular piece of plate ss (fig. 181) two thermometers are fixed, whose stems are bent



Fig. 181.

izontally. The one, A, is a mercurial, and the other, B, an ohol thermometer. In A there is a small piece of iron wire, A, ving freely in the tube, which serves as an index. The ther- meter being placed horizontally, when the temperature rises the rcury pushes the index before it. But as soon as the mercury ntracts, the index remains in that part of the tube to which it has n moved, for there is no adhesion between the iron and the rcury. In this way the index registers the highest temperature ch has been obtained; in the figure this is 31°. In the minimum mometer there is a small hollow glass tube which serves as x. When it is at the end of the column of liquid, and the tem- ture falls, the column contracts and carries the index with it,

in consequence of adhesion, until it has reached the greatest contraction. When the temperature rises, the alcohol expands, and passing between the sides of the tube and the index does not displace B. The position of the index gives therefore the lowest temperature which has been reached : in the figure this was 9½ degrees below zero.

205. **Pyrometers.**—The name *pyrometers* is given to instruments for measuring temperatures so high that mercurial thermometers could not be used. The older contrivances for this purpose, Wedgwood's, Daniell's (which in principle resembled the apparatus in fig. 170), Brongniart's, etc., are gone entirely out of use. None of them gives an exact measure of temperature.

CHAPTER II.

RADIATION OF HEAT.

206. **Radiant heat.**—If we stand in front of a fire, or expose ourselves to the sun's heat, we experience a sensation of warmth which is not due to the temperature of the air, for if a screen be interposed, the sensation immediately disappears, which would not be the case if the surrounding air had a high temperature. Hence bodies can send out rays which excite heat, and which penetrate through the air without heating it, as rays of light through transparent bodies. Heat thus propagated is said to be *radiated*; and we shall use the term *ray of heat*, or *thermal*, or *calorific ray*, in a similar sense to that in which we use the term *ray of light*, or *luminous ray*.

We shall find that the property of radiating heat is not confined to incandescent substances, such as a fire, or a lamp, or a red-hot ball, but that bodies of all temperatures radiate heat. Thus a bottle full of hot water and a bottle full of cold water both emit heat; the first emits more as compared with the second, the greater the difference of temperature between the two.

207. **Laws of radiation.**—The radiation of heat is governed by three laws.

I. *Radiation takes place in all directions round a body.* If a thermometer be placed in different positions round a heated body, it indicates everywhere a rise in temperature; at equal distances from the source of heat it indicates the same rise in temperature.

II. *Heat is propagated in a right line.* For, if a screen be placed
n the right line which joins the source of heat and the thermometer,
o as to stop the rays, the latter is not affected.

But in passing obliquely from one medium into nother, as from air into a glass, calorific like luminous ays become deviated, an effect known as *refraction.* The laws of this phenomenon are the same for heat us for light, and they will be more fully discussed nder the latter subject.



Fig. 182.

III. *Radiant heat is propagated in vacuo as well as in air.* This is demonstrated by the following experiment.

In the bottom of a glass flask a thermometer is fixed in such a manner that its bulb occupies the centre of the flask (fig. 182). The neck of the flask is then carefully narrowed by means of the blow-pipe, and then the apparatus having been suitably attached to an air-pump a vacuum is produced in the interior. This having been done, the tube is sealed at the narrow part. On immersing this apparatus in hot water, or on bringing near it some hot charcoal, the thermometer is at once seen to rise. This could only be due to radiation through the vacuum in the interior, for glass is so bad a conductor, that the heat could not travel with this rapidity through the sides of the flask, and the stem of the thermometer.

208. **Causes which modify the intensity of radiant heat.**—The *intensity of radiant heat* transmitted to us by heated bodies depends on the temperature of the source of heat, and on its distance. The corresponding laws may be thus stated :

I. *The intensity of radiant heat is proportional to the temperature of the source.*

II. *The intensity of radiant heat is inversely as the square of the distance.*

The first law is demonstrated by placing a metal box containing water at 10°, 20°, or 30°, successively at equal distances from the bulb of a differential thermometer. The temperatures indicated by the latter are then found to be in the same ratio as those of the box : for instance, if the temperature of that corresponding to the box at 0° be 2°, those of the others will be 4° and 6° respectively.

The second law is demonstrated experimentally by placing the differential thermometer at a certain distance from the source of heat, a yard for distance, and then removing it to double the

distance. In the latter case, the amount of heat received is not one-half but one-quarter. If the distance be three yards the quantity of heat is one-ninth, and so forth.

209. **Interchange of heat among all bodies.**—Owing to the radiation which is continually taking place in all directions round a body, there is a continual interchange of heat. If the bodies are all at the same temperature, each one sends to the surrounding ones a quantity equal to that which it receives, and their temperatures remain stationary. But if their temperatures are unequal, as the hot bodies emit more heat than they receive, they therefore sink in temperature; while, as the bodies of lower temperatures receive more heat than they emit, their temperature rises; thus the temperatures are all ultimately equal. The radiation does not stop; it goes on, but without loss or gain from each body, and this condition is accordingly known as the *mobile equilibrium of temperature.*

From what has been said it will be understood that bodies placed in our rooms all tend to assume a uniform temperature; generally speaking this is not the case, for many causes concur in cooling one set, and in heating the others. Thus bodies placed near a wall cooled by the outer air find a cause for cooling. Those, on the contrary, which are at the top of the room, tend to acquire a higher temperature; for as heated air rises as being less dense, the layers nearest the ceiling are always hotter than the lower ones.

From this continual interchange of heat, there is necessarily a limit to the cooling of bodies, for they always tend to resume, on the one hand, what they lose on the other. To have an indefinite cooling, a body should be suspended in space, not receiving heat from any body. As it would then lose heat without acquiring any, there is no telling to what extent its temperature would sink.

CHAPTER III.

REFLECTION OF HEAT. REFLECTING, ABSORBING, AND EMISSIVE POWERS.

210. **Law of the reflection of heat.**—When the heat rays emitted by a source of heat fall upon the surface of a body, they are divided generally into two parts; one, which passes into the mass of a body and raises the temperature; the other, which darts

f from the surface like an elastic ball striking against a hard body; is is expressed by saying that these rays are *reflected.* Thus let be the source of heat, a cubical box filled with hot water (fig. 3), and near it a screen which does not allow heat to pass, but ar the bottom of which is an aperture. If behind this screen a lished surface be placed on which the rays emitted by the cube pinge, and beyond this again a differential thermometer, the ter indicates an increase of temperature when one of its bulbs is placed that it receives the rays reflected by the polished body. this experiment, rays like AB which fall on the reflecting surface



Fig. 183.

e called *incident* rays, from a Latin word which signifies to fall; id the *angle of incidence* is not the angle which they make with e reflecting surface, but the angle, ABC, which they make with a raight line, BC, perpendicular to this surface. In like manner the gle, CBD, which the reflected rays make with the same straight ne, is called the *angle of reflection.*

The reflection of heat is always subject to the law, that *the angle f reflection is equal to the angle of incidence.* We shall subsequently see that the reflection of light is governed by the same law.

211. **Reflection of heat from concave mirrors.**—The effects of e reflection of heat may be very powerful when it takes place from e surface of *concave mirrors*, which are spherical surfaces of glass r of metal. These mirrors may be regarded as being made up of n infinite number of extremely small planes inclined towards each ther in such a manner as to determine the curvature. From the mmetrical grouping of these small facets, it follows that when a roup of rays fall upon a concave mirror, these rays, in obedience

to the laws of reflection coincide in a single point, to which the name *focus* is applied, to express the great quantity of heat which is concentrated there. (321).

In treating of light we shall discuss in detail the properties of the focus in concave mirrors; for the present it will be sufficient to describe experiments which demonstrate the great intensity which radiant heat may acquire when concentrated in these points. Fig. 184 represents an experiment which is frequently made in physical lectures. Two reflectors, A and B (fig. 185), are arranged at a distance of 4 to 5 yards, and so that their axes coincide. In the focus of one of them, A, is placed a small basket, *n*, containing a red-hot



Fig. 184.

iron ball. In the focus of the other, B, is placed an inflammable body, such as gun-cotton or phosphorus. The rays emitted from the focus, *n*, are first reflected from the mirror, A, in a direction parallel to the axis; and impinging on the other mirror, B, are reflected so that they coincide in the focus *m*. That this is so, is proved by the fact that the inflammable substance placed in this point takes fire, which is not the case if it is above or below it.

The same effect may be produced by the sun's rays. For this purpose a concave reflector is so placed that the sun's rays strike directly against it (fig. 185); if then a combustible substance, such as paper, wood, cork, etc., be held by means of a pincette in the focus, these bodies are seen to take fire. The effect produced

ends on the magnitude of the mirrors. With a mirror having *perture* of 6 feet, that is, the distance from one edge to the er, copper and silver are melted in a few minutes ; and silicious es and flints are softened and even melted.

In consequence of the high temperatures produced in the foci of cave mirrors and of the facility with which combustible bodies be ignited there, they have been called *burning mirrors.* s stated that Archimedes burnt the Roman vessels before Syra- e by means of such mirrors. Buffon constructed burning

Fig. 185.

ors of such power as to prove that the feat attributed to Archi- es was possible. The mirrors were made of a number of silvered e mirrors about 8 inches long by 5 broad. They could be ed independently of each other in such a manner that the rays cted from each coincided in the same point. With 128 mirrors a hot summer's sun Buffon ignited a plank of tarred wood at a ance of 70 yards.

12. **Reflecting power of various substances.**—It has been that heat which falls upon a body is always divided into two

parts, one which is reflected on the surface, and the other which passes into the mass of the body, and raises its temperature. The quantities of heat thus absorbed, or reflected, vary in different substances; one set reflects much and absorbs little, which is expressed by saying that they have a great *reflecting power*; others, on the contrary, reflect very little heat, but absorb a great deal, and are therefore spoken of as having great *absorbing power*. It is clear that these properties are the inverse of each other, for every body which absorbs much heat can reflect but little, and conversely.

In order to compare the reflecting powers of various substances, Leslie took as a source of heat a tin plate cube full of boiling water, which he placed in front of a concave mirror (fig. 186). The rays



Fig. 186.

emitted from this towards the reflector tended after reflection to become concentrated on the focus F. In front of this were placed successively small square plates of paper, glass, metal, in short, of all the substances whose reflecting power was to be examined. As shown in the drawing, these rays after a first reflection from the mirror, were reflected a second time from these plates, and finally impringed against the bulb of a differential thermometer. Now, as in this experiment the source of heat was the same, as was also the distance from the reflector; yet the thermometer indicated very various degrees of heat according to the material of which the small plates were formed. The temperature was highest when the

late was made of polished brass, which metal is therefore the best reector. The reflecting power of silver is only $\frac{9}{10}$ that of brass; that f tin $\frac{8}{10}$; of glass $\frac{1}{10}$. Water and lampblack were found to be destitute of reflecting power, for when the plates were coated with ampblack, or moistened with water, the thermometer indicated no ncrease in temperature, showing that it received no heat.

213. **Absorbing power.**—In order to compare the absorbent powers of various substances, Leslie arranged the experiment as shown in fig. 187. The source of heat and the reflector being the



Fig. 187.

ame as in the preceding experiment, the differential thermometer as placed in the focus, where it received directly all the heat reected by the mirror. The surface of the *focal* bulb was altered or each experiment by coating it successively with various materials, paper, tinfoil, gold, silver, copper, and leadfoil; it was also coated with a thin layer of lampblack; it was moistened, and so on. It was thus found that when the focal bulb was coated with lampblack, or with water, the thermometer indicated the highest temperatures; whence it was concluded that lampblack and water have the greatest absorbing power. The lowest temperature was exhibited when the bulb was coated with thin metal foil, more especially with silver; thus indicating that these substances absorb the least proportion of the heat which is of the temperature of boiling water (216). The result was arrived at which could indeed be fore-

seen, that those bodies which best reflect heat absorb it least; and that, conversely the best absorbents are the worst reflectors.

214. **Emissive power.**—The *emissive* or *radiating* power is the property bodies have of emitting more or less easily the heat they contain; it is the inverse of the absorbing power.

Leslie compared the emissive powers of various bodies by means of the apparatus represented in fig. 187. The focal bulb of the thermometer was left uncoated, and the various substances were applied successively to the sides of the tin cube. One of them, for instance, was left in its ordinary condition; the second was coated with lampblack; to the third a sheet of white paper was fixed, and to the fourth a glass plate.

Turning first of all the blackened face towards the reflector, the thermometer indicated a considerable increase of temperature, thus showing that the cube sent much heat towards the reflector. Turning then successively the other faces towards the reflector, it was found that the paper side emitted less heat than the blackened face, but more than the glass side, which in turn emitted more than the tin side.

Working in this manner, Leslie found that lampblack has the greatest emissive power, then paper, then ordinary glass, then the metals. The order of their emissive powers is thus the same as that of their absorbing powers. It is thus concluded that bodies which best absorb heat, also radiate best; and Dulong and Petit have proved that for each substance the emissive power is in all cases proportional to the absorbing power.

215. **Causes which modify the reflecting, absorbing, and radiating powers.**—As the radiating and absorbing powers are equal, any cause which affects the one affects the other also. And as the reflecting power varies in an inverse manner, whatever increases it diminishes the radiating and absorbing powers, and *vice versâ*.

It has been already stated that these different powers vary with different bodies, and that metals have the greatest reflecting power, and lampblack the feeblest. In the same body these powers are modified by the degree of polish, the density, the thickness of the radiating substance, the obliquity of the incident or emitted rays, and, lastly, by the nature of the source of heat.

It has been assumed usually that the reflecting power increases with the polish of the surface, and that the other powers diminish therewith. But Melloni showed, that by scratching a polished metallic surface its reflecting power was sometimes diminished and sometimes increased. This phenomenon he attributed to the

reater or less density of the reflecting surface. If the plate had een originally hammered, its homogeneity would be destroyed by his process, the molecules would be closer together on the surface han in the interior, and the reflecting power would be increased. But if the surface is scratched the internal and less dense mass ecomes exposed, and the reflecting power diminished. On the ontrary, in a plate which has not been hammered and which is omogeneous, the reflecting power is increased when the plate is cratched, because the density at the surface is increased by the cratches.

The absorbing power varies with the inclination of the incident ays. It is greatest at right angles; and it diminishes in propor- ion as the incident rays deviate from the perpendicular direction. This is one of the reasons why the sun is hotter in summer than n winter, because, in the former case, the solar rays are less oblique.

The radiating power of gaseous bodies in a state of combustion s very weak, as is seen by bringing the bulb of a thermometer near a hydrogen flame, the temperature of which is very high. But if a platinum spiral be placed in this flame, it assumes the temperature of the flame, and radiates a considerable quantity of heat, as is in- dicated by the thermometer. It is for an analogous reason, that the flames of oil and of gas lamps radiate more than a hydrogen flame, in consequence of the excess of carbon which they contain, and which, not being entirely burned, becomes incandescent in the flame.

The absorbing power of a body is also influenced by the nature of the source of heat. Thus, for the same quantity of heat emitted, a surface coated with white lead absorbs twice as much, if the heat comes from a cube filled with hot water, as it does if the heat is that of a lamp. Lampblack, on the contrary, absorbs the same amount of heat whatever be the source.

216. **Different kinds of heat. Diathermaneity.**—Just as different substances possess the power of allowing the rays of light to pass through them to different extents, and are said to be more or less transparent (305), so also modern investigation has shown that all bodies do not allow the rays of heat to traverse them with equal facility, and are therefore said to be more or less *diathermanous*. Thus the metals are just as *adiathermanous* for heat rays as they are opaque for the rays of light. On the other hand *rock salt* stands in the same relation to heat rays that a perfectly colourless and transparent body, such as glass, does to luminous rays. It is perfectly diathermanous.

One and the same substance may be diathermanous to varying extents for *heat from different sources.* Thus *colourless glass* allows the sun's rays to pass through it with facility, but less so the heat emitted by a flame, or by an incandescent body, and far less again the heat of a cube filled with boiling water, which is known as a *Leslie's cube* (212). *Water* allows the solar heat to traverse it partially, but stops the obscure heat of a Leslie's cube. Again, *alum* is colourless and transparent for light, but almost entirely diathermanous for obscure rays.

A body which is opaque for light may be diathermanous for certain kinds of heat. Thus, a solution of iodine in bisulphide of carbon is perfectly opaque for the rays of light, but is traversed by obscure heat rays with facility.

In investigating the diathermaneity of bodies, Melloni used the thermo-multiplier, for a description of which we must refer to Book VIII. Chapter xiii. He first of all placed the thermo-multiplier at a certain distance from a source of heat, and having observed the deflection, he determined to what extent this was enfeebled by the interposition of various bodies, such as plates of glass, alum, and rock salt. In like manner he used various sources of heat, for instance the sun, an oil or spirit lamp, an ignited spiral of platinum wire, a heated blackened metal plate, or a cube filled with hot water, and he concluded that there are *different kinds of heat rays*, or different *colours of heat*, with regard to which various diathermanous substances behave just as coloured transparent substances do in regard to different kinds of light. Thus when white light traverses red glass, only the red rays are transmitted, all other kinds being absorbed. If this red light falls on another red glass it traverses it without enfeeblement; but is completely absorbed by blue glass. Similar results are met with in regard to the rays of heat.

217. **Applications.**—The property which bodies possess of absorbing, emitting, and reflecting heat, meets with numerous applications in domestic economy and in the arts. Leslie stated that white bodies reflect heat very well, and absorb very little, and that the contrary is the case with black substances. This principle is not universally true, as Leslie supposed; for example, white lead has as great an absorbing power for non-luminous rays as lamp-black. But it holds good in regard to absorbents like cloth, cotton, wool, and other organic substances when exposed to luminous heat, such as that of the sun's rays. Accordingly, the most suitable

lothing for summer is just that which experience has to use, namely, white, for it absorbs less of the sun's black clothing, and hence feels cooler.

lished fire-irons before a fire are cold, whilst the black often unbearably hot. If a liquid is to be kept hot as ssible, it must be placed in a brightly polished metallic hen, the emissive power being less, the cooling is slower. his reason advantageous that the steam pipes, etc., of s should be kept brightly polished.

a powerful reflector, and, therefore, neither absorbs nor heat; owing to its small emissive power it protects he ground and the plants which it covers; and owing ll absorbing power it melts but slowly during a thaw. f a tree, a bar of metal, a stone in the midst of a mass celerate the fusion by the heat they absorb, and which e about them.

Alps the mountaineers accelerate the fusion of the snow r it with earth, which increases the absorbing power.

ooking vessels should be black and rough on the outside, eir absorbing power is greater and they become heated ly. Their bright and polished surface is purchased at e of combustible. This is what is seen in vessels of of white procelain. In common unglazed earthenware more rapidly heated, but also more rapidly cooled.

served that the ripening of grapes and other fruits is ac- hen they are placed in contact with a black wall (mortar lampblack). This arises from the fact, that from the ive power of the wall, as well as from its great absorbing comes more highly heated under the influence of the ves up more to the fruit.

used for fire-screens, for while it allows the cheerful fire to pass, it stops most of the heat.

CHAPTER IV.

CONDUCTING POWER OF BODIES.

nductivity of solids.—In the phenomena of radiation been considered, heat is transmitted from one body to rough space, without raising the temperature of the

medium through which it passes. It may also be propagated through the mass of a body by an internal radiation from molecule to molecule. This internal propagation in the mass of a body is called *conductivity*; and *good conductors* are those bodies which readily transmit heat in their mass, while those through which it passes with difficulty are called *bad conductors*.

Organic substances conduct heat badly. De la Rive and De Candolle have shown that woods conduct better in the direction of their fibres than in a transverse direction; and have remarked upon the influence which this feeble conducting power, in a transverse direction, exerts in preserving a tree from sudden changes of temperature, enabling it to resist alike a sudden abstraction of heat from within, and the sudden accession of heat from without. Tyndall

Fig. 188.

has also shown that this tendency is aided by the low conducting power of the bark, which is in all cases less than that of the wood.

Cotton, wool, straw, bran, powdered gypsum, etc., are all bad conductors.

In order to compare the conducting power or *conductivity* of different solids, Ingenhousz constructed the apparatus which bears his name, and which is represented in fig 188. It is a metal trough, in which, by means of tubulures and corks, are fixed rods of the same dimensions, but of different materials; for instance, iron, copper, wood, glass. These rods extend to a slight distance in the trough, and the parts outside are coated with wax, which melts at 61°. The box being filled with boiling water, it is observed that the wax melts to a certain distance on the metal rods, while on the

there is no trace of fusion. The conducting power is evidently
r in proportion as the wax has fused to a greater distance.
cperiment is sometimes modified by attaching glass balls or
:s to the ends of the rods by means of wax. As the wax
the balls drop off, and this in the order of their respective con-
ities. By these and other experiments it has been ascer-
that metals are the best conductors, then marble, porcelain,
wood, glass, etc.

). **Conducting power of liquids. Manner in which they
ated.**—Liquids, with the exception of mercury, which is a
are all bad conductors of heat. They conduct so imperfectly
umford assumed water to be entirely destitute of conducting
But its conductivity, though small, has been established
l doubt, as well as that of other liquids, by the most accurate
ments.

)m their small conducting power, liquids are not heated in the
manner as solids. If heat be applied to a solid, whether on
), the bottom, or the sides, it is transmitted from layer to
and the whole mass becomes heated. This is not the case
liquid ; if it is heated at
p, the heat is only pro-
d with extreme slowness,
t cannot be completely
. But if it be heated at
ttom, the temperature of
luid rapidly rises. This
er, is not owing to its
:tivity, but to ascending
:scending currents, which
ue of the mobility of the
ıles, are produced through-
: whole mass of liquid.
e existence of these cur-
nay be demonstrated by
ɜ in the water a powder
ır the same density, for
:e, oak sawdust, and then



Fig. 189.

heating the vessel at the bottom. As the lower layers of the
become heated they expand, while the upper layers, which are
and therefore denser, sink and take the place of the first ;
n their turn become heated, rise, and so on, until the entire

mass is heated. These currents are evident from the sawdust which is seen to rise slowly in the centre, and to redescend near the edges.

220. **Conductivity of gases.**—Gases are extremely bad conductors of heat; but this cannot be easily demonstrated by experiment, owing to the extreme mobility of their particles. For so soon as they are heated in any part of their mass, expansions and currents are produced, in virtue of which the heated parts mingle with the cold ones; hence a general elevation of temperature, which we might be tempted to consider as due to conductivity. When, however, gases are hindered in their motion, their conductivity seems extremely small, as the following examples show.

221. **Applications.**—The greater or less conductivity of bodies meet with numerous applications. If a liquid is to be kept warm for a long time, it is placed in a vessel and packed round with non-conducting substances, such as shavings, straw, bruised charcoal. For this purpose water pipes and pumps are wrapped in straw at the approach of frost. The same means are used to hinder a body from becoming heated. Ice is transported in summer by packing it in bran, or folding it in flannel.

Double walls constructed of thick planks having between them any finely divided materials such as shavings, sawdust, dry leaves, etc., retain heat extremely well; they are likewise advantageous in hot countries, for they prevent its access. If a layer of asbestos, a very fibrous substance, is placed on the hand, a red-hot iron ball can be held without inconvenience. Red-hot cannon balls can be wheeled to the gun's mouth in wooden barrows partially filled with sand. Lava has been known to flow over a layer of ashes underneath which was a bed of ice, and the non-conducting power of the ashes has prevented the ice from fusion. A covering of snow protects seed and young grain from frost.

In fireproof safes the hollow walls are filled with wood ashes, or powdered gypsum, or ignited alum.

The clothes which we wear are not warm in themselves; they only hinder the body from losing heat, in consequence of their spongy texture and the air they enclose. The warmth of bed-covers and of counterpanes is explained in a similar manner. Double windows are frequently used in cold climates to keep a room warm —they do this by the non-conducting layer of air interposed between them. It is for the same reason that two shirts are warmer than one of the same material, but of double the thickness. Hence too the warmth of furs, eider down, etc.

That water boils more rapidly in a metallic vessel than in one of rcelain of the same thickness ; that a burning piece of wood can held close to the burning part with the naked hand, while a ece of iron heated at one end can only be held at a great distance, e easily explained by reference to their various conductivities.

The sensation of heat or cold which we feel when in contact th certain bodies is materially influenced by their conductivity. If eir temperature is lower than ours, they appear colder than they ally are, because, from their conductivity, heat passes away from . If, on the contrary, their temperature is higher than that of our dy, they appear warmer from the heat which they give up at dif-rent parts of their mass. Hence it is clear why carpets, for ex-mple, are warmer than wooden floors, and why the latter are armer than stone floors.

CHAPTER V.

EASUREMENT OF THE EXPANSION OF SOLIDS, LIQUIDS, AND GASES.

222. **Expansion of solids.**—The expansion of bodies by heat ing a general effect which exerts its influence on all bodies, and is ntinually changing their volume, it will be readily understood that e determination of the amount of this expansion is a problem of eat importance, both in its purely scientific, as well as in its prac-al, aspects. We shall first describe the method of determining e expansion of solids. We have already seen that the expansion solids may be either as regards the length or the volume. ence the investigation of the expansion of solids may be divided to two parts, the first relating to *linear*, and the second to *cubical* pansion.

Linear expansion. In order to compare with each other the ex-nsion of bodies, the elongation is taken which the unit of length dergoes when he is heated from zero to 1 degree, and this elonga-n is called the *coefficient of linear expansion.* The coefficients of great number of substances were accurately determined towards e end of the last century by Lavoisier and Laplace. They took bar of the substance to be determined, placed it in melting ice, d then accurately determined its length. Having placed it then a bath of boiling water, they again measured its length. They

then observed an elongation, which represented the total e
for an increase of temperature of 100 degrees. This, di
100, gave the coefficient of linear expansion for one degree.
manner the following numbers may be obtained :—

Coefficients of linear expansion for 1° *between* 0° *and* 10

White glass . .	0·00000861	Bronze . .	0·00
Platinum . .	0·00000884	Brass . . .	0·00
Steel . . .	0·00001079	Silver . . .	0·00
Iron . . .	0·00001220	Tin . . .	0·00
Gold . . .	0·00001466	Lead . . .	0·00
Copper . .	0·00001718	Zinc . . .	0·00

It will be seen from this table, that the coefficients of e
are in all cases very small. Thus, when we say that the c
of expansion of copper is about 0·00017, we mean that a ro
metal when heated through 1 degree, will expand by 17 m
of its length ; that is to say, a rod of copper a million feet i
would be longer by 17 feet under these circumstances.

Cubical expansion. The *coefficient of cubical expansion* i
crease in volume for a temperature of one degree. Ca
shows that the coefficient of cubical expansion is three
coefficient of linear expansion ; and these coefficients may t
be obtained by multiplying the above numbers by three.

223. **Applications of the expansion of solids.**—In
we meet with numerous examples of the influence of ex
(i.) The bars of furnaces must not be fitted tightly at their
ities, but must, at least, be free at one end, otherwise, in ex
they would exert sufficient force to split the masonry.
making railways a small space is left between the success
for, if they touched, the force of expansion would cause
curve or would break the chairs. (iii.) Water pipes are
one another by means of telescopic joints, which allow 1
expansion. (iv.) If a glass is heated or cooled too r
cracks ; this arises from the fact that glass being a bad c
of heat, the sides become unequally heated, and consequ
equally expanded, and the strain thereby produced is suf
cause a fracture.

When bodies have been heated to a high temperature,
produced by their contraction on cooling is very conside
is equal to the force which is needed to compress or ex
material to the same extent by mechanical means. Acc

Barlow a bar of malleable iron a square inch in section is stretched $\frac{1}{8000}$ of its length by a weight of a ton; the same increase is experienced by about 9° C. A difference of 45° C. between the cold of winter and the heat of summer is not unfrequently experienced in this country. In that range a wrought iron bar, ten inches long will vary in length by $\frac{1}{200}$ of an inch, and will exert a strain, if its ends are securely fastened, of fifty tons.

An application of this contractile force is seen in the mode of securing the tires on wheels. The tire being made red hot, and thus considerably expanded, is placed on the circumference of the wheel, and then cooled. The tire, when cold, clasps the wheel with such force as not only to secure itself on the rim, but also to press home the joints of the spokes into the felloes and nave. Another interesting application was made in the case of a gallery at the Conservatoire des Arts et Métiers in Paris, the walls of which had begun to bulge outwards. Iron bars were passed across the building, and screwed into plates on the outside of the walls. Each alternate bar was then heated by means of lamps, and when the bar had expanded, it was screwed up. The bars being then allowed to cool contracted, and in so doing drew the walls together. The same operation was performed on the other bars.

224. **Compensation pendulum.**—An important application of the expansion of metals has been made in *the compensation pendulum*. To understand the utility of such an arrangement, we must call to mind what has been said about pendulums; namely, that their oscillations are *isochronous*, that is, are made in equal times, and that their application to the regulation of clocks depends upon this property. But we have also seen that the duration of an oscillation depends on the length of the pendulum; the longer the pendulum the more slowly it oscillates, and, therefore, the shorter it is, the more rapidly does it oscillate. Hence a pendulum formed of a single rod terminated by a metal bob, *c*, as represented in fig. 52, would not be an exact regulator; for, as the temperature rises, it would elongate, and the clock would go slower: the exact opposite would take place when it contracted by cooling. These inconveniences have been remedied by taking the remedy from the cause of the evil.

For this purpose the pendulum rod consists of several metal bars arranged as represented in fig. 190. The rods, *a*, *b*, *c*, *d*, are of steel, and all expand in a downward direction when the temperature rises, thus making the bob sink. The rod, *d*, supporting the

bob is fixed to a cross-piece *mn*, which in turn is fastened to two rods, *k* and *h*, which are connected to the piece *or*, and therefore cannot expand downwards, but only in an upward direction; they raise the piece *mn*, and with it the bob. In order, therefore, that this latter shall neither raise nor sink, it is necessary that the upward expansion of the rods, *k* and *h*, shall exactly compensate the downward expansion of the rods, *a*, *b*, *c*, *d*.



Fig. 190.

Brass being more expansible than steel, compensation is effected by taking the first metal for the rods *h* and *k*, and the second for the rods, *a*, *b*, *c*, and *d*. The only condition necessary for compensation is that *the lengths of the two metals must be inversely as their coefficients of expansion.* That is to say, that if brass is two or three times as expansible as steel, its length must be one-half or one-third as much.

In fig. 190 the pendulum has been represented with a single frame of steel and one of brass; but in order to reduce the length, there are always at least two rows of steel and brass.

EXPANSION OF LIQUIDS.

225. **Absolute and apparent expansion.**—We have already seen that liquids are more expansible than solids (200), which is a consequence of their feeble cohesion; but their expansibility is far less regular, and the less so the nearer their temperature approaches that of their boiling point.

In solids two kinds of expansion have to be considered, the longitudinal and the cubical. Now it is clear that the latter is the only kind of expansion which can be observed in the case of liquids. The expansion may be either *real* or *apparent*. The former is the real increase in volume which a liquid assumes when it is heated; while the latter is that which the eye actually observes, that produced in the vessel containing the liquid. Thus in thermometers, when the liquid expands and rises in the stem, the apparent expansion is observed, which is less than the real or absolute expansion. For, while the mercury expands, the bulb of the thermometer does so too: its volume is greater, and hence the

d does not rise so high in the stem as it would if the volume e bulb were unaltered. If a flask of thin glass, provided with pillary stem, the flask and part of the stem being filled with coloured liquid, be immersed in hot water, the column of d in the stem at first sinks, but then immediately after rises, continues to do so until the liquid inside has the same erature as the hot water. The first sinking of the liquid is not to its contraction; it arises from the expansion of the glass, h becomes heated before the heat can reach the liquid; but expansion of the liquid soon exceeds that of the glass, and the id then ascends.

Hence, since, whatever be the nature of the material in which a id is contained, it has some expansibility, and always expands the liquid, the apparent expansion is the only one directly ob-ed in liquids.

The coefficient of expansion of a liquid is the increase which unit of volume experiences for a rise in temperature of one ree. These coefficients greatly vary. In a glass vessel the arent expansion of mercury is 1·5 parts in ten thousands; that ater is 4·6 parts, that is, three times as great; alcohol is still e expansible, for its coefficient is 11·6 parts in ten thousands.

226. **Maximum density of ter.**—Water presents the re-rkable phenomenon that when temperature sinks it contracts to 4°; but from that point, ough the cooling continues, expands up to the freezing nt, so that 4° represent the nt of greatest contraction of ter, or, what is called, its *point maximum density*.



Fig. 191.

These phenomenon may be served by comparing a water rmometer, one, that is to say, ed with water, with one of rcury; both being exposed gradually diminishing tempe-ture.

Hope used the following thod to determine the maximum density of water. He took

a deep vessel perforated by two lateral apertures, in which he fixed thermometers (fig. 190), and having filled the vessel with water at 0°, he placed it in a room at a temperature of 15°. As the layers of liquid at the sides of the vessel became heated they sank to the bottom, and the lower thermometer marked 4°, while that of the upper one was still at zero. Hope then made the inverse experiment; having filled the vessel with water at 15°, he placed it in a room at zero. The lower thermometer having sunk to 4°, remained stationary for some time, while the upper one cooled down until it reached zero. Both these experiments prove that water is heavier at 4° than at 0°, for in both cases it sinks to the lower part of the vessel.

This phenomenon is of great importance in the economy of nature. In winter the temperature of lakes and rivers falls, from being in contact with the cold air, and from other causes, such as radiation. The colder water sinks to the bottom, and a continual series of currents goes on until the whole has a temperature of 4°. The cooling on the surface still continues, but the cooled layers being lighter remain on the surface, and ultimately freeze. The ice formed thus protects the water below, which remains at a temperature of 4°, even in the most severe winters, a temperature at which fish and other inhabitants of the waters are not destroyed.

EXPANSION OF GASES.

227. **Value of the coefficient of expansion of gases.**—Not merely are gases the most expansible of all bodies, but their expansion is the most regular. It was originally assumed, on the basis of Gay Lussac's experiments, that all gases expanded to the same extent for the same increase of temperature, that is, that they had all the same coefficient of expansion. It has, however, been established that the coefficients of various gases do present slight differences. They are, however, so slight, that for all practical purposes they may be assumed to be the same; that is to say, 367 parts in a hundred thousand, or, in other words, that 100,000 volumes of air, or any other gas, when heated through 1 degree Centigrade, would become 100,367 volumes or 1 volume in 273. This expansibility is about 13 times as great as that of water.

228. **Effects of the expansion of gases.**—The expansion of gases affords us numerous important applications, not merely in

ic economy, but also in atmospheric phenomena. Thus in illings, when the air is heated and vitiated by the presence eat number of persons, it expands and rises in virtue of its hed density to the highest parts of rooms ; and to allow this pe, apertures are made in the cornice, while fresh and pure rs by the joints of the doors and of the windows.

en in winter the door of a warm room is put ajar, and a candle held near the top, fig. 192, the direction of the flame the existence of a current of warm n the inside to the outside. If we ne flame, it will be found that at ne middle it is not affected by any ent, but that lower down near the the flame is driven inwards.

Fig. 192.

heatres the spectators in the gal- re exposed to the highest tempera- l the most impure air, while those e orchestra respire in a purer air.

ughts in chimneys are due to the on of air. Heated by the fire in te, the air rises in the chimney elocity which is greater the more it is expanded. Hence a rapid current of air, which supports and quickens the tion by constantly renewing the oxygen absorbed.

expansion and contraction of air have a fortunate influence temperature of that part of the atmosphere in which we or when the ground is strongly heated by the sun's burning e layers of air in immediate contact with it tend to acquire e temperature and to form a stifling atmosphere ; but these gradually expanding, rise in virtue of their diminished den- hile the higher layers, which are colder and denser, gradually them. Thus the high temperature which would otherwise uced in the lower regions is moderated, and never exceeds ts which plants and animals can support.

expansion and contraction produced in the atmosphere over tract of country are the cause of all winds, from the lightest to the most violent hurricane. These winds, which at re so destructive, so capricious in the direction, and so in their intensity, not merely have the effect of mixing the und the cooler part of the atmosphere, and of thus modera- remes of temperature, but by driving away the vitiated at-

mosphere of our towns, and replacing it by pure air, they ar
of the principal causes of salubrity; without them our cities
be the centres of infection, where epidemic diseases of all
would be permanent. Without winds, clouds would remain m
less over the country where they were formed, the greater p
the globe would be condemned to absolute aridity, and n
rivers nor brooks would moisten the soil. But, carried b
winds, the clouds formed above the seas are transported t
centres of continents, where they fall as rain; and this h
fertilised the soil, gives rise to the numerous rivers which fal
the ocean, thus establishing a continuous circulation from the
towards the continents and from continents towards seas.

229. **Density of gases.**—The densities of solids and of l
have been determined in reference to water (101); those of
by comparison with air; that is, having taken as a term of
parison, or *unity*, the weight of a certain volume of air, the v
of the same volume of other gases is determined. But as
are very compressible and very expansible, and as therefore
densities may greatly vary, they must be reduced to a definite
sure and temperature. This is why *the temperature of zero* a
pressure of 30 *inches* have been chosen.

Hence the *relative density* of a gas, or its *specific gravity*,
relation of the weight of a certain volume of the gas to that
same volume of air; both the gas and the air being at zero
a pressure of 30 inches.

In order therefore, to find the specific gravity of a gas, o
for instance, it is necessary to determine the weight of a c
volume of this gas, at a pressure of 30 inches, and a temperat
zero, and then the weight of the same volume of air under the
conditions. For this purpose a large globe of about two g
capacity is used, like that represented in fig. 88, the neck of
is provided with a stop cock, which can be screwed to the air-
The globe is first weighed empty, and then full of air, and
wards full of the gas in question. The weights of the gas
the air are obtained by substracting the weight of the exh
globe from the weight of the globes filled, respectively, wi
and gas. The quotient, obtained by dividing the latter b
former, gives the specific gravity of the gas. It is difficult to
these determinations at the same temperature and pressur
therefore all the weights are reduced by calculation to zero, a
standard pressure of 30 inches.

In this manner the following densities have been found :

Air	1·0000	Oxygen	1·1056
Hydrogen	0·0692	Carbonic acid	1·5290
Nitrogen	0·9714	Chlorine	3·4400

From these numbers the lightest of gases, and therefore of a bodies, is hydrogen, whose density is less than $\frac{1}{14}$th of air.

CHAPTER VI.

CHANGES OF STATE OF BODIES BY THE ACTION OF HEAT.

230. **Fusion.**—In treating of the general effects of heat, we have seen that its action is not only to expand them, but to cause them to pass from the solid to the liquid state, or from the latter state to the former, according as the temperature rises or falls ; then from the liquid to the aëriform state, or conversely. These various changes of state we shall now investigate under the name of *fusion*, *solidification*, *vaporisation*, and *liquefaction*.

Fusion is the passage of a solid body to the liquid state by the action of heat. This phenomenon is produced when the force of cohesion which unites the molecules is balanced by the force of repulsion (4) ; but as the cohesive force varies in different substances, the temperature at which bodies melt does so likewise. For some substances this temperature is very low, and for others very high, as the following table shows :

Fusing points of certain substances.

Mercury	−38·8°	Sulphur	114°
Bromine	12·5	Tin	228
Ice	0	Bismuth	264
Butter	+33	Lead	335
Phosphorus	44	Zinc	422
Potassium	55	Antimony	450
Stearine	60	Silver	1000
White wax	65	Gold	1250
Sodium	90	Iron	1500

Some substances, however, such as paper, wood, wool, and certain salts, do not fuse at a high temperature, but are decomposed. Many bodies have long been considered *refractory*; that is, incapable of fusion; but, in the degree in which it has been possible to produce higher temperatures, their number has diminished. Gaudin has succeeded in fusing rock crystal by means of a lamp fed by a jet of oxygen; and more recently Despretz, by combining the effects of the sun, the voltaic battery, and the oxy-hydrogen blow-pipe, has melted alumina and magnesia, and has softened carbon, so that it was flexible, which is a condition near that of fusion.

Some substances pass from the solid to the liquid state without showing any definite melting point; for example, glass and iron become gradually softer and softer when heated, and pass by imperceptible stages from the solid to the liquid condition. This intermediate condition is spoken of as the state of *vitreous fusion*. Such substances may be said to melt at the lowest temperature at which perceptible softening occurs, and to be fully melted when the further elevation of temperature does not make them more fluid; but no precise temperatures can be given as their melting points.

231. **Laws of fusion.**—It has been experimentally found, that the fusion of bodies is governed by the two following laws:

I. *Every substance begins to fuse at a certain temperature, which is invariable for one and the same substance if the pressure be constant.*

II. *Whatever be the intensity of the source of heat, from the moment fusion commences, the temperature of the body ceases to rise, and remains constant until the fusion is complete.*

For instance, the melting point of ice is zero, and a piece of this substance exposed to the sun's rays, placed in front of a fire or over a lamp, could never be heated beyond this temperature. Exposure to a more intense heat would only accelerate the fusion, the temperature would remain at zero until the whole of the ice was melted.

232. **Latent heat.**—Since, during the passage of a body from the solid to the liquid state, the temperature remains constant until the fusion is complete, whatever be the intensity of the source of heat, it must be concluded that, in changing their condition, bodies absorb a considerable amount of heat, the only effect of which is to maintain them in the liquid state. This heat, which is not indicated by the thermometer, is called *latent heat*, or *latent heat of fusion*

expression which, though not in strict accordance with modern eas, is convenient from the fact of its universal recognition and nployment.

An idea of what is meant by latent heat may be obtained from ie following experiment. If a pound of *water* at 80° is mixed with pound of water at zero, the temperature of the mixture is 40°. ut if a pound of pounded *ice* at zero is mixed with a pound of ater at 80°, the ice melts, and two pounds of water at *zero* are btained. The pound of ice at zero is changed into a pound of ater also at zero, but as the hot water is also lowered to this temerature, what has become of the 80° of heat it possessed? They xist in the water which results from the ice; their effect has ieither been to increase its temperature nor its volume, but simply o impart fluidity to it. Consequently, the mere change of a pound f ice to a pound of water at the same temperature requires as much eat as will raise a pound of water through 80°. This quantity of eat represents the *latent heat of the fusion* of ice, or the *latent eat of water.*

Every substance in melting absorbs a certain amount of heat, hich, however, varies materially with different substances.

The enormous quantity of heat absorbed by ice in melting, exlains how it is that so long a time is required for thaw. And onversely, it is owing to the latent heat of water, that even when ts temperature has been reduced to zero, so long a time is required efore it is entirely frozen. Before it can be so it must give out he heat which had been consumed in its liquefaction: it thus becomes a source of heat which retards the solidification. Faraday as calculated that the heat given out by a cubic yard of water in reezing is equal to that which would be produced by the complete ombustion of a bushel of coals.

Were it not for the great amount of heat which must be absorbed by snow or ice in melting, we should, on a change from frost to ild weather, be liable to the most destructive floods, from the sudden melting of the accumulated snow and ice.

233. **Solidification.**—Those substances which are liquefied by eat revert to the solid state on cooling, and this passage from the iquid to the solid state is called *solidification.* If this solidification akes place at a low temperature it is frequently spoken of as *conelation.*

In all cases the phenomenon is subject to the following laws:

I. *Every body, under the same pressure, solidifies at a fixed temperature, which is the same as that of fusion.*

II. *From the commencement to the end of the solidification, the temperature of a liquid remains constant.*

Thus if lead begins to melt at 335°, melted lead in like manner when cooled down begins to solidify at 335°. Moreover, until it is completely solidified, the temperature remains constant at 335°. This arises from the fact, that the liquid metal in proportion as it solidifies restores the heat it had absorbed in being melted. The same phenomenon is observed whenever a liquid solidifies (232).

Many liquids, such as alcohol, ether, and bisulphide of carbon, do not solidify even at the lowest known temperature. Pure water solidifies at zero; salt water at −2·5°, olive and rape oils at −6°; linseed and nut oils at −27°.

Water presents the remarkable phenomenon, that when it solidifies and forms ice its volume undergoes a material increase. In speaking of the maximum density of water we have already seen that, on cooling, it expands from 4 degrees to zero; it further expands on the moment of solidifying, or contracts on melting by about 10 per cent. One volume of ice at 0° gives 0·908 of water at 0°, or 1 volume of water at 0° gives 1·102 of ice at the same temperature.

The increase of volume in the formation of ice is accompanied by an expansive force which sometimes produces powerful mechanical effects, of which the bursting of water pipes and the breaking of jugs containing water are familiar examples. The splitting of stones, rocks, and the swelling up of moist ground during frost, are caused by the fact that water penetrates into the pores and there becomes frozen.

The expansive force of ice was strikingly shown by some experiments of Major Williams in Canada. Having quite filled a 13-inch iron bomb-shell with water, he firmly closed the touch-hole with an iron plug weighing 3 pounds, and exposed it in this state to the frost. After some time the iron plug was forced out with a loud explosion, and thrown to a distance of 415 feet, the shell was cracked, and a mass of ice projected from the crack as shown in fig. 193.

Fig. 193.

From the expansion which water undergoes in freezing, it is clear that ice must be less dense than water; and this in fact is the

se, for ice floats on the surface of the water. In the polar seas, ıere the temperature is always very low, masses of floating ice are ɛt with which are called *ice-fields*. They rise out of the sea to a ight of 4 or 5 yards, and are immersed to a depth of 7 or 8 yards, ıd they frequently extend over 40 miles. True mountains of ice, *icebergs*, are found floating on those seas; they have not the me area, but attain very great heights.

Cast-iron, bismuth, and antimony expand on solidifying like ater, and can thus be used for casting; but gold, silver, and cop- ɛr contract, and hence coins of these metals cannot be cast, but ust be stamped with a die.

234. **Crystallisation.**—When bodies pass slowly from the liquid the solid state, their molecules, instead of becoming grouped in confused manner, generally acquire a regular order and arrange- ent, in virtue of which these bodies assume the geometrical shapes cubes, pyramids, and prisms, etc., which are perfectly definite, ıd are known as *crystals*. Flakes of snow, when looked at under ıe microscope, ice in the process of formation, sugar candy, rock ystal, alum, common salt, and many other substances afford well- ıown instances of crystallisation.

Two methods are in use for crystallising substances; the *dry ay* and the *moist way*. By the first method bodies are melted by ɛat, and then allowed to cool slowly. The vessel in which the ɔeration is performed becomes lined with crystals, which are made ɔparent by inverting the vessel and pouring out the excess of ɥuid before the whole of it is melted. Sulphur, bismuth, and ıany other metals are thus easily crystallised. The second method ɔnsists in dissolving in hot water the substance to be crystallised, ıd then allowing it to cool slowly. The body is then deposited on ıe sides of vessels in crystals which are larger and better shaped ıe more slowly the crystallisation is effected. In this manner ıgar candy and salts are crystallised.

235. **Solution.**—A body is said to *dissolve* when it becomes ɥuid in consequence of an affinity between its molecules and ose of a liquid. Gum arabic, sugar, and most salts dissolve in ıter.

During solution, as well as during fusion, a certain quantity of at always becomes latent, and hence it is that the solution of a ɔstance usually produces a diminution of temperature. In cer- n cases, however, instead of the temperature being lowered, it ually rises, as when caustic potass is dissolved in water. This

depends upon the fact that during the solution ofa solid in a liquid, two simultaneous and contrary phenomena are produced. The first is the passage from the solid to the liquid condition, which always lowers the temperature. The second is the *chemical* combination of the body dissolved with the liquid, and which, as in the case of all chemical combinations, produces an increase of temperature. Consequently, as the one or the other of these effects predominates, or as they are equal, the temperature either rises, or sinks, or remains constant.

236. **Freezing mixtures.**—The absorption of heat in the passage of bodies from the solid to the liquid state has been used to produce artificial cold. This is effected by mixing together bodies which have an affinity for each other, and of which one at least is solid, such as water and a salt, ice and a salt, or an acid and a salt. Chemical affinity accelerates the fusion, the portion which melts robs the rest of the mixture of a large quantity of sensible heat, which thus becomes latent. In many cases a very considerable diminution of temperature is produced.

If the substances taken be themselves first previously cooled down, a still more considerable diminution of temperature is occasioned.

Freezing mixtures are frequently used in chemistry, in physics, and in domestic economy. The portable ice-making machines which have come into use during the last few years, consist of a cylindrical metallic vessel divided into four concentric compartments. In the central one is placed the water to be frozen; in the next there is the freezing mixture, which usually consists of sulphate of sodium and hydrochloric acid; 6 pounds of the former and 5 of the latter will make 5 to 6 pounds of ice in an hour. The third compartment also contains water, and the outside one contains some badly conducting substance, such as cotton, to prevent the influence of the external temperature. The best effect is obtained when pretty large quantities, 2 or 3 pounds, of the mixture are used, and when they are intimately mixed. It is also advantageous to use the machines for a series of successive operations.

CHAPTER VII.

RMATION OF VAPOURS. MEASUREMENT OF THEIR ELASTIC FORCE.

237. **Vapours.**—We have already seen (109) that *vapours* are aëriform fluids into which substances, such as ether, alcohol, ter, and mercury, are changed by the absorption of heat.

In respect to the property of disengaging vapours, liquids are ided into two classes, *volatile* liquids, and *fixed* liquids. The st are those which have a tendency to pass into the state of pour at the ordinary or even at lower temperatures; such, for tance, are water, ether, chloroform, alcohol, which disappear more less rapidly when exposed to the air in open vessels. To this class longs a numerous family of liquids met with in nature, such as ence of turpentine, oil of lemons, of lavender, of thyme, of roses, , which are known as the *essential oils.*

Fixed liquids, on the contrary, are those which emit no vapour any temperature; such, for instance, are the *fatty oils*, as olive, e, etc. When strongly heated these oils are decomposed, and e rise to gaseous products; but they do not emit vapours of same nature as their own. There are some of them which are own as *drying oils*, that become thicker in the air; but this is in sequence of their having absorbed oxygen, and not in con- luence of evaporation.

Some substances give vapours even in the solid state. Ice gives instance of this, as is seen in dry cold winters, where the snow d ice quite disappear from the ground, without there having been y fusion. Camphor and odoriferous bodies, in general present same phenomenon.

238. **Elastic force of vapours.**—Vapours formed on the surface a liquid are disengaged in virtue of their elasticity; but this e is generally far lower than the pressure of the atmosphere, l hence liquids exposed to the air only evaporate slowly.

The following experiment renders evident the elastic force of ours. A bent glass tube has the shorter limb closed (fig. 194); branch and part of the longer are filled with mercury. A p of ether is then passed into the closed leg, which in virtue

of its lower density rises to the top of the tube at B. The tube thus arranged is immersed in a water bath at a temperature of about 45°. The mercury then sinks slowly in the short branch, and the space AB is filled with a gas which has all the appearance of air. This gas or aëriform fluid is nothing but the vapour of ether, whose elastic force counterbalances not only the pressure of the column of mercury CA, but also the atmospheric pressure exerted at C.



Fig. 194.

If the water in the vessel be cooled, or if the tube be withdrawn, the mercury gradually rises in the short leg, and the drop of liquid which seemed almost to have disappeared is re-formed. If, on the contrary, the water in which the tube is immersed be still more heated, the drop diminishes and the mercury descends further in the short leg; thus showing that fresh vapours are formed, and that the elastic force increases. This increase of tension with the temperature continues as long as any liquid remains to be vaporised.

The crackling of wood in fires is due to the increased tension of the vapours and gases formed in the pores of the wood during combustion. In roasting chesnuts it is usual to slit the outer skin; the object of this is to allow the vapour formed to escape, for otherwise it would be liable to acquire such a tension as to burst the chesnut and scatter the particles far and wide.

239. **Formation of vapours in a vacuum.**—In the previous experiment the liquid changed very slowly into the state of vapour; the same is the case when a liquid is freely exposed to the air. In both cases the atmosphere is an obstacle to the vaporisation. In a vacuum there is no resistance, and the formation of vapours is instantaneous, as is seen in the following experiment. Four barometer tubes, filled with mercury, are immersed side by

ide in the same trough (fig. 195). One of them, A, serves as a arometer, that is, only contains dry mercury, and a few drops of ater, alcohol, and ether are respectively introduced into the tubes, 3, C, D. When the liquids reach the vacuum a depression of the ercury is at once produced. But this depression cannot be produced y the weight of the liquid, or it is but an infinitely mall fraction of the eight of the displaced ercury. Hence in the ase of each liquid, some apour must have been rmed whose elastic force as depressed the mer-rial column, and as the epression is greater in e tube D than in the be C, and greater in is than in the tube B, it concluded that, for the me temperature, the lastic force of ether is reater than that of alco-ol vapour, and that is in turn has a greater lastic force than that of ater. If the depression e measured by means of a graduated scale, it will be found that t a temperature of 20° the elastic force of ether is twenty-five mes as great as that of water, and that of alcohol almost four mes as great. From these experiments we obtain the two follow-g laws for the formation of vapours :



Fig. 195.

I. *In a vacuum all volatile liquids are instantaneously converted to vapour.*

II. *At the same temperature the vapours of different liquids have fferent elastic forces.*

240. **Limit to the formation and to the tension of vapours. turated space.**—The quantity of vapour which can be formed a given space, whether at the ordinary or at higher temperatures,

is always limited. For instance, in the above experimer pression of mercury in each tube, B, C, D, is not stoppec of liquid which might form fresh vapours, for care is tak to add so much that a slight excess remains unvaporise in the tube D, enough ether is left ; yet we might wait w years, and if the temperature did not increase, we shou see a portion of liquid in the tube, and the level of the remain stationary. This shows that no new vapours can l in the tube, and at the same time that the elastic for vapour which is there cannot increase, which is expressed that it has attained its *maximum tension.*

When a given space has acquired all the vapour wh contain, it is said to be *saturated.* For instance, if in a of dry air a little water be placed, and the vessel be he closed, part of the water will evaporate slowly, until t force of the vapour formed holds in equilibrium the expar of that which still tends to form ; the formation of va ceases, and the space is saturated.

241. **The quantity of vapour which saturates a gi is the same whether this is vacuous or contains** the same temperature the quantity of vapour necessary t a given space is the same, whether the space is quite v contains air or any other gas. In the above bottle, whe full of air, or has been exhausted, the total quantity whi rates is exactly the same ; the difference being that, ir case, the evaporation only takes place slowly, while in t case it is instantaneous. Yet, for the same space, whe vacuous or full of air, the quantity of vapour formed wh sponds to the state of saturation, varies with the ter The higher the temperature, the greater is the quantity contained in a given space, the denser it is therefore ; on hand, the lower the temperature, the less is the quantit to saturate a given space.

The quantity of vapour present in air is very variable ; of the abundant vaporisation produced on the surfac lakes, and rivers, the air in the lower regions of the atm never quite saturated, even when it rains. This arises fro that aqueous vapour being less dense than air, in pro it is formed, rises into the higher regions of the atmosph condensed by cooling, it falls as rain.

242. **Evaporation. Causes which accelerate it.**—We have hitherto designated, under the general term of *vaporisation*, all production of vapour under whatever circumstances it takes place, whether slow or rapid, whether in air or in a vacuum ; while the term *evaporation* is especially assigned to the slow formation of a vapour on the surface of a volatile liquid when it is exposed in the open air. It is in consequence of evaporation that the level gradually diminishes in a pond full of water, and ultimately dries up if it is not fed by a spring. Owing to the same cause the earth moistened by rain dries up and ultimately hardens ; that moist linen exposed in the air soon dries up. Several causes influence the rapidity of the evaporation of a liquid : the temperature ; the quantity of the same vapour in the surrounding atmosphere ; the renewal of this atmosphere ; the extent of the surface of evaporation.

Influence of temperature. Heat being the agent of all evaporation, the higher the temperature the more abundant is the formation of vapour. This property is utilised in the arts to hasten and complete the drying of a large number of products which are exposed in *stoves* ; that is to say, in chambers, the temperature of which is kept at 30, 40, 50, and even 60 degrees, and the air of which is continually renewed to allow the vapour formed to escape.

Influence of pressure. We have already seen that the pressure of the atmosphere is an obstacle to the disengagement of vapours, and it will thus be understood that when this pressure is diminished they ought to be formed more abundantly. This, in point of fact, is what takes place whenever liquids are removed from the pressure of the atmosphere. In sugar refineries, in order to concentrate the syrups (that is, to reduce the volume by removing part of the water they contain), they are placed in large spherical vessels ; and then, by the aid of large air-pumps of special construction, and worked by steam engines, the air in the boilers is rarefied, which considerably accelerates the evaporation of water, and quickly brings the syrups to the wished-for degree of concentration.

Influence of the renewal of air. In order to understand the influence of the third cause, it is to be observed that no evaporation could take place in a space already saturated with vapour of the same liquid, and that it would reach its maximum in air completely freed from this vapour. It therefore follows that, between

these two extremes, the rapidity of evaporation varies according as the surrounding atmosphere is already more or less charged with the same vapour.

The effect of the renewal of this atmosphere is similarly explained; for if the air or gas, which surrounds the liquid, is not renewed, it soon becomes saturated, and evaporation ceases.

Thus it is that the wind, removing the layers of air which are in contact with the earth, soon dries up the roads and streets. Hence, too, it is that linen hung out to dry, does so far more rapidly on a windy than on a dry day.

The greater the extent of surface which a liquid presents to the air, the more numerous are the points from which vapour is disengaged. Hence the evaporation of a liquid should be effected in vessels which are wide and shallow. This is what is done in the process of extracting salt from sea water in *salt gardens*. The sea water is admitted into broad and shallow pits excavated in the ground. Under the influence of the sun's heat the water evaporates slowly, and when its concentration has reached the point at which the liquid is saturated, the salt then begins to form on the surface and is raked off.



Fig. 196.

243. **Ebullition.**—*Ebullition*, or *boiling*, is the rapid production of elastic bubbles of vapour in the mass of a liquid itself.

When a liquid, water for example, is heated at the lower part of a vessel, the first bubbles are due to the disengagement of air which had previously been absorbed. Small bubbles of vapour

hen begin to rise from the heated parts of the sides, but as they ass through the upper layers, the temperature of which is lower, hey condense before reaching the surface. The formation and uccessive condensation of these first bubbles occasion the *singing* oticed in liquids before they begin to boil. Lastly, large bubbles ise and burst on the surface, and this constitutes the phenomenon f ebullition (fig. 196).

244. **Laws of ebullition.**—The laws of ebullition have been etermined experimentally, and are as follows :

I. *The temperature of ebullition, or the boiling point, increases vith the pressure.*

II. *For a given pressure ebullition commences at a certain tem- erature, which varies in different liquids, but which, for equal ressures, is always the same in the same liquid.*

III. *Whatever be the intensity of the source of heat, as soon as ullition commences, the temperature of the liquid remains sta- ionary.*

Thus, the boiling point of water under the ordinary atmospheric pressure being 100°, it could not be heated beyond that point, whatever the intensity of the source of heat; hence all the heat which passes from the source into the liquid is absorbed by the vapour disengaged. But, as this vapour is itself at 100°, we must conclude that this heat is not absorbed to raise the temperature of the vapour, but *simply to produce it*; that is, to change the substance from the liquid into the gaseous state, a phenomenon analogous to that which fusion presents (232). This disappearance of heat during ebullition will be subsequently investigated under the name of latent heat of vaporisation (250).

Boiling points under the pressure of an atmosphere.

Sulphurous acid	−10°	Turpentine	160°
Ether	37	Strong sulphuric acid . .	325
Bisulphide of carbon . .	48	Mercury	350
Bromine	63	Sulphur	447
Alcohol	78	Cadmium	860
Distilled water	100	Zinc	1040

245. **Causes which influence the boiling point.**—The boiling oint of a liquid is affected by the substances in solution, by the legree of pressure to which it is subjected, and by the nature of he vessels in which the boiling takes place.

The ebullition of a liquid is the more retarded, the greater the quantity of any substance it may contain in solution, provided that the substance be not volatile, or, at all events, be less volatile than the liquid itself. Water which boils at 100° when pure, boils at 109° when it is *saturated* with common salt; that is, when it has taken up as much of this salt as it can dissolve. Fatty matters combined with water also raise its boiling point; hence it is that fat soup burns more severely than water.

Fig. 197.

Pressure. The degree of pressure to which a liquid is subjected has a most important influence on its boiling point. The greater the pressure the greater must be the tension, in order that the vapour may be disengaged, and therefore the higher the temperature On the contrary, the less the pressure, the lower the temperature at which ebullition takes place. If the pressure of the atmosphere be removed, water may be made to boil, even at the ordinary tem-

ure. The experiment may be arranged in the manner repre-
d in fig. 197. A glass cup containing water is placed under
ell-jar of an air-pump, or, in order that the experiment may be
by a number of spectators, the bell is placed on a movable
connected with the pump by a tube. When a vacuum is pro-
d, or when the air is very rarefied, the water is seen to boil,
ntly indicating a considerable disengagement of vapour. Yet
emperature of the liquid is not raised ; the boiling is, on the
rary, a source of cold, owing to the heat, which becomes latent
e formation of vapours.

he influence of pressure on ebullition may further be illustrated
eans of an experiment of Franklin's. The apparatus consists
bulb and a tube, joined by a tube of smaller dimensions (fig.
. The tube is drawn out, and the apparatus filled with water,
h is then in great part boiled away by means of a spirit-lamp.



Fig. 198.

en it has been boiled sufficiently long to expel all the air, the
is sealed. There is then a vacuum in the apparatus, or rather,
e is only a pressure due to the tension of aqueous vapour,
h at ordinary temperatures is very small. Consequently, if the
be placed in the hand, as shown in the figure, the heat is
cient to produce a pressure, which drives the water into the
and causes a brisk ebullition.

A paradoxical but very simple experiment also well illustrates
dependence of the boiling point on the pressure. In a glass
water is boiled for some time, and when all air has been ex-
d by the steam, the flask is closed by a cork and inverted, as
n in fig. 199. If the bottom is then cooled by a stream of

cold water from a sponge, the water begins to boil again. This arises from the condensation of the steam above the surface of the water, by which a partial vacuum is produced.

As the pressure of air diminishes in proportion as we rise in the atmosphere, it will be seen from what has been said, that on high mountains water must boil at lower temperatures than on the sea level. This, in fact, is the case; on Mont Blanc, at a height of 15,800 feet, water boils at 84°; at Quito, at a height of 11,000 feet, at 90°; and at Madrid, the height of which is 3,000 feet, it boils at 97°. This diminution in the temperature of ebullition at great heights is a material obstacle to the preparation of food, for, at the temperature of 90°, the extraction of the nourishment and of the flavour is far more imperfect than under the usual conditions.



Fig. 199.

In deep mines, on the contrary, such as those of Cornwall and Lancashire, the reverse is the case: the pressure increases with the depth, and the boiling point is higher than at 100°.

Influence of the nature of the vessel on the boiling point. Gay-Lussac observed that water in a glass vessel required a higher temperature for ebullition than in a metal one. Taking the temperature of boiling water in a copper vessel at 100°, its boiling point in a glass vessel was found to be 101°; and if the glass vessel had been previously cleaned by means of sulphuric acid and of potass, the temperature would rise to 105° or even to 106° before ebullition commenced. Whatever be the boiling point of water, the temperature of its vapour is uninfluenced by the substance of the vessels.

246. **Papin's digester.**—What has hitherto been said in reference to the formation of vapour has applied to the case of liquids heated in open vessels. Only under these conditions can ebulli-

tion take place; for, in a closed vessel, since the vapours cannot escape into the atmosphere, their elastic force and their density continually increase, but that peculiarly rapid disengagement which constitutes boiling is impossible. There is, moreover, this difference between heating in an open and in a closed vessel; that, in the former case, the temperature can never exceed that of ebullition, while in a closed vessel it may be raised so to speak, to an indefinite extent. Thus we have seen (246) that, in an open vessel, water cannot be heated beyond 100° C., all the heat imparted to it being absorbed by the vapours disengaged. But as this disengagement of vapour cannot take place in a closed vessel, water and the vapour may be raised to a far higher temperature than 100°. Yet this is not unattended with danger, from the very high tension which the vapour then assumes.



Fig. 200.

Figure 200 represents the apparatus used in physical lectures for the purpose of heating water in a closed vessel beyond 100 degrees. It is known as *Papin's Digester*. It consists of a cylindrical bronze vessel, M (fig. 200), provided with a cover, which is firmly fastened down by a screw. In order to close the vessel hermetically, sheet lead is placed between the edges of the cover and the vessel. At the bottom of a cylindrical cavity, which traverses a cylinder and tubulure, the cover is perforated by a small orifice in which there is a rod, *u*. This rod presses against a lever, *ab*, movable at *a*, and the pressure may be regulated by means of a weight, *p*, movable on this lever. The lever is so weighted, that when the tension in the interior is equal to six atmospheres, for example, the valve rises and the vapour escapes. The destruction of the apparatus is thus avoided, and the mecha-

nism, which will be described in speaking of the steam engine (269) has hence received the name of *safety valve*. The digester is filled about two-thirds with water, and is heated on a furnace. The water may thus be raised to a temperature far above 100°, and the tension of the vapour increased to several atmospheres, according to the weight on the lever.

The apparatus has received the name *digester*, from a Latin word signifying to dissolve, for the high temperature which water can acquire greatly increases its solvent power. Thus it is used to extract from bones the substance known as *glue*, which could not be accomplished at 100°.



Fig. 201

From the enormous elastic force which vapour may acquire in a closed vessel, it will be understood how important it is not to close tightly the vessel in which water is contained for domestic purposes. Thus a hot water-bottle for heating the feet of invalids should be uncorked before being placed near the fire; for it might burst, or at any rate the cork might be driven out, and a more or less serious accident be caused. In like manner, when a locomotive stops, the steam must be allowed to escape; for otherwise, as it is continually being formed in the boiler without any being consumed in working the engine, it would ultimately acquire such an elastic force that an explosion would ensue.

247. **Measurement of the elastic force of aqueous vapour.**—The important applications which have been made of the elastic force of aqueous vapour, have led philosophers to measure with care the intensity of this force at various temperatures.

Dalton first measured the elastic force of aqueous vapour for

nperatures between 0° and 100°, by means of the apparatus re-esented in fig. 201. Two barometer tubes, A and B, are filled th mercury, and inverted in an iron bath full of mercury, and aced on a furnace. The tube, A, is an ordinary barometer tube, ed from air and moisture; but into the tube, B, is introduced a nall quantity of water. The tubes are supported in a cylindrical ssel full of water, the temperature of which is indicated by the ermometer *t*. The bath being gradually heated, the water in the linder becomes heated too: the water which is in the tube B porises, and in proportion as the elastic force of its vapour in-eases, the mercury sinks. The depressions of the mercury cor-sponding to each degree of the thermometer, are indicated on the ale. Thus, if, when the thermometer is at 70°, the mercury is 233 illimetres lower in the tube B than in the tube A, this shows that at 70° the tension of aqueous vapour is 233 millimetres; which amounts saying that it exercises on the sides of the vessel which contains it pressure equal to the weight of a column of mercury 233 millimetres height.

By noting in the above manner the depression in the baro-eter, B, as compared with A, Dalton determined the elastic force aqueous vapour from 0° to 100°. He found it to be 760 milli-etres, or 29·92 inches; that is to say, an atmosphere (118).

Dulong and Arago determined the elastic force of aqueous pour above 100° up to pressures of 24 atmospheres. More cently Regnault measured the elastic force of aqueous vapour th above and below 100°; and from the researches of this perimenter the following table has been taken, in which the elas-: forces at various temperatures are respectively measured by the ight in millimetres of the column of mercury which they can lance.

Elastic force of aqueous vapour.

Temperatures	Tensions in millimetres	Temperatures	Tensions in millimetres
0	4·60	60	148·79
5	6·53	70	233·09
10	9·17	80	354·64
15	12·70	90	525·45
20	17·39	100	760·00
30	31·55	101	787·63
40	54·91	120	1520·00
50	91·98	160	4580·00

This table shows that the elastic force of aqueous vapour increases far more rapidly than the temperature. Thus at 50° the tension is only 91·9 millimetres; while at 100 degrees, that is to say, double the temperature, the tension is eight times as great.

248. **Latent heat of vapour.**—In speaking of ebullition we have seen that, from the moment a liquid begins to boil, its temperature ceases to rise whatever be the intensity of the source of heat. It follows that a considerable quantity of heat becomes absorbed in ebullition, the only effect of which is to transform the body from the liquid to the gaseous condition. And conversely, when a saturated vapour passes into the state of liquid, it gives out an amount of heat.

These phenomena were first observed by Black, and he described them by saying that, during vaporisation, a quantity of sensible heat became latent, and that the latent heat again became free during condensation. The quantity of heat which a liquid must absorb in passing from the liquid to the gaseous state, and which it gives out in passing from the state of vapour to that of liquid, is spoken of as the *latent heat of evaporation.*

The analogy of these phenomena to those of fusion will be at once seen. The modes of determining them need not be described; but the following results which have been obtained for the latent heats of evaporation of a few liquids may be here given:—

Water	540	Bisulphide of carbon . .	87
Alcohol	208	Turpentine . . .	74
Ether	90	Bromine	46

The meaning of these numbers is, in the case of water, for instance, that it requires as much heat to convert a pound of water from the state of liquid at the boiling point to that of vapour at the same temperature, as would raise a pound of water through 540 degrees, or 540 pounds of water through one degree; or that the conversion of one pound of vapour of alcohol at 78° into liquid alcohol of the same temperature would heat 208 pounds of water through *one* degree.

249. **Cold due to evaporation.**—Whatever be the temperature at which a vapour is produced, an absorption of heat always takes place. If, therefore, a liquid evaporates, and does not receive from without a quantity of heat equal to that which is expended in producing the vapour, its temperature sinks, and the cooling is greater in proportion as the evaporation is more rapid.

may become a source of very great cooling. Thus if a ps of ether be placed on the hand, and this be agitated to te the evaporation, great cold is experienced. With vhich are less volatile than ether, like alcohol and water, e phenomenon is produced, but the cooling is less marked. coming out of a bath, and more especially in the open air h some wind, a very sharp cold is experienced, due to the ormed on the surface of the body. Moist linen is cold and s, because it withdraws from the body the heat which the e requires for evaporation.

cooling effect produced by a wind or draught does not ily arise from the wind being cooler, for it may, as shown thermometer, be actually warmer; but arises from the vaporation it causes from the surface of the skin. We have ng of oppression, even at moderate temperatures, when we n atmosphere saturated by moisture in which no evaporation ace.

cooling produced by the use of fans is due to the increased tion they produce. The freshness occasioned by watering ets is also an effect of evaporation.

cold produced by evaporation is used in hot climates to cool y means of *alcarrazas*. These are porous earthen vessels, which water percolates, so that outside there is a continual evapo- which is accelerated when the are placed in a current of air. For ie reason wine is cooled by wrap- e bottles in wet cloths and placing i a draught.

Fig. 202.

Water and mercury frozen in uum.—From the great quantity of vhich disappears when a liquid verted into vapour it will be seen accelerating the evaporation we means of producing intense cold. ve seen that liquids vaporise more the lower the pressure. Hence, if l containing water be placed in a rom which the air is exhausted, it should cool very rapidly. lie succeeded in freezing water by means of rapid evapora- Under the receiver of the air-pump is placed a vessel con-

taining strong sulphuric acid, a substance which has a great affinity for water, and above it a thin, shallow, porous capsule (fig. 202) containing a small quantity of water. By exhausting the receiver the water begins to boil, and since the vapours are absorbed by the sulphuric acid as fast as they are formed, a rapid evaporisation is produced, which quickly effects the freezing of the water.

By using liquids more volatile than water, more particularly liquid sulphurous acid, which boils at $-10°$, a degree of cold is obtained sufficiently intense to freeze mercury. The experiment may be made by covering the bulb of a thermometer with cotton wool, and after having moistened it with liquid sulphurous acid, placing it under the receiver of the air pump. When a vacuum is produced the mercury is quickly frozen.

Thilorier, by directing a jet of liquid carbonic acid on the bulb of an alcohol thermometer, obtained a cold of $-100°$ without freezing the alcohol. With a mixture of solid carbonic acid, liquid protoxide of nitrogen and ether, M. Despretz obtained a sufficient degree of cold to reduce alcohol to the viscous state.

By means of the evaporation of bisulphide of carbon the formation of ice may be illustrated without the aid of an air-pump. A little water is dropped on a small piece of wood, and a capsule of thin copper foil, containing bisulphide of carbon, is placed on the water. The evaporation of the bisulphide is accelerated by means of a pair of bellows, and after a few minutes the water freezes round the capsule, so that the latter adheres to the wood.

CHAPTER VIII.

LIQUEFACTION OF VAPOURS AND GASES.

251. **Liquefaction of vapours.**—The *liquefaction* or *condensation* of vapours is their passage from the aëriform to the liquid state. Condensation may be due to three causes—*cooling*, *compression*, or *chemical affinity*.

When vapours are condensed, their latent heat becomes free, that is, it affects the thermometer. This is readily seen when a current of steam at 100° is passed into a vessel of water at the ordinary temperature. The liquid becomes rapidly heated, and soon reaches 100°. The quantity of heat given up in liquefaction is equal to the quantity absorbed in producing the vapour.

Liquefaction by chemical affinity.—The affinity of certain substances for water is so great as to condense the vapours in the atmosphere, even when they are far from their point of saturation. Thus, when highly hygroscopic substances, such as quicklime, potass, sulphuric acid, are exposed in the air, they always absorb aqueous vapour. Certain varieties of common salt exposed to the air absorb and condense so much aqueous vapour as to become liquid. Many other salts have the same property, and are hence called *deliquescent salts.*

Liquefaction by pressure.—Let us suppose a vessel containing aqueous vapour, a cylinder for instance, and in this cylinder a piston which can be depressed at will, like that represented in fig. page 9. As the vapour is not at first in a state of saturation, when the piston is depressed, it behaves like a true gas, the pressure increasing its elastic force and density without liquefying it. But the more the piston is depressed the smaller does the volume of the vapour become, and a point is ultimately reached at which the vapour present is just sufficient to saturate the space. From this point the slightest increase of pressure causes a portion of vapour to pass into the liquid state, and the liquefaction continues as long as the excess of pressure lasts; so that if the piston descends to the bottom of the cylinder all the vapour is condensed. In this experiment it is to be observed, that when once saturation is attained, provided there is no air in the cylinder, the resistance to the depression of the piston does not increase in proportion as it descends, which arises from the condensation of the vapour, and confirms what was previously said (240), as to the maximum tension of vapour in a state of saturation.

Liquefaction by cooling.—Cooling, as well as pressure, only causes vapours to liquefy when they are in a state of saturation. But when once a given space is saturated, the slightest lowering of temperature takes from the vapours the heat which gives them their fluidity, the attraction between the molecules preponderates, they agglomerate, forming extremely small droplets, which float in the air and are deposited on the surrounding bodies.

Vapours are ordinarily condensed by cooling. Thus, the vapours exhaled from the nose and mouth of animals first saturate the colder air in which they are disengaged, and they condense with a cloud-like appearance. It is owing to the same phenomenon that the vapours become visible which are disengaged from boiling water, those which rise from chimneys, the fogs formed above

rivers, and so forth. All these vapours are more apparent in winter than in summer, for then the air is colder, and the condensation more complete.

In cold weather, the windows in heated rooms are seen to become covered with dew on the inside. The air of these rooms is in general far from being saturated with vapour, but the layers of air in immediate contact with the windows become colder; and as the quantity of vapour necessary to saturate a given space is less, the colder this space, a moment is reached at which the air in contact with the windows is saturated, and then the vapours they contain are quickly deposited. In a time of thaw, when the air is hotter on the outside than on the inside, the deposit is formed on the outside. To the same cause is due the deposit of moisture formed on walls, which is expressed by saying that they *sweat*; an unsuitable expression, for the moisture does not come from the walls but from the atmosphere. The walls are colder than the air, and they lower the temperature of the layers in contact with them, and condense the vapours. A similar effect is produced when in summer a bottle of wine is brought from the cellar, or when a glass is filled with cold water; a deposit of dew is formed on the surface of these vessels. The same phenomenon does not occur in winter, for then the temperature of the atmosphere being the same as that of the bottle, or even lower, the layers of air in immediate contact with it are not cooled.

252. **Heat disengaged during condensation.**—It has been seen that any liquid in vaporising absorbs a quantity of heat. This heat is not destroyed, for, in the converse change, it reappears in the *sensible* state; that is to say, it is capable of acting on our sense of feeling and on the thermometer. For instance, we know that a pound of water absorbs in vaporising 540 units of heat (248): that is to say, a quantity of heat necessary to raise 540 pounds of water from 0° to 1°; conversely, a pound of steam at 100°, which is liquefied and gives a pound of water at 100°, causes 540 units to pass from the latent to the sensible state, an amount of heat which is utilised in heating by steam.

253. **Application to heating by steam.**—The quantity of heat which becomes free when aqueous vapour is condensed is utilised in the arts for heating private houses, hot-houses, and public buildings. Steam is produced in boilers like those used in steam engines, and passes from thence into metal tubes concealed behind the wainscot, or into columns which serve at the same time as ornaments

ms. The steam condensing in these tubes gives up a con-
ıle quantity of heat, which they impart to the surrounding air.
. **Distillation. Stills.**—*Distillation* is an operation by which
: liquid may be separated from substances which it holds in
n, or by which two liquids of different volatilities may be sepa-
The operation depends on the transformation of liquids into
s by the action of heat, and on the condensation of these
s by cooling.
: apparatus used in distillation is called a *still*. Its form may
:eatly, but consists essentially of three parts; 1st, the *body*.



Fig. 203.

203), a copper vessel containing the liquid, the lower part
ch fits in the furnace; 2nd, the *head*, B, which fits on the
and from which a lateral tube, C, leads to, 3rd, the *worm*,
ng spiral tin or copper tube, placed in a cistern kept con-
' full of cold water. The object of the worm is to condense
pour, by exposing a greater extent of cold surface.
free ordinary well water from the many impurities which it
ns, it is placed in a still and heated. The vapours disen-
are condensed in the worm, and the distilled water arising
he condensation is collected in the receiver, D. The vapours
densing rapidly heat the water in the cistern, which must,

therefore, be constantly renewed. For this purpose a continual supply of cold water passes into the bottom of the cistern, while the lighter heated water rises to the surface, and escapes by a tube in the top of the cistern.

Brandy is obtained from wine by means of distillation. Wine, consists essentially of water, alcohol, and colouring matter; when heated in a still to a temperature between 78° and 100°, the alcohol, which boils at 78°, vaporises, while water, which only boils at 100°, remains behind, or at all events only passes over in small quantity. The liquid resulting from this distillation, is brandy, which is essentially a mixture of alcohol and water.

255. **Liquefaction of gases.**—We have already seen that a saturated vapour, the temperature of which is constant, is liquefied by increasing the pressure, and that, the pressure remaining constant, it is brought into the liquid state by diminishing the temperature.

Unsaturated vapours behave in all respects like gases. And it is natural to suppose, that what are ordinarily called *permanent gases* are really unsaturated vapours. For the gaseous form is accidental, and is not inherent in the nature of the substance. At ordinary temperatures sulphurous acid is a gas, while in countries near the poles it is a liquid; in temperate climates ether is a liquid, at a tropical heat it is a gas. And just as unsaturated vapours may be brought to the state of saturation and then liquefied by suitably diminishing the temperature or increasing the pressure, so, by the same means, gases may be liquefied. But as they are mostly very far removed from this state of saturation great cold and pressure are required. Some of them may indeed be liquefied either by cold or by pressure; for the majority, however, both processes must be simultaneously employed. Few gases can resist these combined actions, and probably those which have not yet been liquefied, hydrogen, oxygen, nitrogen, binoxide of nitrogen, and carbonic oxide, would become so if submitted to a sufficient degree of cold and pressure.

One of the most remarkable experiments on the liquefaction of gases is that made by Thilorier to liquefy and solidify carbonic acid. The principle of the method was first devised and applied by Faraday. The apparatus consists of two cast iron cylinders with very thick sides, of 5 to 6 quarts capacity. They are hermetically closed, and are connected by means of a leaden tube. *In one of* these cylinders, A, called the *generator*, are placed the

tances by whose chemical action carbonic acid is evolved. se are ordinarily bicarbonate of soda, D, and sulphuric acid in tube, C. The second cylinder, called the *receiver*, B, is empty; the gas disengaged by the chemical action in the generator ils over, and as the receiver is colder, it condenses in virtue of ncreasing pressure. As much as two quarts of liquid carbonic have thus been prepared.



Fig. 204.

At a temperature of 15 degrees the tension of the compressed in the cylinders is not less than 50 atmospheres; a pressure ch would burst the vessels if they were not solidly constructed. accident of this kind happened some years ago, and caused the th of Thilorier's assistant.

To obtain solid carbonic acid, the receiver is provided with a cock attached to a tube, which dips in the liquid acid. On ning this stopcock the liquid acid driven by pressure jets out; sing then from a tension of 50 atmospheres down to a single , a part of the liquid volatilised; and in consequence of the t absorbed by this evaporation, the rest is so much cooled as olidify in white flakes *like snow, or* anhydrous phosphoric acid.

Solid carbonic acid evaporates very slowly. By means of an alcohol thermometer its temperature has been found to be about $-90°$. A small quantity placed on the hand does not produce the sensation of such great cold as might be expected. This arises from the imperfect contact. But if the solid be mixed with ether the cold produced is so intense, that when a little is placed on the skin all the effects of a severe burn are produced. A mixture of these two substances solidifies four times its weight of mercury in a few minutes. When a tube containing liquid carbonic acid is placed in this mixture the liquid becomes solid, and looks like a transparent piece of ice.

CHAPTER IX.

SPECIFIC HEAT. CALORIMETRY.

256. **Calorimetry. Thermal unit.**—The object of calorimetry is to measure the *quantity of heat* which a body parts with or absorbs when its temperature sinks or rises through a certain number of degrees, or when it changes its condition.

Quantities of heat may be expressed by any of its directly measurable effects, but the most convenient is the alteration of temperature; and quantities of heat are usually defined by stating the extent to which they are capable of raising the temperature of a known weight of a known substance, such as water.

The unit chosen by comparison, and called the *thermal unit*, is not everywhere the same. In France it is the quantity of heat necessary to raise the temperature of *one* kilogramme of water through *one* degree Centigrade; this is called a *calorie*. In this book we shall adopt, as a thermal unit, *the quantity of heat necessary to raise one pound of water through one degree Centigrade*: 1 *calorie* = 2·2 thermal units, and 1 thermal unit = 0·45 *calorie*.

257. **Specific heat.**—When equal weights of two different substances at the same temperature placed in similar vessels are subjected for the same length of time to the heat of the same lamp, or are placed at the same distance in front of the same fire, it is found that their temperature will vary considerably; the mercury will be much hotter than the water. But as from the conditions of the

periment, they have each been receiving the same amount of at, it is clear that the quantity of heat which is sufficient to se the temperature of mercury through a certain number of de- ees will only raise the temperature of the same quantity of water rough a less number of degrees ; in other words, that it requires re heat to raise the temperature of water through one degree an it does to raise the temperature of mercury by the same extent. nversely, if the same quantities of water and of mercury at 100° be allowed to cool down to the temperature of the atmosphere, water will require a much longer time for the purpose than the rcury ; hence, in cooling through the same number of degrees, ter gives out more heat than does mercury.

It is readily seen that all bodies have not the same specific heat. a pound of mercury at 100° is mixed with a pound of water at o, the temperature of the mixture will only be about 3°. That is say, that while the mercury has cooled through 97°, the tempe- ure of the water has only been raised 3°. Consequently, the ne weight of water requires about 32 times as much heat as rcury does to produce the same elevation of temperature.

If similar experiments are made with other substances it will be nd that the quantity of heat required to effect a certain change of nperature is different for almost every substance, and we speak the *specific heat* or *calorific capacity* of a body as the quantity of at which it absorbs when its temperature rises through a given nge of temperature, from zero to 1° for example, compared with e quantity of heat which would be absorbed under the same cir- mstances, by the same weight of water. In other words, water taken as the standard for the comparison of specific heats. Thus, say that the specific heat of lead is 0·0314, means that the quan- y of heat which would raise the temperature of any given quantity lead through 1° C. would only raise the temperature for the same antity of water through 0·0314.

258. **Determination of the specific heats of solids and of uids.**—Three methods have been employed for determining the ecific heats of bodies ; (i.) the method of melting ice, (ii.) the thod of mixtures, and (iii.) that of cooling. In the latter, the ecific heat of a body is determined by the time which it takes to l through a certain temperature.

Method of the fusion of ice.—This method of determining specific ats is based on the fact that to melt a pound of ice, 80 thermal ts are necessary, or more exactly 79·25. The substance to be

determined is raised to a known temperature, 100° for instance, and is then rapidly placed in ice. In cooling from 100° to zero, the body melts a certain quantity of ice, which is collected in the form of water. From the weight of this water, from that of the body, and from the number of degrees through which it is cooled, the specific heat may be readily calculated.

To facilitate the execution of this method Lavoisier and Laplace devised an apparatus which is called the *ice calorimeter*. Fig. 205 gives a perspective view of it, and fig. 206 represents a section. It consists of three concentric tin vessels, M, A, B, each with covers of the same material; in the central one is placed the body M, whose

Fig. 205.

Fig. 206.

specific heat is to be determined, while the two others, A and B, are filled with pounded ice. The ice in the compartment A is melted by the heated body, and the water resulting from the liquefaction runs off by the stopcock D, and is collected in a vessel; the ice in the compartment B cuts off the heating influence of the surrounding atmosphere. The stopcock E gives issue to the water which arises from the liquefaction of the ice in B.

Method of mixtures.—In determining the specific heat of a solid body by this method, it is weighed and raised to a known temperature, by keeping it, for instance, for some time in a closed space heated by steam; it is then immersed in a mass of cold water, the weight and temperature of which are known. The water becomes

by the heat given up by the body in cooling, and both are tely at the same temperature. From this common tempera- om the respective weights of the water and of the substance, stly from their temperatures at the time of mixture, the spe- eat of the body is deduced by a simple calculation.

Substances.	Specific heats.	Substances.	Specific heats.
. . . .	1·0000	Zinc	0·0955
ntine . . .	0·4259	Copper . . .	0·0951
charcoal . .	0·2411	Silver	0·0570
ir	0·2025	Tin	0·0562
ite . . .	0·2018	Antimony . . .	0·0507
ometer glass .	0·1976	Mercury . . .	0·0333
horus . . .	0·1895	Gold . . .	0·0324
nd . . .	0·1469	Platinum	0·0324
. . . .	0·1138	Lead	0·0314
. . . .	0·1086	Bismuth . . .	0·0308

will be seen from the above table that water and oil of tur- e have a much greater specific heat than that of other sub- s, and more especially than the metals. It is from its great c heat that water requires a long time in being heated or ; and that, for the same weight and temperature, it absorbs es out far more heat than substances. This double ty is applied in heating by ater, and it plays a most im- t part in the economy of



Fig. 207.

ose bodies which have great c heat, and therefore which e a great quantity of heat to hem through a given tempera- lso in cooling through the ange give out a great quantity. ifference between bodies as to antities of heat they contain e illustrated by a simple ex- nt. A number of small bullets of various metals, iron, tin, ismuth, and copper are heated to a temperature of about by immersing them in hot oil; they are then placed on a

cake of bees-wax, C D, about half an inch in thickness It will then be found that the iron and copper melt t through first, then follows the tin, while the lead an make but little way, being unable to sink much more their way through the wax.

CHAPTER X.

STEAM ENGINES.

259. **Invention of the steam engine.**—*Steam engine* doubtedly the most important of the applications of th sciences to the arts. Based on the very great elastic fo aqueous vapour assumes at a high temperature (247), a condensation of this vapour by cooling (251), steam eng created, in a small volume and at small expense, very co motive powers.

Their importance has caused much discussion and inv as to their inventor, or rather inventors; for it is only by cessive efforts of several men of genius that these machine tained their present simplicity and precision.

The history of the steam engine commences with He ventor of the fountain which bears his name, who invent two thousand years ago, a steam tourniquet, known as th analogous to the hydraulic tourniquet. The names of S Caux, and then of the Marquis of Worcester, are mention history of the steam engine.

Denis Papin, a French physicist, to whom is due the already described (246), was the first who caused a ascend in a vertical cylinder closed at the bottom and o top by means of the elastic force of steam, and to descen densing this vapour by cooling; so that the piston which in virtue of atmospheric pressure had an up and down the cylinder, which is still the principle of all steam Papin, who was a Protestant, was obliged to fly from consequence of the revocation of the Edict of Nantes description and plan of his machine was published in G 1690. He even made a model large enough to move means of paddle-wheels. In this model there was wa

ıth the piston at the bottom of the cylinder. When a furnace s placed under this, the water vaporised, and the elastic force sed the piston; when it was at the top of its course the furnace ıs withdrawn; the cylinder cooling, the vapour was condensed, d the piston sank.

In 1705 Newcomen and Cawley constructed a steam engine, or .re-pump,' as it was then called, the object of which was to drain ines. In this engine the steam was produced separately in a ıiler *m* below the cylinder *c* containing the piston *p*. The conden-



Fig. 208.

ıtion also was effected by cold water from a cistern, *n*, being in-cted into the cylinder through a cock, *b*. This was opened when e piston was to descend, and was closed after the descent; a cond one, *a*, was opened through which steam entered, and so . But the sides of the cylinder being cooled by this injection cold water, the steam which filled it was partially condensed, til the sides were again heated: there was thus a considerable loss steam, and therefore of fuel. The condensed water flowed out a pipe, at the end of which was the valve *v*, which opened as piston *p* descended. *w w* is the beam by which the motion is nsmitted to the pump rod, *d*.

260. **Watt's improvements in the steam engine.**—James Watt, a mathematical instrument maker in Glasgow, had to repair the model of a Newcomen's engine belonging to the physical cabinet of the University. Struck by the enormous quantity of steam and of condensing water used by this engine, he entered upon a long series of researches and improvements, which he pursued with admirable perseverance for fifty years, without ever being content with the success he obtained. Thus it was that Newcomen's machine, successively metamorphosed in all its parts, at last really became Watt's machine.

Condenser. Watt's first and principal invention was the *condenser*. This name is given to a closed vessel quite distinct from the cylinder in which the piston moves, and only connected with it by a tube provided with a stopcock. In this vessel cold water is injected, and the vapour is condensed by opening the connecting stopcock. Thus as the sides of the cylinder are not cooled, all the steam which enters there is utilised. Thus there was effected so great an economy of steam, and therefore of fuel, that Watt and Boulton his partner, having taken a patent, realised great profits by only requiring, for a certain number of years, a third of the saving in the consumption of coal as compared with Newcomen's engine.

Single-acting engine. In Newcomen's engine the cylinder of which was open at the top, the steam only lifted the piston; and then, when steam was condensed, the pressure of the atmosphere brought it down again; whence the name *atmospheric engine*, by which it was designated. As the piston descended, air penetrated into the cylinder and cooled the sides, in consequence of which a portion of the vapour which penetrated into the cylinder was condensed until the sides were again heated. To remove this source of loss, Watt closed the cylinder altogether, and caused the vapour to act above the piston, so as to make it descend; then by an arrangement of stopcocks, alternately opened and closed by the action of the engine itself, the steam passed simultaneously above and below the piston. This being pressed equally in opposite directions, remained in equilibrium; so that a simple counterpoise acting by means of a lever at the end of the piston rod raised the piston again, and so on. This machine, into which air did not enter, and where the atmospheric pressure did not act, was called the *single-acting engine*, to express that the steam had a useful action on only one side of the piston.

The single-acting engine had the great disadvantage that it had

real force except when the piston was descending. It could nsmit motion to pumps for emptying mines, because, for that, ort in only one direction was required ; but it would not furnish sufficiently regular motion for many industries, for cotton manuctures for instance. Hence Watt's task was not completed ; and : was not long in finding another plan.

Double-acting engine. In this engine, one form of which we iall presently describe, and which is represented in fig. 209, the ylinder is closed both at top and at the bottom, but the steam acts lternately on the two faces of the piston ; that is to say, that by a ystem of stopcocks, opened and closed by the engine itself, when he lower part of the cylinder communicates with the condenser, he upper part, on the contrary, is connected with the boiler, and he steam acting in all its force on the piston causes it to descend. Then when this is at the bottom of its stroke the parts change ; the op of the cylinder is in connection with the condenser, and the ottom with the boiler ; the piston rises again and so forth, whence esults an alternating rectilinear motion which is changed into a ontinuous circular motion, as will be presently described (262).

Air-pump. Watt completed his engine by the addition of three umps, which are worked by the engine, and play an important art. For the cold water of the condenser becomes rapidly heated y the heat which the steam gives up to it (253), and this water, oon reaching 100 degrees, would no longer condense the steam. Moreover the air, which is always dissolved in cold water, is libeated in the boiler, owing to the increase in temperature. Now this ir, passing both above and below the piston, would soon stop its notion. To prevent these two injurious effects, Watt applied o the engine a suction-pump, which continually withdrew from he condenser the air and water which tended to accumulate there.

Feed-pump and *cold-water-pump.* The two other pumps which Watt added are the feed-pump and the cold-water-pump. The rst is a force-pump which sends into the boiler the hot water withrawn from the condenser by the air-pump, thus producing a conderable saving in fuel. The other is a suction-pump, which raises ither from a well or a river, or some other source, the cold water ntended to replace that heated in the condenser, and withdrawn by e air-pump.

Besides the important parts which have thus been described, we re to Watt the arrangement for distributing the steam alternately ove and below the piston : the *regulator*, whose function, when

the machine works too slowly, is to admit more steam into the cylinder, and, on the other hand, to diminish the quantity when the velocity is too great. Lastly, the *parallelogram*, which imparts to the piston rod a rectilinear motion. We may add that Watt, who had begun life as a philosophical instrument maker, carried into the execution of these great mechanisms the same perfection as is required for the best scientific instruments.

261. **Description of the double-acting engine.**—We have already seen that the double-action engine is that in which the steam acts alternately above and below the piston (260). Fig. 209 represents an engine of this kind, and fig. 213 gives a section of the cylinder, of the piston, and of the distribution of steam. The entire engine is of iron. To the piston T is fixed a rod A, which slides with gentle friction in a tubulure U placed at the centre of the plate which closes the cylinder (fig. 213). As it is very important that no steam shall escape between the piston rod and this tubulure, the latter is formed of two pieces, one attached to the plate, while the other, which fits in the first, can be pressed as tightly as is desired, so as to compress the material soaked with fat which is between the two tubulures. This arrangement is called a *stuffing box*; it prevents the escape of steam without interfering with the motion of the piston.

On the two sides of the cylinder are two columns *k k*, which guide the piston rod in its upward and downward motion. The end of the piston rod is connected with a long piece B, called the *connecting rod*, which in turn is jointed with a shorter piece M, called the *crank*, the length of which is just half that of the stroke of the piston. This is rigidly fixed to a *horizontal shaft*, D, so that it cannot move without transmitting its motion.

By means of this connecting rod and crank, the alternating rectilinear motion of the piston and of the rod is changed into a continuous circular motion. For the rod during the ascent of the piston, acts upwards upon the crank, making it turn in the direction of the arrow. When the piston is at the top of its stroke, the motion rod and the crank are one in front of the other. As the piston descends the motion rod again acts, so as always to turn it in the same direction; and when the piston is at the bottom of the stroke, they are again vertical, but one in the prolongation of the other. Hence it follows that the axle which has made half a turn during the ascent, makes a second one during the descent, and thus a complete revolution during each double oscillation of the piston.

To transmit the motion to machinery, on the axle D is fixed a ave on which works an *endless band* XY of leather, or of gutta-



Fig. 209.

percha, which works on another sheave fixed to the machinery to be turned. Moved by the first sheave, this band communicates its motion to the second ; in this manner the motion is transmitted to all the workshops of a large factory. On the right of the fixed sheave, G, there is a second, which is not fixed to the horizontal shaft ; this is the movable sheave. Its object is to suspend all the motion in the machine without stopping the steam engine. By means of an iron fork not seen in the figure, which encloses the band, the latter may be slid from the fixed to the movable sheave. As this latter is not connected with the horizontal shaft, it does not turn with it, and does not transmit its motion to the band.

On the horizontal shaft is a very large iron wheel V, called the *fly-wheel*, which is necessary for keeping up the motion. For each time that the piston is at the top or bottom of its stroke, there is a momentary arrest, during which the motion of the whole machine tends to stop. These are called the *dead points*. It is then that the fly-wheel, in virtue of its inertia and of its acquired velocity, moves the horizontal shaft, and thus keeps up a regular motion.

262. **Excentric. Valve-chest.**—The excentric is an arrangement by which a continuous circular motion is changed into an alternating rectilinear motion. It is very frequently used in machinery.

One of these is fitted to the horizontal shaft at E, and the other at *e*. The former works the *feed-pump*, and the latter the *valve-chest*. The action of both is the same. Figures 210 and 211 represent it on a larger scale, in two diametrically opposite positions. It consists of a circular piece KE, fixed to the horizontal shaft, but in such a manner that the centre of rotation does not coincide with the centre of the piece ; the latter being at C, the former at O. It follows from this construction that the point C constantly describes a circumference about O, which is represented in the drawing by a dotted line. Hence in each half turn it passes from the position represented in fig. 210 to that represented in fig. 211, and *vice versâ*. So that the point C, in turning about the point O, does really perform an up and down motion.

To use this motion, the excentric is surrounded by a *collar m*, in which it can turn freely like an axle in its box : hence, during the rotation of the horizontal shaft, the collar shares the ascending and descending motion of the point C, but not its rotatory motion. The excentric alone turns, the collar only rises and

nks. By thus transmitting its motion to a rod *i*, it works the lve-chest.



Fig. 210.



Fig. 211.

Valve-chest. We have still to describe the valve-chest, the arrangement by which steam passes alternately above and below the piston. Fig. 213 presents a vertical section of this valve-chest, and of the cylinder. The steam enters the valve-chest from the boiler by the brass tube *x*. From the valve-chest two conduits, *a* and *b*, are connected with the cylinder, one above and the other below. If they were both open at once, the steam acting equally on the two faces of the piston would keep it at rest. But one of these is always closed by a *slide valve*, *y*, fixed to a rod, *i*. This moves alternately, up and down, by means of an excentric, *e*, placed on the horizontal shaft. In fig. 213 the slide-valve closes the conduit *a*, and allowing the steam to enter at *b*, below the piston, the latter rises. But when it reaches the top of the stroke the excentric has passed from the position represented in fig. 210 to that in fig. 211; hence the rod, *i*, sinks, and with it the slide-valve, which then closes the conduit *b*, and allows the vapour to enter at *a* (fig. 212). The piston then sinks, and so forth at each displacement of the slide valve.

In completing this account of the manner in which steam is dis-

tributed, it remains to explain what happens when the steam presses below the piston (fig. 213). It must not remain above, otherwise the piston could not move. But while the steam enters below by the conduit *b*, the top of the cylinder, by means of a conduit *a*, is connected with a cavity O, from which passes a tube L. Through this tube the steam which has already acted upon the piston passes into the atmosphere, or else is condensed in a vessel filled with



Fig. 212. Fig. 213.

cold water, which has been already mentioned, *the condenser* (262). If, on the other hand, the piston sinks, the slide-valve being in the position of fig. 212, the vapour below the piston passes by the conduit *b*, to the cavity O, and to the tube L.

263. **Regulator.**—The object of this arrangement is to regulate the quantity of steam which reaches the valve-chest, increasing it when the machine works too slowly and diminishing it when it works too rapidly. It consists of a parallelogram *kr*, each apex of

ich is jointed. A toothed wheel, *a*, connected with the horizontal aft, transmits its motion to a similar wheel, *b*, fixed to the rod *c*, ıich supports the parallelogram. This turns then with the rod e more rapidly the greater the velocity of the machine. But the 'o upper arms are provided with two solid balls, *m* and *n*; oreover, a socket, *r*, to which are attached the two lower arms, is ıt fixed to the rod *c*, but can glide along it. Hence the centrigal force (29) acting on the balls *m* and *n* makes them diverge, e parallelogram opens, and the socket rises. It transmits its otion to a lever, *s*, the short arm of which being lowered presses ›on a long rod, *t*. This inclining the lever, O, effects a small rota›n in a valve, *v*, placed in the tube *x*, by which steam comes g. 213). This valve, either by stopping the tube *x*, or leaving it ›en, admits more or less steam.

264. **Feed-pump.**—The object of this, as its name implies, is to new the water in the boiler in the degree in which it evaporates. fig. 209 this pump, placed at Q, on the left of the drawing, reives its motion from an excentric by means of a long rod, and it ›rks both as *cold-water-pump* and as *feed-pump*; as cold-water-ımp, inasmuch as it withdraws water from a well by a suction-pipe aced below the engine; and as feed-pump by its then forcing ıter into the boiler by the pipe R.

265. **Various kinds of steam engines.**—A *low pressure engine* one in which the pressure of the vapour does not much exceed an mosphere; and a *high pressure engine* is one in which the essure of the steam usually exceeds this amount considerably. ›w pressure engines are mostly *condensing engines*: in other ›rds, they generally have a condenser where the steam becomes ndensed after having acted on the piston; on the other hand, *gh pressure engines* are frequently without a condenser; the locootive is an example.

If the communication between the cylinder and the boiler remains ›en during the whole motion of the piston, the steam retains es:ntially the same elastic force, and is said to act *without expansion*: ut if, by a suitable arrangement of the slide-valve, the steam ceases › pass into the cylinder when the piston is at $\frac{2}{3}$ or $\frac{3}{4}$ of its course, ıen the vapour *expands*; that is to say, in virtue of its elastic force hich is due to the high temperature, it still acts on the piston and ıuses it to finish its course. Hence a distinction is made between *panding* and *non-expanding* engines.

The principle of expansion is not applicable to low pressure

engines, for the elastic force of the steam is inconsiderable. But for high or mean pressure engines it not only effects a great saving in steam, and therefore in fuel, but it regulates the motion by diminishing the pressure the moment the acquired velocity of the piston tends to increase.

266. **Work of an engine. Horse-power.**—The work of an engine is measured by the mean pressure on the piston multiplied by the area of the piston multiplied by the length of the stroke. In



Fig. 214.

England the unit of work is the *foot-pound*; that is, the work performed in raising a weight of one pound through a height of a foot. Thus, to raise a weight of 14 pounds through a height of 20 feet would require 280 foot-pounds. In France the *kilogrammetre* is used; that is, the work performed in raising a kilogramme through a metre. This unit corresponds to 7·233 foot-pounds.

The *rate of work* in machines is the amount of work performed

n a given time ; a second or an hour, for example. In England he rates of work are compared by means of *horse-power*, which is ı conventional unit, and represents 550 foot-pounds in a second. :n France a similar unit is used, called the *cheval vapeur*, which 'epresents the work performed in raising 75 kilogrammes through ɔne metre in a second. It is equal to about 542 foot-pounds per second.

267. **Steam boiler.**—We have still to describe the steam boiler or arrangement by which the steam is generated, and its various accessories.

Fig. 214 gives a longitudinal and fig. 215 a transverse section of the steam boiler and its furnace. The generator consists of two wrought iron cylinders with hemispherical ends. Below are two cylinders, BB, of smaller diameter, which are called *heaters*, and which are connected with the generators by two strong tubes. The object of these heaters is to expose a greater surface to be heated. They are full of water, as also are the tubes which connect them with the boiler, which is only half full.

Fig. 215.

The feed-water sent by the pump, Q, reaches the boiler by a tubulure, *n*, which is immersed to the bottom to prevent cold water from condensing steam ; a second tubulure, *m*, leads the vapour to the valve-chest. In the middle of the boiler is an oval hole, called a *manhole*, the object of which is to allow workmen to enter the boiler when it needs repair. This hole, as well as two front ones, B B, of the heaters are closed by what are called *autoclaves*. Here the cover instead of being on the outside is on the inside. A screw T fixed to this cover makes it press against the sides ; and as the pressure of the steam acts in the same direction, the greater the pressure the more tightly is the vessel closed.

The furnace in which the boiler is placed, is so constructed as to multiply the surface heated, and to render the combustion as

complete as possible. The products of combustion pass into tall chimneys, which from their great height increase the draught and thereby promote the combustion.

268. **Float.**—This is a small apparatus, the object of which is to show the level of water in the boiler. It consists of a lever, at one end of which is a piece of stone, F, and at the other a counterpoise, *a*. The mass F weighs more than the counterpoise *a*; but as it is immersed in water, and thus loses part of its weight (96), it is in equilibrium, and the lever is horizontal so long as the level of water is at the desired height. But it sinks when there is too little water, and rises in the contrary direction when there is too much. Guided by these indications, the stoker can regulate the supply of water.

269. **Safety-valve.**—The pressure of steam in the boiler is measured by means of the manometer (134). But this instrument would not prevent explosions if its indications were neglected. Hence on boilers two safety-valves, are placed, similar to that which Papin adopted in his digester (248). Fig. 216 represents on a larger scale one of these valves. It consists of a metal stopper *c* closing a tubulure A. fixed on the boiler. To prevent this from sticking to the sides, the metal stopper is hollowed on three sides, as shown at S. It thus more resembles a clack-valve than an ordinary cork. On the piece rests a movable lever, *ab*, loaded with a weight, *p*. By moving this along the lever the load on the valve can be modified at will. For this purpose marks are placed which indicate the position of the load which corresponds to a given pressure. Thus, suppose it is desired that the pressure shall not exceed 5 atmospheres, the weight is placed at the division 5 on the lever. Then, as long as the pressure is less than 5, the safety-valve remains closed: but, if the pressure exceeds this amount, the valve opens and gives exit to the steam, thus preventing an explosion.



Fig. 216.

270. **Safety-whistle.**—This is another safety apparatus, which indicates at a distance when the level of water in the boiler is too low. It consists of a float, F (fig. 217), supported by a lever, *ik*,

:h moves about the joint *c*; a counterpoise, *p*, balances the , and a small conical stopper, *a*, fixed to the lever, closes a lure on the boiler. This tubulure is closed at the top by two ɔw hemispheres. In the centre of the lower arc is a disc, which ; not quite reach the edges. Between the two hemispheres is a ılar interval through which vapour escapes when the cone *a* ; not close the tubulure.

\s long as the water is at the right height the float F is raised,



Fig. 217.

l presses the cone against the tubulure; but if the level sinks float sinks, and with it the cone. The steam escapes round the : *e*, and gives a very acute sound in striking against the edges he upper hemisphere which are bevelled. The system con- ıtes, in fact, an ɔrgan pipe with a very short mouthpiece, and ding, therefore, a very acute sound.

On locomotives a similar whistle enables the driver to signal at eat distance by opening a stopcock, which allows the steam to .pe.

CHAPTER XI.

HYGROMETRY.

271. **Object of hygrometry.**—The object of *hygrometry* is to determine the quantity of aqueous vapour contained in a given volume of air. This quantity is very variable; but the atmosphere is never completely saturated with vapour, at any rate, in our climates. Nor is it ever completely dry; for if *hygrometric substances*, that is to say, substances with a great affinity for water, such as chloride of calcium, sulphuric acid, etc., be at any time exposed to the air, they absorb more or less aqueous vapour.

The degree of moisture does not depend on the absolute quantity of aqueous vapour present in the air, but on the greater or less distance of the air from its point of saturation. When the air is cold, it may be moist with very little vapour, and, on the contrary, when it is warm, it may be very dry, even with a large quantity of vapour. In summer the air usually contains more aqueous vapour than in winter, notwithstanding which it is less moist, because, the temperature being higher, the vapour is farther from its point of saturation. When a room is warmed, the quantity of moisture is not diminished, but the moisture of the air is lessened, because its point of saturation is raised. The air may thus become so dry as to be injurious to the health, and it is hence usual to place vessels of water on the stoves used for heating.

The quantity of vapour contained in the air varies greatly with the seasons, the climates, the temperature, and various local causes. A mean degree of moisture is best suited to the animal economy. In a state of great dryness, as is the case, for instance, during the prevalence of north-east winds, the cutaneous transpiration is too abundant, the skin dries up and chaps, and general discomfort ensues. In an atmosphere which is too moist, perspiration stops, a feeling of depression and heaviness is felt. Hence it is necessary to regulate in a suitable manner the moisture of dwelling rooms, so as to avoid these two extremes.

272. **Hygroscopes and hygrometers.**—There are two classes of instruments by which the hygrometric state of the air may be

own. One class, called *hygroscopes*, simply tell whether the air more or less moist, but give no indications as to the quantity of isture it contains ; others, called *hygrometers*, enable us to mea- e it with some accuracy.

All substances which absorb aqueous vapour, like common salt l many others known as *deliquescent salts*, may serve as hygro- pes. This is also the case h a great number of animal l vegetable substances, such paper, parchment, hair, cat- t, etc., which, elongating the air becomes moist, and ntracting as it becomes dry, e an indication of the greater less quantity of vapour in the .

Fig. 218.

A great number of instru- nts have been constructed ich serve as *hygroscopes*. One the commonest is that repre- nted in fig. 218. It consists of small figure representing a nk fixed on a support ; the ad is provided with a cowl of n cardboard, movable about point *a*, where it is attached the end of a small piece of isted catgut. The other end of this is fixed in a tubulure, *o*, as n in the section. The catgut twisting as it becomes dry, and twisting as it is moist, moves the cowl which is carefully arranged, that the head is covered when the atmosphere is moist, and un- ered when it is dry.

This instrument, and all others of the same class, only change wly, and their indications are always behindhand with the state the weather ; nor are they, moreover, very exact.

273. **Hygrometric state of the air.**—By this term we do not lerstand the actual quantity of vapour present, but the ratio of quantity of vapour which the air actually contains to that which ould contain if it were saturated. Thus, if we say that the air *three-fifths* saturated, we mean that it contains three-fifths of the our which it would contain in a state of saturation.

The most exact of all hygrometers are the *chemical hygrometers.* They consist essentially of an arrangement by which a given measured volume of air is passed through a series of drying tubes —that is, tubes containing some hygroscopic substance, such as chloride of calcium, or pumice saturated with sulphuric acid. These tubes, being previously weighed, are weighed again after the operation; an increase of weight is observed, which is due to the moisture absorbed by the hygroscopic substance, and this increase represents the weight of the moisture in the volume of air taken.

This method is very exact, but it is both difficult and tedious of execution.

More convenient than the above are what are called *condensation hygrometers,* in which the vapour of the atmosphere is made to condense on a body artificially cooled. When a body gradually cools in a moist atmosphere, the layer of air in immediate contact with it cools also, and a point is ultimately reached at which the vapour present is just sufficient to saturate the air: the least diminution of temperature then causes a precipitation of moisture on the body in the form of dew. When the temperature rises again, the dew disappears, and the mean of these two temperatures is taken as the *dew point.*



Fig. 219.

A good example of an instrument of this class is met with in *Daniell's hygrometer.* This consists of two glass bulbs at the extremities of a glass tube bent twice (fig. 219). The bulb A is two-thirds full of ether, and a very delicate thermometer dips in it; the rest of the space contains nothing but the vapour of ether, the ether having been boiled before the bulb B was sealed. The bulb B is covered with muslin, and ether is dropped upon it. The ether in evaporating cools the bulb, and the vapour contained in it is condensed. The internal tension being thus diminished, the ether in

vapours which condense in the other bulb, B. In proporher distils from the lower to the upper bulb, the ether in A colder, and ultimately the temperature of the air in immetact with A sinks to that point at which its vapour is just ın sufficient to saturate it, and the excess is accordingly l on the outside as a ring of dew corresponding to the surıe ether. The temperature of this point is noted by means ermometer in the inside. The addition of ether to the bulb ı discontinued, the temperature of A rises, temperature at which the dew disappears . In order to render the deposition of e perceptible, the bulb A is made of black



Fig. 220.

e two points having been determined, their taken as that of the dew-point. The tem- of air at the time of the experiment is l by the thermometer on the stem. The *f*, corresponding to the temperature of the ıt, is then found in the table of tensions (249). sion is exactly that of the vapour present in t the time of the experiment. The tension, our saturated at the temperature of the ate is found by means of the same table; the obtained by dividing *f* by F, represents ometric state of the air. For instance, the ture of the air being 15°, suppose the dew 5°. From this table the corresponding ten- : $f = 6{\cdot}53$ millimetres, and $F = 12{\cdot}70$ millis which gives 0·514 for the ratio of *f* to F, or ometric state.

ry convenient form of hygrometer, and one se is gradually extending, is that known as the *pyschrometer bulb hygrometer*, which is based on the principle that a ed body evaporates in the air more rapidly in proportion ir is drier (242); and, in consequence of this evaporation, perature of the body sinks. The application of the printhis purpose was first suggested by Leslie. The form of ıratus usually adopted in this country is due to Mason. It of two delicate thermometers placed on a wooden stand). One of the bulbs is covered with muslin, and is kept ılly moist by being connected with a reservoir of water by

means of a string. Unless the air is saturated with moisture, the wet bulb thermometer always indicates a lower temperature than the other, and the difference between the indications of the two thermometers is greater in proportion as the air can take up more moisture.

According to Glashier the temperature of the dew point may be obtained by multiplying the difference between the temperatures of the wet and dry bulb by a number which depends on the temperature of the air at the time of observation, and subtracting the product thus obtained from this last-named temperature. The following are the numbers :

Dry bulb temperature F.°	Factor	Dry bulb temperature F.°	Factor
Below 24°	8·5	34 to 35°	2·6
24 to 25	7·3	35—40	2·5
25—26	6·4	40—45	2·3
26—27	6·1	45—50	2·1
27—28	5·9	50—55	2·0
28—29	5·7	55—60	1·8
29—30	5·0	60—65	1·8
30—31	4·6	65—70	1·7
31—32	3·6	70—75	1·5
32—33	3·1	75—80	1·3
33—34	2·8	80—85	1·0

These are often known as *Glashier's factors.* The temperatures are expressed on the Fahrenheit scale.

CHAPTER XII.

METEOROLOGICAL PHENOMENA WHICH DEPEND UPON HEAT.

274. **Meteorology.**—Meteorology is that part of physics which is concerned with the phenomena which occur in the atmosphere; such, for instance, as variations in the temperature of the air, wind, rain, storms, electrical phenomena, etc. Though of quite recent origin, this science is an important application of the physical sciences, and furnishes useful indications to navigation, to agriculture, and to hygiene.

275. **Mean temperature.**—The *mean daily temperature*, or ıply *temperature*, is that obtained by adding together 24 hourly ervations, and dividing by 24. A very close approximation to mean temperature is obtained by taking the mean of the xima and minima temperatures of the day and of the night, ich are determined by means of the maximum and minimum rmometers (204). These ought to be protected from the solar s, raised above the ground, and be far from all objects which ght influence them by their radiation. The lowest daily tem- rature is at 4 A.M., and the highest at 2 P.M.

The *temperature of a month* is the mean of those of 30 days, and e *temperature of the year* is the mean of those of 12 months. The ghest mean monthly temperature is in July, and the lowest in ınuary. Finally, the temperature of a place is the mean of its ınual temperature, for a great series of years. The mean tem- erature of London is 8·28° C., or 46·9° F. The temperatures in ll cases are those of the air and not those of the ground.

276. **Causes which modify the temperature of the air.**—The rincipal causes which modify the temperature of the air are the ıtitude of a place, its height—that is, its distance above the sea— he direction of the winds, and the proximity of seas.

Influence of the latitude. The temperature of the air and of the round diminishes from the equator towards the poles. This is lue to the fact, that the sun's rays, which are perpendicular at the quator, are more and more inclined as we come near the poles. Now we have seen (215) that the greater the obliquity under which he rays of heat fall upon a body, the less is the body heated ; ence the heat absorbed decreases from the equator to the poles, for he rays are then more oblique. Yet, as in summer, the days are onger as we get nearer the north, the loss due to the increasing bliquity of the sun is partially compensated by the sun remaining onger above the horizon. Under the equator, where the length f the days is constant, the temperature is almost invariable ; in he latitude of London, and the more northerly countries, where the lays are very unequal, the temperature varies greatly ; but in ummer it sometimes rises almost as high as under the equator. The lowering of the temperature produced by the latitude is small ; hus in a latitude of 115 miles north of ours, the temperature is nly 1° C. lower.

Influence of altitude. The height of a place has a much more onsiderable influence on the temperature than its latitude. In

the temperate zone a diminution of 1° C. corresponds in the mean to an ascent of 180 yards.

The cooling on ascending in the atmosphere has been observed in balloon ascents, and a proof of it is seen in the perpetual snows which cover the highest mountains, even under the torrid zones. The height at which snow remains unmelted through the year, or the *line of perpetual snow* met with, differs in different places. On the Andes it commences at a height of 14,760 feet, and on the Alps at 8,880 feet.

Direction of winds. As winds share the temperature of the countries which they have traversed, their direction exercises great influence on the air in any place. In our climate the hottest winds are the south, then come the south-east, the south-west, the west, the east, the north-west, north, and lastly, the north-east, which is the coldest. The character of the wind changes with the seasons; the east-wind, which is cold in winter, is hot in summer.

Proximity of the seas. The neighbourhood of the sea tends to render the temperature of the air uniform, by heating it in winter, and cooling it in summer. The average temperature of the sea in equatorial and polar countries is always higher than that of the atmosphere. With reference to the uniformity of the temperature, it has been found that in temperate regions, that is, from 25° to 50° of latitude, the difference between the maximum and minimum temperature of a day does not exceed, on the sea, 2° to 3°; while on land it amounts to 12° to 15°. In islands the uniformity of temperature is very perceptible, even during the greatest heats. In continents, on the contrary, the winters for the same latitudes become colder, and the difference between the temperature of summer and winter becomes greater.

277. **Gulf stream.**—A similar influence to that of the winds is exerted by currents of warm water. To one of these, the Gulf stream, the mildness of the climate in the north-west of Europe is usually assigned. This great body of water, taking its origin in equatorial regions, flows through the Gulf of Mexico, from whence it derives its name; passing by the southern shores of North America it makes its way in a north-westerly direction across the Atlantic, and finally washes the coast of Ireland and the north-west of Europe generally. Its temperature in the Gulf is about 28° C.; and generally is a little more than 5° C. higher than the rest of the ocean on which it floats, owing to its lower specific gravity. To

s influence is due the milder climate of western Europe, as compared with that of the opposite coast of America; thus the river Hudson, which is in the same latitude as Rome, is frozen over three months in the year. It also causes the polar regions to be separated from the coasts of Europe by a girdle of open sea; and hence he harbour of Hammerfest is open the year round. Besides its influence in thus moderating climate, the Gulf stream is an important elp to navigators.

278. **Isothermal lines.**—When on a map all the points whose emperature is known to be the same are joined, curves are obtained hich Humboldt first noticed, and which he called *isothermal lines.* f the temperature of a place only varied with the obliquity of he sun's rays, that is, with the latitude, isothermal lines would all e parallel to the equator; but as the temperature is influenced y many local causes, especially by the height, the isothermal lines, re always more or less curved. On the sea, however, they are lmost parallel. A distinction is made between *isothermal lines*, *sotheral lines*, and *isochimenal lines*, where the mean *general*, the *nean summer*, and the *mean winter* temperatures are respectively onstant. An *isothermal zone* is the space comprised between two sothermal lines. Kupffer also distinguishes *isogeothermal lines*, here the mean temperature of the soil is constant.

279. **Climate.**—By the *climate* of a place is understood the hole of the meteorological conditions to which a place is subected; its mean annual temperature, summer and winter temperatures, and by the extremes within which these are comprised. Some writers distinguish seven classes of climates, according to heir mean annual temperature, a *hot climate* from 30° to 25° C.; a *varm climate* from 25° to 20° C.; a *mild climate* from 20° to 15° C.; *temperate climate* from 15° to 10° C.; a *cold climate* from 10° to 5° C.; a *very cold climate* from 5° to zero; and an *arctic climate* here the temperature is below zero.

Those climates again, are classed as *constant climates*, where he difference between the mean and summer and winter temperature does not exceed 6° to 8°; *variable climates*, where the difference amounts to from 16° to 20°; and *extreme climates*, where the difference is greater than 30°. The climates of Paris and London re variable; those of Pekin and New York are extreme. Island climates are generally little variable, as the temperature of the sea s constant; and hence the distinction between land and sea climates. *Marine climates* are characterised by the fact, that the

difference between the temperature of summer and winter is always less than in the case of continental climates. But the temperature is by no means the only character which influences climates; there are, in addition, the moisture of the air, the quantity and frequency of the rains, the number of storms, the direction and intensity of the winds, and the nature of the soil.

FOG. RAIN. DEW.

280. **Fogs and mists.**—When aqueous vapours, rising from a vessel of boiling water, diffuse in the colder air, they are condensed; a sort of cloud is formed which consists of a number of small hollow vesicles of water, which remain suspended in the air. These are usually spoken of as vapours, yet they are not so, at any rate not in the physical sense of the word; for they are partially condensed vapours.

When this condensation of aqueous vapours is not occasioned by contact with cold solid bodies, but takes place throughout large spaces of the atmosphere, the effect is to form *fogs* or *mists*, which, in fact, are nothing more than the appearance seen over a vessel of hot water.

A chief cause of fogs consists in the moist soil being at a higher temperature than the air. The vapours which then ascend condense and become visible. In all cases, however, the air must have reached its point of saturation before condensation takes place. Fogs may also be produced when a current of hot and moist air passes over a river at a lower temperature than its own, for then the air being cooled, as soon as it is saturated the excess of vapour present is condensed.

The distinction between mists and fogs is one of degree rather than of kind. A fog is a very thick mist.

281. **Clouds.**—*Clouds* are masses of vapour, condensed into little drops or vesicles of extreme minuteness, like fogs; from which they only differ in occupying the higher regions of the atmosphere; they always result from the condensation of vapours which rise from the earth or the sea. According to their appearance, they have been divided by Howard into four principal kinds: the *nimbus*, the *stratus*, the *cumulus*, and the *cirrus*. These four kinds are represented in fig. 221, and are designated respectively by one, two, three, and four birds on the wing.

The *cirrus* consist of small whitish clouds, which have a fibrous

wispy appearance, and occupy the highest regions of the atmo-here. The name of *mare's tails*, by which they are generally iown, well describes their appearance. From the low tempera-re of the spaces which they occupy, it is more than probable that rrus clouds consist of frozen particles; and hence it is that haloes, ironæ, and other optical appearances, produced by refraction and flection from ice crystals, appear almost always in these clouds id their derivatives. Their appearance often precedes a change weather.

The *cumulus* are rounded spherical forms which look like moun-

Fig. 221.

ns piled one on the other. They are more frequent in summer an in winter, and, after being formed in the morning, they gene-lly disappear towards evening. If, on the contrary, they become ore numerous, and especially if surmounted by cirrus clouds, rain storms may be expected.

Stratus clouds consist of very large and continuous horizontal eets, which chiefly form at sunset, and disappear at sunrise.

They are frequent in autumn and unusual in spring time, and are lower than the proceeding.

The *nimbus*, or rain clouds, which are sometimes classed as one of the fundamental varieties, are properly a combination of the three preceding kinds. They affect no particular form, and are solely distinguished by a uniform grey tint, and by fringed edges. They are indicated on the right of the figure by the presence of one bird.

The fundamental forms pass into one another in the most varied manner; Howard has classed these traditional forms as *cirro-cumulus*, *cirro-stratus*, and *cumulo-stratus*, and it is often very difficult to tell, from the appearance of a cloud, which type it most resembles. The cirro-cumulus is most characteristically known as a 'mackerel sky;' it consists of small roundish masses, disposed with more or less irregularity and connection. It is frequent in summer, and attendant on warm and dry weather. *Cirro-stratus* appears to result from the subsidence of the fibres of cirrus to a horizontal position, at the same time that they approach each other laterally. The form and relative position when seen in the distance frequently give the idea of shoals of fish. The tendency of *cumulo-stratus* is to spread, settle down into the *nimbus*, and finally fall as rain.

The height of clouds varies greatly; in the mean it is from 1,300 to 1,500 yards in winter, and from 3,300 to 4,400 yards in summer. But they often exist at greater heights; Gay-Lussac, in his balloon ascent, at a height of 7,650 yards, observed cirrus-clouds above him, which appeared still to be at a considerable height. In Ethiopia M. d'Abbadie observed storm-clouds whose height was only 230 yards above the ground.

In order to explain the suspension of clouds in the atmosphere, Halley first proposed the hypothesis of *vesicular vapours*. He supposed that clouds are formed of an infinity of extremely minute vesicles, hollow, like soap bubbles filled with air, which is hotter than the surrounding air; so that these vesicles float in the air like so many small balloons. This theory has at present many opponents, who assume that clouds and fogs consist of extremely minute droplets of water, which are retained in the atmosphere by the ascensional force of currents of hot air, just as light powders are raised by the wind. Ordinarily, clouds do not appear to descend, but this absence of downward motion is only apparent. In fact, clouds do usually fall slowly, but then the lower part is continually

dissipated on coming in contact with the lower and more heated layers ; at the same time the upper part is always increasing from the condensation of new vapours, so that from these two actions clouds appear to retain the same height.

282. Formation of clouds.—Many causes may concur in the formation of clouds. I. The low temperature of the higher regions of the atmosphere. For owing to the solar radiation, vapours are constantly disengaged from the earth and from the waters, which from their elastic force and lower density rise in the atmosphere ; meeting there continually colder and colder layers of air, they sink to the point of saturation, and then condensing in infinitely small droplets, they give rise to clouds.

II. The hot and moist currents of air rising during the day undergo a gradually feebler pressure, and thus is produced an expansion, which is a source of intense cold, and produces a condensation of vapour. Hence it is that high mountains, stopping the aerial currents, and forcing them to rise, are an abundant source of rain.

III. A hot, moist current of air mixing with a colder current, undergoes a cooling, which brings about a condensation of the vapour. Thus the hot and moist winds of the south and south-west, mixing with the colder air of our latitudes, give rain. The winds of the north and north-east tend also, in mixing with our atmosphere, to condense the vapours; but as these winds, owing to their low temperature, are very dry, the mixture rarely attains saturation, and generally gives no rain.

283. Rain.—When, by the constant condensation of aqueous vapour, the individual vapour vesicles become larger and heavier, and when finally individual vesicles unite, they form regular drops, which fall as *rain*. The quantity of rain which falls annually in any given place, or the annual rainfall, is measured by means of a *rain gauge* or *pluviometer*.

Many local circumstances may effect the quantity of rain which falls in different countries ; but, other things being equal, most rain falls in hot climates, for there the vaporisation is most abundant. The rain-fall decreases, in fact from the equator to the poles. At London it is 23·5 inches; at Bordeaux it is 25·8 ; at Madeira it is 27·7 ; at Havannah it is 91·2 ; and at St. Domingo it is 107·6. The quantity varies with the seasons ; in Paris, in winter it is 4·2 inches ; in spring 6·9 ; in summer 6·3 ; and in autumn 4·8 inches.

An inch of rain on a square yard of surface expresses a fall of 46·74 pounds, or 4·67 gallons. On an acre it corresponds to 22,622 gallons, or 100·9935 tons. 100 tons per inch per acre is a ready way of remembering this.

284. **Dew. Hoar frost.**—*Dew* is merely aqueous vapour which has condensed on bodies during the night in the form of minute, globules. It is occasioned by the chilling which bodies near the surface of the earth experience in consequence of nocturnal radiation. Their temperature having then sank several degrees below that of the air, it frequently happens, especially in hot seasons, that this temperature is below that at which the atmosphere is saturated. The layer of air which is immediately in contact with the chilled bodies, and which virtually has the same temperature, then deposits a portion of the vapour which it contains: just as when a bottle of cold water is brought into a warm room, it becomes covered with moisture, owing to the condensation of aqueous vapour upon it.

According to this theory, which was first propounded by Dr. Wells, all causes which promote the cooling of bodies increase the quantity of dew. These causes are the emissive power of bodies, the state of the sky, and the agitation of the air. Bodies which have a great radiating power more readily become cool, and therefore ought to condense more vapour. In fact there is generally no deposit of dew on metals, whose radiating power is very small, especially when they are polished; while the ground, sand, glass, and plants, which have a great radiating power, become abundantly covered with dew. On some plants, for instance, not merely are droplets of dew formed, but regular layers of water.

The state of the sky also exercises a great influence on the formation of dew. If the sky is cloudless, the planetary spaces send to the earth an inappreciable quantity of heat, while the earth radiates very considerably, and therefore becoming very much chilled, there is an abundant deposit of dew. But if there are clouds, as their temperature is far higher than that of the planetary spaces, they radiate in turn towards the earth, and as bodies on the surface of the earth only experience a feeble chilling, no deposit of dew takes place

Wind also influences the quantity of vapour deposited. If it is feeble, it increases it, inasmuch as it renews the air; if it is strong, it diminishes it, as it heats the bodies by contact, and thus does not allow the air time to become cooled. Finally, the deposit of dew is

more abundant according as the air is moister, for then it is nearer its point of saturation.

Hoar frost and *rime* are nothing more than dew which has been deposited on bodies cooled below zero, and has therefore become frozen. The flocculent form which the small crystals present, of which rime is formed, shows that the vapours solidify directly, without passing through the liquid state. Hoar frost, like dew, is formed on bodies which radiate most, such as the stalks and leaves of vegetables, and is chiefly deposited on the parts turned towards the sky.

285. **Snow. Sleet.** *Snow* is water solidified in stellate crystals, variously modified, and floating in the atmosphere. These crystals arise from the congelation of the minute vesicles which constitute the clouds, when the temperature of the latter is below zero. They

Fig. 222.

are more regular when formed in a calm atmosphere. Their form may be investigated by collecting them on a black surface, and viewing them through a strong lens. The regularity, and at the same time variety, of their forms are truly beautiful. Fig. 222 shows some of the forms as seen through a microscope.

It snows most in countries near the poles, or which are high above the sea level. Towards the poles, the earth is constantly covered with snow; the same is the case on high mountains, where there are perpetual snows even in equatorial countries.

Sleet is also solidified water, and consists of small icy needles pressed together in a confused manner. Its formation is ascribed to the sudden congelation of the minute globules of the clouds in an agitated atmosphere.

286. **Hail.**—*Hail* is a mass of compact globules of ice of different sizes, which fall in the atmosphere. In our climates hail falls principally during spring and summer, and at the hottest times of the day: it rarely falls at night. The fall of hail is always preceded by a peculiar noise. Hail is generally the precursor of storms, it rarely accompanies them, and follows them more rarely still. A hailstone consists of a core of snow, which is surrounded by concentric layers of ice. Hail falls from the size of small peas to that of an egg or an orange. The formation of hailstones, and more especially their great size, have never been altogether satisfactorily accounted for. While snow sometimes falls for days together, hailstorms seldom last longer than a quarter of an hour, and they are also far less frequent.

ON WINDS IN GENERAL.

287. **Direction and velocity of winds.**—*Winds* are currents moving in the atmosphere with variable directions and velocities. There are eight principal directions in which they blow: *north*, *north-east*, *east*, *south-east*, *south*, *south-west*, *west*, and *north-west*. Mariners further divide each of the distances between these eight directions into four others, making in all 32 directions, which are called *points* or *rhumbs*. A figure of these 32 rhumbs on a circle in the form of a star, is known as the *mariner's card*.

The direction of the wind is determined by means of *vanes*, and its velocity by means of the *anemometer*. There are several forms of this instrument; the most usual consists of a small vane with fans, which the wind turns; the velocity is deduced from the number of turns made in a given time, which is measured by means of an endless screw and wheel-work. In our climate the mean velocity is from 18 to 20 feet in a second. With a velocity of 6 or 7 feet, the wind is moderate; with 30 or 35 feet, it is fresh; with 60 or 70 feet, it is strong; with a velocity of 85 to 90 feet, it is a tempest, and from 90 to 120 it is a hurricane.

288. **Causes of winds.**—Winds are produced by the disturbance of the equilibrium in some part of the atmosphere, a disturbance

ways resulting from a difference in temperature between adjacent ıuntries. Thus, if the temperature of a certain extent of ground :comes higher, the air in contact with it becomes heated, it ex-ınds, and rises towards the higher regions of the atmosphere; hence it flows, producing winds which blow from hot to cold ıuntries. But at the same time the equilibrium is destroyed at .e surface of the earth, for the barometric pressure on the colder ljacent parts is greater than on that which has been heated, and ence a current will be produced with a velocity dependent on the ifference between these pressures; thus two distinct winds will e produced, an upper one setting *outwards* from the heated region, nd a lower one setting *inwards* towards it.

289. **Regular, periodical, and variable winds.**—According to he more or less constant directions in which winds blow, they may ıe classed as regular, periodical, and variable winds.

i. *Regular winds* are those which blow all the year through in virtually constant direction. These winds, which are also known s the *trade winds*, are uninterruptedly observed far from the land equatorial regions, blowing from the north-east to the south-west the northern hemisphere, and from the south-east to the north-est in the southern hemisphere. They prevail on the two sides the equator as far as 30° of latitude, and they blow in the me direction as the apparent motion of the sun, that is, from st to west.

The air above the equator being gradually heated, rises as the n passes round from east to west, and its place is supplied by e colder air from the north or south. The direction of the wind, wever, is modified by this fact; that the velocity which this lder air has derived from the rotation of the earth, namely, the locity of the surface of the earth at that point from which it arted, is less than the velocity of the surface of the earth at the oint at which it has now arrived; hence the currents acquire, in ference to the equator, the constant direction which constitutes he trade winds.

ii. *Periodical winds* are those which blow regularly in the same irection at the same seasons, and at the same hours of the day; he monsoon, simoom, and the land and sea breeze are examples f this class. The name *monsoon* is given to winds which blow r six months in one direction, and for six months in another. hey are principally observed in the Red Sea and in the Arabian ulf, in the Bay of Bengal and in the Chinese Sea. These winds

blow towards the continents in summer, and in a contrary direction in winter. The *simoom* is a hot wind which blows over the deserts of Asia and Africa, and which is characterised by its high temperature and by the sands which it raises in the atmosphere and carries with it. During the prevalence of this wind the air is darkened, the skin feels dry, the respiration is accelerated, and a burning thirst is experienced.

This wind is known under the name of *sirocco* in Italy and Algiers, where it blows from the great desert of Sahara. During its prevalence people remain at home, the windows and doors being carefully closed. In Egypt, where it prevails from the end of April to June, it is called *kamsin*, from a word signifying *fifty*: for it lasts ordinarily 50 days; 25 before the spring equinox, and 25 after. When caravans are surprised by this wind, men cover their faces with thick clothes, and camels turn their backs to the torment. The natives of Africa, in order to protect themselves from the effects of the too rapid perspiration occasioned by this wind, cover themselves with fatty substances.

The *land* and *sea breeze* is a wind which blows on the sea coast during the day from the sea towards the land, and during the night from the land to the sea. For during the day the land becomes more heated than the sea, in consequence of its lower specific heat (257) and greater conductivity, and hence as the superincumbent air becomes more heated than that upon the sea, it ascends and is replaced by a current of colder and denser air flowing from the sea towards the land. During the night the land cools more rapidly than the sea, and hence the same phenomenon is produced in a contrary direction. The sea breeze commences after sunrise, increases to three o'clock in the afternoon, decreases towards evening, and is changed into the land breeze after sunset. These winds are only perceived at a slight distance from the shores. They are regular in the tropics, but less so in our climates; and traces of them are seen as far as the coasts of Greenland. The proximity of mountains also gives rise to periodical daily breezes.

iii. *Variable winds* are those which blow sometimes in one direction and sometimes in another, alternately, without being subject to any law. In mean latitudes the direction of the winds is very variable; towards the poles this irregularity increases, and under the arctic zone the winds frequently blow from several points of the horizon at once. On the other hand, in approaching the torrid zone, they become more regular. The south-west wind

evails in the north of France, in England, and in Germany; in e south of France the direction inclines towards the north, and Spain and Italy the north wind predominates.

290. **Law of the rotation of winds.**—Spite of the great irregu- rity which characterises the direction of the winds in our latitude, has been ascertained that the wind has a preponderating ten- ncy to veer round according to the sun's motion ; that is, to pass om north, through north-east, east, south-east to south, and so on und in the same direction from west to north ; that it often makes complete circuit in that direction, or more than one in succes- on, occupying many days in doing so, but that it rarely veers, and ery rarely or never makes a complete circuit in the opposite direc- on.

For a station in south latitude a contrary law of rotation pre- ails.

This law, though more or less suspected for a long time, was irst formally enunciated and explained by Dove, and is known as *Dove's law of rotation of winds.*

CHAPTER XIII.

SOURCES OF HEAT AND COLD.

291. **Different sources of heat.**—The following different sources of heat may be distinguished : i. the *mechanical sources*, comprising friction, percussion, and pressure ; ii. the *physical sources*—that is, solar radiation, terrestrial heat, the molecular actions, the changes of condition and electricity ; iii. the *chemical sources*, or molecular combinations, and more especially combustion.

MECHANICAL SOURCES.

292. **Heat due to friction.**—The friction of two bodies, one gainst the other, produces heat, which is greater the greater the ressure and the more rapid the motion. For example, the axles f carriage wheels, by their friction against the boxes, often become o strongly heated as to take fire. By rubbing together two pieces f ice in a vacuum below zero, Sir H. Davy partially melted them.

In boring a brass cannon Rumford found that the heat developed in the course of 2½ hours was sufficient to raise 26½ pounds of water from zero to the boiling point.

This may be well illustrated by an experiment, fig. 223, devised by Prof. Tyndal. A brass tube, *b*, closed at the bottom, about 4 inches long and less than an inch in diameter, fits on the whirling table, having been three-quarters filled with cold water and corked.



Fig. 223.

If now it be clasped by a sort of wooden squeezer in which there are two semicircular grooves, and then be made to rotate, the heat developed by the friction is sufficient to boil the water and expel the cork by which it is closed.

293. **Heat due to pressure and percussion.**—If a body be so compressed that its density is increased, its temperature rises according as the volume diminishes. In solids and liquids, which are but little compressible, the disengagement of heat is not great; though Joule has verified it in the case of water and of oil, which were exposed to pressures of 15 to 25 atmospheres. Similarly, when weights are laid on metallic pillars, heat is evolved, and absorbed when they are removed.

The production of heat by the compression of gases is easily shown by means of the *pneumatic syringe* (fig. 224). This consists of a glass tube with thick sides, closed hermetically by a leathern piston. At the bottom of this, there is a cavity in which a small piece of tinder is placed. The tube being full of air the piston is suddenly plunged downwards, the air thus compressed disengages as much heat as to ignite the tinder, which is seen to burn when the piston is rapidly withdrawn. The inflammation of the tinder in this experiment indicates a temperature of at least 300°. At the moment of compression a bright flash is observed, which was

ginally attributed to the high temperature of the air; but it is ıply due to the combustion of the oil which greases the piston.



Fig. 224.

Percussion is also a source of heat, as is observed in the sparks vhich are thrown off by horses in trotting over a hard pavement. n firing a shot at an iron target, a sheet of flame is frequently seen it the moment of impact; and Mr. Whitworth has used iron shells vhich are exploded by the concussion on striking an iron target. A small piece of iron hammered on the anvil becomes very hot. The heat is not simply due to an approximation of the molecules, hat is, to an increase in density, but arises from a vibratory motion nparted to them; for lead, which does not become denser by being ammered, nevertheless becomes heated.

PHYSICAL SOURCES.

294. **Solar radiation.**—The most intense of all sources of heat the sun. The cause of its heat is unknown; some have con-dered it to be an ignited mass experiencing immense eruptions, hile others have regarded it as composed of layers acting ıemically on each other like the couples of a voltaic battery, and ıving rise to electrical currents, which produce light and solar eat. On both hypotheses the incandescence of the sun would have limit.

Different attempts have been made to determine the quantity of eat annually emitted by the sun. M. Pouillet, by means of an pparatus which he calls a *pyrheliometer*, has calculated that if ıe total quantity of heat which the earth receives from the sun in ıe course of a year were employed to melt ice, it would be capable melting a layer of ice all round the earth of 35 yards in thickness.

But from the surface which the air exposes to the solar radiation, and from the distance which separates the earth from the sun, the quantity of heat which the earth receives can only be $\frac{1}{2{\cdot}381{\cdot}000{\cdot}000}$ of the heat emitted by the sun.

Faraday has calculated that the average amount of heat radiated in a day on each acre of ground in the latitude of London is equal to that which would be produced by the combustion of sixty sacks of coal.

295. **Terrestrial heat.**—Our globe possesses a heat peculiar to it, which is called the *terrestrial heat.* The temperature of the earth gradually sinks from the surface to a certain depth, at which it remains constant in all seasons. It is hence concluded that the sun's heat does not penetrate below a certain internal layer, which is called the *layer of constant temperature*: its depth below the earth's external surface varies, of course, in different parts of the globe; at Paris it is about thirty yards, and the temperature is constant at 11·8° C.

Below the layer of constant temperature, the temperature is observed to increase, on the average 1° C. for every 90 feet. This increase has been verified in mines and artesian wells. According to this, at a depth of 3,000 yards, the temperature of a corresponding layer would be 100°, and at a depth of 20 to 30 miles there would be a temperature sufficient to melt all substances which exist on the surface. Hot springs and volcanoes confirm the existence of this central heat.

The heat produced by the changes of condition has been already treated of in the articles *solidification* and *liquefaction*; the heat produced by electrical action will be discussed under the head of ELECTRICITY.

CHEMICAL SOURCES.

296. **Chemical combinations. Combustion.**—Whenever two bodies unite in virtue of their reciprocal affinity this operation is known as the act of *chemical combination.* Chemical combinations are usually accompanied by a certain elevation of temperature. When these combinations take place slowly, as when iron oxidises in the air, and produces rust, the heat produced is imperceptible; but if they take place rapidly, the disengagement of heat is very intense. The same quantity of heat is produced in both cases, but when evolved slowly it is dissipated as fast as formed.

Combustion is chemical combination attended with the evolution of light and heat. In the ordinary combustion in lamps, fires, candles, the carbon and hydrogen of the coal or of the oil, etc., combine with the oxygen of the air, giving rise to aqueous vapour, gases, and other volatile products which are given off as smoke. The old expression that *fire destroys everything* is incorrect. It destroys nothing, it simply puts certain elements at liberty to unite with others; it *decomposes* but at the same time *produces*. A body in being burned is transformed, but its substance is not destroyed.

Many combustibles burn with flame. A *flame* is a gas or vapour raised to a high temperature by combustion. Its illuminating power varies with the nature of the products formed. The presence of a solid body in the flame increases the illuminating power. The flames of hydrogen, carbonic oxide, and alcohol are pale, because they only contain gaseous products of combustion. But the flames of candles, lamps, coal gas, have a high illuminating power. They owe this to the fact that the high temperature produced decomposes certain of the gases with the production of carbon, which, not being perfectly burned, becomes incandescent in the flame. Coal gas, when burnt in an arrangement by which it obtains an adequate supply of air, is almost entirely devoid of luminosity. A non-luminous flame may be made luminous by placing in it platinum wire, or asbestos. The temperature of a flame does not depend on its illuminating power. A hydrogen flame, which is the palest of all flames, gives the greatest heat.



Fig. 225.

297. **Rumford's calorimeter.**—In order to determine the amount of heat which is produced by combustion, Rumford used the calorimeter depicted in fig. 225. A metal box contains a known weight of water at a known temperature; through it passes a copper worm tube, *ss*, which is open at one end *s'*, and at the other ends in a funnel *c*. The

substance whose heating effect is to be determined, is placed underneath the funnel, and having been previously weighed, is ignited. The gaseous products of combustion pass then through the worm, and imparting their heat to the water, raise the temperature. From the weight of the water and its increase in temperature, which is measured by the thermometer, and from the weight of the body burned, its heating effect may be determined.

By experiments with more perfect arrangements, based however, on the same principle, the heating effect of the following substances has been determined. The numbers represent the number of pounds of water which are raised 1° C. by the combustion of a pound of the substance.

Hydrogen	34000	Dry turf	4800
Petroleum	12300	Wood	2900
Coal	6500	Carbonic oxide . . .	2400
Phosphorus . . .	5700	Sulphur	2200

SOURCES OF COLD.

298. **Various sources of cold.**—Besides the cold caused by the passage of a body from the solid to the liquid state, of which we have already spoken, cold is produced by the expansion of gases, by radiation in general, and more especially by nocturnal radiation.

299. **Cold produced by the expansion of gases.**—We have seen, that when a gas is compressed, its temperature rises. The reverse of this is also the case : when a gas is rarefied a reduction of temperature ensues, because a quantity of sensible heat disappears when the gas becomes increased to a larger volume. This may be shown by placing a delicate Breguet's thermometer under the receiver of an air-pump, and exhausting; at each stroke of the piston the needle moves in the direction of zero, and regains its original temperature when air is admitted. Kirk has invented a machine for the manufacture of ice, which depends on this property. The heat developed by the compression of air is removed by a current of cold water; the vessel containing the compressed air being placed in brine, the air is allowed to expand; in so doing it cools the brine so considerably as to freeze water contained in vessels placed in the brine. It is stated that by this means a ton of coals (used in working a steam engine by which the compression is effected) can produce a ton of ice.

300. **Cold produced by nocturnal radiation.**—During the day, the ground receives from the sun more heat than radiates into space, and the temperature rises. The reverse is the case during night. The heat which the earth loses by radiation is no longer compensated for, and consequently a fall of temperature takes place, which is greater according as the sky is clearer, for clouds send towards the earth rays of greater intensity than those which come from the celestial spaces. In some winters it has been found that rivers have not frozen, the sky having been cloudy, although the thermometer has been for several days below $-4°$; while in other less severe winters the rivers freeze when the sky is clear. The emissive power exercises a great influence on the cold produced by radiation; the greater it is the greater is the cold.

In Bengal, the nocturnal cooling is used in manufacturing ice. Large flat vessels containing water are placed on non-conducting substances, such as straw or dry leaves. In consequence of the radiation the water freezes, even when the temperature of the air is 10° C. The same method can be applied in all cases with a clear sky.

It is said that the Peruvians in order to preserve the shoots of young plants from freezing, light great fires in their neighbourhood, the smoke of which producing an artificial cloud, hinders the cooling produced by radiation.

Country people are in the habit of saying that it freezes more when the moon appears than when it is hidden by clouds. They are right in this; but the freezing is not, as they think, due to the influence of the moon. It is owing to the absence of clouds.

BOOK IV.

ON LIGHT.

CHAPTER I.

TRANSMISSION, VELOCITY, AND INTENSITY OF LIGHT.

301. **Theories of light.**—*Light* is the agent which, by its action on the retina, excites in us the sensation of vision. That part of physics which deals with the properties of light is known as *optics*.

In order to explain the origin of light, various hypotheses have been made, the most important of which are the *emission* or *corpuscular* theory, and the *undulatory* theory.

On the *emission* theory it is assumed that luminous bodies emit, in all directions, an imponderable substance, which consists of molecules of an extreme degree of tenuity : these are propagated in right lines with an almost infinite velocity. Penetrating into the eye they act on the retina, and determine the sensation which constitutes vision.

On the undulatory theory, all bodies, as well as the celestial spaces, are filled by an extremely subtle elastic medium, which is called the *luminiferous ether*. The luminosity of a body is due to an infinitely rapid vibratory motion of its molecules, which, when communicated to the ether, is propagated in all directions in the form of spherical waves; and this vibratory motion, being thus transmitted to the retina, calls forth the sensation of vision. The vibrations of the ether take place not in the direction of the wave, but in a plane at right angles to it. The latter are called the *transversal* vibrations. An idea of these may be formed by shaking a rope at one end. The vibrations, or to and fro movements, of the particles of the rope, are at right angles to the length of the rope, but the onward motion of the wave's form is in the direction of the length of the rope.

On the emission theory the propagation of light is effected by a motion of *translation* of particles of light thrown out from the luminous body, as a bullet is discharged from a gun. On the undulatory theory there is no progressive motion of the particles themselves, but only of the state of disturbance which was communicated by the luminous body; it is a motion of *oscillation*, and, like the propagation of waves in water, takes place by a series of vibrations.

The luminiferous ether penetrates all bodies, but, on account of its extreme tenuity, it is uninfluenced by gravitation; it occupies space, and although it presents no appreciable resistance to the motion of the denser bodies, it is possible that it hinders the motion of the smaller comets. It has been found, for example, that Encke's comet, whose period of revolution is about $3\frac{1}{4}$ years, has its period diminished by about 0·11 of a day at each successive rotation, and this diminution is ascribed by some to the resistance of the ether.

The fundamental principles of the undulatory theory were enunciated by Huyghens, and subsequently by Euler. The emission theory, principally owing to Newton's powerful support, was for long the prevalent scientific creed. The undulatory theory was adopted and advocated by Young, who showed how a large number of optical phenomena, particularly those of diffraction, were to be explained by that theory. Subsequently to, though independently of, Young, Fresnel showed that the phenomena of diffraction, and also those of polarisation, are explicable on the same theory, which, since his time, has been generally accepted.

The undulatory theory not only explains the phenomena of light, but it reveals an intimate connection between these phenomena and those of heat; it shows, also, how completely analogous the phenomena of light are to those of sound, regard being had to the differences of the media in which these two classes of phenomena take place.

302. **Various sources of light.**—The various sources of light are the sun, the stars, heat, chemical combination, phosphorescence, electricity, and meteoric phenomena.

The origin of the light emitted by the sun and by the stars is unknown; it is assumed by some that the ignited envelope by which the sun is surrounded is gaseous, and at a very high temperature.

As regards the light developed by heat, Pouillet has observed that bodies begin to be luminous in the dark at a temperature of

500° to 600° ; above that the light is brighter in proportion as the temperature is higher.

The luminous effects witnessed in many chemical combinations are due to the high temperatures produced. This is the case with the artificial lights used for illuminations ; for luminous flames are nothing more than gaseous matters containing solids heated to the point of incandescence.

Phosphorescence is the property which a large number of substances possess of emitting light when placed under certain conditions.

Spontaneous phosphorescence is observed in certain vegetables and animals ; for instance, it is very intense in the glowworm and in the lampyre, and the brightness of their light appears to depend on their will. In tropical climates the sea is often covered with a bright phosphorescent light due to some extremely small zoophytes. These animalculæ emit a luminous matter so subtle that MM. Quoy and Gaimard, during a voyage under the equator, having placed two in a tumbler of water, the liquid immediately became luminous throughout its entire mass.

Decaying wood, and certain kinds of fish in a state of putrefaction, also exhibit this phenomenon. Certain substances, too, become phosphorescent by friction ; while others become luminous in the dark by having been previously exposed to the sun's rays.

303. **Opaque, transparent, translucent bodies. Absorption of light.**—Bodies illuminated by a source of light present two distinct effects ; one class, such as wood, metals, most stones, completely stop it ; while others, such as air and glass, allow light to pass. The first class of bodies comprehends those which are called *opaque*, and the second the *transparent* and *translucent* bodies. The term transparent or *diaphanous* is applied to all bodies which at all transmit light ; while *translucency* is usually restricted to the case of bodies through which objects cannot be distinctly seen. Polished glass may be called either transparent or diaphanous ; but ground glass, oiled paper, thin porcelain, are translucent ; for, while they transmit light, objects cannot be distinguished through them.

Of all bodies which transmit light, none can be said to be perfectly diaphanous ; all extinguish, or *absorb*, a portion of the light which impinges on them. The most transparent, such as air, water, glass, gradually extinguish the light which penetrates them ; and if their thickness be considerable, they may weaken it so much that no impression is produced on the eye. Thus, on the tops of high

ountains the number of stars visible to the naked eye is greater an in the plain ; a phenomenon arising from the fact, that in the rmer case the layer of air traversed is not so thick as in the latter ıse. In like manner too the sun appears less luminous when on ıe horizon, for then its rays traverse thicker layers of air.

Just as there are no perfectly transparent substances, so too there 'e none which are quite opaque ; at any rate, when the thickness is ıconsiderable. Gold, which is one of the densest metals, when ɛaten out in the form of fine leaf, allows an appreciable quantity of ght to traverse it.

Foucault has recently shown, that when the object glass of a lescope is thinly silvered, the layer is so transparent, that the sun ın be viewed through it without danger to the eyes, since the me-llic layer reflects the greater part of the heat and light ; the tint)pears slightly bluish, while in the case of gold it is greenish.

304. **Propagation of light.**—A *medium* is any space or sub-ance which light can traverse, such as a vacuum, air, water, glass, c. A medium is said to be *homogeneous* when its chemical com-)sition and density are the same in all parts ; conditions which are dependent of each other. The atmosphere, for instance, has every-here the same composition, but not the same density, owing to e variations in pressure and temperature, to which it is subject in ırious places.

Experiment shows that in *every homogeneous medium light is ·opagated in a right line.* For, if an opaque body is placed in the ght line which joins the eye and the luminous body, the light is tercepted. In like manner we cannot receive any impression of ght through a series of holes in opaque plates, superposed in each her, excepting these holes are in a straight line. The light which ısses into a dark room by a small aperture, leaves a luminous trace, hich is visible from the light falling on the particles suspended in ıe atmosphere.

Light emanates from luminous bodies in all directions, for we see ıem equally in all positions in which we are placed round them.

Light changes its direction on meeting an object which it cannot enetrate, or when it passes from one medium to another. These henomena will be described under the heads *reflection* and *re-raction.*

This emanation of light in all directions about a luminous body ; called radiation, as in the case of heat ; a *luminous ray*, or *ray of ght*, is the line in which light is propagated ; a *luminous pencil*, or

pencil of light, is a collection of rays from the same source. It is said to be *parallel*, when it is composed of parallel rays; *divergent*, when the rays separate from each other; and *convergent*, when they tend towards the same point. Examples of these will occur in the study of mirrors and of lenses.

305. **Shadow. Penumbra.**—When light falls upon an opaque body, it cannot penetrate into the space immediately behind it, and this space is called the *shadow*.

In determining the extent and the shape of shadow projected by a body, two cases are to be distinguished: that in which the luminous source is a single point, and that in which it is a body of an appreciable extent.



Fig. 226.

In the first case, let L (fig. 226) be the luminous point, and M a spherical body, which causes the shadow. If an infinitely long straight line move round the sphere M, always passing through the point L, this line will produce a conical surface, which beyond the sphere, separates that portion of space which is in shadow from that which is illuminated. In the present case, on placing behind the opaque body a screen, the limit of the shadow will be sharply defined. This is not, however, usually the case, for luminous bodies have always a certain magnitude, and are not merely luminous points; the shadow formed by a luminous point is called the *geometrical shadow*.

In the second case let L (fig. 227) be a luminous sphere, and let a tangent *bn*, be drawn externally to this sphere and the sphere M. Assuming that this line moves tangentially round the two bodies, it will produce on the screen a circle, *no*, completely in darkness. If now a second straight line, *bm*, be drawn tangentially on the inside of the two spheres, it will produce a cone on the screen, the summit

of which is at S, and the base on the screen is the circle *rm*, which is greater than the circle *no*. The circular space between the two circumferences is neither entirely in the shadow, nor entirely in the light, for it is only illuminated by a part of the body L; whence arises the name *penumbra*. Under ordinary conditions in which luminous bodies have a certain size, shadows are always surrounded by a penumbra. This decreases in intensity from the centre towards the edges, and has a greater extent the nearer the luminous body is to the body illuminated, and the more distant the screen.



Fig. 227.

306. **Velocity of light.**—Light moves with such a velocity that at the surface of the earth there is, to ordinary observation, no appreciable interval between the occurrence of any luminous phenomenon and its perception by the eye. And, accordingly, this velocity was first determined by means of astronomical observations. Römer, a Danish astronomer, in 1675, first deduced the velocity of light from an observation of the eclipses of Jupiter's first satellite.

Jupiter is a planet round which four *satellites* revolve, as the moon does round the earth. This first satellite, *e* (fig. 228), *suffers occultation*—that is, passes into Jupiter's shadow—at equal intervals of time, which are 42 h. 28 m. 36 s. While the earth moves in that part of its orbit nearest Jupiter, its distance from that planet does not materially alter, and the intervals between two successive occultations of the satellite are approximately the same; but in proportion as the earth moves away in its revolution round the sun, S, the interval between two occultations increases; and when, at the end of six months, the earth has passed from the position T to the position *t*, a *total* retardation of 16 m. 36 s. is observed between the time at which the phenomenon is seen and that at

which it is calculated to take place. But when the earth was in the position T, the sun's light reflected from the satellite *e* had to



Fig. 228.

traverse the distance *e*T, while in the second position the light had to traverse the distance *et*. This distance exceeds the first by the quantity *t*T, for, from the great distance of the satellite *e*, the rays *et* and *e*T may be considered parallel. Consequently, light requires 16 m. 36 s. to travel the diameter *t*T of the terrestrial orbit, or twice the distance of the earth from the sun.

To give some idea of this enormous velocity, it may be remarked that a cannon ball would require more than seventeen years to traverse the distance from the earth to the sun, while light would require 8 minutes and 18 seconds.

Spite of this enormous velocity of light, the stars nearest the earth are separated from it by at least 206,265 times the distance of the sun. Consequently, the light which they send requires 3½ years to reach us. Those stars which are only visible by means of the telescope, are possibly at such a distance that thousands of years would be required for their light to reach our planetary system. We may hence form an idea of the immensity of the heavens, and how small is our globe in comparison with this infinity.

307. **Intensity of light. Law of its decrease. Photometer.**—The intensity of a source of light, that is, the energy of its illuminating power, is measured by the quantity of light which it sends on a given surface; for example, a screen a yard square. From the property which luminous rays have of diverging, this quantity of light, this intensity, decreases rapidly as the illuminated body is removed from the luminous body. It may be shown by geometrical considerations, that the intensity of light is inversely as *the square of the distance*; that is, that when the distance of an illuminated body from the source of light is doubled, it receives one-fourth the

amount of light; at three times the distance, one-ninth, and so forth.

This law may be demonstrated by the aid of an apparatus called a ***photometer***, from two Greek words which signify *measure of light*. It consists of a ground glass screen A, fixed vertically on a wooden base (fig. 229). In front of this screen is an opaque rod B, beyond which are the sources of light to be compared, in such a manner that the shadows of the rod form on the screen. Now it will be observed, that when the two sources have the same illuminating power, the depth of the shadows is the same: but if one of the sources of



Fig. 229.

light is more powerful than the other, the corresponding shadow is deeper; and in order that the shadows be of equal intensity, the more powerful light must be removed further away.

These details being premised, the law of the decrease of light may be demonstrated as follows: In a dark room, a candle is placed at any distance from the photometer, a yard for instance; and then, at double the distance, four of the same kind of candles are placed in the same line, in the direction of the opaque rod. The two shadows on the screen will then be found to have exactly the same depth; which shows that, at two yard's distance, four candles have no more illuminating power than one candle at a distance of one yard;

from which it is concluded that each of them, at double the distance, has one quarter the illuminating power. It may also be shown in the same manner, that nine candles, at three yards only, have the same illuminating power as one at a yard, and so forth, which proves the law.

It is important to observe, that it is in consequence of the divergence of luminous rays that light decreases as the distance increases. This decrease does not obtain in the case of parallel rays: their lustre would be the same at all distances, where it not for the absorption which takes place in even the most transparent media.

CHAPTER II.

REFLECTION OF LIGHT. MIRRORS.

308. **Laws of the reflection of light.**—When a ray of light meets a polished surface, it is not destroyed by this obstacle: but



Fig. 230.

ounds off from it, changing its direction, and this phenomenon is rmed *the reflection of light.* Thus, if through a hole in the shutter a dark room, a pencil of the sun's rays, CD, be allowed to enter, nd it be received on a plane mirror, this pencil is reflected in the irection DB, and forms on the ceiling an image, the shape of which ill be discussed in speaking of the camera obscura.

As in speaking of the reflection of calorific rays (210) the ray CD the *incident ray*, BD is the *reflected ray*, and the straight line AD t right angles to the mirror is the *normal.* Lastly, the angles CDA nd ADB are called respectively the *angles of incidence* and the *angles of reflection.*

Fig. 231.

The reflection of light is governed by the following two laws, which, as we have seen, also prevail for heat :—

I. *The angle of reflection is equal to the angle of incidence.*

II. *The incident and the reflected ray are both in the same plane, which is perpendicular to the reflecting surface.*

First proof. The two laws may be demonstrated by the apparatus represented in fig. 231. It consists of a graduated circle in a vertical plane, on three levelling screws. Two brass slides, I and K, move round the circumference. They support two small tubes *i* and *c*, directed exactly towards the centre, and intended to give passage respectively to the incident and reflected rays. On the slide I there is, moreover, a small mirror M, which can be inclined at will. The zero of the graduation is at A, and extends to 90 degrees on each side.

These details being known, the slide I having been more or less removed from zero, the mirror, M, is inclined so that a luminous ray, S, after having been reflected on this mirror, shall pass through

the tube *i*, and fall upon a second mirror, *m*, arranged horizontally in the centre of the circle : there the luminous ray is reflected a second time, and takes the direction *m*E. The slide K is then removed to or from A, until the eye being placed at E, the reflected ray, *m*E, is received through the tube *c*. If, now, the number of degrees contained in the arcs AB and AC be read off, there will be found to be exactly equal. Hence the angles of incidence and of reflection B*ma* and *am*C, measured by their arcs, are equal, which verifies the first law.

The second law is also verified ; for, in the construction of the apparatus, care is taken that the axes of the tubes, *i* and *c*, are in one and the same plane parallel to that of the graduated circle, and therefore perpendicular to the surface of the small mirror *m*, and containing the normal *ma*.

In the above drawing the direction in which light is propagated is represented by arrows ; the same will be the case with all optical diagrams, which we shall have occasion to introduce.

309. **The reflection in light is never complete.**—The light which falls upon a body is never completely reflected ; a certain portion is always extinguished, absorbed by the reflecting surface. If we represent by 100 the quantity of incident light, the reflected portion will be 80, 90, 95, according to the nature and degree of polish of the reflecting body ; but it will never amount to 100.

The best reflectors are polished metals, especially if they are white like mercury, and silver. Black bodies reflect no light. Translucent substances reflect a small quantity, and absorb more or less according to their thickness, while they transmit the remainder. This is what takes place with air, water, glass, and all transparent media.

For one and the same substance the quantity of reflected light increases not only with the degree of polish, but with the obliquity of the incident ray. For instance, if a sheet of white paper be placed before a candle, and be looked at very obliquely, an image of the flame is seen by reflection, which is not the case if the eye receives less oblique rays.

The intensity of the reflection varies with different bodies, even when the degree of polish and the angle of incidence are the same. It also varies with the nature of the medium which the light is traversing before and after reflection. Polished glass immersed in water loses a great part of its reflecting power.

310. **Irregular reflection. Diffused or scattered light.**—The

ion from the surfaces of polished bodies, the laws of which
ust been stated, is called the *regular* or *specular reflection* :
. Latin word signifying mirror : but the quantity thus reflected
i than the incident light. The light incident on an opaque
s separated, in fact, into three parts ; one is reflected regularly,
:r *irregularly*, that is, in all directions ; while a third is ex-
ished, or absorbed by the reflecting body.
ius, if in the experiment represented in fig. 230, the beam, CD,
ight on an unpolished surface instead of on a mirror, not only
be seen in the direction DB, corresponding to regular reflec-
ut it will be seen in all positions in the dark room ; whence it
cluded that light is reflected in all directions and under all
ities ; which is apparently contrary to the laws of reflection.
iis irregularly reflected light is called *scattered* or *diffused light* :
iat which makes bodies visible ; it has its origin in the struc-
f bodies themselves, which, from their roughness, present an
y of small facettes variously inclined, and which reflect light
directions.
iffused light plays an important part in the phenomena of
. For while luminous bodies are visible of themselves, opaque
s are only so in consequence of the diffused light which they
in all directions. Thus when we look at a piece of furniture,
e, or a flower, it is the diffused light reflected on all sides, and
directions by the object, which enables us to see them in what-
direction we may be placed in reference to the light which
inates them. When luminous bodies only reflect light regu-
it is not them we see, but, acting like mirrors, they only give
e image of the luminous body whose light they send towards
If, for example, a beam of the sun's light falls on a well-
ied mirror in a dark room, the more perfectly the light is re-
d the less visible is the mirror in the different parts of the
. The eye does not perceive the image of the mirror, but that
: sun. If the reflecting power of the mirror be diminished by
kling on it a light powder, the sun's image becomes feebler,
the mirror is visible from all parts of the room. Perfectly
th polished reflecting surfaces, if such there were, would be
ble, and absolutely non-reflecting surfaces would also appear
ually black, and would be confounded with each other. Two
s, one white and the other black, placed in darkness, are quite
ble, for that which is white, not receiving any light, can re-
none.

It is the diffused light reflected by the air, by the clouds, by the ground which illuminates our rooms and all bodies not directly exposed to the sun's rays; and the more diffused light a body sends towards us, the more precisely can we distinguish it. From the inside of our rooms we well see external objects, for they are powerfully illuminated; but from the outside we only see confusedly in the interior of apartments the objects found there, for they receive but little light.

311. **Direction in which we see bodies.**—Whenever a pencil of light passes in a straight line from a body to our eye, we see it exactly as it is; but if in consequence of reflection, or any other cause, the pencil of light is deviated in its route, if it ceases to come to us in a straight line, we no longer see the body in its proper



Fig. 232.

place, but *in the direction of the luminous pencil at the moment it enters the eye.* Thus if the pencil AB is deflected at B (fig. 232), and takes the direction BC, the eye does not see the point A at A but at *a*, in the prolongation of CB.

This principle is general, and, though very simple, well deserves the attention of the reader, for on it are based the numerous effects of vision which mirrors and lenses present.

MIRRORS.

312. **Mirrors. Images.**—*Mirrors* are bodies with polished surfaces, which show by reflection objects presented to them. The place at which objects appear is their *image.* According to their shape, they are divided into *plane* and *curved* mirrors.

We have an example of a plane mirror in the looking glasses which adorn our apartments. In these mirrors it is not the glass which reflects light in sufficient quantity to give neat and well defined images; it is a metallic layer on the back of the glass. This layer is an *amalgam* of tin, that is, an alloy of this metal with mercury. The glass only has the effect of giving the metal the necessary polish, and of preserving it from external agencies which tend to tarnish it.

Metal mirrors are also constructed of gold, silver, steel, tin

have all the defect of tarnishing on contact with the air; yet were in frequent use among the Romans. We cannot go o the origin of mirrors. The first was doubtless the surface r water. Those of metal appear to be of high antiquity, for on is made in Exodus of a bronze ewer, made by Moses with irrors offered him by the Israelitish women.

3. **Formation of images in plane mirrors.**—*Plane mirrors* ose whose surface is plane; such, for example, are the pier s which adorn the chimney-pieces of our rooms. To under-

Fig. 233.

the formation of images in these mirrors, let us first con- the case in which a small object is placed in front of such a ; for instance, the flame of a candle (fig. 233). A divergent of light emitted by this flame and falling on the mirror is ed there, as shown, in fig. 233. But it follows from the f reflection, that each ray of this pencil retains, in reference to irror, the same obliquity as it had before; whence it follows ie reflected rays have the same divergence in reference to

each other as the incident rays. Hence if we imagine the reflected pencil prolonged behind the mirror, all the rays composing it will coincide in the same point. But as we always see objects in the direction the luminous rays have when they reach us (311), it follows that the eye which receives the reflected pencil should see the flame of the candle just in the place where the prolongation of these reflected rays coincide. There, in fact, is produced the image of this flame as seen in fig. 233.

If now, instead of supposing a very small object placed in front of the mirror, we consider a body of any dimensions, in order to understand the formation of its image we need do no more than



Fig. 234.

apply to each of its parts what has been said in reference to a single luminous point; for instance, in fig. 234, which represents a person in front of a mirror, the rays from the forehead, for instance, are reflected from the mirror and return to the eye, producing an image of the forehead. In like manner the rays from the chin being reflected from the mirror reach the eye as if they proceeded from the chin of the image, and so on with all parts of the face; hence the illusion which makes us see our image on the other side of the mirror.

314. **Nature of the images in plane mirrors. Real and virtual images.**—If, while looking in a mirror, we raise the right

hand, it is the left which seems raised in the mirror ; and if we raise the left hand the right seems raised. We should falsely express this transposition of the parts of the image in reference to the object if we merely say that the image was reversed ; if it were nothing else than the object reversed, in raising the right hand the image should also raise the right hand, while it really is the left which is raised.

This special equality which exists between an object and its image is expressed by saying, that the image is *symmetrical* in reference to the object; that is, that any point of the image is arranged behind the mirror in identically the same manner as the corresponding point of the object in front. For it may be shown by geometrical considerations, that these two points are equidistant from the mirror, and on the same right line, which is at right angles to the surface. From the respective distance and position of the different parts of the object and of its image, it is concluded that the latter is of the same magnitude as it, and equidistant from the mirror.

Lastly, images formed in plane mirrors are *virtual*, by which we mean, that they have no real existence, and are only an illusion of the eyes. For in fig. 233 as well as in fig. 234 the light, as it does not pass behind the mirror, cannot form any image there, and that which we see has no existence ; this is expressed by the word *virtual* as opposed to *actual* or *real*. Virtual images are only an optical illusion ; but we shall soon see that, in concave mirrors and in lenses, *real* images are produced which can be received on screens ; this is not the case with virtual images.

We may thus sum up what we have said : *images in plane mirrors are symmetrical in reference to the object, of the same magnitude, at the same distance on the other side of the mirror, and are virtual.*

315. **Multiple images formed by glass mirrors.**—Metallic mirrors which have but one reflecting surface only give one image ; it is different with glass mirrors, the two surfaces of which reflect though to an unequal extent. For if we apply any object, the point of a pencil, for instance, against a thick piece of polished glass, at first when it is looked at obliquely a very feeble image is seen in contact with it ; then, beyond it, another and far more intense one. The first image is due to the light reflected from the anterior surface of the plate ; that is, on the glass itself, while the second is due to the light which penetrating into the glass, is re-

flected from the layer of metal by which the posterior face is covered. The difference in intensity of the two images is readily explained; glass being very transparent, only a small quantity of light is reflected from the first face of the mirror, which gives the least intense image; while the greater part of the incident light passing into the mass is reflected from the surface of the metal, and gives the most luminous image.

The above experiment furnishes a simple means of measuring the thickness of a glass mirror. For the more intense image should appear behind the layer of metal at the same distance as the point of the pencil in front; and it follows thence, that the distance between the point of the pencil and the point of its image is double the thickness of the mirror. If this distance seems to be the eighth of an inch, it will be concluded that the real thickness is $\frac{1}{16}$th of an inch.

The double reflection from mirrors is prejudicial to the sharpness of the images, so that, in scientific observations, metallic mirrors are preferred to glass ones.

Fig. 235.

316. **Reflection from transparent bodies.**—We have seen that glass, spite of its transparency, reflects a sufficient amount of light to give images, which, though feeble, are distinct. The same is the case with water and other transparent liquids. Thus, on the borders

of a pool, we see formed in the water the reversed image of objects on the opposite bank. We say *reversed* image, so as to express the appearance; but more strictly we should say symmetrical, from what we have before said (314).

Fig. 235 represents the phenomenon of reflection from the surface of water; it shows how the reflected rays, reaching the eye in an upward direction, reproduce the image of objects situated above the water, just as they would if reflected from a horizontal mirror.

317. **Multiple images in parallel or inclined glass mirrors.**— When a source of light is placed between two plane parallel mirrors, we observe a series of images the brightness of which gradually decreases.



Fig. 230.

These images are due to successive reflections on the two mirrors. Thus, let M and N fig. 236 be the sections of the two mirrors, A a luminous body, and *o* the eye of the observer. This latter receives the rays which come directly from the object A, and in addition the following pencils: i. the ray A*bo*, which after a single reflection gives the first image *a*; ii. the ray A*cdo*, which after two reflections furnishes the second image *a''*; iii. the ray A*efgo*, which is reflected three times, and produces a third image *a'* and so on for rays which

undergo four, five, or six reflections. The number of images is theoretically infinite, but in practice it is limited, for as light is never completely reflected at each incidence (309) the images successively lose their lustre and finish by disappearing entirely.

In order not to complicate the figure, only those rays are given which fall at first on the mirror M; but the same construction should be repeated for the mirror N, which would double the number of images.



Fig. 237.

If the mirrors, instead of being parallel, make an angle with each other, the number of images is less. Fig. 237 represents the case in which they form a right angle; three images, a, a', a'', are then formed; the first two after a single reflection; the third after two reflections. If the angle is one of 60 degrees, there are five images.

The *Kaleidoscope*, which consists of three glass mirrors enclosed in a pasteboard tube at an angle of 60°, and the *Debuscope* of two mirrors at an angle of 60°, are well known applications of this property of reflection from inclined mirrors.

CURVED MIRRORS.

318. **Concave mirrors.**—There are many kinds of curved mirrors; those most in use are called *spherical mirrors*, from their curvature being that of a sphere. They may be either of metal or of glass, and are either *concave* or *convex*, according as the reflection is from the internal or the external face of the mirror.

d watch-glass, seen from above, gives an idea of a convex especially if it is covered by a coating of metal on the in- ıe same glass coated externally and seen from the inside ; a concave mirror.

shall first investigate concave mirrors, and, to facilitate the ation, will first consider what is called a *section*; that is, re obtained by cutting it into two equal parts. Let MN ection of a spherical mirror, and C the centre of the corre- g sphere. In reference to the sphere this point is called *'re of curvature*; the point A is the *centre of the figure.* nite right line, ACX, which passes through A and C, is the *l axis* of the mirror: any right line, *i*C*d*, which simply hrough the centre C, and not through the centre of figure *secondary* axis. The angle MCN, formed by joining the



Fig. 238.

ınd extremities of the mirror, is the *aperture.* A *principal tional section* is any section made by a plane through its ıl axis. In speaking of mirrors those lines alone will be red which lie in the same principal section. There is only ıcipal axis, but the number of secondary axes is unlimited.

theory of the reflection of light from curved mirrors is educed from the laws of reflection from plane mirrors, by ring the surface of the former as made up of an infinitude mely small plane surfaces, all equally inclined to each other) form a regular spherical surface. Thus, on this hypo- vhen a ray of light falls upon any point whatever of a curved it is really from a small plane mirror that it is reflected; ection takes place then in accordance with the laws already vn (308).

Focus of concave mirrors.— The small facettes, of which assumed concave mirrors to be made up, being all inclined a common centre, which is the centre of curvature of the

mirror, it follows from this obliquity that the rays reflected by the mirrors tend to unite in a single point, which is called the *foc* as we have already seen in the case of heat (211).

To explain this property of curved mirrors, let SI be a ray fa ing upon such a mirror parallel to the axis AX (fig. 238). Fr the hypothesis assumed above, the reflection takes place at I, on infinitely small plane mirror. It can be shown by geometrical c siderations that the perpendicular to this small mirror is represen by the right line CI from the centre C to the point I. Hence

Fig 239.

angle SIC represents the angle of incidence ; and if we in the other side of the perpendicular, a straight line IF, wh with CI an angle FIC, equal to CIS, this straight line wil direction of the reflected ray.

But when the incident rays are parallel to the axis of as in the above example, it may be proved by geom siderations, that the point F, where the luminous ray c is the middle of AC ; that is, it is equidistant from th the mirror. This property being common to all ra

axis, it follows that, after reflection, these rays will all coincide the same focus, F, as shown in the figure.

The focus described above, namely, that formed at an equal tance from the centre and from the mirror, is called the *principal us*; it is produced whenever the rays falling on the mirror are allel to its axis. An example of this is seen in fig. 239, which resents a pencil of solar light falling upon a concave mirror. If, ere the reflected rays tend to concentrate themselves, a small und glass screen be placed, a highly luminous point will appear, ich is the principal focus.

320. **Conjugate focus.**—In the preceding examples we have sidered the case of pencils of parallel rays, which presupposes minous object at an infinite, or at all events a very great, tance. Let us now consider the case in which the source of ht being at a small distance, the rays falling on the mirror are ergent, as shown in fig. 240. Here the reflected rays are con-

Fig. 240.

erged, but less so than in figs. 238 and 239, which results from the ivergence of the light in arriving on the mirror. Hence the point here the reflected rays coincide is more distant; instead of being t F, equidistant from the mirror and the centre, it is at *b*, between he points F and C. This point, *b*, where the rays coincide, is lso a focus. To distinguish it from the principal focus F, it is alled the *conjugate focus*, from a Latin word meaning *connected*; or there is between the position of the luminous point B, and that f this focus, this connection, that when the luminous object is t B, the rays form their focus at *b*; and that conversely, if the minous object is removed to *b*, the reflected rays form their focus t B.

We have seen that there is only a single position for the principal focus, which is at an equal distance from the centre and from the mirror: this is not the case with the conjugate focus, the position of which is very variable. For suppose that in fig. 240 the candle is removed away from the mirror, as the incident rays make then, with the perpendicular, *cm*, gradually increasing angles of incidence, the angles of reflection, *cmb*, increase too, and the focus *b* approaches the point F, with which it will ultimately coincide, when the candle is so far distant that the incident rays are virtually parallel.

If, on the contrary, the candle is brought nearer the mirror, the rays falling upon it make with the perpendicular, *cm*, angles which are gradually smaller, the angles of reflection, *cmb*, decrease also. Hence the rays sent by the mirror coincide at gradually greater distances, the focus *b* advances towards the centre *c*; and if the candle comes nearer the point, so as to coincide with it, the case will be the same as the focus *b*; so that the candle and its image will coincide at *c*.

Lastly; if the candle always approaching the mirror passes between the centre and the principal focus F, the conjugate focus *b*, continually removing from the mirror, passes on the other side of the centre, is formed at a greater distance the nearer the luminous body is to the principal focus; if the candle coincides with this latter point, the conjugate focus forms at an infinite distance, and the reflected rays become parallel.

These different effects of reflection are a consequence of the constant equality between the angle of incidence and the angle of reflection. They are very simply verified by placing in a dark room a candle in front of a concave mirror successively in various positions, and then ascertaining by trial where the luminous focus is formed on a small screen of paper held in the hand, and which is approached to or receded from the mirror.

321. **Virtual focus.**—After having described the different positions of the point in which the rays reflected by a concave mirror coincide, when the luminous body is either beyond or in the principal focus, we have to inquire what becomes of these same rays when the source of light is in any point, P, which is nearer the mirror than the principal focus (fig. 241). In this case the reflected rays form a diverging pencil, and cannot therefore produce any focus in front of the mirror; but as regards the eye which receives them, they produce exactly the same effect as in plane mirrors

that is, the eye receives exactly the same impression from the d rays IM and *im*, as if the candle were placed behind the



Fig. 241.

at the point *p*, where the prolongation of these rays coincide. the image of the candle is seen at *p*, but as the light does ietrate behind the mirror, this image does not really exist: the focus which seems to form at *p* is called the *virtual* the expression being understood in the same sense as in nirrors.

Formation of images in concave mirrors.—Concave give rise to two kinds of images, real and virtual. Their on is readily understood after what has been said respecting ijugate and the virtual focus. We may however remark, a luminous or illuminated point is situate on the principal a mirror, its focus, real or virtual, is always formed on this This is the case in figs. 240 and 241, but if the luminous on a secondary axis, the focus is formed on this axis. if in fig. 238 a candle were placed at *d*, on the secondary *d*, the reflected rays would form their focus on the line C*i*. eing admitted, let us see how images are formed in concave

l image. If a person places himself at a certain distance in f a concave mirror, he no longer sees himself erect and of linary size, as in plane mirrors, but reversed, and much , as shown in fig. 242. To this image is given the name *age*, to express that it is not an illusion as that seen in plane , but that it has a real existence. For it may be caught on n. If the mirror be placed in front of an object powerfully ated, as, for instance, before a building on which the sun is , and a person places himself a little on one side, holding a white screen in the position in which the conjugate focus be *formed, the pencils* from the various parts of the edifice

are reflected from the mirror and fall on the screen, forming in minature an image not less remarkable for the colour, than for the fidelity of the contours (fig. 243) : it has no other defect than that of being reversed.

The formation of this image is readily explained. For from what has been said in reference to conjugate foci (320), each point of the image is the conjugate focus of the corresponding point of the illuminated body, and is on the same secondary axis. But as all



Fig. 242.

the secondary axes from the various points of this body cross in the centre of curvature of the mirror, it follows, as shown in the figure, that the rays emitted by the higher parts of the body converge towards the lower part of the image, and that conversely rays from the foot unite on the higher parts of this same image, which explains how it is the latter is reversed.

It is to be observed that the real image in concave mirrors is not always smaller than the object illuminated, as is the case in the above two figures ; it may also be larger. This is the case when, the object being placed between the principal focus and the

ıtre of curvature, its image is formed outside the latter, and it is ın larger the greater the distance at which it is formed.

Virtual image. The above figure (242) shows how, when a person ɔlaced at a certain distance in front of a concave mirror, he sees ıself smaller and reversed. If he comes nearer, there is a nt at which no image is seen. This is the case when he is ween the centre and the principal focus, for the ımage is thus ned behind the observer. If he is in the principal focus itself, ɐe is no image. For we know (320) that the luminous rays

Fig. 243.

ceeding from this focus, after being reflected from a concave ror produce a parallel luminous pencil: hence, as the rays ncide neither behind nor in front of the mirror, they cannot e rise to any image. But, approaching the mirror, the image ldenly reappears, and instead of being smaller and reversed as ras, is now erect and much enlarged, as in fig. 244. This is the *tual image.*

To account for the formation of this image we must recall what been said about the virtual focus (321): First, that it is only

formed as long as the luminous or illuminated object is be
the principal focus and the mirror ; second, that the virtual
or, what is the same thin
virtual image of any point
object, is behind the mir
the secondary axis which
through this point. Hen
head of the observer being
between the mirror and the
pal focus (fig. 245), all ray
any point, *a*, of the face re
the eye after reflection, as
proceeded from the point, A
the prolongations of the re
rays coincide on the sec
axis, C*a*A. In like manne
from the point *b* return to t
as if they were emitted fr
point B, which is on th
longation of the secondary axis, C*b*B. The eye sees, the
at AB, an erect and enlarged image.

Fig. 244.



Fig. 245.

323. **Formation of images in convex mirrors.**—We already seen that convex mirrors are spherical mirrors, wh

ht from their external surface, that is, on their bulbed side. ⁄er the distance of a luminous or illuminated object placed t of these mirrors, we ɔbtain any other than al image situated on er side of the mirror, erect, and smaller ıe object. This may ified by looking in a of this kind, as repre- in figure 246. The ion of this image can ily explained by an ion of figure 247. It smaller than the ob- ɔr it is nearer than ter to the point where ondary axes coincide, he reverse is the case e formation of the vir- age in concave mirrors.

Fig. 246.

. **Applications of mirrors.**—The applications of plane ; in domestic economy are well known. Mirrors are also ıtly used in physical apparatus for sending light in a certain ɔn. The solar light can only be sent in a constant direction



Fig. 247.

cing the mirror movable. It must have a motion which nsates for the continual change in the direction of the sun's oduced by the apparent diurnal motion of the sun. This is obtained *by means of* a clock-work motion, to which the

nirror is fixed, and which causes it to follow the course of the sun. This apparatus is called the *heliostat*. The reflection of light is also used to measure the angles of crystals by means of the instruments known as *reflecting goniometers*.

Concave spherical mirrors are also often used. They are sometimes applied for *magnifying mirrors*, as in a shaving mirror. They have been employed for burning mirrors, and are still used in telescopes, as they only give one image. They also serve as reflectors for conveying light to great distances, by placing a luminous object in their principal focus. For this purpose, however, parabolic mirrors are preferable.

CHAPTER III.

REFRACTION OF LIGHT.

325. **Phenomenon of refraction.**—When a ray of light more or less obliquely from one transparent medium into an for instance, from air into w from air into glass, it undergo flection from the straight line it proceeds, as seen in fig. 2 represents a ray of light pa air into water. This chang tion is called *refraction*, fr word meaning *broken*; fo in fact, broken at the po it passes from the direct direction AK.



Fig. 248.

The ray, LA, is called again the *incident ray*; *fracted ray*; the perpendicular, BC, drawn at the poi A, of the surface, MN, which separates the two me *normal* or *perpendicular*; lastly, the angle, BA *angle of incidence*; and the angle, CAK, the *an* If the angle of incidence is null, that is, if the inci with the normal, the same is the case with the ...avels in a straight line.

ıws of refraction.—When a ray of light is refracted in rom one medium into another of a different refractive : following laws prevail:

latever the obliquity of the incident ray, the ratio which f the incident angle bears to the sine of the angle of refrac- nstant for the same two media, but varies with different

he incident and the refracted ray are in the same plane, berpendicular to the surface separating the two media.

laws may be understood by reference to the adjoined 9), in which the ray, LA, passes from air into water. If point of incidence, with a radius unity, a circle be described, and points, *m* and *p*, where it cuts ent and refracted rays, perpen- *mn* and *pq*, are drawn to the 3C, the former is called the *sine gle of incidence*, and the second *f the angle of refraction.*

Fig. 249.

he ratio of these sines, these per- ırs, which is constant; that is, or instance, being three-quarters the angle of incidence diminishes or increases, the angle ion does so too, but the sine of the latter will always be ırters of the sine of the former.

:onstant ratio is called the *refractive index*, or *index of re-* its value varies with different transparent media.

Refracting substances.—When a ray of light is refracted g from one medium into another, sometimes it approaches al, forming an angle of refraction, which is less than the ıncidence, as is the case in the above figure; sometimes, ɔntrary, it is deflected away, forming an angle of refrac- :h is greater than the angle of incidence. In the first second medium is said to be more *refringent* or *refrac-* the first, and in the second case it is less so.

ıg the most refringent bodies are water, alcohol, ether, the :tc. Diamond is the most refringent of all bodies. Gases efringent than water; their refracting power is increased nsing them, that is, by increasing their density.

Experimental proofs of refraction.—The deviation ıe by *luminous rays*, on passing from one medium to

another, may be demonstrated by numerous experiments. Thus, if in a dark room a pencil of the sun's rays be allowed to fall on a glass vessel containing water (fig. 250), the pencil can be very distinctly seen to be broken as it passes from air into water, especially if some light powder has been diffused through the air and the water so as to make the pencil more visible (309).

Fig. 250.

Or let a coin be placed at the bottom of an opaque vessel (fig. 251), and the eye be placed so that the edge of the vessel just intercepts the view of the coin. If, now, without altering the position of the observer, a little water be gradually poured into the vessel, at first only the edges of the coin will be seen, then half, and finally the entire piece. Now what has taken place here? Nothing has been changed in the position of the eye, or in that of the piece: it is the rays from the latter which have changed their direction. Those which were before intercepted by the sides of the vessel are so still; but rays which, before there was water in the vessel, passed above the observer's head, are directed towards the eye, being re-

fracted in passing from water into air, so as to diverge from the perpendicular to the surface of the liquid, as represented in the figure.

329. **Various effects of refraction.**—Refraction of light produces various phenomenon, the effect of which is to deceive the eye by making us see objects in other than their true positions; thus, we do not see fish in the place they actually occupy, but a little higher, as indicated by the path of the refracted ray in fig. 252. It will be understood that in consequence of the same phenomena we see the bottom of a river or a pond higher than it really is; we thus consider the water to be not so deep, an illusion which may be dangerous.



Fig. 251.

Fig. 252.

The same cause makes a stick half immersed in water appear broken when it is looked at at the side; for the portion out of the water is *seen in its true position*, while that which is immersed

appears raised, from which results the appearance of the stick being broken at the surface of the liquid (fig. 253).



Fig. 253.

We may, in conclusion, cite the influence which refraction exerts upon the apparent rising and setting of the stars, which we can see a little before they are above the horizon, and a little after they have sunk below it. To explain this phenomenon let us suppose the atmosphere divided into layers parallel to the surface of the globe, as represented in fig. 254. Owing to the pressure exerted by the upper layers upon the lower ones, the latter are more dense (129), and therefore more refringent, for, as we have seen, the refracting power of the



Fig. 254.

air increases with its density (327). The sun's rays, which penetrate the atmosphere, are always refracted in the same direction as they pass from one layer to another: hence their path, instead of being that of a straight line, will be really somewhat curved. Thus it is that, while the sun is at S, below the horizon, HH, an observer

at A, on the surface of the earth, will see it raised by an amount which is generally equal to its apparent diameter.

330. **Change of refraction to reflection.**—Whenever light passes from one medium into a more refringent one, from air into water for instance, there is nothing to prevent the refracted ray from approaching the normal, to form an angle smaller than the angle of incidence; but if, on the contrary, the second medium is less refringent than the first, in which case the refracted rays recede from the normal, there is a limit to their deviation, and hence refraction may become impossible.

To get a clearer idea of this, let us imagine a hollow glass sphere half filled with water (fig. 255), and a ray of light, LA, to enter the liquid without being refracted, which is the case when it penetrates at right angles the small facette which we can always conceive to exist at the point at which it enters. This ray is refracted at A in passing from water into air, and diverges from the normal, BAC, in the direction AR. Now, conceive the luminous body to move gradually from AC; as the angle of incidence, CAL, increases, the angle of refraction, BAR, does so too; and an angle, CAL, might acquire such a magnitude as to emerge parallel to the surface, AM, of the liquid. This angle of incidence is what corresponds to the *limit of refraction*. For, for any greater angle of incidence, the angle of refraction should exceed the angle BAM; and the light would then take below AM a direction such as A*r*. There would, however, then be no refraction, for the light, always travelling through water, does not change its medium. If the incident ray be then represented by *l*A, if we measure the two angles *l*AC and CA*r*, it will be found that they are exactly equal, which shows that at the point, A, the light is reflected according to the ordinary laws of reflection.



Fig. 255.

This kind of reflection at the surface which separates two media of different refracting power, is called *internal reflection*: it is also called *total reflection*, for here the whole of the incident light is reflected, which is never the case in ordinary reflection, even in the best polished surfaces (309).

The phenomenon is frequently met with; thus, if a silver spoon be placed in a glass of water, and it be raised above the eye, the surface of the liquid is seen brighter than a polished metal, and one portion of the spoon for an image in it as in a mirror. Similar effects are met with in aquariums. The upper surface of the liquid, when looked at from a suitable position below, gives a reflected image of the object it contains.

331. **Mirage.**—The *mirage* is an optical illusion by which inverted images of distant objects are seen as if below the ground, or in the atmosphere. This phenomenon is of most frequent occurrence in hot climates, and more especially on the sandy plains of

Fig. 256.

Egypt. The ground there has often the aspect of a tranquil lake, on which are reflected trees and the surrounding villages. In vain, however, does the traveller redouble his velocity; this imaginary lake so desired, flees from him as he advances. The phenomenon has long been known; but Monge, who accompanied Napoleon's expedition to Egypt, was the first to give an explanation of it.

It is a phenomenon of refraction, which results from the unequal density of the different layers of the air when they are expanded by contact with the heated soil. The least dense layers are then the lowest, and a luminous ray from an elevated object, *a* (fig. 256), traverses layers which are gradually less refracting; for, as we *have shown* (327), the refracting power of a gas diminishes with

ssened density. The luminous ray continues its path, being, however, more and more bent from one layer to the other, until the angle f incidence, which continually increases, reaches the limit at which nternal reflection succeeds to refraction (330). The ray then rises it *a*, as seen in the figure, and undergoes a series of successive refractions, but in a direction contrary to the first, for it now passes hrough layers, which are gradually more and more dense, and herefore more refracting. The luminous ray then reaches the eye with the same direction as if it had proceeded from a point below the ground, and hence it gives an inverted image of the object, just as if it had been reflected at the surface of a tranquil lake.

Mariners sometimes see in the air images of the shores, or of distant vessels. These are called *fata morgana*. This is due to the same cause as the mirage, but is in a contrary direction, only occurring when the temperature of the air is above that of the sea, for then the inferior layers of the atmosphere are denser, owing to their contact with the surface of the water. To the same class of phenomena belong the tremulous appearance of objects seen through he current of hot air rising from a chimney or a spirit lamp. It is elated that in this way, clandestine stills have been detected by the evenue officers.

CHAPTER IV.

EFFECTS OF REFRACTION THROUGH PRISMS AND THROUGH LENSES.

332. **Media with plane parallel faces.**—When a luminous encil traverses a transparent medium, three cases may be considered. First, that in which the medium is comprised between wo parallel planes; second, that in which it is comprised between wo plane surfaces inclined towards each other; thirdly, that in hich the medium is comprised between two curved surfaces, or etween a curved and a plane surface, which gives rise to the same ffects.

We will start with the consideration of the first case, and let *Lm* a ray of light traversing a glass plate, AB, with parallel faces g. 257). In passing from air into glass at the point *m*, this ray proaches *the normal; but as*, on its emergence from the glass at

the point *n*, it deviates from the perpendicular by exactly the same amount, it follows that, after having traversed the glass plate, its direction O*n* is exactly parallel to L*m*; whence we conclude that light is not deviated when it traverses a medium with parallel faces, such as the glass panes in our windows.

333. **Prisms.**—In optics a *prism* is any transparent medium comprised between two plane faces inclined to each other. Thus, the facettes of a glass stopper taken in pairs form as many prisms.



Fig. 257.

Fig. 258.

Fig. 258 represents the shape and arrangement of prisms for optical experiments. It is a piece of glass cut laterally in three plane faces, and the ends of which are also equal and parallel triangular faces. The three right lines which form the intersection of two faces of the prism are called the *edges*. The mass of glass thus cut may be turned about an axis parallel to its edges; and it is moreover mounted on a stand with a double joint, so that it can be placed in any position whatever.

Prisms produce a remarkable effect upon light which traverses them. First a *deviation*, and second a decomposition into various kinds of light. Although these effects are always simultaneous, we shall examine the first by itself: the second will be afterwards investigated under the head of *dispersion*.

334. **Path of rays in a prism.**—To trace the path of a ray of ht in passing through a prism, let us suppose this cut by a plane rpendicular to its ces, and let *mno*, . 259) be the sec- n thus obtained. If consider the path of ay of light L*a* along s section and meet- the prism at *a*, s ray approaches perpendicular to surface *mn*, and es the direction But on emerging m the prism it is again broken in the same direction, being



Fig. 259.



Fig. 260.

flected from the perpendicular at the surface *mo*; for it passes o a less refracting medium. It forms then a broken line,

L*abc*; so that the eye which receives the ray, *bc*, which is called the *emergent ray*, sees the object in the direction *cbr*; that is raised towards the point *m*; which is expressed by saying that an object seen through a prism appears deflected towards the *summit*; that is, the edge which separates the faces of incidence and emergence.

The phenomenon is very easily demonstrated by observing through a prism any object whatever, as represented in fig. 260. This is seen to be raised when the summit of the prism is uppermost, and lowered when the summit is downward. If the prism is vertical, the image is displaced either to the right or to the left of the observer, according to the position of the summit in either direction.

This property which prisms have, of twice deflecting the light in the same direction, is the basis of all that has to be said about lenses.

LENSES.

335. **Different kinds of lenses.**—In optics the name *lens* is given to discs of glass bounded by two spherical surfaces, or by a



Fig. 261. Fig. 262.

plane and a spherical surface. The true lens, the only one to which the name is strictly applicable, is that in which both surfaces are bulged, such as represented in a side view in fig. 261, and in front in fig. 262.; but this term of lens has been extended to other masses of glass, from the analogy of their action on light.

They are usually made either of *crown glass*, which is free from d, or of *flint glass*, which contains lead, and is more refractive n crown glass.

The combination of spherical surfaces, either with each other or h plane surfaces, gives rise to six kinds of lenses, sections of ich are represented in figs. 263, 264; four are formed by two herical surfaces, and two by a plane and a spherical surface.

M is a *double convex*, N is a *plano-convex*, O is a *converging ncavo-convex*; P is a *double concave*, Q is a *plano-concave*, and is a *diverging concavo-convex*. The lens O is also called the *verging meniscus*, and the lens R the *diverging meniscus*.



Fig. 263.



Fig. 264.

The first three, which are thicker at the centre than at the rders, are *converging*; the others, which are thinner in the ntre, are *diverging*. In the first group, the double convex lens, M, ly need be considered, and in the second the double concave, as the properties of each of these lenses apply to all those of same group.

336. **Principal axis; optical centre; secondary axes.**—Before scribing the properties of double convex lenses, we must premise ne definitions analogous to those already given for mirrors. We y remark that a double convex lens is, as shown in fig. 265, the tion common to two spheres, which intersect each other. That ng premised, the centres C and *c* of these spheres are called the *tres of curvature* of the lens, and the straight line, XY, which ses through these points, is the *principal axis*.

Besides these two centres of curvature, there is a remarkable nt in the lenses, called the *optical centre*. This name is given a point O, on the principal axes, equidistant from the two faces the lens; at all events, when they have the same curvatures, ich is the usual case. Now it can be shown by geometrical siderations, that any ray of light which passes through the tical centre, *emerges without* deflection; that is, it comports

itself just as if it traversed a medium with parallel faces (332), while the luminous rays which do not pass through this point are deflected twice in the same direction, as in passing through prisms (334).



Fig. 265.

Any straight line, KH, which passes through the optical centre, without passing through the centres of curvature, is a *seconday axis*. There is only one principal axis, but the number of secondary axes is unlimited. We shall subsequently learn that the principal and the secondary axes play exactly the same part in the formation of images in lenses, as they do in concave or convex mirrors.

In order to compare the path of a luminous ray in a lens with that in a prism, the same hypothesis is made as for curved mirrors (318), that is, the surfaces of these lenses are supposed to be formed of an infinity of small plane surfaces or elements; the *normal* at any point is then the perpendicular to the plane of the corresponding element: at *m*, for instance, it is the straight line in C joining the points *m* to the centre of curvature; in like manner at *n* the normal is *cn*. This being premised, the properties of lenses are easily deduced from those of prisms (334).

337. **Path of rays in double convex lenses. Foci.**—The rays of light which traverse a lens may be either parallel or divergent; we will first consider the former case, and suppose further that the rays are parallel to the principal axis, as shown in fig. 266. Arguing on the above hypothesis, that the curved surface of a lens is an assemblage of small plane facettes, or elements inclined towards each other, it will be seen that the ray X, which coincides with the principal axis, traverses the lens perpendicularly to the facettes on entrance and emergence; and that, therefore, it continues to travel in a right line as traversing in reality a medium with parallel faces. This, however, is not the case with any other ray, L, more or less

from the principal axes ; for here the small facettes at the
of incidence and emergence, being inclined to each other like
s of a prism, the ray is twice bent in the same direction, so
t the principal axis in a point F. Any other ray, M, is de-
in the same manner, and although more distant from the
l axis, will cut it at F ; which arises from the fact, that the

Fig. 266.

posite facettes at the points of entrance and emergence, being
re inclined to one another the nearer they are to the edges
ens, impart to the ray a greater deviation. All rays parallel
axis behave in the same manner after having traversed the
d it can thus be understood how a parallel pencil is trans-
into a converging pencil. The point where all the rays
vere parallel to the axis coincide is called, as in the case of
, the *principal focus*, and we shall represent it by the letter
may be formed on either side of the lens according to the
n in which light is propagated.

position of the principal focus is fixed and is easy to deter-
nothing more is required than to receive on the lens a pencil
lel rays, a pencil of solar light for instance, and then to hold
the lens a sheet of white paper. By moving this a position
l in which the luminous circle formed on the screen attains
imum lustre : this point is the principal focus.

Conjugate focus.—We will now consider the case in which
rce of light is at a small distance, but yet further than the
al focus (fig. 267). The pencil which is incident upon the
ing than divergent, it follows that, after having traversed the
e rays converge less rapidly than in fig. 266, and that, there-
ey no longer coincide in F, but beyond, in a point *l*, which
d the conjugate focus of the point L, to express, as in con-
irrors, the correlation of these two points ; which is of such

a kind that, when the luminous object passes from L to *l*, the conjugate focus conversely passes from *l* to L.

The position of the conjugate focus is not fixed; it varies with that of the luminous object: the nearer this is to the lens the more distant is the conjugate focus, as shown by comparing fig. 268 with fig. 267; in fact, the incident rays being more and more diverging, the emergent rays are necessarily so too.

Fig. 267.



Fig. 268.

We will now consider the case in which the luminous object coming continually nearer the lens, ultimately coincides with the principal focus (fig. 269). This being the point where rays parallel to the axis coincide, it follows, conversely, that luminous rays, which emanate from this point, pursue in the opposite direction the same path as in arriving; that is to say, that they form on emerging from the lens a pencil parallel to the axis, and that in the present case no focus can be produced at any distance.

339. **Virtual focus.**—We have still to consider another focus, the *virtual focus*. Let us suppose a luminous object continually coming nearer the lens, ultimately comes between it and the principal focus (fig. 270). The divergence of the incident pencil being then greater than in fig. 269, it follows that the rays after emergence will be more and more spread out than in this figure: they should, therefore, become divergent, as shown in the pencil MN. The eye which receives these rays will suppose that they proceed from the *point l*, where their prolongations coincide. In this point the

luminous object will appear ; it is not however a virtual focus, but only an optical illusion, just like that in a concave mirror, when the luminous object is placed between the mirror and its principal focus.

340. **Summary of properties of double convex lenses.**— From what has been said, we may deduce the three following principles as to the properties of double convex lenses.

I. Luminous rays parallel to the axis, after having traversed a double convex lens, coincide in a single point which is the principal focus (fig. 266) ; and conversely, rays from this focus form, on their emergence from the lens, a pencil parallel to the axis (fig. 269).

Fig. 269.



Fig. 270.

II. Luminous rays emitted from a point outside the principal focus emerge convergent from the lens, and coincide in a point called the conjugate focus (fig. 267), which is formed at a greater distance behind the lens, the nearer is the luminous object to the principal focus (fig. 268).

III. Finally, the rays from a point between the lens and the principal focus emerge divergent, and give rise to a virtual focus on the same side as the object (fig. 270).

These ideas in reference to foci are indispensable in the explanation of the formation of images by lenses.

FORMATION OF IMAGES IN LENSES.

341. **Real images in double convex lenses.**—The refraction of light in double convex lenses gives rise to images, which are quite comparable to those seen by reflection in concave mirrors (322), and which like these are of two kinds *real* and *virtual*.

We will first consider the case of the real image. This is formed whenever any object is placed in front of a condensing lens outside its principal focus; the lens reproduces then on the other side a reversed image of the object, which may be caught upon a screen (fig. 271), and is not less remarkable for the fidelity of the colour than for the accuracy of the outline; this is the real image. Its formation may be readily understood by reference to



Fig. 271.

what has been said about conjugate foci (338). Yet it must be added, that as all the properties of the principal axis apply also to the secondary axes, it follows that as a point on the principal axis has always its focus on this axis, so also any point on the secondary axis has its focus on the latter. Hence, in the above figure, all rays from the point A converge at *a* on the secondary axis through this point, and form the conjugate focus of this point, that is to say, its image. In like manner, the image of the point B forms at *b*, and as the same is the case for all points of the object, the result is a series of conjugate foci; these in their entirety constitute the image *ab*, which is inverted and smaller: the reversal arises from the crossing of the secondary axes between

ject and the image, and its smallness from its being formed
the lens than the object is.
t the image is not always smaller than the object ; it may be
r. For, from the reciprocity of position between the object
s conjugate focus (340), if, in fig. 271, *ab* were the object,
s the luminous rays pursue the same path, but in the opposite
on, the image would be formed at AB, reversed as before,
rger. A double convex lens may thus give real images,



Fig. 272.

are either smaller or larger than the object. This may be
d by the following experiment: in a dark room a double
c lens is placed, and in front of it, but some yards beyond
incipal focus, a lighted candle. If then there is placed
l the lens a screen, which can be placed more or less near,
ion is found in which there is produced on the screen a very
and inverted image of the candle, as shown in fig. 272. If,
contrary, the lens be brought nearer the candle, and at the

same time the distance of the screen be increased, a reversed image is obtained, but it is greatly enlarged (fig. 273).

This principle, that *double convex lenses give real and very small images of distant objects*, and, on the contrary, *greatly magnified images of near objects*, will meet with numerous applications in the optical instruments, which will be presently described, such as the microscope, the telescope, magic lantern, phantasmagoria.



Fig. 273.

342. **Virtual images in double convex lenses.**—Besides the real images we have just considered, double convex lenses give also virtual images, which are produced under the same conditions as the virtual foci; that is, when the object is between the lens and the principal focus. For let an object, *ab*, be placed between a double convex lens and its principal focus: applying here what was previously said in reference to virtual foci, we know that all rays proceeding from any point, *a*, of the object emerge while diverging, and reach the eye as if they proceeded from the point *A*, where

prolongation of the same rays coincide, and where there is ed for the eye the virtual image of the point *a*. For the same on the eye sees at B the image of *b*; hence the image of AB ars at *ab*, but it is virtual; that is to say, it does not really , it could not be received on a screen, and is only an optical on.



Fig. 274.

t is to be remarked that in opposition to what takes place when mage is real, the virtual image is erect, and in all cases larger the object; the rectification of the image arises from the fact the secondary axes do not intersect between the image and bject, but beyond it; the magnification arises from the image g further than the object from the point of intersection of the ndary axes which pass through *a* and *b*.

he term lens is applied to the lenticular glasses used as mag- ng glasses. Everyone is aware, that if the print of a book be ly looked at through such a lens it will appear larger; if ens be progressively removed, a moment is reached when the acters disappear. This is the case when they are in the prin- l focus: when it is still further removed the characters re- ar; but they are reversed for then they are beyond the prin- l focus.

43. **Double concave lenses; foci and images.**—We have seen eaking about double convex lenses, that as the thickness de- ses from the centre towards the edges, the small plane facettes, esponding to the incidence and convergence of the same ray, more and *more inclined* from the centre to the periphery.

But in double concave lenses, on the contrary, where the thickness increases from the centre to the edge, the small facettes are more and more apart; and hence the opposite phenomena. For, while double convex lenses cause the rays traversing them to coincide, by breaking them twice in the same direction, so as to bring them nearer the principal axis, double concave lenses produce the opposite effect, and only increase the divergence of the rays.

This phenomenon may be readily understood by reference to fig. 275, in which it is apparent how the rays are twice broken in the same direction, so as to diverge from the axis, and give rise to the diverging pencil MN. But the eye which receives this pencil is acted upon by it, as if the luminous object were at *l*; there is thus produced a virtual focus, the only one possible in double concave lenses.



Fig. 275.

As these kinds of lenses have only virtual foci, they can produce none but virtual images; these images are moreover always erect and smaller than the object. Thus let AB be an object seen through a double concave lens (fig. 276); the luminous pencil from A is deflected on passing through the lens in such a manner as to reach the eye as if it were emitted from a point, *a*, on the secondary axis, AO. In like manner, the pencil from the point, B, reaches the eye as if it started from the point, *b*. There is formed therefore at *ab*, between the secondary axes, AO and BO, a virtual image of the object, AB, which is smaller and erect. This image is necessarily always smaller than the object, for it is nearer the point, O, where the secondary axes intersect.

APPLICATION OF LENSES.

344. **Refraction of heat.**—When a pencil of the sun's rays is received on a condensing lens, not merely is light concentrated on

ts focus, but heat also ; for if a piece of an inflammable substance, such as amadou, paper, cloth, wood, be placed in the focus, the body soon begins to burn. With lenses of large diameter metals even may be melted.

This property which condensing lenses have is utilised for producing fire in what are called *burning glasses.* They may be a source of danger, by becoming a source of fire, when a lens is exposed to the solar rays. The same accident may be produced by spherical glass vessels filled with water ; for they refract the light and heat like double convex lenses. A drop of water, too, on a leaf, concentrates the sun's rays, and frequently marks the leaf.



Fig. 276.

The concentration of the heat rays of the sun has received an application in certain sun dials, when the hour of midday is marked by the discharge of a small cannon (fig. 277). Above the cannon is a condensing lens, the focus of which exactly corresponds to the *touch-hole* of the cannon the moment the sun passes the meridian of this place. Hence, the cannon being charged and primed beforehand, the lens ignites the powder just at midday, and the explosion announces the time at a distance.

Yet the time thus given is what is called in astronomy *solar time*, or *true time*, in which the length of day varies. Now our watches and clocks being regulated for *mean time*, that is to say,

for an unchangeable day, only agree with the sun four times a year; December 24, April 15, June 15, and September 1. On

Fig. 277.

February 11 a clock giving mean time is 14′ 37″ faster than the sun, and on November 3 it is 16′ 17″ slow. The *equation of time* represents the amount which on all the days of the year must be added to or taken from the time of a clock to obtain the mean time. Hence, strictly speaking, it is incorrect to use the ordinary expression, that a good watch or a good clock goes like the sun.

345. **Beacons. Lighthouses.**—These are fires lighted at night on high towers along the shores of the sea, in order to guide mariners in darkness and enable them to keep clear of danger.

Beacon fires were originally wood or coal fires; but these were dull and unsteady. They were afterwards replaced by oil lamps placed in the principal focus of concave reflectors, which sent the reflected light to a great distance, for its rays were parallel.

In 1822 Fresnel made a great improvement in the illumination of *lighthouses* as they are now called. Abandoning the use of metallic reflectors, which soon tarnished under the influence of the sea-fogs, Fresnel substituted large plano-convex lenses, in the focus of which he placed a powerful lamp with four concentric wicks, and equal in illuminating power and quantity of oil consumed to seventeen Carcel lamps. But the difficulty of constructing such lenses, which must necessarily be large, and at the same

not thick, so as not to absorb much light, led Fresnel to
ɔt a special system of lenses, known as *echelon* or *lighthouse*
's.

ɔeen in front in fig. 278, and in profile in fig. 279, they consist
plano-convex lens, A, a foot in diameter, round which are
nged eight or ten glass rings, which are also plano-convex, and
se curvature is calculated, so that each has the same focus as
central lens, A. A lamp being placed in the focus of this
cting system, an immense horizontal pencil, RC, is formed,
h sends the light to a great distance. Further, above and
w these lenses, are placed several silvered glass mirrors, *mm*.

Fig. 278.



Fig. 279.

s the rays, which would be lost towards the sky and the earth,
utilised and sent in a horizontal direction. By this double
ɔination a vast horizontal pencil is obtained, which sends the
t of the lamp to a distance of 20 or 30 miles; but it only sends
n one direction. To increase the number of points of the
ɔon at which the light can be seen, Fresnel, instead of a single
em of lenses and mirrors represented in fig. 279, united eight
ɔ arrangements, so as to form an enormous glass pyramid with
ɪt faces, as seen in fig. 280, which represents a lighthouse lens
ɪe largest size, constructed by M. Soutter, and exhibited at the

Paris Universal Exhibition in 1855. The system of mirrors and lenses alone is 10 feet high.

A lighthouse lens of this kind sends a powerful beam of light towards eight points of the horizon, but all other points are destitute of light, so that vessels sailing in these dark parts would have

Fig. 280.

no help from the lighthouse. This difficulty was removed by Fresnel by means of a very simple mechanism, represented at the lower part of fig. 280. A clockwork motion, M, moved by a weight, P, imparts to the whole system of lenses, AB, a slow rotating motion on six rollers. During a complete revolution of the apparatus, the

ıole horizon is successively illuminated, and the mariner lost in e night, sees the light alternately appear and disappear after ual intervals of time. These alternations serve to distinguish hthouses from an accidental fire or a star. By means too of the mber of times the light disappears in a given time, and by the

Fig. 281.

olour of the light, sailors are enabled to distinguish the lighthouses om one another, and hence to know their position.

Of late years the use of the electric light has been substituted r that of oil lamps; a description of the apparatus will be given a subsequent chapter.

CHAPTER V.

DECOMPOSITION OF LIGHT BY PRISMS.

346. **Solar spectrum.**—In speaking of prisms and lenses have only considered the change in direction which these trar rent media impart to luminous rays, and the images which r therefrom ; but the phenomenon of refraction is by no mea simple as we have hitherto assumed : when *white* light, o which reaches us from the sun, passes from one mediur another, *it is decomposed into several kinds of lights*, a phenon to which the name *dispersion* is given.



Fig. 282.

In order to show that white light is decomposed by refrac pencil of solar light, SA (fig. 282), is allowed to pass through a

perture in the window shutter of a dark chamber. This pencil nds to form a round and colourless image of the sun on the screen; at if a flint glass prism arranged horizontally be interposed in its assage, the beam, on emerging from the prism, becomes refracted owards its base, and produces on a distant screen a vertical band, oloured in all the tints of the rainbow, which is called the *solar pectrum*, rounded at the ends. In this spectrum, the production of which forms one of the most brilliant optical experiments, there is, in reality, an infinity of different tints, which imperceptibly merge into each other; but with Newton, it is customary to distinguish seven principal colours, as seen in the coloured plate. These are *violet*, *indigo*, *blue*, *green*, *yellow*, *orange*, *red*: they are arranged in this order in the spectrum, the violet being the most refrangible, and the red the least so. They do not all occupy an equal extent in the spectrum, violet having the greatest extent, and orange the least.

From the experiment of the solar spectrum Newton concluded that *white* light, that is, light coming from the sun, is not homogeneous, that is simple; but consists of seven different lights which, united, give the impression of white, while, when separated, each produces its own colour. He ascribed the separation of these seven lights on their passage through the prism to their different degrees of refrangibility. For if they were all equally refrangible, as they would be equally bent on entering and emerging from the prism, they would traverse it without being separated, and the light would be white on emerging as well as on incidence.

347. **The colours of the spectrum are simple.**—If one of the colours of the spectrum (the yellow, for instance) be isolated by intercepting the others by means of a screen, and if the light thus intercepted be allowed to pass through a second prism, it is deflected, but without decomposition; that is, it only gives rise to a single emergent pencil. As the same phenomenon is observed with the other colours of the spectrum, it is concluded that they are indecomposable by the prism, which is expressed by saying that the seven colours of the spectrum are *simple* or *primitive colours*.

As regards the cause, in virtue of which one part of the spectrum produces on us the sensation of red, another of yellow, another of orange, and so forth, the undulatory theory teaches us that it depends upon the number of vibrations performed by the molecules of ether. This number, which is very great, differs with each colour, and increases from red to violet. Fresnel has calculated that for the

extreme red it is 458 millions of millions in a second, and for violet 727 millions of millions. As the velocity of propagation is the same for all the colours of the spectrum, but each corresponds to an unequal number of vibrations, it follows that the length of these vibrations must vary with different colours. It has been calculated that, in the case of red, the length of the vibration is 620 millionths of a millimetre, and for violet 425 millionths.

348. **Luminous, calorific, and chemical effects of the spectrum.**—The various spectral rays differ not only in their colour, but also in their luminous power, in the heat by which they are accompanied, and by the chemical effects to which they give rise. It is found that the middle pencils, the yellow and the green illuminate the most powerfully. Thus the print of a book placed in the yellow pencil is seen more distinctly than in the red or violet.

The calorific action of the spectrum is demonstrated by successively placing a very delicate thermometer in the various parts of the spectrum. It is observed that in the red, or even a little beyond it, the heat attains its greatest intensity. This proves the existence of invisible heat rays, which are less refrangible than all other spectral rays (216).

Passing from the calorific action of light to its chemical action, we may first observe that it tends to destroy most vegetable colours, such as wall papers and dyed stuffs, which rapidly fade if exposed to bright light. Some chemical substances are known which are naturally white, and are blackened by the luminous rays: there are gaseous mixtures, also, which suddenly explode when exposed to the sun's rays. These chemical effects are not produced equally in all the parts of the spectrum; the greatest chemical action is met with in the violet, and even a little beyond.

We may thus say that the heating effect is met with in the extreme red, the luminous in the yellow, and the chemical action in the extreme violet.

349. **Dark lines of the spectrum.**—The colours of the solar spectrum are not perfectly continuous: throughout the whole extent of the spectrum are a great number of very narrow dark lines. They are best observed by admitting a pencil of solar rays into a darkened room through a narrow slit. If at a distance of three or four yards we look at this slit through a flint glass prism, with its edge held parallel to the edge of the slit, we observe a number of very delicate dark lines parallel to the edge of the prism, and at very unequal intervals.

The existence of these dark lines was first observed by Wollas- in 1802; but, Fraunhofer, a celebrated optician of Munich, first ied and gave a detailed description of them. He mapped the s, and denoted the most marked of them by the letters A, *a* B, C E, *b*, F, G, H; they are therefore generally known as *Fraun- r's lines.*

The dark line A (see fig. 1 of the coloured plate) is towards the , and B in the middle of the red ray; C is in the red but rather rer the orange ray; D is in the orange ray, E in the yellow, F he transition from green to blue, G in the indigo, H in the et. There are certain other noticeable dark lines, such as *a* in red, and *b* in the green. In the case of the sun's light the posi- is of the dark lines are fixed and definite; in the spectra of arti- il lights and of the fixed stars the relative positions of the dark s vary. For the electric light there are bright lines instead of k ones; and in coloured flames, that is to say flames in which tain chemical substances are being evaporated, the dark lines are laced by very brilliant lines of light, which differ with different stances.

350. **Spectrum analysis.**—This property of coloured flames was t discovered by Sir John Herschell, who remarked that by vola- ing substances in a flame a very delicate means is afforded of ecting certain ingredients by the colours they impart to certain ts of the spectrum; and Fox Talbot, in 1834, suggested ical analysis as probably the most delicate means of detecting iute portions of a substance. To Kirchhoff and Bunsen, how- r is really due a method of basing on the observation of these s a method of analysis. They ascertain that salts of the same tal, when introduced into a flame, always produce lines which identical in colour and position, but different in colour, posi- , or number, for different metals; and, finally, that an exceed- ly small quantity of a metal suffices to disclose its existence. Hence arisen a new method of analysis known as *spectrum analysis.*

351. **Spectroscope.**—The name *spectroscope* has been given to apparatus used by Kirchhoff and Bunsen for the study of the ctrum. One of the forms of this apparatus is represented in fig. . It consists of three telescopes mounted on a common foot, whose axes converge towards a prism, P, of flint glass. The scope A is the one through which the spectrum is observed; it *focussed* by means of the milled head-screw *m*. The telescope as a slit the width of which can be regulated by the screw *v*.

k is what is known as *Bunsen's burner*, in which coal gas is burned, mixed with air in such a manner that a flame of little or no luminosity, but of intense heat, is produced. The substance to be examined is placed in this, either in the solid form, or in a state of solution on the platinum wire at the end of the support, *c*. It is thus volatilised by the intense heat, and the flame G is coloured. The rays emitted from this flame pass through the slit and through a system of lenses, so that on emerging they form a parallel pencil of rays which falls on the prism P. Here they are refracted and de-



Fig. 283.

composed and form the prismatic spectrum. The spectator, on looking through the telescope A, sees a real and inverted image of the spectrum.

The telescope C has a different function; it contains a micrometric scale photographed on glass, so that it is white on a dark ground. The light from the candle passing through the scale and the lens in C falls in parallel rays *on the face* of the prism P, and is *reflected* from thence through the object-glass of A, so that the observer seeing the spectrum and the scale simultaneously can exactly

sure the relative distances of the various spectral lines. M is etal cap with three apertures which covers the prism so as to ude the diffused light.

352. **Experiments with the spectroscope.**—The coloured e shows certain spectra observed by means of the spectroscope. . I. represents the solar spectrum.

Fig. II. shows the spectrum of potassium. It is *continuous*; : is, it contains all the colours of the solar spectrum; moreover, s marked by two bright lines, one in the extreme red, corres- ding to Fraunhofer's dark line A; the other in the extreme violet.

Fig. III. shows the spectrum of sodium. This spectrum con- ıs neither red, orange, green, blue, nor violet. It is marked by a y brilliant yellow ray in exactly the same position as Fraunhofer's k line D. Of all metals sodium is that which possesses the atest spectral sensibility. In fact, it has been ascertained that : two hundred millionth of a grain of common salt is enough to ıse the appearance of the yellow line of sodium. Consequently is very difficult to avoid the appearance of this line. A very le dust scattered in the apartment is enough to produce it, which)ws how abundantly sodium is diffused throughout nature.

Figs. IV. and V. show the spectra of *cæsium* and *rubidium*, tals discovered by Bunsen and Kirchhoff by means of spectral alysis. The former is distinguished by two blue lines, the latter two very brilliant red lines and by two less intense violet lines. hird metal, *thallium*, has been discovered by the same method Mr. Crookes in England, and independently by M. Lamy in ance. Thallium is characterised by a single green line.

Still more recently Richter and Reich have discovered a new tal associated with zinc, and which they call *indium*, from a ple of characteristic lines which it forms in the indigo.

The extreme delicacy of the spectrum reactions, and the ease h which they are produced, constitute them a most valuable p in the qualitative analysis of the alkalies and alkaline earths. is sufficient to place a small portion of the substance under exam- tion on platinum wire as represented in fig. 283, and compare spectrum thus obtained either directly with that of another sub- nce, or with the charts in which the positions of the lines pro- ed by the various metals are laid down.

With other metals the production of their spectrum is more icult, especially in the case of some of their compounds. The t of a Bunsen's burner is insufficient to vaporise the metals, and

a more intense temperature must be used. This is effected by taking electric sparks between wires consisting of the metal whose spectrum is required, and the electric sparks are most conveniently obtained by means of Ruhmkorff's coil. Thus all the metals may be brought within the sphere of spectrum observations.



Fig. 284.

353. **Decomposition of white light.**—Not merely can white light be resolved into lights of various colours, but by combining the different pencils separated by the prism, white light can be reproduced. This may be effected in various ways :

I. A pencil of solar light is decomposed by a prism, as shown in fig. 284, and the spectrum is caught, not on a screen, but on a rather large double convex lens, in the focus of which is placed a small cardboard or ground glass screen. The seven colours of the spectrum coincide in the focus, and there is formed on the



screen a perfectly white circular image, which shows that the union of the seven lights of the spectrum reproduces white light.

II. The same result is attained by replacing the double convex lens in the preceding experiment by a concave mirror. The seven coloured pencils being reflected from this mirror, there is formed in the focus the same white image as in the preceding experiment.

III. By means of Newton's disc it may be shown that the seven colours of the spectrum form white. This is a cardboard disc of



Fig. 285a.

Fig. 285.

it a foot in diameter, the centre and the edges are covered with c paper, while in the space between there are pasted strips of rs of the colours of the spectrum. They proceed from the e to the circumference, and their relative dimensions and tints ich as to represent five spectra (fig. 285*a*). When this disc is y rotated, by means of the turning table represented in fig. 285,

it appears white, or at all events of a greyish-white, for the colours which cover it cannot be arranged exactly in the same dimensions or of the same tints as those of the spectrum.

To explain this phenomenon let us observe that the impression produced upon the eye by the sight of a luminous body lasts a certain time after the cause which produced it has ceased. Thus, if a lighted stick be rapidly turned round, a circle of light is produced, which shows that the sensation produced upon the eye lasts after the stick has passed from in front of this organ. Thus, too, in the above experiment, the disc is turned so rapidly that the action of the seven colours is virtually simultaneous, and the eye is affected as if it received them all together, and the disc therefore appears white.

354. **Newton's theory of the composition of light and the colour of bodies.**—Newton was the first to decompose white light by the prism, and to recompose it. From the various experiments which we have described he concluded that white light was not homogeneous, but formed of seven lights unequally refrangible, which he called *simple* or *primitive* lights.

He was further led to the conclusion, that bodies are not of themselves coloured, that is have no colour of their own, but that they have the property of decomposing the white light, which illuminates them, and of reflecting unequally the various kinds of light of which it is formed. Thus, vermilion is not red of itself, but is endowed with the property of reflecting red light and of absorbing all others, or at any rate of only reflecting them in far less proportion. In like manner the leaves of plants are not truly green; they have merely a greater reflecting power for green than for any other colour. In short, bodies are only coloured by the light they reflect. For, let these same green leaves be placed in a spectrum projected in a dark room, if they are in the green band they will appear of a dazzling green, far brighter than their natural colour; but if they are placed in the red they will appear red, and of violet if placed in violet. A similar effect is produced if a rose be successively placed in each of the spectral bands, showing that the colour of a body is not peculiar to them, but depends upon the kind of light which their molecular constitution gives them the power of reflecting. In speaking, too, of the *green* or the *red pencil*, we do not mean that they are coloured of themselves, but merely that they have the power of producing in us the sensation of red, or of yellow. The eye judges colours as the ear judges sounds; both the colours and the sounds depend on the number of vibrations.

Bodies which reflect all colours in the spectrum equally well are white, those which reflect none at all are black; so that black is not really a colour, but the absence of colour.

The varied shades which coloured bodies present result not merely from the fact that they simultaneously reflect various kinds of light, but reflect them to different extents. Thus, a body which reflects yellow and blue light will be green, but a green the shade of which varies with the quantities of yellow and of blue light which the body reflects. If by means of an opaque screen, part or all of certain colours of the spectrum be intercepted, and the others be united by means of a lens, as shown in fig. 284, there is no shade in nature which cannot be reproduced, but with a lustre and richness of colour which artifical pigments can never attain.

355. **Colours of transparent bodies.**—We have seen above that opaque bodies owe their colour to the power of decomposing light by reflection, that is, of reflecting certain colours more abundantly than others. It is owing to the decomposition of light that transparent bodies seem to be coloured: though here the decomposition is effected by transmission and not by reflection. If all rays of the spectrum were equally transmissible by transparent media they would necessarily be colourless; that, however, is never quite the case, at all events when the media have a certain thickness; for then they absorb certain colours of the spectrum more than others, and have the tint of the more transmissible colour. Water, for instance, when by transmission through a great thickness, has a greenish tint, which shows that of all colours contained in white light, it allows green to pass most easily.

Air, in great thickness, gives a bluish tint to distant objects, which would rather tend to prove that air is more transparent for blue than for any other spectrum colour. It is more probable that this effect is due to the presence of the aqueous vapour in the air.

356. **Complementary colours. Accidental images.**—If in white light any colour be suppressed, a mixture of the remainder is called the *complementary colour*, for it is the colour needed to complete the sensation of white light. A mixture of blue and yellow produces a *green*, and, accordingly, green is the complementary colour to red. In like manner, a mixture of red and yellow produces *orange*, which is complementary to blue. Similarly *indigo* is the complementary colour to yellow, and *yellowish green* to violet.

Effects of complementary colours are met with in many curious

experiments. Thus, let any coloured object, a wafer for instance, be placed on a black ground, and let it be viewed for some minutes until the sight is fatigued ; if then the eyes be turned to a sheet of white paper, an image will be seen of the same form as the object, but of the complementary colour ; that is, that if the wafer is red its image will be green, if it is orange the image will be blue, and so forth. In like manner, if, after looking for some time at the setting sun, the eye be turned to a white wall, an intense green disc will be seen, which lasts for some minutes, after which the red image reappears ; a second green image succeeds to it, and so on for a great number of times, until the appearance fades away.

These images which thus persist sometimes after an object has been looked at, and which have the complementary colours of those of the object, were first observed by Buffon, who gave them the name of *accidental images.*

There is another kind of accidental colour also noticed by Buffon ; when a coloured object placed on a white ground is attentively looked at for some time the object is seen to be surrounded by a colour which is complementary to that of the object. This phenomenon, which is known as the *accidental halo,* is easily verified by means of a coloured wafer placed on a sheet of white paper.

When several pieces of cloth of the same colour are successively looked at it will be seen that the latter ones appear of a bad shade. This arises from the fact, that the accidental colour of the cloth begins to form, and its own tint loses its brightness. So too when designs are printed, or cloth embroidered on a coloured ground, effects may be obtained quite different from those which were desired. Generally if two adjacent colours are complementary, each will acquire a greater lustre ; but if they are of the same tint, they will mutually enfeeble each other. It will thus be seen how numerous are the applications which the phenomenon of accidental images presents in combining colours in pictures, wall papers, tapestry, furniture, even the toilet, although good taste has long been in advance of the data of science.

357. **Irradiation.**—This is a phenomenon in virtue of which white objects, or those of a very bright colour, when seen on a dark ground appear larger than they really are. Thus a white square upon a black ground seems larger than an exactly equal black square upon a white ground fig. 286. With a black body on a bright ground, the converse is the case. Again, a platinum wire made red-hot by the passage of an electrical current seems far thicker

an it is in reality. Irradiation arises from the fact, that the ıpression produced on the retina extends beyond the outline of e image. It bears the same relation to the space cupied by the image that the duration of the ıpression does to the time during which the ıage is seen.



Fig. 286.

The effect of irradiation is very perceptible the apparent magnitude of stars, which may us appear much larger than they really are; so in the appearance of the moon when two or ree days old, the brightly illuminated crescent eming to extend beyond the darker portion of ıe disc, and hold it in its grasp.

Plateau, who has investigated this subject, ıds that irradiation differs very much in different people, and even the same person it differs on different days. He has also found at irradiation increases with the lustre of the object, and the length time during which it is viewed. It manifests itself at all disıces, diverging lenses increase it, condensing lenses diminish it.

358. **Rainbow.**—The *rainbow* is a luminous meteor which apırs in the clouds opposite the sun when they are resolved into n. It consists of seven concentric arcs, presenting successively : colours of the solar spectrum. Sometimes only a single bow perceived, but there are usually two; a lower one, the colours which are very bright, and an external or *secondary* one, which paler, and in which the order of the colours is reversed. In interior rainbow the red is the highest colour; in the other ıbow the violet is. It is seldom that three bows are seen; theo.cally a greater number may exist, but their colours are so feeble t they are not perceptible.

The phenomenon of the rainbow is produced by the decompoon of the white light of the sun when it passes into the drops, l by its reflection from their inside face. In fact, the same phenonon is witnessed in dewdrops and in jets of water; in short, erever solar light passes into drops of water under a certain angle. The appearance and the extent of the rainbow depend on the ıition of the observer, and on the height of the sun above the rizon; hence only some of the rays refracted by the rain-drops, l reflected in their concavity to the eye of the spectator, are adted to produce the phenomenon. Those which do so are called *ıctive rays.*

To get a general idea of this let us refer to fig. 287, in which two rain-drops, *a* and *c*, are represented extremely magnified as compared with the arc of which they form part. The pencil of white light which fall upon *a*, is refracted on entrance into the droplet and decomposed, giving rise to seven rays, red, orange, yellow, green, blue, indigo, and violet (346). At the point *a*, on the posterior face of this droplet, a portion of the refracted light escapes, and is dispersed in the atmosphere without giving rise to any particular phenomenon; the light which has not emerged from the droplet is collected at *a*, returns and emerges in being a second time refracted, and reaches the observer's eye as represented in the figure.

A second droplet, *c*, placed below the preceding one, produces just the same effect; yet it does not send the same colour to the spectator. For, as the different colours are unequally refrangible, the coloured rays which emerge from the same rain-drop diverge, and, therefore, are not propagated together; whence it follows that each drop only sends one kind of colour towards the observer. But from the different degree of refrangibility of each ray, the droplets on the



Fig. 287.

outside of the arc send only red rays towards the eye, and those on the inside violet rays. The other colours arise from intermediate droplets.

In short, the rainbow is the circumference of the base of a cone

ıe apex of which is the observer's eye, and the surface of this cone formed from the outside to the inside of seven successive enve-pes, red, orange, yellow, etc., corresponding to each of the bands the spectrum. The nearer the sun is to the horizon the larger is ıe visible part of the rainbow ; but, as the sun rises, the arc dimi-shes, and entirely disappears when the sun is 42 degrees above e horizon. Hence the rainbow is never seen except in the morn-g and evening.

CHAPTER VI.

INJURIOUS EFFECTS OF COLOUR IN LENSES. ACHROMATISM.

359. **Aberration of refrangibility.**—In speaking of lenses we ave been silent about a serious defect to which they are liable, hich is, that objects seen through these lenses at a certain distance ɛem surrounded by an iridescent fringe, which fatigues the sight nd greatly injures the precision of the images.

For, as lenses may be compared to a series of prisms with infi-itely small faces, and united at their bases, they not only refract ght, but also decompose it like a prism. On account of this dis-ersion, therefore, lenses have really a distinct focus for each olour. In condensing lenses, for example, the red rays, which are he least refrangible, form their focus at a point r on the axis of the ens (fig. 288), while he violet rays, which re most refrangible, oincide in the nearer oint, v. The foci of he orange, yellow, reen, blue, and indigo re between these oints. Hence a double convex lens tends to give seven images, ifferently coloured, of objects seen through them. These images eing partly superposed, the seven colours combine in the centre form white light, but, on the contours, the extreme colours of e spectrum are visible, that is, more especially red and blue.



Fig. 288.

This injurious colouration of the images is called the *chromatic erration.*

360. **Achromatic lenses.**—By observing the phenomenon of the dispersion of colours in prisms of water, of oil of turpentine, and of crown-glass, Newton was led to suppose that dispersion was proportional to refraction. He concluded that there could be no refraction without dispersion, and therefore, that achromatism was impossible. Almost half a century elapsed before this was found to be incorrect. Hall, an English philosopher, in 1733, was the first to construct achromatic lenses, but he did not publish his discovery. It is to Dollond, an optician in London, that we owe the greatest improvement which has been made in optical instruments. In 1757 he combined two lenses, one a double convex *crown-glass* lens, the other a double concave lens of *flint-glass* (fig. 289), a kind of glass which contains a good deal of lead, and which has greater dispersive power than flint-glass.

Fig. 289.

By suitably choosing the curvatures of these two lenses, they may become unequally dispersive, and as the dispersion is in opposite directions, one of the lenses being convergent and the other divergent, two effects are produced, which compensate each other as regards colouration, but not as concerns refraction ; that is, a ray of white light which has traversed such a lens emerges colourless, but converging, and forming a single focus on the axis.

The lenses thus formed of flint and crown-glass give images which are not coloured on the edges ; they have hence been called *achromatic* lenses ; *achromatism* being the term applied to the phenomenon of the refraction of light without decomposition.

361. **Spherical aberration.**—Chromatic aberration is not the only defect which lenses present ; they have another, which is known as *spherical aberration*, and which arises from the fact, that, apart from dispersion, the rays which traverse a condensing lens do not exactly coincide in a single focus. Those which traverse the lens near the edges are too much refracted as compared with those which traverse the central part ; hence the former rays converge nearer to the lens than the latter, in consequence of which the images are distorted.

This inconvenience is obviated in optical instruments by intercepting the rays which traverse the lens near the edge by *diaphragms* or *stops*, which are opaque screens perforated by circular holes, and which only allow the central rays to pass.

CHAPTER VII.

OPTICAL INSTRUMENTS.

362. **The different kinds of optical instruments.**—By the term *optical instrument* is meant any combination of lenses, or of lenses and mirrors. By their means the limits of vision have been enormously increased, and the most favourable influence has been exerted on the progress of science, by opening out new worlds to investigation which would otherwise have remained unknown. Optical instruments may be divided into three classes according to the ends they are intended to answer, viz. :—i. *Microscopes*, which are designed to obtain a magnified image of any object whose real dimensions are too small to admit of its being seen distinctly by the naked eye. ii. *Telescopes*, by which very distant objects, whether celestial or terrestrial, may be observed. iii. *Instruments*, designed to project on a screen a magnified or diminished image of any object which can thereby be either depicted, or be rendered visible to a crowd of spectators ; such as the *camera lucida*, the *camera obscura*, *photographic apparatus*, the *magic lantern*, the *solar microscope*, the *photo-electric microscope*, etc. The two former classes yield virtual images, the last, with the exception of the *camera lucida*, yield real images.

General composition of optical instruments. Of the various instruments enumerated above, those of the first two groups consist essentially of two lenses : one called the *object glass*, or *objective*, receives the light from the objects, and concentrates it in a focus where it gives a small image ; the other, called the *eyepiece*, or *ocular*, acts as a magnifying glass, is near the eye, and serves to view the image formed by the object glass. In what are called *reflecting telescopes*, a concave mirror is used instead of an object glass. Generally speaking the object-glass and the eyepiece are not formed of a single glass, but of several, in order to obtain a greater magnifying power, and to correct chromatic and spherical aberration (361). These glasses are, moreover, mounted in long metal tubes, blackened on the inside so as to absorb the oblique rays, which would otherwise injure the sharpness of the image ; these tubes can further be slid in or out so that the glasses may be brought to the proper distance.

363. **Galileo's telescope.**—Like many great discoveries, that of the telescope seems due to chance. For it is stated to have been made accidentally by the children of a Dutch spectacle maker at Middlebourg. Looking at a vane on the top of a church spire through a convex and concave glass, the latter being nearer the eye, they were surprised to see the object magnified, and apparently almost within reach. The father repeated the experiment and arranged the two glasses in tubes, one which slided in the other, and thus constructed the telescope.

This telescope bears Galileo's name, for this illustrious astronomer was the first to direct it towards the heavens, and to make astronomical observations. It is stated that he was at Venice when he learnt that Zacharia Jans had offered to Prince Maurice of Nassau an instrument which brought objects nearer: he quickly



Fig. 290.

started for Padua, where, after meditating on the matter, he made some experiments, and in twenty-four hours rediscovered the telescope.

The telescopes constructed by Galileo were gradually improved from a magnifying power of four up to one of thirty times. By its means Galileo discovered the mountains of the moon, Jupiter's satellites, and the spots on the sun. From these numerous discoveries he acquired the name *Lynceus*, from one of the Argonauts whose sight is said to have been so penetrating that he could see to the bottom of the sea.

Fig. 290 represents the arrangement of the lenses and the path of the rays in a Galileo's telescope. The object glass, O, is a double convex, while the eyepiece, *o*, is a double concave lens. If AB is the object observed, the rays, from any one of its points, A, for instance, tend to form an image of this point beyond the object-glass; but meeting the double concave lens, *o*, these rays appear divergent, and seem to the eye which receives them as if they proceeded from

the point *a*; and it is there the image of A appears. In like manner the image of B is formed at *b*, so that a virtual image, *ab*, is formed, which is erect, and very near.

Galileo's telescope is very short and portable. It has the advantage of showing objects in their right position, and further, as it

Fig. 291.

has only two lenses, it absorbs very little light; in consequence, however, of the divergence of the emergent rays it has only a small field of view, and in using it the eye must be placed very near the eyepiece. The eyepiece can be moved to or from the object

glass, so that the image is always formed at the distance of distinct vision.

Opera glasses are constructed on this principle. They are usually double, so as to produce an image in each eye, by which greater brightness is attained.

364. **Astronomical telescopes.**—In observing the stars a telescope with two condensing lenses is used, in order to obtain a greater field of view. Its invention is due to Kepler, and it is known as the *astronomical telescope*. It gives reversed images of objects, but this is not prejudicial in observing the stars.

Fig. 291 represents an astronomical telescope with a cast iron support, and mounted with a hinge motion on a column of the same metal; so that, not only can any degree of inclination be imparted to it, but it can be directed to any part of the horizon. By means of a handle and two toothed wheels the telescope can be raised or lowered at pleasure. On the side of the telescope is



Fig. 292.

a smaller one called the *finder*; for as it magnifies less than the large one, it embraces a greater extent of sky, and therefore is more suited for finding any given star, which is then observed more minutely with the large glass.

Fig. 292 represents the arrangement of the glasses, and the path of the rays in an astronomical telescope. It consists of two double convex glasses; the object glass, which is of large diameter, and but slightly convergent, gives at *ab* a reversed and very small image of the star towards which the telescope is directed. This image is looked at through the eyepiece, O, which acts here as a magnifying glass, and which, for that purpose, is placed so that the image, *ab*, is formed between this glass and the principal focus, F. Thus the observer sees a reversed and greatly enlarged image of the star at *cd*.

As in all telescopes, the *eyetube*, that is, the tube in which is the eyepiece, slides in the other, so that it can be brought nearer or further from the image, *ab*, which can thus be seen at the distance

f distinct vision. In powerful telescopes the eyepiece is not simple, s in the above case, but consists of a greater number of glasses, ıe object of which is not only to increase the magnifying power, ut also to correct spherical and chromatic aberration.

The magnifying power of a telescope is greater the greater the iameter of the object glass, and the less its convexity ; and the ıore convex, on the contrary, is the eyepiece. The greatest ob- :acle met with in the construction of these telescopes is the ifficulty of manufacturing large object-glasses.

When the telescope is used to make an accurate observation of ıe stars, for example, their zenith distance, or their passage over ıe meridian, a *cross wire* is added. This consists of two very fine ıetallic wires or spider threads stretched across a circular aper- ıre in a small metal plate. The wires ought to be placed in the osition where the inverted image is produced by the object glass, nd the point where the wires cross ought to be on the optical xis of the telescope, which thus becomes the *line of sight*, or *ollimation.*

365. **Terrestrial telescopes.**—The *terrestrial telescope* differs om the astronomical telescope in producing images in their right

Fig. 293.

ositions. This is effected by means of two condensing lenses, vhich are interposed between the object glass and the eyepiece, as een in fig. 293. The object glass forming then, at I, a reversed mage of the object, AB, the two glasses, *m* and *n*, impart such a lirection to the rays traversing them, that, after having crossed etween the two glasses, the rays reproduce an erect image at *i*. The eyepiece acts then just as in the astronomical telescope, giving very near, erect, and magnified image, *ab*.

The terrestrial telescope is sometimes mounted on a stand, and ometimes held in the hand ; its uses are too well known to need ny description.

366. **Reflecting telescopes.**—The telescopes previously de- :ribed are *refracting* or *dioptric* telescopes. It is, however, only ı recent times that it has been possible to construct achromatic

lenses of large size; before this, a concave metallic mirror was used instead of the object glass. Telescopes of this kind are called *reflecting* or *catoptric telescopes.* The principal forms are those devised by Gregory, Newton, Herschel, and Cassegrain.

Of these we shall describe the Newtonian telescope, which, after long disuse, has been restored to favour, in great measure owing to the improvements made in the construction of the concave mirror used in it.

Fig. 294 represents the section of a Newtonian telescope as modified by M. Foucault, and fig. 295 a perspective view. The principal piece of the telescope is a concave mirror, M, placed at the end of a long wooden tube. These mirrors were formerly of metal, and the difficulty of working such mirrors, so as to give them a perfect curvature, was so great, that the use of reflecting telescopes was virtually abandoned.

Foucault having discovered a method of silvering glass without



Fig. 294.

injuring its polish, and as glass is more easily worked than metal mirrors, reflectors for telescopes are now made of polished glass, silvered on the concave surface itself, the rays of light which come from the star observed are there reflected, and tend to form at the other end of the tube a real and very small image of the star; but these rays fall upon a small rectangular prism, *mn*, into which they pass without being refracted, and form with the large face, *mn*, such an angle of incidence that they are reflected out instead of being refracted (330). The image is then formed at *ab*, in front of a horizontal tube, in which are a series of magnifying glasses, which act as ocular, and give of the image, *ab*, a very amplified virtual image, AB.

Fig. 295 shows how the instrument is worked. The right hand of the observer holds a handle which transmits the motion to an endless chain, and this to two other chains, which pass round

pulleys, and enable the tube to be more or less inclined ; with the left hand the same observer turns a small wheel, fixed to a screw, which enables him to move slowly the front part of the apparatus in a lateral direction, so that he can follow the star in its motion.



Fig. 295.

A little lower than the eyepiece and above the small wheel is a milled head, which works a small rack and pinion motion : this is fixed to a movable piece, which, at the same time, supports the prism, *mn*, and the eyepiece (fig. 294). By turning this milled head in

either direction, the prism and the eyepiece may be adjusted until the image, AB, is formed at the distance of distinct vision of the observer.

On the side of the tube is a smaller telescope, quite similar to the large one, but of far less magnifying power. This is the *finder*. From its small magnifying power, not more than ten, it embraces a far greater extent of the sky, and is therefore more favourable for finding the desired star.

367. **Herschel's telescope.**—Sir W. Herschel's telescope, which, until lately, was the largest instrument of modern times, was constructed on a method differing from those described. The mirror was so inclined that the image of the star was formed on the side of the telescope near the eyepiece (fig. 296); hence it is termed



Fig. 296.

the *front view* telescope. As the rays in this telescope only undergo a single reflection, the loss of light is less than in either of the preceding cases, and the image is therefore brighter. The magnifying power is the quotient of the principal focal distance of the mirror by the focal distance of the eyepiece.

Herschel's great telescope was constructed in 1789; it was 40 feet in length, the great mirror was 50 inches in diameter. The quantity of light obtained by this instrument was so great as to enable its inventor to use magnifying powers far higher than anything which had hitherto been attempted.

Herschel's telescope has been exceeded by one constructed by the late Earl of Rosse. This magnificent instrument has a focal length of 53 feet; the diameter of the mirror is 6 feet, and it weighs 8,400 pounds. It is at present used as a Newtonian telescope, but it can also be arranged as a front view telescope.

MAGNIFYING INSTRUMENTS.

368. **Simple microscope.**—*Microscopes* are instruments which, ving very magnified images, enable us to observe objects which e too small to be seen with the naked eye. Two kinds are dis-ıguished, the simple and the compound microscope.

The first of these is nothing more than a small highly convergent ns, which is used as a magnifying glass as seen in fig. 297. The ›ject observed is then placed between the lens and its principal cus, and the magnifying power is greater the more condensing is e lens. When it is rather large it is mounted in horn or in ivory, ıd is then known as a *lens*. It is frequently used to assist the

Fig. 297.

;ht of the aged, or to facilitate certain kinds of work, which, as in ıtchmaking and engraving, require great accuracy. But no great ıgnification is thus attainable, and in order to observe very small jects, the *compound microscope* is used, which is so called, for it made up of several lenses.

369. **Compound microscope.**—Fig. 298 represents the mode of ing a compound microscope, and fig. 299 the path of the luminous ys in the interior of the apparatus. The object observed, which always very small, is placed at *a*, between two glass plates on a pport called the stage. OA*o* is a brass tube in which are two ndensing lenses, the *object-glass*, *o*, at the bottom, and the *eyepiece*, at the top. The *object*, *a*, being placed very little beyond the

principal focus of the eyepiece, we know that a real, erect, and greatly magnified image will be formed at *bc* (343). But as the eyepiece, O, is at such a distance that the image, *bc*, is between this glass and its principal focus, F, it follows that for an eye looking

Fig. 298.

through it the eyepiece acts as a lens (344), and gives at BC a virtual and amplified image of the first image, *bc*. It may thus be said, that the compound microscope is nothing more than a simple mi-

scope applied not to the object, but to its image already magni-
l by the first lens.

The magnification depends more especially on the object-glass.
order to increase its power it consists of two or three small
ses, superposed, as seen in H, on the right of the drawing (fig. 299).
the eyepiece a second glass is used, the object of which is less
obtain increased magnification than
render the images more defined by
ninishing, as in telescopes, chro-
tic and spherical aberration. All
glasses are, moreover, achromatic.
e magnifying power in compound
croscopes has been carried to 1,800
ies, and even more, but then what
gained in magnification is lost in
niteness. A good magnification
es not exceed 600 in length and
adth, which amounts to a super-
ial enlargement of 360,000 times.



Fig. 299.

From the great magnification of
image the object must be power-
ly illuminated. For this purpose,
en it is sufficiently transparent, it
illuminated from below by a con-
e mirror, M, which concentrates
on it a large quantity of light, as
own in fig. 299. If the object is
aque it is illuminated above by a con-
nsing lens, L (fig. 298), the focus of
ich is formed upon the object itself.

370. **Origin and use of the mi-
oscope.** — The invention of the
icroscope does not extend further
ck than the commencement of the
venteenth century, which is surprising, for it had long been
own that a drop of water placed in a small hole in a thin opaque
ate magnified objects seen through it. From the commencement
the first century, A.D., the philosopher Seneca announced that
iting appeared larger under a glass globe containing water.
nally, in the thirteenth century, *spectacles* were used, that is,
agnifying *glasses, to assist* the sight of the aged. The inventor

of the microscope is not known ; it has, probably, only acquired its present form after numerous successive improvements.

The microscope has been the origin of discoveries in the vegetable and animal kingdom, as curious as they are varied. Botanists owe to it their most beautiful discoveries on the structure of the cellular tissue in plants, the circulation of the sap, the function of leaves in the respiration of vegetables. In entomology it has enabled us to discover a crowd of small animals which would otherwise have remained unknown from their extreme minuteness. Thus there have been observed, in vinegar and in sour paste, thousands of small organisms called *vibrions* ; in stagnant waters myriads of animalcules, as remarkable for their fantastical forms as for their beautiful colours, their instincts, their warlike or sociable manners. Mould presents the appearance of small mushrooms with the most brilliant colours. In short, any object seen through the microscope becomes an object of astonishment and admiration : thus, for instance, a hair, a piece of silk thread, the eye or wing of a fly, a bee's sting, a spider's claw, a cat's or mouse's hair, the down of fruit, the scales of a butterfly's wing or of fish, starch grains, spider-web, etc., etc., everywhere we recognise the infinite perfection of nature's works.

The microscope may also be advantageously used to recognise fraudulent mixtures in cloths of various kinds, by giving a means of ascertaining whether they contain wool or silk, linen or cotton.

CHAPTER VIII.

OPTICAL RECREATIONS.

371. **Magic lantern.**—In the instruments that still remain to be described, the object is to project on a screen reduced or enlarged images of an object, so as to exhibit them to a number of spectators, or to utilise them for drawing.

The oldest and most simple of these apparatus is the *Magic lantern*, which, as everyone knows, is one of the first physical instruments placed in children's hands. It was invented by Father Kircher, a German Jesuit, about 200 years ago, and is used to project a magnified image of small objects painted on glass on a white screen in a dark room (fig. 300). It consists of a tin plate box

a which there is a lamp placed in the focus of a concave mirror, M fig. 301). The reflected rays fall upon a condensing lens, L, which oncentrates them on the figure painted on a glass plate, *ab*. There s a system of two lenses, *m*, acting as a single one of great magni- ying power, at a distance from *ab* of rather more than its focal listance. At this distance the system of two lenses acts as in the xperiment (fig. 300); that is, a real and very much magnified nage of the figure on the glass is produced on the screen. The



Fig. 300.

nage is made erect by placing in the lantern the glass painted ı such a manner that the design is reversed. The image, AB, is ırmed at so much the greater distance, and is so much the more mplified, the nearer the glass, *ab*, is to the principal focus of the ystem of lenses, *m*, and the greater the magnification of this ystem.

372. **Phantasmagoria.**—This is only a modification of the agic lantern, and dates from the end of the eighteenth century: its ame is derived from two Greek words, which signify *assemblage of*

phantoms, for it was originally used to produce fright, by making spectres appear in darkness.

The internal arrangement of the phantasmagoria is just the same as in the magic lantern, the only difference being, that in the magic lantern the image projected on the screen is always of the same size, while, in the case of the phantasmagoria, the size may be varied at pleasure. To understand how this is effected, let us refer to fig. 301, which represents the arrangement of glasses in the magic lantern. The lenses, *m*, which are used to project the images on the screen, being always at the same distance from the painted glass, *ab*, the image, AB, is always at the same distance, and is always therefore of the same size. Now if one of the lenses, *m*, be brought



Fig. 301.

nearer the glass, *ab*, it follows from the properties of lenses (349) that the image will be formed at a greater distance, and will be larger. Hence the effect sought requires two movements; one which brings the system of lenses, *m*, nearer the painted glass, to amplify the image: the other, which makes the whole apparatus recede, so that the image, while being moved away, is always formed upon the same screen as at first.

To obtain this double effect the whole apparatus is mounted upon four small wooden wheels covered with cloth, so that they roll noiselessly on the floor. Figure 302 represents a phantasmagoria thus arranged, with the difference that in the figure it is double, that is, consists of two apparatus united. We shall presently (373) see the reason for this double use, and for the moment we shall only consider one of the parts. The front of the box is provided with a conical brass tube: in this tube is the lens of projection, which is

ed, but may be advanced or receded by means of a milled d screw, which the experimenter turns with the hand.



Fig. 302.

A large white sheet is stretched in front of the apparatus, and the spectators are on the other side of the sheet. The whole being in profound darkness, the experimenter is careful first of all to keep the projecting lens away from the glass, on which are painted the objects he desires to show. Thus there is at first formed on the sheet a very small image of the object. Then, with one hand, the experimenter brings the lens near the painted glass, while with the other he draws towards himself the apparatus, and away from the cloth; the image projected on the latter gradually increases, and ultimately becomes very large. But the spectators, who are prevented from seeing whether the position of the image changes or not, and who see the image very distinctly through the cloth, fall into the illusion that its increase in size is due to its coming nearer them. Some authors have supposed that use was made of the phantasmagoria in remote antiquity, and, by means of apparatus of this kind, those initiated into the mysteries of Isis and Ceres were terrified, and the infernal deities evoked were made to appear. Yet nothing indicates that lenses were then known; concave mirrors, however, would be sufficient for producing effects analogous to those of the phantasmagoria.

373. **Polyorama, or dissolving views.**—The *polyorama*, is an application of the phantasmagoria. It is double, as represented in fig. 302, and the two systems of lenses converge towards the same point of the cloth which receives the image. Two pictures on glass are used representing the same view under different conditions; for example, Mount Vesuvius seen at daytime, calm, and with a slight cloud of smoke rising from it; the other when seen at night vomiting forth flames and torrents of fiery lava. Having arranged these glasses, each in one of the phantasmagoria, and the lenses being so arranged as to project the magnified images on exactly the same part of the cloth, the diaphragm of the one containing the picture representing the effect of day is opened; the other remaining closed. Then when the image has for some time been exposed to the view of the spectators, a mechanism, *a*, is worked, which gently closes the one which has been exposed, and opens the other. It follows, that in gradually passing through all the shades of light, the image which produces the effect of day disappears, while it is gradually succeeded by the effect of night represented on the other. In like manner, too, the effect of the moon rising may be made to succeed to sunset; to a calm and transparent sea, a tempest; to a smiling landscape, a snow effect, and so

. Hence the name *polyorama*, from two Greek words, which fy several views.

74. **Photo-electrical microscope.**—This apparatus is based on ame principles as the magic lantern and the phantasmagoria. as in these apparatus, the subjects painted on glass are of : size, no great enlargement is required, and therefore the illumi-

Fig. 303.

)n need not be very intense. Whereas objects, the image of h is reproduced by the photo-electrical microscope, being very l, should be considerably magnified, and the light must there- be very powerful, or else the image will be confused and indis- . Hence the apparatus is illuminated by the powerful light h the electric battery yields.

Figure 303 represents the use of the photo-electric microscope. At the base of the vessel is a series of vessels which serve for the disengagement of electricity, and which we shall afterwards describe as the electric battery. From these vessels the electricity passes by two stout copper wires to two rods of charcoal, contained in the box B. Thus charged with electricity, these carbons become heated to incandescence, and emit such a bright light that the eye cannot support it. A reflector, I, sends the luminous rays in the direction of the tube, C, where they meet two condensing lenses, which concentrate them on the very small object which is to be magnified, and which is arranged between two glass plates, X. The rays pass from thence into a tube D, where there is a system of condensing lenses intended to produce the same effect of projection as the lenses, *m*, in the magic lantern (371) ; that is, it is a system of lenses which produces on a white screen at a distance an extremely magnified image of the small object placed between the glass plates. The tube, D, is movable, and may be approached to or receded from the object, so as to vary the magnification.

In the adjacent figure, the image projected on the screen is that of the infusoria which are found in paste when it has fermented. A small quantity is mixed with water, and a few drops put in a small glass box with parallel faces, which is placed at X. A multitude of these animalculæ are seen on the screen, ten or twelve inches in length, which move about in a confused mass, and soon die in consequence of the heat which is concentrated along with the light in the focus of the lenses.

375. **Experiments with the photo-electric microscope** are among the most interesting in the whole range of physics. By its means, objects of extreme minuteness may be exhibited, greatly magnified, to a large number of spectators. A hair, for example, looks like a broomstick ; a flea like a sheep ; the itch-tick, an animalcule found in itch pustules, and by which this disease is propagated, appears like a man's head ; the same is the case with the animalcules found in decayed cheese, although these cannot be seen by the naked eye. One of the most remarkable experiments is that showing the circulation of the blood. This is made by placing between two glass plates the tail of a living tadpole, that is to say, the young of a frog, before its upper and lower limbs are developed. There is then observed on the screen a kind of illuminated map, all the rivers in which appear to flow very rapidly : this is the blood which circulates in the veins. A very beautiful experiment is the

rystallisation of salts, and especially of sal ammoniac. This salt is issolved in water, and a drop of the solution is spread on a glass late, which is placed in the apparatus. As the heat makes the ater evaporate, a vegetation quickly forms, which is surprising om the promptitude with which the crystalline molecules group hemselves together to produce magnificent ramifications like fern aves.

The apparatus we have described is sometimes modified, so as to e illuminated by sunlight, and is then called the *solar microscope.* : is also illuminated by the intense light produced by allowing the oxyhydrogen flame to impinge upon a piece of lime. It is then alled the *oxyhydrogen microscope.*

376. **Camera obscura.**—A Neapolitan physician, Jean Baptiste

Fig. 304.

'orta, first observed in 1680, that if a very small hole be perforated n the shutter of a *dark room,* one that is quite deprived of light, all bjects which can reach the hole depict themselves on the opposite creen, and of so much the smaller dimension the nearer this screen s to the aperture.

Porta also found, that by fixing a double convex lens in the aperure, and placing a white screen in the focus, the image was much

brighter, and more definite. In both cases the images are inverted. Fig. 304 shows how images formed in the camera obscura are reversed upon the screen. It is due to the rays crossing on entering the aperture. It follows in fact, that rays from the higher parts of the object proceeding in a straight line meet the lower part of the screen, while the reverse is the case with rays from the lower part. The colouration of the image is readily understood by observing, that the reflected rays are of the same colour as the reflecting body;



Fig. 305.

that is, that a red body reflects red rays, a yellow body yellow rays, and so on; each portion of the image is formed by the coincidence of rays of the same colour as the corresponding part of the object it represents.

The images formed in the camera obscura have the peculiarity of being independent of the shape of the aperture through which the rays enter *provided this is very small*, that is, that whether this aperture is round, square, or triangular, the image formed on the screen is always a faithful reproduction of external objects, and not

the hole made in the shutter. To account for this phenomenon t us consider the case of a pencil of solar light passing into a dark om of any shape whatever (fig. 305). From the magnitude of the n this hole is really nothing more than a point ; whence it follows, at the whole of the rays which traverse it represents an immense ninous cone, of which the hole is the summit and the sun the se. By their being prolonged into the chamber these rays give e to a second cone resembling the first, but far smaller ; and if s second cone falls upon a screen which is perpendicular to the aight line joining its summit to the centre of the sun, it produces

Fig. 306.

this screen a circular image like the sun. If the screen is iquely inclined towards this line, as represented in fig. 305, the age is elongated, but it never has the shape of the aperture unless screen is very close.

In the same manner we must explain the luminous circles former the ground under an avenue of trees illuminated by the sun, atever be the shape of the spaces on the foliage through which light passes, a circular image of the sun is projected upon the ound (fig. 306.)

377. **Rectification of images of the camera obscura.**—When

in a camera obscura a monument or a landscape is to be reproduced, the image must be rectified. For this purpose the apparatus is arranged as in fig. 307. A little above the hole through which the light enters a plane mirror is placed, inclined so as to send the rays towards a condensing lens fixed at the end of a tube. Below this lens, and at its focus, is placed a white screen, on which external

Fig. 307.

objects depict themselves. The images thus obtained, rectified by the reflection of the rays from the plane mirror and their passage through the lens, are not merely admirable from their fidelity and colour, but they do what no other kind of reproduction can do, they reproduce motion. If the camera obscura is set up in front of a promenade, or a public place, the images of the passers-by are seen

to move across the screen with such fidelity that they can be recognised.

The camera obscura gives in this manner an amusing spectacle; it may, moreover, be used in drawing, for even a person who cannot draw can trace with a pencil the outlines of the image, and trace it on a screen. For this latter purpose the following arrangement is usually adopted.

378. **Portable camera obscura.**—To make views by means of the camera obscura, it should be light and portable, and should not occupy too large a space. Fig. 308 represents a simple and con-

Fig. 308.

venient form of the apparatus. It consists of a wooden tripod, supporting a board of the same material, and surrounded by a curtain which forms a small tent, in which the artist places himself. In the centre of the tent is a small table resting on a tripod, on which is produced the image. At the top of the apparatus, in a brass tube open at the side, is a glass prism, which produces the effect both of the inclined mirror and of the lens in the camera obscura described above. For this purpose the first face of the prism is convex, as represented in fig. 309. Hence on passing

into this prism the rays from a distant object converge ; then undergoing a total reflection on the side *m* (330), they are sent toward the third face, which is concave, whence they emerge with the same degree of convergence that they had before traversing the



Fig. 309.

lens, and there is thus reproduced at *ab* on the table P the image of the object AB, from which they come. The designer takes then the outlines of this image on a sheet of paper.

PHOTOGRAPHY.

379. **Photography.**—*Photography* is the art of fixing the images of the camera obscura on substances *sensitive* to light. The various photographic processes may be classed under three heads : photography on metal, photography on paper, and photography on glass.

Wedgwood was the first to suggest the use of chloride of silver in fixing the image ; and Davy, by means of the solar microscope, obtained images of small objects on paper impregnated with chloride of silver ; but no method was known of preserving the images thus obtained, by preventing the further action of light. Niepce, in 1814, obtained permanent images of the camera by coating glass plates with a layer of a varnish composed of bitumen dissolved in oil of lavender. This process was tedious and inefficient, and it was not until 1839 that the problem was solved. In that year, Daguerre described a method of fixing the images of the camera, which, with the subsequent improvements of Talbot and Archer, has rendered the art of photography one of the most marvellous discoveries ever made, either as to the beauty and perfection of the results, or as to the celerity with which they are produced. Fig. 310 gives a vertical section of the kind of camera obscura used by

aphers. It consists of a rectangular wooden box in two ne of which, C, is fixed, and the other, B, can be drawn in ke a drawer. In the front of the box is a brass tube, A, in a condensing lens, L, which is fixed. In A is a second ich can be moved backwards or forwards by a rack and noved by the milled head, D. In this second tube is a ens, L′, which, by the motion of the tube, is brought nearer r from the lens, L. The combination of the two lenses hat is called an object glass with combined lenses. The ge of this arrangement is that it works more rapidly than t glass with a single lens, has a shorter focal distance, and nore readily focussed.

he face of the box opposite the object glass is a screen of



Fig. 310.

glass, E, which can be removed at will, and on which a re-mage of the object is formed. Thus, if a portrait is to be e person is placed at a distance of three or four yards from era, which is then adjusted until the image is formed in the osition on the glass. It is then placed in exact focus by pproaching or removing the lens, L′. The glass is con-n a frame which can be easily removed and replaced by containing the material on which the photograph is to be

photographs on metal, or *daguerreotype*, so called from Da-he inventor, are now seldom used. The photographic in glass and paper are infinitely varied, not as regards the art, but as concerns the substances employed, and there-egards the chemical reactions involved. We will content s with describing the ordinary method of taking a portrait r.

For this purpose what is called a *negative* must first be taken—an inverse image of the object, that is to say, in which the light parts are dark, and *vice versâ*. With this view a glass plate is coated with a thin layer of *collodion* (gun cotton dissolved in ether), containing a certain quantity of iodide of potassium. This plate thus coated is then placed in a solution of nitrate of silver. By the chemical reaction between the iodide of potassium and the nitrate of silver a coating of iodide of silver is formed on the plate, which is sensitive to light, and hence the operation must be performed in a dark room. The plate is then placed in the slide, and inserted in the camera instead of the focussing-glass. The slide is so constructed that the plate can be instantaneously exposed to or cut off from the action of light. After exposure for a suitable time the slide is removed to a dark room. No change is visible in the plate, but on pouring over it a solution called the *developer*, an image gradually appears. The principal substances used for developing are protosulphate of iron and pyrogallic acid. The action of light on iodide of silver produces some change, in virtue of which the developers have the property of reducing to the metallic state, those parts of the iodide of silver which have been most acted upon by the light. When the picture is sufficiently brought out, water is poured over the plate, in order to prevent the further action of the developer. The parts on which light has not acted are still covered with iodide of silver, which would also be affected if the plate were now exposed to the light. It is, accordingly, washed with solution of hyposulphite of sodium, which dissolves the iodide of silver and leaves the image unaltered. The picture is then coated with a thin layer of spirit-varnish, to protect it from mechanical injury.

When once the negative is obtained, it may be used for printing an indefinite number of positive pictures. For this purpose, paper is impregnated with chloride of silver, by immersing it first in a solution of chloride of sodium and then in one of nitrate of silver; chloride of silver is thus formed on the paper by double decomposition. The negative is placed on a sheet of this paper in a copying frame, and exposed to the action of light for a certain time. The chloride of silver becomes acted upon—the light parts of the negative being most affected, and the dark parts least so. A copy is thus obtained, on which the lights of the negative are replaced by shades, and conversely. In order to fix the picture, it is washed in a solution of hyposulphite of sodium, which dissolves the unaltered

of silver. The picture is afterwards immersed in a bath of of gold, which gives it tone.

Positives on glass.—Very beautiful positives are obtained uring the plates as in the preceding cases; the exposure in era, however, is not nearly so long as for the negaives.

Fig. 311.

ture is then developed by pouring over it a solution o f phate of iron, which produces a negative image; and by

afterwards pouring a solution of cyanide of potassium over the plate, this negative is rapidly converted into a positive. It is then washed and dried, and a coating of varnish poured over the picture.

381. **Diorama.**—The name *diorama* is derived from two Greek words which signify *viewed through*, and is applied to pictures painted on muslin or on calico, so as to represent two opposite effects like the polyorama, according as the pictures are seen by reflection or by transmission.

The picture is arranged vertically in a dark room as represented in fig. 311. The first effect, that painted on the front of the cloth, is illuminated by reflection : the second, that painted behind, is illuminated by transmission. With this view light enters through a window, M, in an upper story, and is sent to a screen, E, which reflects it towards the picture, and lights it from the front ; behind the picture is another window, N, which, when open, lights it behind. The shutters, NN, being closed, the spectators first see the subject on the front of the cloth. By a simple arrangement, a shutter, A, which slides without noise in two grooves, is made to advance, and when the picture is scarcely illuminated, by degrees the shutters, NN, are opened ; and then the picture painted on the other side of the cloth appears through it, and is substituted for the former one.

The diorama was invented by Daguerre, who had great skill in this kind of painting. The above figure represents the valley of Goldau before the terrible landslip, which took place on September 2, 1806. At the moment light was intercepted by the screen, lightning flashed, thunders roared, and there were all the effects of a violent storm. On the return of day, the rocks had given way, the lake had been partly filled up, and the chalet destroyed ; in short, the image of ruin and desolation was reproduced with astounding fidelity.

382. **Ghost scenes.**—We will give here a description of a curious optical effect, which was first introduced some years ago in the theatres, under the name of *ghost scenes.*

In order the more readily to understand the appearance of these spectres, let us recal an effect which everyone has observed. When towards evening on a railway we look at the windows of carriage doors, we see a pale and indistinct image of the travellers inside. This is an effect of reflection from the panes, which reflect the light that illuminates persons and objects placed in the compartment ; and the faint light of the images arises from the fact, that the panes

lowing great part of the light to be transmitted, send very little wards the observer. A similar effect is produced when in the ening, in a well-lighted street, a window front, which is little or

Fig. 312.

not at all lighted, is looked at. The observer sees his own image and that of the passengers on the other side of the panes. These effects are not seen in full daylight, for the images which tend to be reproduced are effaced by the brightness of the light.

These effects have been utilised in public to simulate the appearance of ghosts. Fig. 312 represents the arrangement of the apparatus intended for this use. On the floor of the stage, and not visible by the spectators, is an actor covered by a sheet, and intended to represent the ghost. Between the actor and the public is a dark lantern, in which is the lime light, which gives an extremely bright light. An assistant directs the light upon the actor, and the white cloth, thus powerfully illuminated, sends its rays towards an inclined sheet of glass, placed near the assistant. This glass, which is silvered, sends almost all the reflected light towards a second sheet, which is not silvered, on the stage itself. This latter plate acts like those in carriages and in shopwindows, which we have mentioned above, and being traversed by the greater part of the incident rays, sends but little light towards the spectator. Yet, as during this time, care is taken that the illumination in the room is very faint, the light is sufficient to give a cloudy image of the actor placed under the stage.

If another actor enters the scene the public see very distinctly through the glass, which is carefully concealed by hangings and decorations; and if this actor is behind the plate at the same distance as the image, he can join his action with that of the ghost, and produce a complete illusion.

The same effects are produced with a single plate, but as its obliquity tends to give inclined images, to rectify them, the actor under the theatre must hold himself so much inclined as to render his play very difficult. With the two sheets represented in the above figure, the actor retains his natural position.

VISION AND STEREOSCOPE.

383. **Structure of the eye and mechanism of vision.**—Although the description of the eye belongs to physiology rather than to physics, we may give an account of this organ, which is not merely a true optical instrument, but one of great perfection; it has, for instance, the remarkable property of adapting itself at once to see distinctly at all distances, which the best optical instruments could not do.

The eye is almost spherical in shape, and is surrounded by veral membranes, which fig. 313 represents open from back to ont. The front part of the eye is a perfectly transparent membrane, called the transparent cornea, and which is commonly called the *hite of the eye.* At a small distance behind the cornea, is a membranous diaphragm, *hi*, called the *iris*; it constitutes the variously loured disc which appears in the middle of the white of the eye, d to which is due the colour. In the centre of the iris is an erture called the *pupil*; in man this is circular, and in the cat rrow and elongated, and through it rays pass into the eye. Behd the iris, but very near it, is the *crystalline*, *o*, which is a transrent mass, having the shape and fulfilling the functions of a ıble convex lens. The whole of the back part, from the crystal- to the back of the eye, is filled with a gelatinous transparent



Fig. 313.

ss, like white of egg, which is called the *vitreous humour.* In nt of the eye, between the crystalline and the cornea, is a perly transparent liquid called the *aqueous humour.* The whole he back inside part of the eye is lined with a soft, whitish, transent membrane, R, called the *retina*; it is nothing more than the ension of a nerve, N, which proceeds to the brain, and transmits sensation of vision, whence it receives the name *optic nerve.* ıind the retina is a second membrane, C, called the *choroid*, ch is impregnated by a black matter, that absorbs all rays which uld not cooperate in producing vision. Lastly, a membrane, S, *sclerotica*, surrounds the whole eyeball behind, and joins the ısparent cornea in front.

These details being known, we may easily account for the meıism of vision; for the eye is nothing more than a small camera :ura (376), of which the pupil is the aperture, the crystalline is condensing lens, and the retina is the screen on which the

image is formed. Thence the optic nerve, carrying to the brain the impression produced by the vibrations of the ether on the nervous system of the retina, enables us to perceive external objects. In accordance with this explanation, we should see objects reversed, and not in their natural position. The inversion of images in the eye has greatly occupied both physicists and physiologists, and many theories have been proposed to explain how it is that we do not see inverted images of objects. Some have supposed that it is by custom, and by a regular education of the eye, that we see objects in their true position, that is to say, in their position relative to us. The visual impression becomes corrected by the impression of other senses, such as that of touch. Müller, Volkmann, and others contended that, as we see everything inverted, and not simply one object among others, nothing can appear inverted, because terms of comparison are wanting. It must, however, be admitted that none of these theories is quite satisfactory.

384. **Distance of distinct vision. Short and long sight.**—We know that in double convex lenses the distance of images from the lens increases or diminishes as the object is approached or receded (338). Hence, according to the distance of the objects looked at, it would seem that the image formed by the crystalline should be sometimes formed exactly on the retina, and sometimes a little in front of or behind this membrane. Only objects placed at a certain distance should then be seen distinctly; all those nearer or further should appear confused. This does not occur with a well-shaped eye, for it sees objects distinctly at very different distances; whence it is concluded, that the eye has the power of equally accommodating itself, so that the image is always formed exactly upon the retina.

Yet, though the eye can well distinguish objects at very different distances, there is in the case of each person a distance at which objects are more distinctly seen than at any other. This distance is called *the distance of distinct vision*; it varies with different persons, and often in different eyes in the same individual; for small objects like print it is usually about ten or twelve inches.

Those who can only see well at shorter distances have a defect in the shape of the eye; they are said to be *myoptic* or *short-sighted*, from two Greek words which signify close the eyes; for myoptic persons, in order to see more distinctly, do in fact involuntarily half close the eyes. If the distance of distinct vision is greater than ten or twelve inches, that is also due to a malformation of the eye, and

hose affected by it are called long-sighted or *presbyoptic*, from a Greek word which signifies *aged*, for this defect is usually met with n aged persons.

Myopy, or short-sight, results from too great a convexity of the cornea, or of the crystalline. The eye being too convergent, the rays of light are refracted in such a manner, that instead of forming their focus exactly on the retina, they form it a little in front, and therefore the image which this membrane perceives is confused. But if objects are approached to the eye, the image recedes, and is formed exactly on the retina, when the objects are sufficiently near, which explains why short-sighted persons only see objects when they are very close. They can also see more distinctly by contracting the pupil, or by looking through a small hole perforated in a card; for then, as the diameter of the luminous pencil which penetrates into the eye is less, the rays mainly penetrate the crystalline at the centre, and being therefore less affected by its excess of convexity, they form the focus at a greater distance. Myopy is mainly met with in young people; as they grow older, the convexity of the eye diminishes, so that their sight generally becomes better, when that of other people becomes worse.

Presbytism, or long-sight, is due to the flattening of the crystalline, as the eye is then no longer sufficiently convergent, the rays, instead of forming their focus on the retina, tend to form beyond it, whence it arises that the eye only observes a confused object. But as the objects recede, the image comes nearer the crystalline, and is ultimately formed exactly on the crystalline, when objects are sufficiently distant; which explains why long-sighted persons only see objects when they are distant.

Short-sight is remedied by the use of concave or diverging lenses before the eyes; as the pencil is spread out before entering the eye, by the action of these glasses, the focus of the crystalline is receded as far as the retina, provided the degree of divergence of the glasses is suitably adapted to the excess of convexity of the crystalline. For far-sight, on the contrary, condensing or convex lenses should be used, so as to correct the want of convexity of the crystalline. As the rays then become more convergent before entering the eye, the image, which would otherwise be formed beyond the retina, approaches it, and is ultimately formed exactly upon it.

For a long time double concave lenses were exclusively used for short-sight, and double convex for far-sight. We may mention,

however, the concavo-convex lenses represented in O, in fig. 262 for long sight, and those in R (fig. 263) for short sight. These are called *periscopic glasses*, from two words meaning *to see round*; for, as their shape better enables them to embrace the eyeball, they facilitate vision in all directions; and, as they do not deform objects, they do not fatigue the eye like other glasses.

385. **Binocular vision.**—Although we have two eyes, and when we fix them on the same object, each forms its own image upon the retina, yet we only see one object, just as with two ears we only hear one sound. Various hypotheses have been made to account for single vision with two eyes. Some have considered it as an effect of habit; others assigning to it a physiological cause, have assumed that two points similarly placed on the two retinas correspond to the same nervous filament which, coming from the brain, bifurcates towards each eye. Hence the two impressions simultaneously produced on the two retinas result in a single sensation.

Not only does simultaneous vision with two eyes enable us to see bodies with greater lustre, but it gives us the impression of relief, as the stereoscope well shows.

386. **Stereoscope.**—The *stereoscope*, so called from two Greek



Fig. 314.



Fig. 315.

words which mean *perception of solidity*, is an ingenious instrument, which was invented by Sir C. Wheatstone, and modified to its present form by Sir D. Brewster.

To understand the effect of the stereoscope, let us observe that when we look at an object with two eyes, each eye does not see it under exactly the same aspect, but under a slightly different perspective. Thus let a small object, such as a dice, be successively viewed with one eye, at a slight distance, without moving the head. If the cube be just in front of the observer, looking at it with his left eye, he will see this face, and a small portion of the left side, the other being concealed (fig. 314); if, on the contrary, he views it with his right eye, he sees the front and a portion of the right side,

the other being hidden (fig. 315). Thus the two images formed on the retina are not quite identical, for each corresponds to a different point of view. It is this difference in the images which gives us the sensation of relief in bodies, and enables us to appreciate their shape and their distance.



Fig. 316.

This may be confirmed by making two drawings of the same object, taken respectively with the perspective belonging to the right and to the left eye; then, as each eye looks separately at the drawing through prisms or lenses, which makes the two drawings coincide, by giving the rays of light the same direction as if they converged from a single object, the impressions produced upon each retina will be the same as if the object itself were viewed. The illusion is in fact so complete, that, however prejudiced we may be, it is impossible not to be deceived, so true are the effects of relief and perspective.

Fig. 317.

This is the principle of the stereoscope. Fig. 316 shows the path of the rays of light in the instrument. At A is the drawing of the object seen with the left eye; at B that of the same object seen with the right. The rays from these images fall on two lenses *m* and *n*, and take, after having traversed them, the same direction as if they came from the point C; the object represented at A and B appears in relief at this spot.

The lenses *m* and *n* must impart exactly the same deviation to the rays, and they should therefore be exactly identical. Brewster



Fig. 318.

attained this result by cutting in two halves a double convex lens, and placing the right half in front of the left eye, and the left half in front of the right eye, as shown in fig. 316.

To produce the sensation of relief, the two dissimilar images at A and B should give from two different points of view so faithful a representation of the same object, that these separate views cannot be taken by the hand. And it is only practicable by means of photography. Fig. 317 represents two photographs of a statuette

of Franklin, taken at a slightly different angle. That of the left represents more of the full face, and must be looked at with the left eye; the other one is more in profile, and must be viewed with the right eye. These two views being placed in the stereoscope disappear for each observer, for then the two sensations special to each eye coalesce, and form a single image as represented in fig. 318, and the original appears so solid, with such perfect relief, that the imagination can with difficulty realise the fact that we are only concerned with a drawing on a plane surface.

BOOK VII.

ON MAGNETISM.

CHAPTER I.

PROPERTIES OF MAGNETS.

387. **Natural and artificial magnets.**—Natural magnet, or *loadstone*, is a mineral which has the property of attracting iron and a few other metals, especially nickel and cobalt. This mineral is an oxide of iron, that is, a compound of iron and oxygen like rust, from which it only differs chemically in containing rather less oxygen.

Loadstone has another property, which is not less remarkable, namely, that when it is balanced on a pivot, or suspended to a thread, it points towards a certain direction of the horizon; and by this property this mysterious stone, which is of a dull brown colour, and has no lustre, deserves a place above the most valuable precious stones, for, like a new Ariadne's thread, it guides mariners in darkness, and enables them to steer with the same certainty on sea as on a travelled road.

This loadstone, or magnetic stone, was known to the ancients, who called it Lydian stone, or stone Magnesia; for it was first found near a village of this name in Lydia. And from the town of Magnesia the Greeks derived the name *magnes*, from which is derived the word magnetism, under which name philosophers understand the whole of the properties which magnets possess. Magnetic iron ore is very abundant in nature; it is met with in the older geological formations, especially in Sweden and Norway, where it is worked as an iron ore, and furnishes the best quality of iron.

Besides natural there are also *artificial* magnets, so-called from their being produced by art. They are usually made of steel. When steel is *tempered*, that is, when it is raised to a high temperature, and suddenly cooled by being immersed in cold water,

quires great hardness ; and it is in virtue of this property that ecomes so valuable for cutting instruments. Steel has not rally the power of attracting iron ; but when it is tempered made hard this property may be imparted to it by rubbing it a powerful magnet ; and it then becomes itself a magnet.

Artificial magnets have just the same properties as natural ones ; are far more powerful and convenient ; they are, accordingly, erally used in experiments. They are sometimes made into

Fig. 319.

a foot or two long, like that represented in fig. 319 ; some- s in a horseshoe form (fig. 329) ; or lastly, if they are to be able, they are cut out of a thin sheet in the shape of a lozenge as n in fig. 321. A small agate cup is let into the centre in such nner that the needle can rest on a vertical pivot and oscillate y in a vertical plane. Thus arranged, the artificial magnet mes a *magnetic needle.*

388. **Distribution of magnetic force in magnets.**—The force with which a magnet attracts iron is not everywhere the same. The greatest attraction is at the ends; it decreases rapidly from there towards the middle, where there is no attraction. For, if a magnetised bar is immersed in iron filings, when it is withdrawn the filings are seen to adhere to the end in long and compact filaments (fig. 319), but not a particle adheres to the middle.

The two points near the ends where the attraction is most powerful are called the *poles* of the magnet, and the medial part, where there is no attraction, is called the *neutral line*. All magnets, natural or artificial, have each two poles and a neutral line. Some-

Fig. 320.

times, besides the two principal poles, there are observed intermediate poles, which are called *consequent poles*. This arises from some inequality in the temper of the steel, or in the manner in which the bar has been magnetised. We shall always assume that magnets have only two poles.

The action of magnets upon iron is exerted through all bodies which are not magnetic. Thus, a magnet being placed on a table and a piece of cardboard rested upon it, iron filings are allowed to fall through a sieve (fig. 320). As the filings fall, acted upon by the two poles, they become arranged in long filaments, which group themselves along curved lines from one pole to the other; but over the middle of the magnet no action is observed, and the filings are arranged as they would be upon any other substance.

9. **Laws of magnetic attraction and repulsion.**—When
vo poles of a magnet are compared as to the action they exert
iron, they seem to be completely identical; this identity is,
ver, only apparent: for, if to the same pole of a magnetic
e (fig. 321) the two poles of a bar magnet held in the hand be
ssively presented, the curious phenomenon is observed that,
pole *a* of the needle is attracted by pole B of the bar, it is
e contrary, repelled by the other pole of the latter; which



Fig. 321.

s that the poles of the bar are not exactly identical, for one
s the pole *a*, while the other attracts it. The same difference
be ascertained to exist between the two poles of the needle
for if the same pole, B, of the bar be successively presented
e two ends of the movable needle, in one case there is re-
on, in the other attraction.

Ve shall presently see that a freely suspended magnet always
with one pole pointing to the north, and the other towards the
ı. The end *pointing towards the north* is called in this country
orth pole, and the other end is the *south pole*. The end of
nagnetic needle pointing to the north is sometimes called the
ed end of the needle.

'ence, in reference to magnetic attractions and repulsions the
ving law may be enunciated:

Poles of the same name repel, and poles of contrary name attract one another.

The opposite actions of the north and south poles may be shown by the following experiment :—A piece of iron, a key for example, is supported by a magnetised bar (fig. 322). A second magnetised bar of the same dimensions is then moved along the first, so that their poles are contrary. The key remains suspended so long as the two poles are at some distance, but when they are sufficiently near, the key drops just as if the bar which supported it had lost its magnetism. This, however, is not the case, for the key would be again supported if the first magnet were presented to it after the removal of the second bar.



Fig. 322.

The attraction which a magnet exerts upon iron is reciprocal, as is easily verified by presenting a mass of iron to a movable magnet, when the latter is attracted.

390. **Hypothesis of two magnetic fluids.**—In order to explain the phenomena of magnetism, the existence of two hypothetical *magnetic fluids* has been assumed, each of which acts repulsively on itself, but attracts the other fluid. The fluid whose resultant effects predominate at the north pole of the magnet is called the *north* or *boreal* fluid, and that at the south pole, the *south* or *austral* fluid. Sometimes the terms *positive* and *negative* are employed, corresponding to the north and south fluids.

It is assumed that, before magnetisation, these fluids are combined round each molecule, and mutually neutralise each other; they can be separated by the influence of a force greater than that of their mutual attraction, and can arrange themselves in a certain definite position about the molecules to which they are attached, but cannot be removed from them.

The hypothesis of the two fluids is convenient in explaining magnetic phenomena, and will be adhered to in what follows. But it must not be regarded as anything more than an hypothesis, and it

wards be shown that magnetic phenomena can also be ex-
by assuming that they result from electrical currents,
ıg in magnetic bodies.

Influence of magnets upon magnetic substances.—Mag-
ıstances are substances containing the two magnetic fluids,
ıe neutral state, that is to say, holding each other in check
reciprocal action : such substances are iron, steel, nickel,
alt. Magnets also contain the two fluids, but there is
them and magnetic substances this difference : that in
the two fluids present in each molecule are separated, and
duces a separate effect ; while in magnetic substances the
ɜ combined and produce no effect.

ıgnetic substance is readily distinguished from a magnet.
ner has no poles ; if successively presented to the two ends
netic needle, *ab* (fig. 322), it will attract both ends equally,
ıe end of a magnet would attract the one, but repel the
d of the needle. Magnetic substances also have no action
other, while magnets attract or repel, according as unlike
oles are presented to each other.

n a magnetic substance is placed in contact with the poles
agnet, the north
r instance, this
ttractively on the
uid of the sub-
ınd repelling the
iid, it follows that
ıody a separation
o fluids is effected,
her words, a true
s produced. For,
iece of soft iron,
ring, for example,



Fig. 323.

ınted to a magnetised bar, not merely is this ring supported,
cquires the property of supporting the second ; then this
ı third, and so forth. Remove the bar, and the invisible link
nites this marvellous chain is broken, and the rings separate.

action in virtue of which a magnet can develope magnetism
is called *magnetic induction* or *influence*, and it can take
thout actual contact between the magnet and the iron, as
in the following experiment. A bar of soft iron is held with
l near a magnetic needle. If now the north pole of a
be approached to the other end of the iron bar without

touching it, the needle will be attracted or repelled, according as its south or north pole is near the bar. For the north pole of the magnet will develope south magnetism in the end of the bar nearest it, and, therefore, north magnetism at the other end, which would thus attract the south, but repel the north end of the needle. Obviously, if the other end of the magnet were brought near the iron, the opposite effects would be produced on the needle.

Magnetic induction explains the formation of the tufts of iron filings which become attached to the poles of magnets. The parts in contact with the magnet are converted into magnets; these act inductively on the adjacent parts, these again on the following ones, and so on, producing a filamentary arrangement of the filings.

392. **Coercive force.**—We have seen from the above experiments, that soft iron becomes instantaneously magnetised under the influence of a magnet, but that this magnetism is not permanent, and ceases when the magnet is removed. Steel likewise becomes magnetised by contact with a magnet, but the operation is effected with difficulty, and the more so as the steel is more highly tempered. Placed in contact with a magnet, a steel bar acquires magnetic properties very slowly, and, to make the magnetism complete, the steel must be rubbed with one of the poles. But this magnetism, once evoked in steel, is permanent, and does not disappear when the inducing force is removed.

These different effects in soft iron and steel are ascribed to a *coercive force*, which, in a magnetic substance, offers a resistance to the separation of the two fluids, but which also prevents their recombination when once separated. In steel this coercive force is very great, in soft iron it is very small or even quite absent. By oxidation, pressure, or torsion, a certain amount of coercive force may be imparted to soft iron, as will be explained under Magnetisation.

CHAPTER II.

TERRESTRIAL MAGNETISM. COMPASSES.

393. **Directive action of the earth on magnets.**—The power of attracting iron filings is not the only one which magnets present; they have also that of setting in a certain definite direction, when they can turn freely in a horizontal direction. Thus, when a

sed needle is placed on a pivot on which it can move freely), it ultimately sets in a position which is more or less north th. If removed from this position, it always returns to it ertain number of oscillations.

ıstead of placing the needle on a pivot, it be placed on a ıd this in turn be floated on water, the needle will after a illations come into a which is the same as had on the pivot, that y due north and south. ıportant in this second ent to observe, that the only sets in a certain ı, and that, though free e either a progressive trograde motion, it re- ı the middle of the vessel, ves neither towards the ıor the south; hence e which acts upon the s simply *directive*, and ıctive.



Fig. 324.

ogous observations have ıde in different parts of the globe, from which the earth ı compared to an immense magnet, whose poles are very terrestrial poles, and whose neutral line virtually coincides equator.

polarity in the northern hemisphere is called the *northern l* polarity, and that in the southern hemisphere the *southern al* polarity. In French works the end of the needle point- h is called the *austral* or *southern* pole, and that pointing ɔuth the *boreal* or *northern* pole; a designation based on othesis of a terrestrial magnet, and on the law that unlike sms attract each other. In practice it will be found more ent to use the English names, and call that end of the which points to the north the north pole, and that which ɔ the south the south pole.

Magnetic meridian. Declination.—When a magnetic ɔoints towards the north, if we conceive an infinitely long line passing through its two poles, this line is what is ıe *magnetic meridian* of the place. The direction of this

line does not in general coincide with the geographical meridian of the place, which is the imaginary plane which passes through this place and through the earth's poles. The angle which the direction of the magnetic needle makes with the geographical meridian is called the *declination* of the place. In other words, as the magnet needle does not exactly point to the earth's north, the declination is the difference between this direction and the true north. Sometimes the north pole of the needle is to the west of the meridian, and sometimes it is to the east. In the former case the declination is said to be *easterly*, and in the latter case *westerly*.

The declination of the magnetic needle, which varies in different places, is at present west in Europe and in Africa, but east in Asia and in North and South America. It shows further considerable variations even in one and the same place.

Thus, at London the needle showed in 1580 an east declination of 11° 36′; in 1663 it was at zero; from that time it gradually tended towards the west, and reaching its maximum declination of 24° 41′ in 1818; since then it has steadily diminished; it was 22° 30′ in 1850, and is now (1875) 19° 16′ W.

At Yarmouth and Dover the variation is about 40′ less than at London; at Hull and Southampton about 20′ greater; at Newcastle and Swansea about 1° 15′, and at Liverpool 1° 30′, at Edinburgh 2° 5′, and at Glasgow and Dublin about 2° 25′, greater than at London.

Besides these variations, which are called *secular variations*, the declination of the magnetic needle undergoes accidental variations, known as *perturbations* or *magnetic storms*; these are manifested during the occurrence of thunder storms, of volcanic eruptions, and during the appearance of aurora borealis. The effect of the aurora is felt at great distances. Auroras which are only visible in the north of Europe act on the needle even in these latitudes. In polar regions the needle frequently oscillates several degrees; its irregularity on the day before the aurora borealis is a presage of the occurrence of this phenomenon.

395. **Mariner's compass.**—The magnetic action of the earth has received a most important application in the *mariner's compass*. This is a declination compass used in guiding the course of a ship. Fig. 325 represents it in about half its ordinary size. At the bottom of a wood or metal box is drawn a star or *rose*, with sixteen branches, representing the points of the compass. On the contour

the box is a graduated circle, the zero of which is on the line S, which marks the direction from north to south. In the centre the box, finally, is a steel pivot, on which rests a very mobile agnetic needle.

When the geographical meridian is known, the declination is sily determined by means of the compass. It need only be ned until the line NS is exactly in the direction of the geographical eridian of the place. The point at which the needle stops marks e declination. If, on the contrary, the declination is known, and

Fig. 325.

e geographical meridian is desired, the compass is turned until the edle deviates from the line NS by a quantity equal to the decli- ation, and in the same direction, that is to say, to the east if e declination is easterly, and to the west if it is westerly; the e NS prolonged represents the direction of the geographical eridian.

Neither the inventor of the compass, nor the exact time of its ention, is known. Guyot de Provins, a French poet of the elfth century, first mentions the use of the magnet in navigation, ugh it is probable that the Chinese long before this had used

The ancient navigators, who were unacquainted with the com-

pass, had only the sun or pole-star as a guide, and were accordingly compelled to keep constantly in sight of land, for fear of steering in a wrong direction when the sky was clouded. But guided by the indications of the compass, which are disturbed neither by darkness nor by the most violent tempests, they can pursue their true route by night as well as by day.

The compass is also used by miners to direct them in the excavation of subterranean passages.

396. **Inclination compass.**—When a steel needle supported on a vertical pivot, as represented in fig. 324, has been so accurately balanced that it is quite horizontal *before magnetisation*, it is observed that when it is magnetised it ceases to retain its horizontal position, and the north pole dips downward. When this phenomenon was first observed, it was ascribed to a defect of construction, but the regularity with which it occurred proved that it must be ascribed to the directive action of the earth.



Fig. 326.

In order to observe this phenomenon, the mode of suspension is modified, and it is fixed to a horizontal axis, so that it can move in a vertical plane, as represented in fig. 326. The angle it forms is read off on the divided circle.

Thus arranged, the apparatus is called the *declination compass*, or *dipping needle*, and the angle which the needle makes with the horizon is called the *magnetic inclination* or *dip*.

The value of the dip, like that of the declination, differs in different localities. It is greatest in the polar regions, and decreases with the latitude towards the equator, where there is a series of points at which it is zero; that is, at which the needle is horizontal. The line joining these parts is called the terrestrial *magnetic equator*. In Greenwich at the present time (1875) the dip is 67° 42′, reckoning from the horizontal line. In the southern hemisphere the inclination is again seen, but in a contrary direction; that is, the south pole of the needle dips below the horizontal line.

The terrestrial *magnetic poles* are those places in which the dipping needle stands vertical; that is, where the inclination is 90°. In 1830 the first of these, the terrestrial north pole, was found by Sir James Ross, in 96° 43′ west longitude and 70° north latitude. The same observer found in the South Sea, in 76° south latitude and 168° east longitude, that the inclination was 88° 37′. From this and other observations, it has been calculated that the position of the magnetic south pole was at that time in about 154° east longitude and 75½° south latitude.

Lines connecting places in which the dipping needle makes equal angles are called *isoclinic lines.*

The inclination is subject to secular variations, like the declination. At Paris, in 1671, the inclination was 75°; since then it has been continually decreasing and in 1859 was 66° 14′. In London also the dip has continually diminished since 1720 by about 2·6′ per annum. In 1821 it was 70° 3′; in 1838, 69° 17′; in 1854 it was 68° 31′; in 1859 it was 68° 21′; it is now 67° 42′. It is also subject to slight annual and diurnal variations; being, according to Hansteen, about 15′ greater in summer than in winter, and 4′ or 5′ greater before noon than after.

CHAPTER III.

METHODS OF MAGNETISATION.

397. **Magnetisation by the influence of the earth.**—To *magnetise a substance* is to impart to it the magnetic properties of attracting particles of iron, and of turning towards the north. Magnetisation can be produced slowly by the influence of the earth, or more rapidly by rubbing with a magnet; or by means of electricity, in which case the magnetisation is almost instantaneous.

The magnetic action of the globe is powerful enough to act as a source of magnetisation. This may be illustrated by taking a tolerably thick iron wire, and placing it in the magnetic meridian, so that it makes an angle equal to the angle of dip. In this position the earth's magnetism, acting by induction on the iron wire, decomposes the two fluids, and converts the lower end into a north pole, and the upper into a south pole. Yet this magnetisa-

tion is very unstable, for if the wire be turned upside down, the poles are inverted, for pure soft iron is destitute of coercive force. But, if while the bar is in the above position, it be hammered, or twisted, the pressure or the twisting imparts to it a certain amount of coercive force, and it retains for some time the magnetisation evoked thus. If several wires thus magnetised are united so that poles of the same name are together, a tolerably powerful magnet is obtained.

It is this magnetising action of the earth which developes the magnetism frequently observed in steel and iron instruments, such as fire-irons, railings, lightning conductors, lamp posts, etc., which remain for some time in a more or less inclined position. They

Fig. 327.

become magnetised with the north pole downward, just as if placed over the pole of a powerful magnet. The magnetism of native black oxide of iron has doubtless been produced by the same causes; the very different magnetic power of different specimens being partly attributable to the different positions of the veins of ore with regard to the line of dip. The ordinary irons of commerce are not quite pure, and possess a feeble coercive force; hence a feeble magnetic polarity is generally found to be possessed by the tools in a smith's shop. Cast-iron, too, has usually a great coercive force, and can be permanently magnetised.

The turnings, too, of wrought iron and of steel produced by the powerful lathes of our ironworks are found to be magnetised.

lagnetisation by magnets. In magnetising bar magnets, and ially magnetic needles, the method generally adopted is b them with powerful magnets. This principle is applied e methods of what are called *single*, *separate*, and *double* .

he method of single touch consists in moving the pole of a rful magnet from one end to the other of the bar to be mag- ed, and repeating this operation several times, always in the direction. The neutral fluid is thus gradually decomposed ghout all the length of the bar, and that end of the bar which

Fig. 328.

ouched last by the magnet is of opposite polarity to the end e magnet by which it has been touched. This method only uces a feeble magnetic power, and is, accordingly, only used nall magnets. It has further the disadvantage of frequently oping consequent points.

the method of separate touch the steel bar is rubbed sepa- r with the contrary poles of two magnets, proceeding in opposite tions from the centre towards the ends.

lagnetisation by double touch. In this method the two magnets laced with their poles opposite each other in the middle of the be magnetised. But, instead of moving them in opposite

directions towards the two ends, as in the method of separate touch, they are kept at a fixed distance by means of a piece of wood placed between them (fig. 328), and are simultaneously moved first towards one end, then from this to the other end, repeating this operation several times, and finishing in the middle, taking care that each half of the bar receives the same number of frictions.



Fig. 329.

Magnetisation by means of electrical currents (476) is the most powerful means of imparting magnetism, and is the one generally used for large magnets, whether bar or horse-shoe.

398. **Magnetic batteries. Armatures.**—Magnetic *battery*, or *magazine*, is the name given to a system of bars joined with their similar poles together. Sometimes the bars are straight, as represented in figs. 327 and 328, and sometimes they are curved, as in fig. 329, which represents a horse-shoe battery.

Magnets, whether natural or artificial, would soon lose their power if they were left to themselves, and they must therefore be provided with *armatures*. These names are given to pieces of soft iron which are placed in contact with the poles, such as the piece, *ab*, in fig. 329. The two poles of the magnet acting inductively on this piece produce in it at *a* a north pole, and at *b* a south pole, and these two poles thus produced react in turn upon the magnetised bar, and by preventing the recomposition of its two fluids cause it to retain its force. The piece, *ab*, is also called the *keeper*; to it is suspended the weights which the magnet is intended to support.

BOOK VIII.

FRICTIONAL ELECTRICITY.

CHAPTER I.

FUNDAMENTAL PRINCIPLES.

Electricity. Its nature.—Electricity is a powerful physi-
it which manifests itself mainly by attractions and repulsions,
) by luminous and heating effects, by violent shocks, by che-
ecompositions, and many other phenomena. Unlike gravity,
: inherent in bodies, but is evoked in them by a variety of
among which are friction, pressure, chemical action, heat,
gnetism.

les, one of the Greek sages, 600 B.C., knew that when amber
bbed with silk it acquired the property of attracting light
such as feathers, pieces of straw, etc., and from the Greek
this word (ηλεκτρον, *electron*) the term *electricity* has been
. Six centuries after it was found, Pliny, the celebrated
naturalist, writes, 'When the friction of the fingers has im-
to it heat and life, it attracts pieces of straw as a magnet
particles of iron.' This is nearly all the knowledge left by
ients; and it was not until towards the end of the sixteenth
that Dr. Gilbert, physician to Queen Elizabeth, called
n to this property of amber, but showed also that it was not
to amber, but that other bodies, such as sulphur, wax, glass,
o acquired the property of attracting light bodies when they
bed or struck with flannel or with catskin.

repeat this experiment, a glass rod, or a stick of sealing wax,
ac, is held in the hand, and rubbed with a piece of flannel,
the skin of a cat; it is then found that the parts rubbed have
perty of attracting light bodies, such as pieces of silk, wool,

feathers, paper, bran, gold leaf, etc., which, after remaining a sh time in contact, are again repelled. Not only have the substan thus rubbed the property of attracting light particles, but they also come luminous in the dark; they give sparks, and present a numbe

Fig. 330.

phenomena, the cau of which is describ under the general te *electricity*, the deri tion of which h already been given.

However slow th progress of the scien of electricity in ancie times and in th middle ages, its pr gress during the eigh teenth and nineteent centuries has been extremely rapid. In the last seventy or eight years, more especially, the new facts discovered have been s numerous and remarkable, their applications so curious and impo tant, that electricity has been compared to a kind of fairy, of whos it was only necessary to ask miracles, to have them realised.

400. **Sources of electricity.**—The causes which develope elec tricity are numerous; they may be divided into mechanical, physica and chemical sources.

The *mechanical sources* are friction, pressure, and cleavage. Thus when a piece of sugar is broken in the dark, a feeble luminosity i seen, due to the electricity liberated. Cleavage is also a source o electricity; if a plate of mica be rapidly split in the dark, a sligh phosphorescence is perceived.

The *physical sources* are variations in temperature: these effect are observed in some minerals, and more especially in tourmalin which exhibits electrical properties when either heated or cooled.

Lastly, the *chemical sources* are the combinations and the de compositions of bodies. Thus, the metals, like zinc, iron, coppe when placed in an acid, unite with this to form salts. Now durin these combinations considerable quantities of electricity are dev loped; the same is the case with chemical decomposition; that i when compound bodies are separated into their elements.

The most powerful sources of electricity are friction and chem cal action. We shall first of all investigate the influence of the firs

ise; and shall subsequently investigate the latter under the me of VOLTAIC ELECTRICITY.

401. **Electroscopes. Electrical pendulum.**—In order to ascertain whether bodies are electrified or not, instruments called *electroscopes* are used. The simplest of these, the *electric pendulum* fig. 331), consists of a small pith ball attached by means of a silk thread to a brass rod resting on a glass support. To ascertain whether a body is electrified or not, it need only be presented to an electrical pendulum; in the first case there is attraction, while in the second case there is not. Yet the electrical pendulum would not be affected by a body very feebly charged with electricity.



Fig. 331.



Fig. 332.

lore complicated and more delicate apparatus must then be had ecourse to, which will afterwards be described (415, 430).

402. **Distinction of the two kinds of electricity.**—If electricity be developed on a glass rod by friction with silk, and the rod e brought near an electrical pendulum (fig. 331), the ball will be attracted to the glass, and after momentary contact will be again epelled. By this contact the ball becomes electrified, and so long s the two bodies retain their electricity, repulsion follows when ey are brought near each other. If a stick of sealing wax, electrified by friction with flannel or skin, be approached to another ectrical pendulum, the same effects will be produced, the ball will

fly towards the wax, and after contact will be repelled. Two bodies which have been charged with the same electricity, repel one another. But the electricities, respectively developed in the preceding cases are not the same. If, after the pith ball has been touched with an electrified glass rod, an electrified stick of sealing wax, and then an electrified glass rod, be alternately approached to it. the pith ball will be *attracted* by the former and *repelled* by the latter. Similarly, if the pendulum be charged by contact with electrified sealing wax, it will be *repelled* when this is approached to it, but *attracted* by the approach of the electrically excited glass rod.

On experiments of this nature, Dufay first made the observation that there are two different electricities: the one developed by the friction of glass, the other by the friction of resin or shellac. To the first the name *vitreous* electricity is given; to the second the name *resinous* electricity.

403. **Hypothesis of two electrical fluids.**—Notwithstanding the great importance and interest of the numerous electrical phenomena we are still ignorant of their real cause. Various hypotheses have been made to account for them. The most convenient, perhaps, is that which was propounded by Symmer, an English physicist.

Symmer's theory assumes that every body contains an indefinite quantity of a subtile imponderable matter, which is called the *electrical fluid.* This fluid is formed by the union of two fluids—the *positive* and the *negative.* When they are combined they neutralise one another, and the body is then in the natural or neutral state. By friction, by chemical action, and by several other means, this neutral fluid may be decomposed and the two fluids separated, but one of them can never be excited without a simultaneous production of the other. There may, however, be a greater or less excess of the one or the other in any body, and it is then said to be electrified *positively* or *negatively.* The two fluids were formerly called *vitreous* and *resinous*, but these have given place to the terms *positive* and *negative* fluids, to which they respectively correspond, and which were first used by Franklin. This distinction is merely conventional; it is adopted for the sake of convenience, and there is no other reason why resinous electricity should not be called positive electricity.

Fluids of the same name repel one another, and fluids of opposite kinds attract each other. The fluids can circulate freely on the surface of certain bodies, which are called *conductors*, but remain

fined to certain parts of others, which are called *nonconductors* 6).

As has been already said, this theory is quite hypothetical; but general adoption is justified by the convenient explanation which gives of electrical phenomena.

404. **Laws of electrical attraction and repulsion.**—Adopting is two-fluid theory, the qualitative and quantitative laws of ectrical attraction and repulsion may be stated as follows:

I. *Two bodies charged with the same electricity repel each other; o bodies charged with opposite electricities attract each other.*

II. *The repulsions or attractions between two electrified bodies e in the inverse ratio of the square of their distances.* That is to y, that if two bodies be charged to a certain extent with elec- icity, and the distance between them be increased to twice or thrice ie original amount, the attraction or repulsion will be one-fourth one-ninth the original amount.

III. *The distance remaining the same, the force of attraction or pulsion between two electrified bodies is directly as the product of e quantities of electricity, with which they are charged.* Thus if ie quantity of electricity with which a body is charged be twice or irice its original amount, it will have twice or three times the ttractive or repulsive force.

These attractions and repulsions take place in virtue of the action hich the two electricities exert on themselves, and not in virtue of eir action on the particles of matter.

The first of these laws follows from the experiment described bove (402); the second or third were first stated by Coulomb, nd may be demonstrated by an apparatus which he devised, which known as *Coulomb's balance.*

405. **Coulomb's balance.**—Represented in fig. 333, this appa- atus consists of a cylindrical glass case closed at the top by a late of the same material. In this is an aperture on which is glass support, *d*. This is not rigidly fixed but can be turned ound. At the top of this tube is a brass cap, consisting of two ieces, one *b*, which is rigidly fixed to the tube, *d*, and the other ting in the first like a socket, so that it can be turned by the itton, *t*. On *k* is a scale *c*, graduated in 360 degrees, and turning th it; *b* is provided with a fixed index, *a*, which shows by how any degrees the disc is turned.

To the disc is fixed a very fine silver wire, to which is suspended shellac thread, *p*, terminated at one end by a small disc of thin

metal foil, *n*. In the cover, A, near the edge, is a second aperture through which can be passed a glass rod, *i*, with a wooden handle *r*, at one end, and terminating in a brass ball, *m*. A scale of 360 degrees is fixed on the cage, opposite the zero of which is the ball, *m*.

In experimenting with this apparatus the air is dried by placing in the cage some chloride of calcium, which is a highly hygroscopic substance. To establish the second law, that electrical attractions vary inversely as the square of the distance, the disc, *e*, is first turned until its zero corresponds to the mark, *a*; the tube, *d*, and



Fig. 333.



Fig. 334.

the whole cap, *k*, is slowly turned, until the silver thread being destitute of torsion, and the needle, *p*, at rest, the latter corresponds to the zero of the graduated circle : the knob, *m*, is in the same position, and thus presses against *n*. The knob, *m*, is then removed and electrified, and replaced in the apparatus, through the aperture, *r*. As soon as the electrified knob, *m*, touches *n*, the latter becomes electrified, and is repelled, and after a few oscillations comes to rest, at ten degrees for instance ; the resistance of the wire to further torsion then just balances the force of repulsion.

the arc of ten degrees is virtually the same as its chord, the nber ten may be regarded as representing the distance of *m* and

If the cap, *e*, is turned from left to right in the figure, it is found at, to reduce the distance to five degrees, it must be turned through irty-five degrees. The wire is thus twisted through thirty-five grees at the top and through five at the bottom ; its total rsion is forty degrees, that is to say, four times as much as it as at first. Hence at the distance five the repulsion is four nes as great as at the distance ten ; for it is a known law, that e angle of torsion is proportional to the force of torsion. It may shown in the same manner that, to make the distance from *m* to one-third what it was, the total torsion must be ninety degrees, at is, nine times as great ; the second law is thus thereby proved.

order to prove that attractions and repulsions between electrified dies are proportional to the quantities of electricity which each them possesses, the ball, *m*, is again electrified and placed in the ge ; after contact it repels the disc, *n*, through a distance of, let us , twelve degrees. The ball, *m*, is now withdrawn and placed in ntact with a second brass ball of the same diameter, but insulated d unelectrified. As the electricity is equally distributed over th balls, the ball, *n*, loses half its electricity, and on again placing in the cage, the repulsion which was twelve degrees is now only , which verifies the third law.

406. **Conductors and nonconductors.**—When a glass rod, bbed at one end, is brought near an electroscope, that part only ill be electrified which has been rubbed ; the other end will pro- ce neither attraction nor repulsion. The same is the case with rod of shellac or of sealing wax. In these bodies electricity does ot pass from one part to the other—they do not *conduct* electricity. xperiment shows, that when a metal has received electricity in ny of its parts, the electricity instantly spreads throughout its ntire surface. Metals are hence said to be good *conductors* of lectricity.

Bodies have, accordingly, been divided into *conductors* and *non- nductors*. This distinction is not absolute, and we may advan- geously consider all bodies as offering a *resistance* to the passage electricity which varies with the nature of the substance. Those dies which offer little resistance are then conductors, and those ich offer great resistance are nonconductors or *insulators* : elec- cal *conductivity* is thus the inverse of electrical *resistance*. We to consider that between conductors and nonconductors there

is a *quantitative* and not a *qualitative* difference; there is no conductor so good but that it offers some resistance to the passage of electricity, nor is there any substance which insulates so completely but that it allows some electricity to pass. The transition from conductors to nonconductors is gradual, and no sharp line of demarcation can be drawn between them.

In this sense we are to understand the following table in which bodies are classed as *conductors*, *semiconductors*, and *nonconductors*; those bodies being conveniently designated as conductors which, when applied to an electroscope charged with either kind of electricity discharge it almost instantaneously; semiconductors being those which discharge it in a short but measurable time, a few seconds, for instance; while nonconductors effect no discharge even, in the course of a minute.

Conductors.	*Semiconductors.*	*Nonconductors.*
Metals.	Alcohol and ether.	Dry oxides.
Graphite.	Powdered glass.	Air and dry gases.
Acids.	Dry wood.	Dry paper.
Water.		Silk.
Snow.		Diamond and precious stones.
Vegetables.		Caoutchouc.
Animals.		Glass.
		Sulphur.
		Resins.

407. **Insulating bodies. Common reservoir. Electrification of conductors.**—Bad conductors are called *insulators*, for they are used as supports for bodies in which electricity is to be retained. A conductor remains electrified only so long as it is surrounded by insulators. If this were not the case, as soon as the electrified body came in contact with the earth, which is a good conductor, the electricity would pass into the earth, and diffuse itself through its whole extent. On this account, the earth has been named the *common reservoir*. A body is insulated by being placed on a support with glass feet, or on a resinous cake, or by being suspended by silk threads. No bodies, however, insulate perfectly; all electrified bodies lose their electricity more or less rapidly by means of the supports on which they rest. Glass is in itself a very perfect insulator but it is always somewhat hygroscopic, and the aqueous vapour which condenses on it affords a passage for the electricity; the insulating power of glass is materially improved by

ng it with shellac or copal varnish. Dry air is a good insulator ; when the air contains moisture, it conducts electricity, and this ɛ principal source of the loss of electricity.

ɪ is from their great conductivity, that metals do not become rified by friction. But if they are insulated, and then rubbed, give good indications. This may be seen by the following rɪment. A brass tube is provided with a glass handle, by h it is held, and then rubbed with silk or flannel. On ap-ɛhing the metal to the electric pendulum (fig. 331), the pith vill be attracted. If the metal is held in the hand electricity is ɛd produced by friction, but it immediately passes through ɒody into the ground.

ɩlectrifying by contact is due to conductivity. For when an ated conductor in the neutral state is made to touch an elec-d conductor, a portion of the latter passes instantaneously to ɔrmer. If the two bodies have the same surface, and the same e, for instance, two spheres of the same diameter, the electricity ually distributed on the two ; but if the bodies differ in shape ɪrface the electricity is unequally distributed.

ɔ8. **Law of the development of electricity by friction.**—never two bodies are rubbed together, the neutral fluid is de-ɒosed. The two electricities are developed at the same time in equal quantities—one body takes the positive, and the other ɪegative fluid. This may be proved by the following simple rɪment devised by Faraday:—A small flannel cap provided a silk thread is fitted on the end of a stout rod of shellac, and ɛd round a few times. When the cap is removed by means of ɪ thread, and presented to a pith ball pendulum charged with ive electricity, the latter will be repelled, proving that the el is charged with positive electricity ; while, if the shellac is ɪnted to the pith ball, it will be attracted, showing that the ɑc is charged with negative electricity. Both electricities are ɪnt in equal quantities ; for if the rod be presented to the elec-ope before removing the cap, no action is observed.

he electricity developed on a body by friction depends on the rubbed. Thus glass becomes negatively electrified when ɛd with catskin, but positively when rubbed with silk. In ɔllowing list the substances are arranged in such an order, that becomes positively electrified when rubbed with any of the ɪs following, but negatively when rubbed with any of those ɪ precede it :

1. Catskin.
2. Flannel.
3. Glass.
4. Silk.
5. The hand.
6. Wood.
7. Metals.
8. Caoutchouc.
9. Resin.
10. Sulphur.
11. Gutta percha.
12. Gun-cotton.

409. **Accumulation of electricity on the surface of bodies.**— Numerous experiments show that when a body is electrified, all the electrical fluid goes to the surface, where it is accumulated as an extremely thin layer, tending incessantly to escape, and flying off in short, when it is not retained by any obstacle.



Fig. 335.

This may be demonstrated by the following experiment, which is due to Biot.

A hollow brass globe, fixed to an insulating support, is provided with two brass hemispherical envelopes which fit closely, and can be separated by glass handles. The interior is now electrified, and

: two hemispheres brought in contact. On then rapidly removing
em (fig. 335), the coverings will be found to be electrified, while
e sphere is in its natural condition, and indicates no electricity.
ius in removing, so to say, the surface of a body, all the free
ectricity it contained is also removed, which shows clearly that
e electricity is on the surface. That electricity resides solely in
ie surface is further proved by the fact, that two metal spheres of
ie same diameter, but one of them solid and the other hollow,
ike the same charge of electricity when applied to the same
ource.

The same point may also be illustrated by means of a bird cage,
referably of metal wire, which is suspended by insulators and
ontains either a gold leaf electroscope, or pieces of Dutch metal,
athers, etc. When the cage is charged by being connected with an
ectrical machine at work, the articles in the interior are quite un-
ffected, although strong sparks may be taken from the outside. A
rd in the inside is quite unaffected by the charge or discharge of
e electricity of the cage.

When accumulated on the surface of bodies, electricity tends to
ass off to adjacent objects with an effort which is known as the
ension. This increases with the quantity of electricity. So long
it does not exceed a certain limit, it is balanced by the resistance
esented by the small conducting power of the air when it is dry.
the tension increases, this resistance is overcome, and the elec-
city springs off to an adjacent body with a sound, and in the form
a bright spark. In moist air the tension is always feeble, for the
ectricity passes away almost as rapidly as it is supplied, moisture
ing a good conductor of electricity. In very rarefied air, on the
ntrary, where there is little resistance, electricity passes off,
esenting the appearance of a luminous glow.

410. **Influence of the shape of a body on the accumulation electricity. Power of points.**—The manner in which electricity distributed on the surface of a body varies with its shape. If it spherical the amount is everywhere the same, which might in-ed be predicted, and which may be readily confirmed by means the *proof plane*. This is a small thin metal disc fixed at the end a thin shellac rod. This is held in the hand, and successively plied to different parts of the electrified body, and after each ntact is presented to an electrical pendulum. If the body is a here the attraction is in each case the same, which shows that e disc has taken the same charge of electricity from each part

of the sphere, and, therefore, that the distribution of the electrica fluid is uniform.

This is no longer the case if the electrified body is more or le elongated, as, for instance, a kind of ovoid shape, as shown in fi 336. In this case the proof plane is the more charged the near it is applied to the elongated end; and at this end itself mo electricity is removed. This experiment shows that, in good con ductors, electricity always tends to accumulate towards the most



Fig. 336.

elongated parts, towards the points. This accumulation produces a greater tension, which is sufficient to overcome the resistance of the air, and allow electricity to escape. It is in fact observed, that metal bodies provided with a point quickly lose their electricity, and, if the hand be held over such a point, a sort of wind or draught is felt. If this takes place in darkness, a kind of luminous brush appears on the top of the point.

This property of points, placed on electrified conductors, of allowing electricity to escape, has been called the *power of points*; and in electrical experiments we meet with numerous instances where it comes into play.

CHAPTER II.

ACTION OF ELECTRIFIED BODIES ON BODIES IN THE NATURAL STATE ; INDUCED ELECTRICITY. ELECTRICAL MACHINES.

411. **Electricity by influence or induction.**—An insulated conductor, charged with either kind of electricity, acts on bodies in a natural state placed near it, in a manner analogous to that of the action of a magnet on soft iron, that is, it decomposes the neutral fluid, attracting the opposite, and repelling the like kind of electricity. The action, which is a consequence of the attractions and repulsions of the two electricities, and which is exerted not only through air but also through insulating bodies like air, glass, resins, etc., is said to take place by *influence* or *induction.*



Fig. 337.

The phenomena of induction may be demonstrated by means of the experiment represented in fig. 337. On the right hand of the figure is the conductor of the electrical machine, which, as we shall afterwards see, is charged with positive electricity ; on the left is a brass cylinder, insulated by being placed on a glass support, and provided with small pith ball pendulums, suspended by linen

threads, which are conductors. When the cylinder of the machine is brought near this conductor, the pendulums are found to diverge but to unequal extents, the greatest divergence being met with at the ends. Near the middle the pith balls do not diverge at all; the electricity is, therefore, accumulated at the ends, and the middle is in the neutral state. If, moreover, a sealing-wax rod which has been rubbed with flannel be approached to the pendulums nearest the electrical machine, they will be repelled, showing that they are charged with the same electricity as the rubbed sealing wax, that is, with negative electricity. If, in like manner, a glass rod, which has been rubbed with silk, be approached to the other end of the cylinder, the pendulums are also repelled, which shows that they are charged with positive electricity. The electricities thus separated are equal in quantity, for if the machine is removed all the pendulums cease to diverge, since the two electricities have recombined, and the body is restored to the neutral state.

This *electrifying by influence*, or *induction* as it is called, which is produced by an electrified body or bodies in the neutral state explains a host of phenomena. In order to explain all its effects, it is important to inquire what takes place when, in the above experiment, the insulated cylinder is placed for a short time in contact with the ground, while it is still under the influence of the machine. Suppose, for instance, the further end be placed in contact with the ground, the positive electricity will escape, while the negative remains held by the attraction of the opposite electricity of the machine. If now connection with the ground be interrupted, and the cylinder be moved away from the influence of the machine, the pendulums will diverge, and, as can be easily verified, owing to their being charged with negative electricity. Even if the end nearest the machine be connected with the ground the result is still the same. The negative electricity does not pass into the ground; it is the positive which still escapes; the negative being attracted by the contrary electricity of the machine, on interrupting the communication with the earth, the cylinder remains charged with negative electricity.

Thus a body can be charged with electricity by induction as well as by conduction. But, in the latter case, the charging body loses part of its electricity, which remains unchanged in the former case. The electricity imparted by conduction is of the same kind as that of the electrified body, while that excited by induction is of the opposite kind. To impart electricity by conduction, the body must

be quite insulated, while, in the case of induction, it must be in connection with the earth, at all events, momentarily.

What has here been said has referred to the inductive action exerted on good conductors. Bad conductors are not so easily acted upon by induction, owing to the great resistance they present to the circulation of electricity, but, when once charged, the electric state is more permanent.

This is analogous to what is met with in magnetism; a magnet instantaneously evokes magnetism in a piece of soft iron; but this is only temporary, and depends on the continued action of the magnet; a magnet magnetises steel with far greater difficulty, but this magnetism is permanent.

ELECTRICAL MACHINES.

412. **Ramsden's electrical machine.** — The first electrical machine was invented by Otto von Guericke, the inventor also of the air-pump. It consisted of a sphere of sulphur, which was turned on an axis by means of the hand, while the other, pressing against it, served as a rubber. Resin was afterwards substituted for the sulphur, which in turn, Hawksbee replaced by a glass cylinder. In all these cases the hand served as rubber; and Winckler, in 1740, first introduced cushions of horsehair covered with silk as rubbers. At the same time, Bose collected electricity disengaged by friction, on an insulated cylinder of tin plate. Lastly, Ramsden, in 1760, replaced the glass cylinder by a circular glass plate, which was rubbed by cushions. The form which the machine has now is but a modification of Ramsden's original machine.

Between two wooden supports (fig. 338), a circular glass plate, P, about a yard in diameter, is suspended by an axis passing through the centre, and which is turned by means of a glass handle. The plate revolves between two sets of *cushions* or *rubbers*, of leather or of silk, one set above the axis and one below, which, by means of screws, can be pressed as tightly against the glass as may be desired, by which means the plate becomes electrified on both sides. In front of the plate also are two brass rods, provided with a series of points in the sides opposite the glass; these rods are fixed to two large metal cylinders, AA, which form the *prime conductor*. The latter are insulated by being supported on glass feet, and are connected with each other by a smaller rod.

The action of the machine is founded on the excitation of elec-

tricity by friction, and on the action of induction. By friction with the rubbers, the glass becomes positively, and the rubbers negatively electrified. If now the rubbers were insulated, they would receive a certain charge of negative electricity which it would be



Fig. 338.

impossible to exceed, for the tendency of the opposed electricities to reunite would be equal to the power of the friction to decompose the neutral fluid. But the rubbers communicate with the ground by means of bands of tinfoil, fixed to the supports, not shown in the figure, and, consequently, as fast as the negative electricity is generated it passes off. The positive electricity of the glass acts then by induction on the conductor, attracting the nega-

ive fluid. The conductors thus lose their negative electricity, and emain charged with positive fluid. The plate accordingly gives up iothing to the conductors ; in fact, it only abstracts from them their iegative fluid.

As thus described, the elèctrical machine yields only positive lectricity ; it may, however, be arranged so as to give negative lectricity. For this purpose the four feet of the table are insulated y being placed on thick plates of resin, of glass, or of sulphur, and he conductors are connected with the ground by a metallic chain. his allows the electricity of the positive conductors to escape, hile the negative electricity of the rubbers accumulates on the upports and on the bands of tinfoil.

413. **Measurement of the charge of the electrical machine. uadrant electrometer.**—The amount of electrical charge, or lectric tension, is measured by the *quadrant* or *Henley's electro- teter*, which is represented in fig. 339 attached to the conductor. his is a small electric pendulum, consisting of a wooden rod, which is attached an ivory or cardboard scale (fig. 339). In ie centre of this is a small whalebone index, movable on an axis, id terminating in a pith ball. Being attached to the conductor, ie index rises as the machine is charged, ceasing to rise when the mit is attained. When the rotation is discontinued the index falls ipidly if the air is moist ; but in dry air it only falls slowly, show- g, therefore, that the loss of electricity in the latter case is less an in the former.

Hence in moist and rainy weather all experiments with the e'ec- ical machine are difficult to perform. All parts of the apparatus ust be carefully warmed by a charcoal chauffer, and the supports id plate must be rubbed with hot cloths.

The rubbers require great care both in their construction and in eir preservation. They are commonly made of leather stuffed ith horse-hair. Before use they are coated either with powdered *trum musivum* (sulphuret of tin), or graphite, or amalgam. The tion of these substances is not very clearly understood. Some nsider that it merely consists in promoting friction. Others ain believe that a chemical action is produced, and assign support of this view the peculiar smell noticed near the rubbers hen the machine is worked. Amalgams, perhaps, promote most werfully the disengagement of electricity. *Kienmayer's amalgam* the best of them.

Whatever precautions be taken to avoid the loss of electricity,

or however rapidly the machine is turned, it is impossible to exceed a certain limit. For as the electricity accumulates on the machine, its tension increases too, and very soon its tendency to escape exceeds the resistance offered by the air and the supports of the conductors. From this moment the loss of electricity equals the electricity disengaged by friction, and hence the tension can never exceed the limit it has attained, which is indicated by the electrometer remaining stationary although the rotation is continued.

If, moreover, the maximum effect is desired, the machine must not be placed too near the walls or the furniture; in short, away from all objects on which it could act by induction, especially if these



Fig. 339.

are angular, for it then continually withdraws the negative electricity and tends to revert to the neutral state. Thus if a point be presented to a machine in action, as represented in fig. 339, the electrometer falls, even though the point is at some distance. This is due to the fact that the positive electricity of the machine induces negative in the point, which flows out as fast as it is produced, and combining with the positive by means of which it was evoked, continually brings the machine back to the neutral state.

414. **Electrophorus.**—This is a very simple apparatus invented by Volta, and by means of which considerable quantities of electricity may be produced. It consists of a *cake* of resin, C (fig. 340), of about twelve inches diameter, and an inch thick, which is placed

netallic surface, or very frequently fits in a wooden mould with tinfoil, which is called the *form*. Besides this, there is a n disc, of a diameter somewhat less than that of the cake, on its under surface with tinfoil, and provided with an insu- glass handle. This is called the *cover*. The mode of ng this apparatus is as follows: All the parts of the apparatus ; been well warmed, the cake, which is placed in the form, or on a metallic surface, is briskly flapped with a catskin, as in fig. 340, by which it becomes charged with negative

Fig. 340.

city. The cover held by the insulating handle is then placed cake. The negative electricity of the cake acting thus in- ely on the cover attracts positive electricity to the lower sur- nd repels negative to the upper. If now this upper surface be d by the finger, as shown in fig. 341, the negative electricity out into the ground, and the disc only retains positive elec- . Now when the cover is raised by one hand by means of the ting handle, and the other hand is brought near it, a smart

spark passes, due to the recombination of the positive of the disc with the negative produced by its induction in the hand (fig. 342).

Replacing the disc upon the cake, this again exerts its inductive action, for it is such a bad conductor that the electricity does not pass off to the cover, and if the same operations be repeated, a succession of such sparks may be obtained even after the lapse of some time. The retention of electricity is greatly promoted by keeping the cake in the form, and placing the cover upon it, by

Fig. 341.



Fig. 342.

which the access of air is hindered. Instead of a cake of resin, a disc of gutta percha, or vulcanised cloth, or vulcanite, may be substituted; and of course, if any material which becomes positively electrified by friction be used, the cover acquires a negative charge.

415. **Gold leaf electroscope.**—The *gold leaf electroscope*, also called *Bennett's electroscope*, from the name of its inventor, is a small but delicate apparatus for ascertaining whether a body is electrified, and if so with what kind of electricity it is charged. It consists of a tubulated glass shade (fig. 343), the neck of which is closed by a cork. In this is fitted a brass rod terminating at the top in a knob, and at the bottom in two strips of gold leaf. The neck, the cork,

and the upper part of the shade are coated with a thick layer of sealing wax varnish, which is nothing more than a solution of sealing wax in spirits of wine. The object of this coating is to improve the insulating qualities of the glass. Glass is indeed a bad conductor, but it is very hygroscopic; that is, it readily attracts aqueous vapour from the air, and thus becomes coated with a layer of moisture which renders its surface a conductor. When covered with varnish this evil is removed, for varnishes, which are usually made of resin, are not at all hygroscopic.



Fig. 343.

The air in the inside is dried by quicklime, or by chloride of calcium, and on the insides of the shade there are two strips of gold leaf communicating with the ground.

When the knob is touched with a body charged with either kind of electricity, the leaves diverge; usually, however, the apparatus is charged by induction thus:

If an electrified body, a stick of sealing wax rubbed with flannel for instance, be brought near the knob, it will decompose the natural electricity of the system, attracting to the knob the fluid of

the opposite kind and retaining it there, and repelling the electricity of the same kind to the gold leaves, which consequently diverge. In this way, the presence of an electrical charge is ascertained, but not its quality.

To ascertain the kind of electricity the following method is pursued: If, while the instrument is under the influence of the body, which we will suppose has a negative charge, the knob be touched by the finger, the negative electricity decomposed in induction passes off into the ground, and the previously divergent leaves will collapse: there only remains positive electricity retained in the knob by induction from the sealing wax. If now the finger be first removed, and then the electrified body, the positive electricity previously retained by the sealing wax will spread over the system, and cause the leaves to diverge with positive electricity. If now, while the system is charged with positive electricity, a positively electrified body, as, for example, an excited glass rod, be approached, the leaves will diverge more widely; for the electricity of the same kind will be repelled to the extremities. If, on the contrary, an excited shellac rod be presented, the leaves will tend to collapse, the fluid, with which they are charged, being attracted by the opposite electricity. Hence we may ascertain the kind of electricity, either by imparting to the electroscope electricity from the body under examination, and then bringing near it a rod charged with positive or negative electricity; or the electroscope may be charged with a known kind of electricity, and the electrified body in question brought near the electroscope.

It has been proposed to use the electroscope as an *electrometer*, or measurer of electricity, by measuring the angle of divergence of the leaves. This is done by placing behind them a graduated scale. There are, however, many objections to such a use, and it is rarely employed for this purpose.

CHAPTER III.

ELECTRICAL EXPERIMENTS.

416. **Electrical spark.**—One of the first experiments which is ıade by those who see an electrical machine at work for the first me is that of taking from it an electrical spark by bringing the and near the conductor. The positive electricity of the conductor :ting inductively on the neutral fluid of the body decomposes it,



Fig. 344.

Fig. 345.

Fig. 346.

›elling the positive and attracting the negative fluid. When the ısion of the opposed electricities is sufficiently great to over- me the resistance of the air, they recombine with a smart crack· d a spark. The spark is instantaneous, and is accompanied by ;harp prickly sensation, more especially with a powerful machine.. ; shape varies. When it strikes at a short distance, it is recti-

linear, as seen in fig. 344. Beyond two or three inches in length, the spark becomes irregular, and has the form of a sinuous curve with branches (fig. 345). If the discharge is very powerful, the spark takes a zigzag shape (fig. 346). These two latter appearances are seen in the lightning discharge.

417. **Insulating stool.**—A spark may be taken from the human body by the aid of the *insulating stool*, which is simply a low stool



Fig. 347.

with stout varnished glass legs. The person standing on this stool touches the prime conductor, and as the human body is a good conductor, the electrical fluid is distributed over its surface as over an ordinary insulated metallic conductor (fig. 347). The hair diverges in consequence of repulsion, a peculiar sensation is felt on the face, and if another person, standing on the ground, presents his hand to any part of the body, a smart crack with a pricking sensation is produced.

418. **Electrical chimes.**—*The electrical chimes* is a bell work

ch is worked by electrical attraction and repulsion. It consists hree metal bells suspended to a horizontal brass rod, *m*, which is nected with the electrical machine (fig. 348). The two bells, *b* *c*, are suspended by light metal chains ; the middle one is sus- led by silk, and is moreover connected with the ground by a n. Between the bells are two small hollow copper balls sus- led by silk threads to which they are attached. When the



Fig. 348.

hine is worked these small copper balls are attracted by the ricity which passes to the bells, *b* and *c*, and strike against ı; but being at once repelled they strike against the middle bell, hich they give up their electricity, which thus passes into the nd. They are then again attracted, again repelled, and so on ng as the machine is at work.

19. **Dancing puppets.**—This, like the chimes, is an application e attractions and repulsions of electrified bodies. It consists lacing a small, very light figure of pith, loaded at the feet, een two metal discs, one connected with the ground and the r with the electrical machine (fig. 349). As soon as this latter mes charged, the small puppet is successively attracted and lled from one to the other disc, as if it executed of its own er action a series of jumps.

20. **Electrical whirl or vane.**—The electrical *whirl* or *vane* ists of four to six wires, terminating in points, all bent in the

same direction, and fixed in a central cap, which rotates on a pivot (fig. 350). When the apparatus is placed on the conductor,



Fig. 349.

and the machine worked, the whirl begins to revolve in a direction opposite that of the points. This motion is not analogous to that of the hydraulic tourniquet (79). It is not caused by a flow of material fluid, but is due to a repulsion between the electricity of the points and that which they impart to the air by conduction. The electricity, being accumulated on the points in a high state of tension, passes into the adjacent air, and imparting thus a charge of electricity, repels this electricity while it is itself repelled. That this is the case, is evident from the fact that, on approaching the hand to the whirl while in motion, a slight draught is felt, due to the movement of the electrified air; while in vacuo the apparatus does not act at all. This draught or wind is known as the electrical *aura*.

When the electricity thus escapes by a point, the electrified air is

pelled so strongly as not only to be perceptible to the hand, but lso to engender a current strong enough to blow out a candle. he same effect is produced by lacing a taper on the con- uctor, and bringing near it a ointed wire held in the hand. he current arises, in this case, om the contrary fluid, which capes by the point under the fluence of the machine.



Fig. 350.

The *electrical orrery* and the *ctrical inclined plane* are alogous to these pieces of paratus.

421. **Electric egg.**—The in- ence of the pressure of the , or rather of its nonconduc- ity, on the electric light, may studied by means of the *ctric egg*. This consists of an



Fig. 351.

ellipsoidal glass vessel (fig 351), with metallic caps a
The lower cap is provided with a stopcock, so tha
screwed into an air-pump, and also into a heavy meta
upper metal rod moves up and down in a leather s
the lower one is fixed to the cap. An almost comp
having been made, the stopcock is turned, and the ve
into its foot; the upper part is then connected with
electrical machine, and the lower one with the ground
ing the machine, the globe becomes filled with a feebl

Fig. 352.

continuous from one end to the other, and resulting fro
position of the positive fluid of the upper cap with th
the lower. If the air be gradually allowed to enter

the stopcock, the resistance increases, and the light which appeared continuous, white, and brilliant, is now only seen as an ordinary spark.

422. **Magic pane.**—The magic pane consists of a glass plate, one side of which is covered with several folds of tinfoil, arranged so as to form a series of metallic bands, arranged parallel and close to each other. The pane is supported vertically by two glass rods, and the upper end of the tinfoil is connected with the electrical machine by a conductor, and the lower one with the ground



Fig. 353.

by a chain. In this condition, if the machine be worked, the electricity will pass into the ground by the tinfoil, without any interruption ; but if a series of breaks are made in the tinfoil by cutting

it away with a penknife, a spark appears at each break ; and if these breaks be so arranged as to represent a given object, a flower, or a monument, or words, these objects are reproduced in a line of fire when the electrical machine is set to work. This experiment is really due to the prodigious velocity of electricity, which is not less than about 190,000 miles in a second. Hence, in the above experiment, although the sparks are really successive, they follow each other with such rapidity as to seem continuous.

423. **Luminous globe and tube.**—The *luminous globe* is a glass globe lined on the inside with a series of small lozenges of tinfoil placed very near each other without actually touching. The first plate is connected with an electrical machine at work, and the last with the ground, upon which a series of bright sparks appears at each break in the metallic conductor (fig. 353).

If the small metal plates are arranged inside a spiral glass lustre from one end to the other, this arrangement forms a *luminous tube*.

424. **Volta's cannon.**—This is not merely interesting as an experiment, but also as demonstrating an important fact, namely, that

Fig. 354.

the electrical spark can establish chemical action. Thus, water is formed of two gases, hydrogen and oxygen, in the ratio of one volume

of the latter to two volumes of the former. Now, when an electrical spark is passed through a mixture of these two gases, they combine in their proportions, and form water. This combination is, moreover, attended by a bright flash of light and a loud report, the latter being due to the expansive force of aqueous vapour, due to the high temperature produced by the combination.

On this property which mixtures have of detonating by the electrical spark, Volta's cannon, represented in fig. 354, is constructed. It is a small brass cannon resting on an insulating support. In the touchhole is a small glass tube, and in this a brass wire with a small knob at each end ; one of which knobs is on the outside, and the other very near the inside of the cannon but not touching it. Having introduced a mixture of two parts of hydrogen and one of oxygen, the cannon is closed by a cork, and is connected with the ground by a metal chain. If then the charged disc of the electrophorus be approached, a spark passes to the small knob, and at the same time inside the cannon. This latter causes the two gases to combine with a violent explosion, which drives out the cork.

CHAPTER IV.

CONDENSATION OF ELECTRICITY.

425. Electrical condensers.—*Condensers* are apparatus by which electricity may be accumulated. Their shape is greatly varied, but they are all composed essentially of two insulated conductors separated by a non-conductor, and their working is an application of the action of induction. Epinus's condenser consists of two metal plates, A and B, insulated by being supported on glass legs (fig. 355); between them is a pane of ordinary glass, of somewhat larger diameter than that of the plates, A and B, which are about six inches in diameter. The legs can be moved along a support, and fixed in any position.

In explaining the action of the condenser, it will be convenient to call that side of the metal plate nearest the glass the *anterior*, and the other the *posterior*, side. And first let A be at such a distance from B as to be out of the sphere of its action. The plate B, which is then connected with the conductor of the electrical machine, takes its maximum charge, which is distributed equally on its two faces,

and the pendulum diverges widely. If the connection with the machine be interrupted, nothing would be changed ; but if the plate,



Fig. 355.

A, be slowly approached, its neutral fluid being decomposed by the



Fig. 356.

influence of B, the negative is accumulated on its anterior face, *a*, (fig. 357), and the positive passes into the ground. But as the

egative electricity of the plate, A, reacts in its turn on the positive f the plate, B, the latter fluid ceases to be equally distributed on oth faces, and is accumulated on its anterior face, *m*. The pos-rior face, *p*, having thus lost a portion of its electricity, its tension as diminished, and is no longer equal to that of the machine, and ie pendulum, *b*, diverges less widely. Hence B can receive a fresh uantity from the machine, which acting as just described, decom-oses by induction a second quantity of neutral fluid on the plate, . There is then a new accumulation of negative fluid on the ice, *n*, and consequently of positive fluid on *m*. But each time ie machine gives off electricity to the plate B, only a proportion of iis passes to the face, *m*, the other remaining on the face, *p* ; the nsion here, therefore, continues to increase until it equals that of ie machine. From this moment equilibrium is established, and a mit to the charge attained, hich cannot be exceeded. The uantity of electricity accumula-d now on the two faces, *m* and is very considerable, and yet the ndulum diverges just as much it did when A was absent and) more ; in fact, the tension at is just what it was then, name-, that of the machine.



Fig. 357.

The accumulation of electri-ty in condensers was formerly explained by saying that the elec-icity of the *condensing* plate, A, *neutralised* the contrary electricity the *collecting* plate, and it was because the electricity on this tter was then *dissimulated* or *latent* that it could receive a fresh pply. But from what has been said, it is unnecessary to recur to iy special hypothesis as to the state of electricity to explain the eory of condensers.

When the condenser is charged, that is, when the opposite elec-icities are accumulated on the anterior faces, connection with e ground is broken by raising the wires. The plate A is charged th negative electricity, but simply on its anterior face (fig. 356), e other side being neutral. The plate B, on the contrary, is elec-fied on both sides, but unequally ; the accumulation is only on ; anterior face, while on the posterior, *p*, the tension is simply ual to that of the machine at the moment the connections are terrupted. In fact the pendulum, *b*, diverges and *a* remains

vertical. But, if the two plates are removed, the two pendulums diverge (fig. 357), which is owing to the circumstance that, as the plates no longer act on each other, the positive fluid is equally distributed on the two faces of the plate B, and the negative on those of the plate A.

426. **Slow discharge and instantaneous discharge.**—While the plates, A and B, are in contact with the glass (fig. 356), and the connections interrupted, the condenser may be discharged, that is, restored to the neutral state, in two ways; either by a slow or by an instantaneous discharge. To discharge it slowly, the plate B, that is, the one containing an excess of electricity is touched with the finger; a spark passes, all the electricity on *p* escapes into the ground, the pendulum, *b*, falls, but *a* diverges. For B having lost part of its electricity only retains on the face, *m*, that held by the inductive influence of the negative on A. But the quantity thus retained at B is less than that on A: this has free electricity, which makes the pendulum, *a*, diverge; and, if it now be touched, a spark passes, the pendulum, *a*, sinks while *b* rises, and so on by continuing to touch alternately the two plates. The discharge only takes place slowly; in very dry air it may require several hours. If the plate, A, were touched first, no electricity would be removed, for all it has is retained by that of the plate B. To remove the total quantity of electricity by the method of alternate contacts, an infinite number of such contacts would theoretically be required.

To obtain an instantaneous discharge one hand may be placed on one plate, and the second touched with the other hand; a violent shock is then felt, far more violent than that produced by the electrical machine. To avoid this a *discharging rod* is used, which consists of two bent stout brass wires terminating in knobs and joined by a hinge. If this be held in the hand as represented in fig. 359, and one knob be applied to one plate of the condenser while the arc is bent, so that the second touches the other plate. Just as this is on the point of touching a spark passes, which is due to the reunion of the two electricities accumulated on the condenser; no shock is felt, for the recombination does not take place through the arms and body of the experimenter, but through the metallic arc, which is a far better conductor.

427. **Limit of the charge of condensers.**—The quantity of electricity which can be accumulated on each plate is, other things being equal, proportional to the tension of the electricity on the conductor, and to the surface of the plates: it decreases as the insulating plate

is thicker, and it differs with the specific inductive capacity of the substance. Two causes limit the quantity of electricity which can be accumulated. First, that the electric tension of the collecting plate gradually increases, and ultimately equals that of the machine, which cannot, therefore, impart any free electricity. The second cause is the imperfect resistance which the insulating plate offers to the recombination of the two opposite electricities; for when the force which impels the two fluids to recombine exceeds the resistance offered by the insulating plate, it is perforated, and the contrary fluids unite.

428. **The Leyden jar.**—The *Leyden jar*, or *flask*, so called from the town of Leyden, where it was invented, is essentially a condenser, only differing in shape from that which has been described. It



Fig. 358.

was accidentally discovered in 1746 by Muschenbrock, a Dutch physician. Wishing to electrify water contained in a flask, he passed through the cork a wire which he presented to the conductor of the machine. After holding it in this position for some time he was on the point of removing the rod with the other hand when he received in the arms and breast a shock so violent that it was two days before he recovered from the effects; and writing to his friend Reaumur he said, he would not repeat the experiment for the whole kingdom of France.

The fact thus discovered caused probably a greater sensation throughout Europe than any other one has ever done. It was repeated innumerable times, and the apparatus, after successive modifications and improvements, acquired its present form. It is not

difficult to see that the above experiment is a case of condensation. The liquid in the flask acts as a collector, the hand acts as a condensing plate, and the insulating plate is formed by the material of the flask itself.

The ordinary form of the Leyden jar consists of a glass bottle of any convenient size, the interior of which is either coated with tinfoil or filled with thin leaves of copper, or with gold leaf. Up to a certain distance from the neck the outside is coated with tinfoil. The neck is provided with a cork, through which passes a brass

Fig. 359.

rod, which terminates at one end in a knob, and communicates with the metal in the interior. The metallic coatings are called respectively the *internal* and *external armatures* or *coatings*. Like the condenser, the jar is charged by connecting one of the armatures with the ground, and the other with the source of electricity. When it is held in the hand by the outer coating, and the knob presented to the conductor of the machine, positive electricity is accumulated on the inner, and negative electricity on the outer coating. The reverse is the case if the jar is held by the knob, and the outer coating presented to the machine. The action of the jar is the same as that of the condenser, and all that has been said of this applies to the jar, substituting the two armatures for the two plates A and B, of the condenser.

To charge the jar it is held in the hand as represented in fig. 358, d the knob is applied to an electrical machine, which is at work. ıe positive electricity of the machine acting inductively through e sides of the glass on the tinfoil and on the hand, condenses a rge quantity of electricity.

Like the condenser, the Leyden jar may be discharged either ›wly or instantaneously. For the latter it is held in the hand by e outside coating, and the two coatings are then connected by eans of the simple discharger (fig. 359). Care must be taken to uch *first* the external coating with the discharger, otherwise a ıart shock will be felt. To discharge it slowly the jar is placed ı an insulated plate, and first the internal and then the external ating touched, either with the hand or with a metallic conductor. slight spark is seen at each discharge.

Fig. 360 represents a very pretty experiment for illustrating the ›w discharge. The rod terminates in a small bell, *d*, and the ıtside coating is connected with an upright metallic support, on ıich is a similar bell, *e*. Between the two bells a light copper ball suspended by a silk thread. The r is then charged in the usual anner, and placed on the support, . The internal armature contains quantity of free electricity; the ndulum is attracted and imme- ately repelled, striking against e second bell, to which it imparts free electricity. Being now utralised it is again attracted by e first bell, and so on for some ne, especially if the air be dry, d the jar pretty large.



Fig. 360.

429. **Electric batteries.**—The arge which a Leyden jar can ce depends on the extent of the ated surface, and for small thick- sses is inversely proportional to e thickness of the insulator. Hence the larger and thinner e jar the more powerful the charge. But very large jars are ex- nsive, and liable to break; and, when too thin, the accumulated ectricities are apt to discharge themselves through the glass es- ecially if it is not quite homogeneous. Leyden jars have usually

from ½ to 3 square feet of coated surface. For more powerful charges electric batteries are used.

An *electric battery* consists of a series of Leyden jars, whose internal and external coatings are respectively connected with each other (fig. 361). They are usually placed in a wooden box lined on the bottom with tinfoil. This lining is connected with two metal handles in the sides of the box. The internal coatings are connected with each other by metallic rods, and the battery is charged by placing the internal coatings in connection with the prime conductor, while the external coatings are connected with the ground by means of a chain fixed to the handles. A quadrant electrometer



Fig. 361.

fixed to the jar serves to indicate the charge of the battery. Although there is a large quantity of electricity accumulated in the apparatus the divergence is not great, for it is simply due to the free electricity on the internal coating. The number of jars is usually four, six, or nine. The larger and more numerous they are, the longer is the time required to charge the battery, but the effects are so much the more powerful.

When a battery is to be discharged, the coatings are connected by means of the discharging rod, the outside coating being touched first. Great care is required, for with large batteries serious accidents may be produced, resulting even in death.

430. **Condensing electroscope.**—We shall conclude the study

ıdensers by an application which Volta made of this principle
: ordinary gold leaf electroscope, by which a far greater degree
icacy is attained (fig. 362). The rod to which the gold leaves
fixed, terminates in a disc instead of in a knob, and there is
er disc of the same size provided with an insulating glass
e. The discs are covered with a layer of insulating shellac
ıh (fig. 362).

Fig. 362.

Fig. 363.

ɔ render very small quantities of electricity perceptible by this
atus, one of the plates, which thus becomes the *collecting*
is touched with the body under examination. The other
the *condensing plate*, is connected with the ground, by
ing it with the finger. The electricity of the body, being
ed over the collecting plate, acts inductively through the
ıh on the neutral fluid of the other plate, attracting the
ite electricity, but repelling that of like kind. The two
icities thus become accumulated on the two plates just as in
ıs's condenser, but there is no divergence of the leaves, for the
ite electricities counteract each other. The finger is now

removed, and then the source of electricity, and still there is no divergence ; but if the upper plate be raised (fig. 363), the neutralisation ceases, and the electricity being free to move diffuses itself over the rod and the leaves, which then diverge widely. The delicacy of the apparatus is increased by adapting to the foot of the apparatus two metallic rods, terminating in knobs, for these knobs being excited by induction from the gold leaves react upon them.

CHAPTER V.

VARIOUS EFFECTS OF ACCUMULATED ELECTRICITY.

431. **Effects of the electric discharge.**—The recombination of the two electricities which constitutes the electrical discharge may be either continuous or sudden ; *continuous*, or of the nature of a current, as when the two conductors of a cylinder machine are joined by a chain or a wire ; and *sudden*, as when the opposite electricities accumulate on the surface of two adjacent conductors, till their mutual attraction is strong enough to overcome the intervening resistances, whatever they may be. But the difference between a sudden and a continuous discharge is one of degree and not of kind, for there is no such thing as an absolute non-conductor, and the very best conductors, the metals, offer an appreciable resistance to the passage of electricity. Still, the difference at the two extremes of the scale is sufficiently great to give rise to a wide range of phenomena.

The phenomena of the discharge are usually divided into the *physiological*, *luminous*, *mechanical*, *magnetical*, and *chemical* effects.

432. **Physiological effects.**—The physiological effects are those produced on living beings, or on those recently deprived of life. In the first case they consist of a violent excitement which the electric fluid exerts on the sensibility and contractibility of the organic tissues through which it passes ; and in the latter, of violent muscular convulsions which resemble a return to life.

The shock from the electrical machine has been already noticed (416). The shock taken from a charged Leyden jar by grasping the external coating with one hand and touching the inner with the other, is much more violent, and has a peculiar character.

With a small jar the shock is felt in the elbow; with a jar of about a quart capacity it is felt across the chest, and with jars of still larger dimensions in the stomach.

A shock may be given to a larger number of persons simultaneously by means of the Leyden jar. For this purpose they must form a chain by joining hands. If then the first touches the outside coating of a charged jar, while the last at the same time touches the knob, all receive a simultaneous shock, the intensity of

Fig. 364.

which depends on the charge, and on the number of persons receiving it. Those in the centre of the chain are found to receive a less violent shock than those near the extremities. The Abbé Nollet discharged a Leyden jar through an entire regiment of 1,500 men, all of whom received a violent shock in the arms and shoulders.

With large Leyden jars and batteries the shock is sometimes very dangerous. Priestley killed rats with batteries of 7 feet

coated surface, and cats with a battery of about 4½ square yards coating.

433. **Luminous effects. Luminous jar.**—The luminous effects of electricity are in all cases due to the combination of the two fluids, positive and negative. Some of these effects have already been made known in describing *the electrical egg* and *the magic pane.* We here give a description of another one.

The *luminous jar* (fig. 365) is a Leyden jar, whose outer coating consists of a layer of varnish strewed over with metallic powder.

Fig. 365.



Fig. 366.

A strip of tin fitted on the bottom is connected with the ground by means of a chain; a second band at the upper part of the coating has a projecting part, and the rod of the bottle is curved so that the knob is about ¾ of an inch distant from the projection. This bottle is suspended from the machine, and as rapidly as this is worked large and brilliant sparks pass between the knob and the outer coating, illuminating the outside of the apparatus.

434. **Heating effects.**—Besides being luminous, the electric spark is a source of intense heat. When it passes through inflammable liquids, as ether or alcohol, it inflames them. An arrangement for effecting this is represented in fig. 366. It is a small glass cup through the bottom of which passes a metal rod, terminating in a knob and fixed to a metal foot. A quantity of liquid sufficient to cover the knob is placed in the vessel. The outer coating of the jar having been connected with the foot by means of a chain, the spark which passes when the two knobs are brought near each

Fig. 367.

other, inflames the liquid. With ether the experiment succeeds very well, but alcohol requires to be first warmed.

Coal gas may also be ignited by means of the electric spark. A person standing on an insulated stool places one hand on the conductor of a machine which is then worked, while he presents the other to the jet of gas issuing from a metallic burner. The spark which passes ignites the gas. This experiment may be

curiously varied by igniting the gas by means of a piece of ice held in the hand.

When a battery is discharged through a metal wire it becomes incandescent, and may be melted or even volatilised provided the charge be sufficiently powerful.

For this experiment an apparatus is used which is called the *universal discharger*, for it may be employed in a host of experiments on the electrical discharge. It consists (fig. 367) of two brass rods, A and B, each insulated on a glass stem. These rods can slide along hinged joints, so that they can be placed at any distance from each other and inclined in any direction. Between them is a small table support, which can be placed at any height, and which is intended to support objects which are to be submitted to the action of the discharge.

To melt a metal wire it is fixed at *i* to two knobs fastened on the rods, then connecting one of these by means of a chain with the outside of a powerful battery, the other is brought in contact with the inner coating, either by means of the discharging rod, or by a chain attached to a metal rod fixed on a glass handle. The moment the spark passes between the knob and the battery, the wire, if it is fine enough, is melted in incandescent globules, and is even volatilised, that is, converted into vapours which disappear in the atmosphere. If the wire is thicker it simply becomes red hot but does not melt, and if still larger it is merely heated without becoming luminous.

When an electric discharge is sent through gunpowder placed on the table of a Henley's discharger, it is not ignited, but is projected in all directions. But if a wet string be interposed in the circuit, a spark passes which ignites the powder. This arises from the retardation which electricity experiences in traversing a semi-conductor, such as a wet string; for the heating effect is proportional to the duration of the discharge.

435. **Electrical portraits.**—The fusion of metals by the electrical discharge is applied to make what are called *electrical portraits*. For this purpose a thin card is taken of the shape *abm*, and the design to be copied is cut out: a sheet of tinfoil is fastened on the rest of the card at *a* and *b*, but not at *c*. A leaf of gold is then placed upon the design, care being taken that it touches both the pieces of tinfoil, *a* and *b*. The lateral portion of the card, *m*, is then bent over, the card placed on a silk ribbon, and the whole pressed in a frame, P. When the discharge is passed from *a* to *b*, the

tinfoil being thicker is not melted; but the gold which is very thin is volatilised, and forms on the ribbon through the pattern a brown coating, which reproduces all the details as seen in R.

Fig. 368.

436. **Mechanical effects.**—The mechanical effects are the violent acerations, fractures, and sudden expansions which ensue when a powerful discharge is passed through a badly conducting substance. Glass is perforated, wood and stones are fractured, and gases and iquids are violently disturbed. The mechanical effects of electricity may be demonstrated by a variety of experiments. The body to be submitted to experiment is placed on the plate, N, in contact with the two knobs which terminate the rods, A and B, so hat they cannot receive the discharge without transmitting it to he object on the table. Thus, for instance, if a piece of wood is placed so as to be struck in the direction of the fibres, it is smashed nto pieces the moment the discharge passes.

Fig. 369 represents an arrangement for perforating a piece of glass or card. It consists of two glass columns, with a horizontal cross piece, in which is a pointed conductor. The piece of glass, s placed on an insulating glass support, in which is placed a second onductor, terminating also in a point, which is connected with the utside of the battery, while the knob of the inner coating is brought ear the other knob. When the discharge passes between the two onductors the glass is perforated. The experiment only succeeds ith a single jar when the glass is very thin; otherwise a battery ust be used.

437. **Chemical effects.**—The chemical effects are the decompositions and recombinations effected by the passage of the electrical discharge. When two gases which act on each other are mixed in the proportion in which they combine, a single spark is

generally necessary to determine their combination; but, when either of them is in great excess, a succession of sparks is necessary. Priestley found, that when a series of electric sparks was passed



Fig. 369.

through moist air, its volume diminished, and blue litmus introduced into the vessel was reddened. This, Cavendish found, was due to the formation of nitric acid.

Among the chemical effects must be enumerated the formation of *ozone*, which is recognised by its peculiar odour and by certain chemical properties. The odour is perceived when electricity issues through a series of points from a conductor into the air. Its true nature is not accurately known: some regard it, and with great probability, as an allotropic modification of oxygen, and others as a teroxide of hydrogen.

438. **Magnetic effects.**—By the discharge of a large Leyden jar or battery, a steel wire may be magnetised if it is laid at right angles to the conducting wire, through which the discharge is passed, either in contact with the wire or at some slight distance. And even with less powerful discharges a steel bar or needle may be magnetised by placing it inside a tube on which is coiled a fine insulated copper wire. On passing the discharge through this wire the steel becomes magnetised.

CHAPTER VI.

SPHERIC ELECTRICITY. THUNDER AND LIGHTNING.

Thunder and lightning the effect of electricity.—The sicists who observed the zigzag motion of the electric spark, d it to the gleam of lightning, and its crackling to the thunder. But Franklin, by the aid of powerful electrical , first established a complete parallelism between lightning tricity ; and, in a memoir published in 1749, he indicated riments necessary to attract electricity from the clouds by f pointed rods. The electric fluid, said he, in concluding oir, is attracted by points ; we know not whether lightning ed with the same property ; but, since electricity and lightee in all other respects, it is probable they will not differ in d the *experiment should be made.* The experiment was Dalibard in France ; and Franklin, pending the erection of l rod on a spire in Philadelphia, had the happy idea of flying rovided with a metal point, which could reach the higher of the atmosphere. In June, 1752, during stormy weather, he kite in a field near Philadelphia. The kite was flown inary pack-thread, at the end of which Franklin attached a l to the key a silk cord, in order to insulate the apparatus ; fixed the silk cord to a tree, and having presented his hand ey, at first he obtained no spark. He was beginning to of success, when, rain having fallen, the cord became a nductor, and a spark passed. Franklin, in his letters, s his emotion on witnessing the success of the experiment ; so great that he could not refrain from tears.

klin, who had discovered the power of points (422), but who understand its explanation, imagined that the kite withdrew e cloud its electricity ; it is, in fact, a simple case of induc- l depends on the inductive action which the thunder-cloud pon the kite and the cord.

Atmospheric electricity.—In order to ascertain the e of electricity in the atmosphere, many forms of apparatus en used. To observe the electricity in fine weather, when ion is generally small, an electrometer may be used, as de- r Saussure for this kind of investigation. It is an electro- milar to that already described, but the rod to which the

gold leaves are fixed, is surmounted by a conductor two feet in length, and terminating either in a knob or a point. To protect the apparatus against rain, it is covered with a metallic shield, four inches in diameter. The glass case is square, instead of being round, and a divided scale on its inside face indicates the divergence of the gold leaves.

To ascertain the electricity of the atmosphere, Saussure also used a copper ball, which he projected vertically with his hand. This ball was fixed to one end of a metallic wire, the other end of which was attached to a ring, which could glide along the conductor of the electrometer. From the divergence of the gold leaves the electrical condition of the air at the height which the ball had attained could be determined. M. Becquerel, in experiments made on Mont St. Bernard, improved Saussure's apparatus by substituting for the knob an arrow, which was projected into the atmosphere by means of a bow. A gilt silk thread, eighty-eight yards long, was fixed with one end to the arrow, while the other was attached to the stem of an electroscope.

Sometimes also kites are used, provided with a point, and connected by means of a gilt cord with an electrometer. Captive balloons are also similarly used.

A good collector of atmospheric electricity consists of a fishing rod with an insulating handle, which projects from an upper window. At the top is a bit of lighted tinder held in metal forceps, the smoke of which, being an excellent conductor, conveys the electricity of the air down a wire attached to the rod. A sponge moistened with alcohol, and set on fire, is also an excellent conductor.

441. **Ordinary electricity of the atmosphere.**—By means of the different apparatus which have been described, it has been found that the presence of electricity in the atmosphere is not confined to stormy weather, but that the atmosphere always contains free electricity, sometimes positive and sometimes negative. When the sky is cloudless, the electricity is always positive, but it varies in intensity with the height of the locality, and with the time of day. The intensity is greatest in the highest and most isolated places. No trace of positive electricity is found in houses, streets, or under trees ; in towns, positive electricity is most perceptible in large open spaces, on quays, or on bridges. In all cases, positive electricity is only found at a certain height above the ground. On flat land it only becomes perceptible at a height of five feet ; above that point it

ıcreases according to a law which is not made out, but which seems) depend on the hygrometric state of the air.

When the sky is clouded, the electricity is sometimes positive nd sometimes negative. It often happens that the electricity hanges its sign several times in the course of the day, owing to the assage of an electrified cloud. During storms, and when it rains · snows, the atmosphere may be positively electrified one day, and :gatively the next, and the numbers of the two sets of days are rtually equal.

The electricity of the ground has been found by Peltier to be ways negative, but to different extents, according to the hygrome-ic state and temperature of the air.

Many hypotheses have been propounded to explain the origin of e atmospheric electricity. Some have ascribed it to the friction the air against the ground, some to the vegetation of plants, or to e evaporation of water. Some, again, have compared the earth a vast voltaic pile, and others to a thermo-electrical apparatus. any of these causes may, in fact, concur in producing the phe-ɔmena.

442. **Lightning.**—This, as is well known, is the dazzling light nitted by the electric spark when it shoots from clouds charged ith electricity. In the lower regions of the atmosphere the light white, but in the higher regions, where the air is more rarefied, it kes a violet tint; as does the spark of the electrical machine in a refied medium (421).

The flashes of lightning are sometimes several miles in length; ey generally pass through the atmosphere in a zigzag direction; a ıenomenon ascribed to the resistance offered by the air condensed the passage of a strong discharge. The spark then diverges ɔm a white line, and takes the direction of least resistance. In ıcuo electricity passes in a straight line.

Several kinds of lightning-flashes may be distinguished: 1. The *zıag* flashes, which move with extreme velocity in the form of a ıe of fire with sharp outlines, and which closely resemble the ark of an electrical machine. 2. The flashes which, instead of ing linear, like the preceding, fill the entire horizon without having y distinct shape. This kind, which is most frequent, appears to produced in the cloud itself, and to illuminate the mass. Another nd is called *heat lightning*, because it illuminates the summer ghts without the presence of any clouds above the horizon, and ithout producing any sound. The most probable of the many hy-

potheses which have been proposed to account for its origin, is that which supposes it to consist of ordinary lightning flashes, which strike across the clouds at such distances that the rolling of thunder cannot reach the ear of the observer. There are, further, the lightning flashes which appear in the form of globes of fire. These, which are sometimes visible for as much as ten seconds, descend from the clouds to the earth with such slowness that the eye can follow them. They often rebound on reaching the ground; at other times they burst and explode with a noise like that of the report of many cannon. This is sometimes known as *globe lightning*.

The duration of the light of the first three kinds does not amount to a thousandth of a second, as has been determined by Mr. Wheatstone by means of a rotating wheel, which was turned so rapidly that the spokes were invisible; on illuminating it by the lightning-flash, its duration was so short that whatever the velocity of rotation of the wheel, it appeared quite stationary; that is, its displacement is not perceptible during the time the lightning exists.

443. **Thunder.**—*Thunder* is the violent report which succeeds lightning in stormy weather. The lightning and the thunder are always simultaneous, but an interval of several seconds is always observed between these two phenomena, which arises from the fact that sound only travels at the rate of about 1,100 feet in a second (161), while the passage of light is almost instantaneons. Hence an observer will only hear the noise of thunder five or six seconds, for instance, after the lightning, according as the distance of the thunder-cloud is five or six times 1,100 feet. The noise of thunder arises from the disturbance which the electric discharge produces in the air. Near the place where the lightning strikes, the sound is dry and of short duration. At a greater distance a series of reports are heard in rapid succession. At a still greater distance the noise, feeble at the commencement, changes into a prolonged rolling sound of varying intensity. Some attribute the noise of the rolling of thunder to the reflection of sound from the ground and from the clouds. Others have considered the lightning not as a single discharge, but as a series of discharges, each of which gives rise to a particular sound. But as these partial discharges proceed from points at different distances, and from zones of unequal density, it follows not only that they reach the ear of the observer successively, but that they bring sounds of unequal density, which occasion the duration and inequality of the rolling. The phenomenon has finally been ascribed to the zigzags of lightning themselves,

assuming that the air at each salient angle is at its greatest compression, which would produce the unequal intensity of the sound.

444. **Effects of lightning.**—The lightning discharge is the electric discharge which strikes between a thunder-cloud and the ground. The latter, by the induction from the electricity of the cloud, becomes charged with contrary electricity, and when the tendency of the two electricities to combine exceeds the resistance of the air, the spark passes, which is often expressed by saying that a thunder-bolt has fallen. Lightning in general strikes from above, but *ascending lightning* is also sometimes observed; probably this is the case when the clouds being negatively, the earth is positively electrified; for experiments seem to show that at the ordinary pressure the positive electricity passes through the atmosphere more easily than negative electricity.

From the law of electric attraction (which is, that it is inversely as the square of the distance), the discharge ought to fall first on the nearest and best-conducting objects, and, in fact, trees, elevated buildings, metals, are more particularly struck by the discharge, Hence it is imprudent to stand under trees during a thunder-storm.

The effects of lightning are very varied, and of the same kind as those of batteries (431), but of far greater intensity. The lightning discharge kills men and animals, inflames combustible matters, melts metals, breaks bad conductors in pieces. When it penetrates the ground it melts the siliceous substance in its way, and thus produces in the direction of the discharge those remarkable vitrified tubes called *fulgurites*, some of which are as much as twelve yards in length. When it strikes bars of iron, it magnetises them, and often inverts the poles of compass needles.

After the passage of lightning, a highly peculiar odour is sometimes produced, like that perceived in a room in which an electrical machine is being worked. This odour is due to the formation of a peculiar oxygenised compound, to which the name *ozone* has been given; this, we have seen, is considered to be a peculiar allotropic modification of oxygen.

Many persons have a very lively fear of the effects of the lightning discharge. This fear would be materially diminished if we remembered the very small number of persons who are really killed by lightning. Arago has estimated the number for France at twenty in a year; this is, one victim for two million inhabitants; which is

a far less proportion than that of many other accidents which *do* not excite nearly so much fear.

445. **Return shock.**—This is a violent and sometimes fatal shock which men and animals experience, even when at a great distance from the place where the lightning discharge passes. This is caused by the inductive action which the thunder-cloud exerts on bodies placed within the sphere of its activity. These bodies are then, like the ground, charged with the opposite electricity to that of the cloud; but when the latter is discharged by the recombination of its electricity with that of the ground, the induction ceases, and the bodies reverting rapidly from the electrical state to the neutral state, the concussion in question is produced, the *return shock*. A more gradual decomposition and reunion of the electricity produces no visible effects; yet it appears that such disturbances of the electrical equilibrium are perceived by nervous persons.

The return shock is always less violent than the direct one: there is no instance of its having produced any inflammation, yet plenty of cases in which it has killed both men and animals; in such cases no broken limbs, wounds, or burns, are observed.

The return shock may be imitated by placing a gold leaf electroscope, connected by a wire with the ground, near the prime conductor of a strong electrical machine in action; at each spark taken from the machine, the leaves suddenly diverge.

446. **Lightning conductor.**—The ordinary form of this instrument is an iron rod, through which passes the electricity of the ground attracted by the opposite electricity of the thunder-clouds. It was invented by Franklin in 1755.

There are two principal parts in a lightning conductor: the rod and the conductor. The *rod* (fig. 371) is a pointed bar of iron, fixed vertically to the roof of the edifice to be protected; it is from six to ten feet in height, and its basal section is about two or three inches in diameter. The conductor is a bar of iron which descends from the bottom of the rod to the ground, which it penetrates to some distance. As, in consequence of their rigidity, iron bars cannot always be well adapted to the exterior of buildings, lightning conductors are best formed of wire cords, such as are used for rigging and for suspension bridges. The conductor is usually led into a well, and to connect it better with the soil it ends in two or three branches. If there is no well in the neighbourhood, a hole is dug in the soil to a depth of six or seven yards, and the foot of the conductor having been introduced, the hole is filled with wood-ashes,

conduct very well and yet preserve the metal from oxidation. red coke does equally well.

the action of a lightning conductor depends on induction and wer of points (410), Franklin, as soon as he had established ntity of lightning and electricity, assumed that lightning con- withdrew electricity from the clouds ; the converse is the When a storm-cloud, positively electrified, for instance, rises atmosphere, it acts inductively on the earth, repels the posi-

Fig. 370.

d attracts the negative fluid, which accumulates in bodies on the surface of the soil the more abundantly as these are at a greater height. The tension is then greatest on the bodies, which are therefore most exposed to the electric ge ; but if these bodies are provided with metallic points, rods of conductors, the negative fluid, withdrawn from the the influence of the cloud, flows into the atmosphere, and ises the positive fluid of the cloud. Hence, not only does a ig conductor tend to prevent the accumulation of electricity surface of the earth, but it also tends to restore the clouds to tural state, both which actions concur in preventing lightning ges. The disengagement of electricity is, however, some- o abundant, that the lightning conductor is inadequate to ge the ground, and the lightning strikes; but the conductor

receives the discharge, in consequence of its greater conductivity, and the building is preserved.

It is stated that, approximately, a lightning conductor protects a circular space around it, the radius of which is double its

Fig. 371.

height. Thus a building, sixty-four yards in length, would be preserved by two rods eight yards in height, at a distance of thirty-two yards.

447. **Aurora borealis.**—The *aurora borealis*, or northern light, or more properly *polar aurora*, is a remarkable luminous phenomenon which is frequently seen in the atmosphere at the two terrestrial poles, but more especially at the north pole. At the close of the day an indistinct light appears in the horizon in the direction of the magnetic meridian. This luminosity gradually changes into a regular arc of a pale yellow with its concave side turned towards the earth. Finally, the rays burst all over the horizon, passing necessarily from yellow to deep green, and to the most brilliant purple. All these rays converge towards one point of the horizon, which is the prolongation of the dipping needle, and they form then a fragment of an immense luminous cupola.

When the luminous arc is formed it often remains visible for some hours; then the lustre diminishes, the colours disappear, and this brilliant phenomenon gradually diminishes, or is suddenly extinguished.

Numerous hypotheses have been devised to account for the auroræ boreales. The constant direction of their arc as regards the magnetic meridian, and their action on the magnetic needle (394), show that they ought to be attributed to electric currents in the

Fig. 372.

higher regions of the atmosphere. This hypothesis is confirmed by the circumstance that during the prevalence of the aurora borealis, electric telegraph lines are spontaneously affected in a powerful but irregular manner; needles are deflected, armatures attracted, and alarums rung. This interference is at times so serious, especially in northern countries, that it is necessary to suspend the ordinary transmission of messages.

According to M. de la Rive the auroræ boreales are due to electric discharges which take place in polar regions between the positive electricity of the atmosphere and the negative electricity of the terrestrial globe; electricities which themselves are separated by the action of the sun, principally in the equatorial regions.

In Chapter XII. an experiment will be described which De la Rive has devised in support of this hypothesis.

448. **St. Elmo's fire.**—This name is given by sailors to the luminous brushes or stars which sometimes appear at the tops of masts and yards of vessels, and which are sometimes accompanied by a cracking sound, which resembles the sparks taken from electrical machines.

These luminous effects were known to the ancients. Pliny speaks of the fiery stars seen on the ends of soldiers' lances. When they were two in number they were compared to Castor and Pollux, and that was a favourable presage; if only one appeared, it was likened to their sister Helena, which was considered a bad omen.

St. Elmo's fire is a simple case of induction. The atmospheric electricity acting on conductors decomposes the neutral fluid, attracting the contrary electricity; which, from the power of points, being liberated at the extremities of the masts, or by the metal of the lances, gives rise to the luminous brush. The same effect is observed when, placing a metal point on the conductor of the electrical machine, it is made to work in darkness.

CHAPTER VII.

ELECTRICITY DUE TO CHEMICAL ACTION. VOLTAIC BATTERY.

449. **Galvani's experiment.**—We have already seen that the two most powerful sources of electricity are friction and chemical combination. Having described the former, we are now to be concerned with the latter. Yet we may premise that this is not a new kind of electricity, but only another method for its production far more abundant than friction, and leading to the most remarkable effects.

To Galvani, professor of anatomy in Bologna, is due the discovery in 1790 of these new electrical phenomena, to which he was led by a casual observation. It is said that a dead frog being accidentally suspended by a hook of copper to the iron railings of a balcony, was observed to be violently contracted whenever the legs of the animal came in contact with the iron bars.

Galvani's observation may be reproduced in the following manner: the legs of a recently killed frog are prepared, and suspended

a copper hook, which passes between the vertebral column, and the nerve filaments on each side of it. If then the copper support and the legs are momentarily connected by a plate of zinc *z*, at each contact a smart contraction of the muscles ensues (fig. 373).

Fig. 373.

Galvani had some time before, observed that the electricity of machines produced in dead frogs analogous contractions, and he attributed the phenomena first described to an electricity inherent in the animal. He assumed that this electricity, which he called *vital fluid*, passed from the nerves to the muscles by the metallic arc, and was thus the cause of contraction. This theory met with great support, especially among physiologists, but it was not without opponents. The most considerable of these was Alexander Volta, professor of physics in Pavia.

450. **Volta's fundamental experiment.**—Galvani's attention had been exclusively devoted to the nerves and muscles of the frog; Volta's was directed upon the connecting metal. Resting on the observation, which Galvani had also made, that the contraction is more energetic when the connecting arc is composed of two metals than when there is only one, Volta attributed to the metals the active part in the phenomenon of contraction. He assumed that the disengagement of electricity was due to their contact, and that the animal parts only officiated as conductors, and at the same time as a very sensitive electroscope.

By means of the then recently invented electroscope, Volta devised several modes of showing the disengagement of electricity on the contact of metals, of which the following is the easiest to perform:

The moistened finger being placed on the upper plate of a con-

densing electroscope (fig. 362, p. 453), the lower plate is touched with a plate of copper, *c*, soldered to a plate of zinc, *z*, which is held in the other hand. On breaking the connection and lifting the upper plate (fig. 363), the gold leaves diverge, and, as may be proved, with negative electricity. Hence, when soldered together, the copper is charged with negative electricity, and the zinc with positive electricity. The electricity could not be due either to friction or pressure; for if the condenser plate, which is of copper, is touched with the zinc plate, *z*, the copper plate to which it is soldered being held in the hand, no trace of electricity is observed.

A memorable controversy arose between Galvani and Volta. The latter was led to give greater extension to his contact theory, and propounded the principle, that when *two heterogeneous substances are placed in contact, one of them always assumes the positive and the other the negative electrical condition.* In this form Volta's theory obtained the assent of the principal philosophers of his time.

Fig. 374.

451. **Voltaic pile.**—Reasoning from this theory of contact, Volta

led, in 1800, to the invention of the marvellous instrument which ıortalised him, and which is known to this day as the *Voltaic* . Wishing to multiply the points of contact, and to collect the tricities produced by each, Volta arranged, as represented in re 374, a disc of zinc, a disc of copper, then a round piece of h moistened with acidulated water, then again a disc of zinc, a : of copper, a piece of cloth, and so forth, great care being taken ays to preserve the same order. What was to be expected from h a combination? Arago says, 'I do not hesitate to assert, that mass so inert in appearance, this pile of so many couples netal separated by a little liquid, is, as regards the singularity of effects, the most remarkable instrument which has ever been in- ted, without even excepting the telescope and the steam engine.' On Volta's view the union of one zinc and one copper forms *a ble*; in the above figure twenty couples are superposed, separated n each other by pieces of cloth, and all arranged in the same er, so that one extremity terminates in a disc of copper, and the er in a disc of zinc. Since its invention it has been greatly lified; but the general name of pile has been retained for all aratus of the same kind, and the electricity furnished by piles is ken of as *voltaic electricity*.

452. **Disengagement of electricity in chemical actions.**— : contact theory which Volta had propounded, and in which he ex- ned the action of the pile, soon encountered objectors. Fabroni, ountryman of Volta, having observed that in the pile the discs inc became oxidised in contact with the acidulated water, ught that this oxidation was the principal cause of the disen- ement of electricity. In England Wollaston soon advanced the ıe opinion, and Davy supported it by many ingenious experi- ıts.

It is true that in the fundamental experiment of the contact ory (451) Volta obtained signs of electricity. But M. de la Rive shown, that if the zinc be held in a wooden clamp, all signs of tricity disappear, and that the same is the case if the zinc be ced in gases, such as hydrogen or nitrogen, which exert upon it chemical action. De la Rive has accordingly concluded, that in lta's original experiment the disengagement of electricity is due he chemical actions which result from the perspiration and from oxygen of the atmosphere.

By a variety of analogous experiments it may be shown, that all mical actions are accompanied by a disturbance of the electrical

equilibrium. This is the case whether the substances concerned in the action are in the solid, liquid, or gaseous state, though of all chemical actions those between metals and liquids are the most productive of electricity. All the various resultant effects may be explained on the general principle, that when a liquid acts chemically on a metal the liquid assumes the positive electrical, and the metal the negative electrical condition.

Hence we arrive at a theory of the origin of electricity in the voltaic pile which will be best illustrated by reference to the following simple experiment.

453. **Current electricity.**—When a plate of zinc, and a plate of copper are partially immersed in dilute sulphuric acid, by means of delicate electroscopic arrangements it may be shown, that the zinc plate possesses a feeble charge of negative and the copper plate a feeble charge of positive electricity. At the same time there is a slight disengagement of hydrogen gas from the surface of the zinc. If now the plates be placed in direct contact, or, more conveniently, be connected by means of a metal wire, the chemical action increases, but the hydrogen is now disengaged from the surface of the copper (fig. 375); and if the connecting wire be examined, it will be found to possess the remarkable properties characteristic of the discharge of opposite electricities. So long as the metals remain in the liquid, the opposite electrical conditions of the two plates discharge themselves by means of the wire, but are instantaneously restored, and as rapidly discharged; and as these successive charges and discharges take place at such infinitely small intervals of time that they may be considered continuous, the wire is said to be traversed by an electric or voltaic *current*. The direction of this current *in the connecting wire* is assumed to be from the copper to the zinc; or, in other words, this is the direction in which the positive electricity is supposed to flow, the direction of the negative current in the wire being from the zinc to the copper. But the existence of this current is purely hypothetical, and must not be taken as more than a convenient mode of explaining the phenomena developed in the wire.



Fig. 375.

454. **Voltaic couple. Electromotive series.**—The arrange-

t just described, consisting of two metals in metallic contact, a conducting liquid in which they are placed, constitutes a *le voltaic element* or *couple*. So long as the metals are not ontact, the couple is said to be *open*, and when connected it is *d*.

For the production of a voltaic current it is not necessary that of the metals be unaffected by the liquid, but merely that the nical action upon the one be greater than upon the other. The l which is most attacked is called the *positive* or *generating* , and that which is least attacked the *negative* or *collecting* . The positive metal determines the direction of the current, h proceeds *in* the liquid from the positive to the negative plate, *out* of the liquid through the connecting wire from the negative e positive plate.

n speaking of the direction of the current, the positive current ways understood ; to avoid confusion, the existence of the current e opposite direction, the negative current, is tacitly ignored.

a voltaic current is produced whenever two metals are placed etallic contact in a liquid which acts more powerfully upon one upon the other, there is great choice in the mode of producing currents. In reference to their electrical deportment, the ls have been arranged in what is called an *electromotive series*, hich the most *electropositive* are at one end, and the most *ronegative* at the other. Hence when any two of these are ed in contact in dilute acid, the current in the connecting wire eeds from the one lower in the list to the one higher. The ipal metals are as follows :—

Zinc	Nickel	Gold
Lead	Copper	Platinum
Iron	Silver	Graphite.

hus iron placed in dilute sulphuric acid is electronegative rds zinc, but is electropositive towards copper; copper in turn ectro-negative towards iron and zinc, but is electropositive rds silver, platinum, or graphite.

he force produced by the difference in chemical action on two ls in a liquid is called the *electromotive force* ; it is greater in ortion to the distance of the two metals from one another in the s. That is to say, it is greater, the greater the difference een the chemical action upon the two metals immersed. Thus

the electromotive force between zinc and platinum is greater than that between zinc and iron, or between zinc and copper.

455. **Poles and electrodes.**—If the wire connecting the two terminal plates of a voltaic couple be cut, it is clear, from what has been said about the origin and direction of the current, that positive electricity will tend to accumulate at the end of the wire attached to the copper or negative plate, and negative electricity on the wire attached to the zinc or positive plate. These terminals have been called the *poles* of the battery. For experimental purposes, more especially in the decomposition of salts, plates of platinum are attached to the ends of the wires. Instead of the term poles the word *electrode* (ἤλεκτρων and ὁδός, a way) is now commonly used; for these are the *ways* through which the respective electricities emerge. It is important not to confound the positive *plate* with the positive *pole* or *electrode*. The positive electrode is that connected with the negative plate, while the negative electrode is connected with the positive plate.

456. **Voltaic battery.**—When a series of voltaic elements or pairs are arranged in such a manner that the zinc of one element is connected with the copper of another; the zinc of this with the copper of another, and so on, such an arrangement is called a *voltaic battery*; and by its means the effects produced by a single element are capable of being very greatly increased.

The earliest of these arrangements was the voltaic pile devised by Volta himself.

It will be readily seen that it is merely a series of simple voltaic couples, the moistened disc acting as the liquid, and that the terminal zinc is the negative and the terminal copper the positive pole. From the mode of its arrangement, and from its discoverer, the apparatus is known as the *voltaic pile*, a term applied to all apparatus of this kind for accumulating the effects of dynamical electricity.

The distribution of electricity in the pile varies according as it is in connection with the ground by one of its extremities, or as it is insulated by being placed on a non-conducting cake of resin or glass.

In the former case, the end in contact with the ground is neutral, and the rest of the apparatus only contains one kind of electricity; this is negative, if a copper disc is in contact with the ground, and positive if it is a zinc disc.

In the insulated pile the electricity is not uniformly distributed

neans of the proof-plane and the electroscope it may be de-
strated that the middle part is in a neutral state, and that one-
is charged with positive and the other with negative electricity,
tension increasing from the middle to the ends. The half
inated by a zinc is charged with negative electricity, and that
copper with positive electricity. The effects of the pile will
liscussed in other places.

The original form of the voltaic pile—for it possesses now only
istorical interest—has a great many inconveniences ; among
e is the fact, that the weight of the discs of zinc and copper is
reat that it presses out the acidulated liquid from the discs, and
electrical action is soon weakened. It has received a great
y improvements, the principal object of which has been to
litate manipulation, and to produce greater electromotive force.
One of the earliest of these modifications was the crown of cups,
couronne des tasses, invented by Volta himself: an improved
n of this is known as *Wollaston's battery* (fig. 378).

Fig. 376 gives a vertical section of two consecutive Wollaston's
ients. The acidulated water is contained in glass vessels, B B



Fig. 376.



Fig. 377.

ach of which is a couple. Fig. 377 represents the arrangement
ne of these couples : it consists of a thick sheet of zinc, Z, and a
of copper, *o*, by which it can be connected with the next
ple. A plate of copper, C C, is bent so as to surround the plate
nc without touching, contact being prevented by small pieces of

cork. The plate, C, is provided with a copper tongue, o', which is soldered to the zinc of the next couple and so forth.

Fig. 378 represents a pile of sixteen couples united in two parallel series of eight each. All these couples are fixed to a cross



Fig. 378.

frame of wood, by which they can be raised or lowered at pleasure. When the battery is not wanted, the couples are lifted out of the liquid. The water in these vessels is usually acidulated with $\frac{1}{10}$ sulphuric and $\frac{1}{20}$ of nitric acid.

457. **Enfeeblement of the current in batteries. Secondary currents.**—The batteries already described, Volta's and Wollaston's, which consist essentially of two metals and one liquid, labour under the objection that the currents produced rapidly diminish in intensity.

This is principally due to three causes; the first is the decrease in the chemical action owing to the neutralisation of the sulphuric acid by its combination with the zinc. This is a necessary action, for upon it depends the current; it therefore occurs in all batteries, and is without remedy, except by replacement of the acid and zinc. The second is due to what is called *local action*; that is, the production of small closed currents in the active metal, from the impurities it contains. These local currents rapidly wear away the active plate, without contributing anything to the general current.

ney are remedied by amalgamating the zinc with mercury, by hich chemical action is prevented until the circuit is closed. The ird arises from *secondary currents*. These are currents which are oduced in the battery in a contrary direction to the principal cur-nt, and which destroy it either totally or partially. In the funda-ental experiment (fig. 367), when the current is closed, sulphate zinc is formed, which dissolves in the liquid, and at the same ne a layer of hydrogen gas is gradually deposited on the surface the copper plate. Now it has been found, that the hydrogen de-sited in this manner on metallic surfaces acts far more energeti-lly than ordinary hydrogen. In virtue of this increased activity gradually reduces some of the sulphate of zinc formed, and a yer of metallic zinc is formed upon the copper; hence, instead of ving two different metals unequally attacked, the two metals be-me gradually less different, and, consequently, in the wire there e two currents tending to become equal; the total effect, and the rrent really observed, become weaker and weaker.

458. **Constant batteries. Daniell's.**—The serious objections the use of what are called *single fluid* elements has led to their ndonment, and they are now replaced by *two fluid* elements, hich are both more constant and more powerful. They have been placed by batteries with two liquids, which are called *constant tteries*, because their action is without material alteration for a onsiderable period of time. The es-ntial point to be attended to in ecuring a constant current is to pre-ent the polarisation of the inactive etal; in other words, to hinder any ermanent deposition of hydrogen on s surface. This is effected by plac-g the inactive metal in a liquid upon hich the deposited hydrogen can act hemically.

Fig. 379.

459. **Daniell's battery.**—This was e first form of the constant battery, nd was invented by Daniell in the ar 1836. As regards the constancy f its action, it is still the best of all nstant batteries. Fig. 379 repre-nts a single element. A glass or porcelain vessel, V, contains a turated solution of sulphate of copper, in which is immersed a

copper cylinder, C, open at both ends, and perforated by holes. At the upper part of this cylinder there is an annular shelf, G, also perforated by small holes, and below the level of the solution: this is intended to support crystals of sulphate of copper to replace that decomposed as the electrical action proceeds. Inside the cylinder is a thin porous vessel, P, of unglazed earthenware. This contains either a solution of common salt or dilute sulphuric acid, in which is placed the cylinder of amalgamated zinc, Z. Two thin strips of copper, *p* and *n*, fixed by binding screws to the copper and to the zinc, serve for connecting the elements in series.

When a Daniell's element is closed, the hydrogen resulting from

Fig. 380.

the action of the dilute acid on the zinc is liberated on the surface of the copper plate, but meets there the sulphate of copper, which is reduced, forming sulphuric acid and metallic copper which is deposited on the surface of the copper plate. In this way the sulphate of copper in the solution is taken up, and if it were all consumed, hydrogen would be deposited on the copper, and the current would lose its constancy. This is prevented by the crystals of sulphate of copper which keep the solution saturated. The sulphuric acid produced by the decomposition of the sulphate permeates the porous cylinder, and tends to replace the acid used up by its action on the zinc; and as the quantity of sulphuric acid formed in the solution of sulphate of copper is regular, and proportional to the acid used in dissolving the zinc, the action of this acid on the zinc is regular also, and thus a constant current is produced.

Fig. 380 represents a series of three Daniell's elements of a newhat different pattern. Here the zinc of one is connected h the copper of the next by a copper strip. Instead of placing crystals of sulphate of copper on a shelf in the copper plate, y are contained in glass flasks, the necks of which are immersed a solution of sulphate of copper. This form of element is exten-ely used in the French telegraphs.

460. **Bunsen's battery.**—*Bunsen's battery*, also known as the *c carbon* battery, was invented in 1843; it is nothing more than niell's battery, in which nitric acid is substituted for solution of phate of copper, and in which copper is replaced by a cylinder



Fig. 381.

carbon. This is made either of the graphitoidal carbon depo-ed in gas retorts, or by calcining in an iron mould an intimate ixture of coke and bituminous coal, finely powdered and strongly mpressed. Both these modifications of carbon are good con-uctors. Each element consists of the following parts: 1. a vessel, (fig. 381), either of stoneware or of glass, containing, as in aniell's, dilute sulphuric acid; 2. a hollow cylinder, Z, of amalga-ated zinc; 3. a porous vessel, V, in which is ordinary nitric acid; a cylinder of carbon, C, prepared in the above manner. In the ssel, F, the zinc is first placed, and in it the carbon as seen in P. the carbon is fixed a binding screw, *m* (fig. 382), to which a pper wire is attached, forming the positive pole. The zinc is ovided with a similar binding screw, *n*, and wire, which is thus negative pole.

In Bunsen's battery the hydrogen resulting from the action is

Fig

clamps, *mn*, and a strip of coppe
figure. The copper is pressed a
the clamp, and at the other it is
fitted on the zinc of the following
of the first carbon and that of th
binding screws, to which are atta

461. **Leclanche's battery.**— sists of a rod of carbon placed in packed with a mixture of

CHAPTER VIII.

EFFECTS OF THE BATTERY.

462. **Physiological effects.**—The remarkable phenomena of the voltaic battery may be classed under the heads physiological, chemical, mechanical, and physical effects; and these latter may be again subdivided into the thermal, luminous, and magnetic

Fig. 383.

effects. All are due to the recombination of the opposite electricities like those of the electrical machine; but they are far more remarkable and more energetic, owing to the continuity of their action. To produce them the body experimented upon must be connected on the one side with the positive and on the other with the negative pole.

The *physiological effects* consist of shocks and violent contractions which the current produces in the muscles, not only of living, but of dead animals, as has been seen in Galvani's experiment with the frog.

When the electrodes of a strong battery are held in the two hands a violent shock is felt, resembling that of a Leyden jar, especially if the hands are moistened with acidulated or saline water, which increases the conductivity. The shock is more violent in proportion to the number of elements used; with a Bunsen's battery of 50 to 60 couples the shock is very strong, with 150 or 200 couples it is unbearable, and even dangerous when continued. It is less perceptible in the fore part of the arms than the shock of the Leyden jar, and when transmitted through a chain of several persons, it is generally only felt by those nearest the poles.

The shock, as in the case of the Leyden jar, is due to the recomposition of the two electricities; with this difference, that with the Leyden jar the discharge being instantaneous, the resultant shock is so also; while in the latter case, as the battery is immediately recharged after each discharge, the shocks succeed each other with rapidity.

John Aldina, a nephew of Galvani, was the first to study the action of the battery on dead animals. He came to Paris at the beginning of the present century, and repeated on a large scale several of his experiments at the veterinary school of Alfort near Paris.

463. **Thermal effects.**—When a voltaic current is passed through a metallic wire the same effects are produced as by the discharge of an electric battery; the wire becomes heated and even incandescent if it is very short and thin. With a powerful battery all metals are melted, even iridium and platinum, the least fusible of metals. Carbon is the only body which hitherto has not been fused by it. M. Despretz, however, with a battery composed of 600 Bunsen's elements joined in six series, has raised rods of very pure carbon to such a temperature that they were softened and could be welded together, indicating an incipient fusion.

A battery of thirty to forty Bunsen's elements is sufficient to melt and volatilise fine wires of [illegible]in, zinc, copper, gold, silver, iron, and even platinum, wi[illegible]tly colour[illegible] Iron and [illegible]num burn with a [illegible]e light [illegible]ple ligh[illegible] light of tin ar[illegible]uish [illegible]nc is [illegible]e of white [illegible]ally [illegible]e a

reen light. The heating effects of the voltaic current are used in ring mines for military purposes and for blasting operations.

464. **Luminous effects.**—In closing a voltaic battery a spark is btained at the point of contact, which is frequently of great brilliance. A similar spark is also perceived on breaking contact. These luminous effects are obtained when the battery is sufficiently owerful, by bringing the two electrodes very nearly in contact; a

Fig. 384.

uccession of bright sparks springs across the interval, which llow each other with such rapidity as to produce a continuous ght. With eight or ten of Grove's elements brilliant luminous

sparks are obtained by connecting one terminal of the battery wi a file, and moving its point along the teeth of another file connect with the other terminal.

The most beautiful effect of the electric light is obtained wh two pencils of charcoal are connected with the terminals of a powerful battery in the manner represented in fig. 384. The two charcoals being placed in contact the current passes, and their ends soon become incandescent. If they are then removed to a distance of about the tenth of an inch, according to the intensity of the current, a luminous arc extends between the two points, which has an exceedingly brilliant lustre, and is called the *voltaic arc.*

The length of this arc varies with the force of the current. In air it may exceed two inches with a battery of 600 elements. If the charcoal attached to the positive pole be examined, it will be found to have become hollowed, and worn away, while the negative charcoal has increased. It thus seems that the carbon is transported from the positive to the negative pole, and that this is the manner in which the transmission of the electricity between the two poles is effected.

The intensity of the electric light is very great. Bunsen, in experimenting with forty-eight couples, and removing the charcoals to a distance of a quarter of an inch, found that the intensity of the electric light is equal to that of 572 candles.

Too great precautions cannot be taken against the effect of the electric light when they attain a certain intensity. The light of 100 couples, he says, may produce very painful affections of the eyes. With 600, a single moment's exposure to the light is sufficient to produce very violet headaches and pains in the eye, and the whole frame is affected as by a powerful sunstroke.

Attempts have been made to apply the electric light to the illumination of rooms and even of streets; but partly the cost, and partly the difficulty of producing with it a uniform illumination, inasmuch as the shadows are thrown into too sharp relief, have hitherto been great obstacles to its use. Yet it is advantageously applied in special cases, such as the photo-electric microscope, illuminations in theatres, &c. Fig. 384 represents an arrangement for public illumination. On a convenient support, an electric lamp is placed; this is a mechanism which is worked by the current from a powerful battery, and which keeps the carbon poles at a suitable distance, a condition necessary for the permanence and steadiness of the light.

DECOMPOSITION OF WATER.

465. **Chemical effects.**—These are among the most important of all the actions, either of the simple or compound circuit. They consist of the separation and transport of the elements of the bodies traversed by the current. The first decomposition effected by the battery was that of water, obtained in 1800 by Carlisle and Nicholson by means of a voltaic pile. Water is rapidly decomposed by four or five Bunsen's cells; the apparatus (fig. 385) is very con-



Fig. 385.

venient for the purpose. It consists of a glass vessel fixed on a wooden base. In the bottom of the vessel two platinum electrodes are fitted, communicating by means of copper wires with the binding screws, *a* and *b*. The vessel is filled with water to which some sulphuric acid has been added to increase its conductivity, for pure water is a very imperfect conductor; two glass tubes filled with water are inverted over the electrodes, and, on interposing the apparatus in the circuit of a battery, decomposition is rapidly set up, and gas bubbles rise from the surface of each pole. The volume of gas liberated at the negative pole is about double that at the positive, and on examination the former gas is found to be hydrogen and the latter gas oxygen. This experiment accordingly gives at once the qualitative and quantitative analysis of water; for it shows that its composition consists of two parts by volume of hydrogen to one part by volume of oxygen.

466. **Electrolysis.**—To those substances which, like water, are resolved into their elements by the voltaic current, the term *electrolyte* has been applied by Faraday, to whom the principal discoveries in this subject, and the nomenclature are due; *electrolysis* is the decomposition by the voltaic battery.

By means of the battery, the compound nature of several substances which had previously been considered as elements has been determined. By means of a battery of 250 couples, Davy, shortly after the discovery of the decomposition of water, succeeded in decomposing the alkalies potass and soda, and proved that they were the oxides of the hitherto unknown metals *potassium* and *sodium*. The decomposition of potass may be demonstrated with the aid of the battery of four to six elements in the following manner; a small cavity is made in a piece of solid caustic potass, which is moistened, and a drop of mercury placed in it (fig. 386). The potass is placed on a piece of platinum connected with the positive pole of the battery. The mercury is then touched with the negative pole. When the current passes, the potass is decomposed, oxygen is liberated at the positive pole, while the potassium liberated at the negative pole amalgamates with the mercury. On distilling this amalgam out of contact with air, the mercury passes off, leaving the potassium.



Fig. 386.

The decomposition of binary compounds, that is, bodies containing two elements, is quite analogous to that of water and of potass; one of the elements goes to the positive, and the other to the negative pole. The bodies separated at the positive pole are called *electronegative* elements, because at the moment of separation they are considered to be charged with negative electricity, while those separated at the negative pole are called *electropositive* elements. One and the same body may be electronegative or electropositive, according to the body with which it is associated. For instance, sulphur is electronegative towards hydrogen, but is electropositive towards oxygen. The various elements may be

arranged in such a series that any one in combination is electronegative to any following, but electropositive towards all preceding ones. This is called the *electrochemical series*, and begins with oxygen as the most electronegative element, ending with potassium as the most electropositive.

APPLICATION OF THE DECOMPOSITION PRODUCED BY THE BATTERY.

467. **Electrotype.**—In the ordinary methods of reproducing in metal statues, basreliefs, etc., moulds of dry earth are prepared, which are faithful hollow copies of these objects; then either melted iron or bronze are run into these; when the metal is solid, an exact copy in relief is obtained of the object. In electrotypes, a mould of the object to be produced is required, but the reproduction is effected without either fusion or fire. The current of a battery quietly deposits a layer of metal of any desired thickness on a faithful impression of the object. This is the meaning of the term of *galvanoplastics*, which is derived from the word galvanism, and from a Greek word which signifies 'to model.'

The practice of electrometallurgy consists of two distinct operations; firstly, the preparation of the mould or impression of the objects to be reproduced; and, secondly, the deposit of the metal in this mould. The first process is the most delicate, and that on which mainly depends the success of the operation.

Various substances are used for taking impressions, wax, stearine, fusible metal, gutta percha, etc. Of these the most useful, at any rate for small objects, is gutta percha. This substance, which is hard at ordinary temperatures, softens when placed in warm water. When it has acquired the proper degree of softness, a plate of this is placed on the object to be copied and pressed against it. When the object is of metal, a medal for instance, the gutta percha is easily detached as soon as it is cold; but with a wood engraving or a plaster cast, the gutta percha adheres, and cannot be detached without danger of tearing. This may be remedied by previously brushing the mould over with black lead or *graphite*, as it ought to be called.

Suppose the subject to be reproduced is a medal (fig. 388), when the mould is obtained we have this metal hollow and inverted. It is now necessary to make its surface a conductor, for gutta percha being an insulator could not transmit the current from the battery.

This is effected by brushing it over very carefully with graphite (which is a very good conductor) in all those places where the metal is to be deposited. Three copper wires are then fixed to it, one of which is merely a support, while the two others conduct the current to the metallic surface.

The mould is then ready for the metal to be deposited upon it; copper is ordinarily used, but silver and gold also deposit well.

In order to take a copper cast, a bath is filled with satu-

Fig. 387.

Fig. 388.

rated solution of sulphate of copper and two copper rods, B and A, stretched across (fig. 389) : one connected with the negative and the other with the positive pole of a Grove's, or preferably, from its greater constancy, a Daniell's element. From the rod connected with the negative pole, B, is suspended the mould, *m*, and from the other A, a plate of copper, C. The current being thus closed, the sulphate of copper is decomposed, acid is liberated at the positive pole, while copper is deposited at the negative pole, on the mould suspended from the rod, B, to which indeed several moulds may be attached.

The copper plate suspended from the positive pole serves a double purpose; it not only closes the current, but it keeps the

solution in a state of concentration, for the acid liberated at the positive pole dissolves the copper, and reproduces a quantity of sulphate of copper equal to that which has been decomposed. The



Fig. 389.

bath always remains, therefore, at the same degree of concentration, that is to say, always contains the same amount of salt in solution, which is a condition necessary for forming a uniform deposit.

468. **Electrogilding.**—The old method of gilding was by means of mercury. It was effected by an amalgam of gold and mercury, which was applied on the metal to be gilded. The objects thus covered were heated in a furnace, the mercury volatilised, and the gold remained in a very thin layer on the objects. The same process was used for silvering; but they were expensive and unhealthy methods, and have now been entirely replaced by electrogilding and electrosilvering. Brugnatelli, a pupil of Volta, appears to have been the first, in 1803, to observe that a body could be gilt by means of the battery and an alkaline solution of gold; but M. de la Rive was the first who really used the battery in gilding. The methods both of gilding and silvering owe their present high state of perfection principally to the improvements of Elkington, Ruolz, and others.

The difference between electrogilding and electrosilvering and the processes described in the previous article is this, that, in the

former, the metal is deposited on a mould in order to rep
the objects given ; while, in the latter, the objects are perm
covered with a thin layer of gold or silver.

The pieces to be coated have to undergo three preparato
cesses.

The first consists in heating them so as to remove t
matter which has adhered to them in previous processes.



Fig. 390.

As the objects to be gilt are usually of copper, and th
during the operation of heating becomes covered with
suboxide or protoxide of copper, this is removed by
operation. For this purpose the objects, while st
immersed in very dilute nitric acid, where they remai
oxide is removed. They are then rubbed with a l
washed in distilled water, and dried in gently heated sa

To remove all spots they must undergo the third pro
consists in rapidly immersing them in ordinary nitri
then in a mixture of nitric acid, bay salt, and soot. Th
well washed in distilled water, and dried as before in s

When thus prepared the objects are attached to the
of a battery of or four cells, and if they are to
they must lver kept at a te
in the bath for
d deposit. Th

nce in the composition of the bath. That most in use con-
f two parts of cyanide of silver and two parts of cyanide of
ium, dissolved in 250 parts of water. In order to keep the
n a state of concentration, a piece of silver is suspended from
ositive electrode, which dissolves in proportion as the silver
ved in the bath is deposited on the objects attached to the
ve pole.

ıe processes of electrogilding are quite the same as those of
silvering, with the exception that a bath of gold is used in-
of one of silver, and the positive plate terminates in a plate
d. The bath used is a solution of cyanide of gold and potas-

ıe method which has just been described can not only be used
lding copper, but also for silver, bronze, brass, German silver,
But other metals, such as iron, steel, zinc, tin, and lead, are
difficult to gild well. To obtain a good coating they must first
vered with a layer of copper by means of the battery and a
of sulphate of copper ; the copper with which they are coated
n gilded, as in the previous case.

CHAPTER IX.

ELECTROMAGNETISM.

9. **Relation between magnetism and electricity.**—Early
history of the two sciences, the analogy was remarked which
d between the phenomena of electricity and magnetism. It
bserved that, in both cases, like kinds of electricity repelled
other, as also did like kinds of magnetism, and that unlike
attracted. It had moreover been observed that lightning,
iking a ship, often reversed the polarity of compass needles,
even sometimes robbed them of all magnetic power. But
h there were many points of resemblance between electricity
nagnetism, the dissimilarities were numerous. For instance,
ietic properties cannot be transmitted to good conductors, as
electrical properties. A magnet placed in contact with the
does not lose its magnetism as does an electrified body.
ı, electricity can be produced in all bodies, while magnetism
ly manifested by a very small number. Among these resem-

blances and dissimilarities, nothing could be affirmed respecting the identity of the causes which produce electricity and magnetism, when, towards the end of 1819, Oersted, a professor of physics in Copenhagen, made a memorable discovery, which for ever intimately connected these two physical agents. Thus arose a new branch of science called *electromagnetism*, to express that the phenomena are at once magnetic and electrical.

470. **Action of current upon magnets.**—The fact which Oersted discovered was the directive action of currents upon magnets. He found that *electrical currents have a directive action upon the magnetic needle, and always tend to set it at right angles to their own direction.*



Fig. 391.

To verify this action of currents upon magnets, the experiment is arranged as shown in fig. 391. A magnetic needle, movable upon a pivot, being at rest in the direction of the magnetic meridian, a wire traversed by a current is brought near it, care being taken to bring it lengthways. The needle is then seen to deviate from its position of rest, to oscillate, and ultimately come to rest in a position which is nearly at right angles to that of the current; and the more nearly, the more powerful the current.

In this experiment the direction in which the north pole is deflected varies with the direction of the current; if it goes from south to north above the needle, the north pole is deflected to the

st; if, on the contrary, it goes from north to south but still above e needle the north pole is deflected to the east. When the cur-nt passes below the needle, the same phenomena are reproduced exactly the reverse order. All these different cases have been duced to a single one by Ampère.

471. **Ampère's rule.**—Ampère has given the following *memoria chnica*, by which all the various directions of the needle under the fluence of a current may be remembered. If we imagine an bserver placed in the connecting wire in such a manner that the rrent entering by his feet issues by his head, and that his face is ways turned towards the needle, we shall see that in the above ur positions, the north pole is always deflected towards the left of e observer. By thus personifying the current, the different cases ay be comprised in this general principle: *In the directive action currents on magnets, the north pole is always deflected towards e left of the current.*

472. **Action of magnets and of the earth on currents.**—Just currents act on magnets, so also magnets act upon currents. To



Fig. 392.

ove this, a circle of copper wire provided at the ends with steel ints dip in two mercury cups (fig. 392). These mercury cups e at the ends of two metal rods attached to two vertical columns, th which can be connected the poles of Bunsen's element. By is arrangement, which is known as *Ampère's stand*, we have a ovable circuit continually traversed by a current. When this rcuit is at rest, if a powerful magnet be placed beneath the circuit,

but in its plane, the circuit will be seen to turn *and set transversely to the bar, which is the converse of Oersted's experiment.*

The terrestrial globe, which acts like a magnet on magnetic needles, acts in the same manner on the movable circuits, that is, it directs them perpendicularly to the magnetic meridian. This action may be demonstrated by the above apparatus. With this view, before the current traverses the circuit, it is placed in the magnetic meridian, and then the two poles of the battery are connected with the two columns : the circuit is soon observed to set transversely to its first position, and so that, in the lower part of the circuit, the direction of the current is from east to west.

473. **Galvanometer, or multiplier.**—The name *galvanometer multiplier*, or *rheometer* is given to a very delicate apparatus, by which the existence, direction, and intensity of currents may be determined. It was invented by Schweigger in Germany a short time after Oersted's discovery.

In order to understand its principle, let us suppose a magnetic needle, *ab*, suspended by a filament of silk (fig. 393), and surrounded in the plane of the magnetic meridian by a copper wire forming a



Fig. 393.



Fig. 394.

complete circuit round the needle in the direction of its length. When this wire is traversed by a current, it follows, from what has been said in the previous paragraph, that in every part of the circuit an observer lying in the wire in the direction of the arrows, and looking at the needle, *ab*, would have his left always turned towards the same point of the horizon, and consequently, that the action of the current in every part would tend to turn the north pole in the same direction : that is to say, that the actions of the four branches of the circuit concur to give the north pole the same direction. By coiling the copper wire in the direction of the needle, as represented

n the figure, the action of the current has been *multiplied.* If nstead of a single one, there are several circuits, provided they are nsulated, the action becomes still more multiplied, and the deflec- ion of the needle increases ; or, what is the same thing, a much eebler current will produce deflection.

As the directive action of the earth continually tends to keep the ieedle in the magnetic meridian, and thus opposes the action of the :urrent, the effect of the latter is increased by using an astatic ;ystem of two needles as shown in fig. 394. The action of the :arth on the needle is then very feeble, and, further, the actions of he current on the two needles become accumulated. In fact, the ıction of the circuit, from the direction of the current indicated by he arrows, tends to deflect the north pole of the lower needle *ab* owards the west. The upper needle, *a' b'*, is subjected to the action



Fig. 395.

of two contrary currents, *no* and *qp*, but as the first is nearer, its action preponderates. Now this current, passing below the needle, evidently tends to turn the pole, *a'*, towards the east, and consequently, the pole, *b'*, towards the west ; that is to say, in the same direction as the pole, *a*, of the other needle.

From these principles it will be easy to understand the theory of the *multiplier*. The apparatus, represented in fig. 395, consists of a thick brass plate resting on levelling screws; on this is a copper frame on which is coiled a great number of turns of wire covered with silk. The two ends terminate in binding screws, *n* and *m*. Above the frame is a graduated circle, with a central slit parallel to the direction in which the wire is coiled. By means of a very fine filament of silk, an astatic system is suspended; it consists of two needles, *ab* and *a' b'*, one above the scale, and the other within the circuit itself.

In using the instrument it is so adjusted that the needles, and also the slit, are in the magnetic meridian.

474. **Uses of the galvanometer.**—To show, by means of the multiplier, the electricity developed in chemical actions, for instance in the action of acids on metals, two platinum wires may be attached to the binding screws, *m* and *n*. Then one of them is plunged in very dilute sulphuric acid, and the other placed in contact with a piece of zinc held in the hand, which is dipped in the liquid. An immediate deflection is observed, which indicates the existence of a current: and from the direction which the north pole of each needle assumes, it is seen that the direction of the current is that indicated by the arrows. From which we may conclude, in accordance with the explanation given as to the origin of electricity in the simple voltaic circuit, that the acid is positively electrified and the zinc negatively.

The length and diameter of the wire vary with the purpose for which the galvanometer is intended. For one which is to be used in observing the currents due to chemical actions, a wire about $\frac{1}{3}$ millimetre in diameter, and making about 800 turns, is well adapted. Those for thermo-electric currents, which have low intensity, require a thicker and shorter wire, for example, thirty turns of a wire $\frac{2}{3}$ millimetre in diameter. For very delicate experiments, as in physiological investigations, galvanometers with as many as 30,000 turns have been used.

475. **Magnetisation by electrical currents.**—From the influence which currents exert upon magnets, turning the north pole to the left and the south pole to the right, it is natural to think, that by acting upon magnetic substances in the natural state the currents would tend to separate the two magnetisms. In fact, when a wire traversed by a current is immersed in iron filings, they adhere to it in large quantities, but become detached as soon as the

ent ceases, while there is no action on any other non-magnetic al.

The action of electrical currents on magnetic substances is well . in an experiment due to Ampère, which consists in coiling an in- ted copper wire round an unmagnetised steel bar. If a current



Fig. 396.

assed through the wire, even for a short time, the bar becomes ngly magnetised. The same effect is produced with a bar of iron, but in this case the magnetisation is temporary; when current ceases, the iron, which is destitute of coercive force, re- s instantaneously to the natural state; and, if in this experi- t, we imagine an observer floating in the direction of the ent, the north pole is always on his left hand.

If the charge of a Leyden jar be transmitted through the wire connecting one end with the outer coating, and the other with inner coating, the bar is also magnetised. Hence both voltaic frictional electricity can be used for magnetising.

CHAPTER X.

ELECTRODYNAMICS.

476. **Reciprocal action of currents on currents.**—Ampère not restrict himself to trying the action of magnets and of the h upon movable currents; he went further, and was led to the ortant discovery, that electrical currents act on each other as do gnets; and he thus created an entirely new branch of physics, hich the name *electrodynamics* has been given. The actions ch currents exert on each other are different according as they parallel or angular.

I. *Two currents which are parallel, but in contrary directions, l each other.*

II. *Two currents, parallel and in the same direction, attract each other.*

To verify these laws use is made of the apparatus represented in fig. 397. On a wooden support are fixed two brass columns, A and B, joined at the top by a wooden cross-piece. In the centre of this is a brass binding screw, *a*, and below this a mercury cup, *o*. In this is placed an iron pivot which joins the end of a copper wire. This wire is coiled in the manner represented in the figure, terminating in a mercury cup, C, on the base of the apparatus. It thus forms a circuit movable about the pivot.



Fig. 397.

This being premised, the circuit is arranged in the plane of the two columns, as shown in fig. 397, and the current from a Bunsen's battery is passed through it to the foot of the column, A ; it passes thence by a copper wire to the binding screw, *a* ; thence into the cup, *ao*, traverses the entire movable circuit in the direction of the arrows, reaches the cup, C, whence, by a copper strip, it reaches the foot of the column, B, rises in this, and ultimately returns to the battery. When the current passes, the circuit moves away from the columns, and, after a few oscillations, comes to rest crosswise to its original position ; thus showing that the ascending current in the columns and the descending current in the circuit repel each other, thereby proving the first law.

The second law may be established by means of the same apparatus, replacing the movable circuit depicted in fig. 397 by another so arranged that the current is ascending in both the columns and in the two branches of the circuit. When the movable circuit is displaced, and the current is passed, the latter returns briskly towards the columns.

Law of angular currents. In the case of two angular currents,

one fixed and the other movable, Ampère found that there was attraction when both the currents moved towards, or both away from, the apex of the angle; and that repulsion took place when, one current moving towards the apex, the other moved away from it.

SOLENOIDS.

477. **Structure of a solenoid.**—A solenoid is a system of equal and parallel circular currents formed of the same pieces of covered copper wire, and coiled in the form of a helix or spiral, as represented in fig. 398. A solenoid, however, is only complete when part of the wire, BC, passes in the direction of the axis in the interior of the helix. With this arrangement, when the circuit is suspended in the mercury cups, *ab*, of the apparatus (fig. 397), and a current is passed through, it is directed by the earth exactly as if it were a magnetic needle. If the solenoid be removed it will, after a few oscillations, return, so that its axis is in the magnetic meridian. Further, it will be found that, in the lower half of the coils of which the solenoid consists, the direction of the current is from east to west; in other words, the current is *descending* on that side of the coil turned towards the east, and ascending on the west. In this experiment the solenoid is directed like a magnetic needle, and the *north pole*, as in magnets, is that end which points towards the north, and the *south pole* that which points towards the south.



Fig. 398.

478. **Mutual actions of magnets and solenoids.**—Exactly the same phenomena of attraction and repulsion exist between solenoids and magnets as between magnets. For if to a movable solenoid traversed by a current, one of the poles of a magnet be presented, attraction or repulsion will take place, according as the poles of the magnet and of the solenoid are of contrary, or of the same name. The same phenomenon takes place when a solenoid, traversed by a current and held in the hand, is presented to a movable magnetic needle. Hence the law of attractions and repulsions applies exactly to the case of the mutual action of solenoids and of magnets.

479. **Mutual actions of solenoids.**—When two solenoids tra-

versed by a powerful current are allowed to act on each other, one of them being held in the hand, and the other being movable about a vertical axis, as shown in fig. 399, attraction and repulsion



Fig. 399.

will take place, just as in the case of two magnets. These phenomena are readily explained by reference to what has been said about the mutual actions of the currents, bearing in mind the direction of the currents in the ends presented to each other.

480. **Ampère's theory of magnetism.**—Ampère has propounded a most ingenious theory, based on the analogy which exists between solenoids and magnets, by which all magnetic phenomena may be referred to electrodynamical principles.

Instead of attributing magnetic phenomena to the existence of two fluids, Ampère assumes that each individual molecule of a magnetic substance is traversed by a closed electric current. When the magnetic substance is not magnetised, these molecular currents, under the influence of their mutual attractions, occupy such positions that their total action on any external substance is null. Magnetisation consists in giving to these molecular currents a parallel direction, and the stronger the magnetising force the more perfect the parallelism. The *limit of magnetisation* is attained when the currents are completely parallel.

The resultant of the actions of all the molecular currents is equivalent to that of a single current which traverses the outside of a magnet. For by inspection of fig. 400, in which the molecular currents are represented by a series of small internal circles in the two ends of a cylindrical bar, it will be seen that the adjacent

parts of the currents oppose one another, and cannot exercise any external electrodynamic action, which is not the case with those on the surface.

The direction of these currents in magnets can be ascertained by considering the suspended solenoid (fig. 398). If we suppose it traversed by a current, and in equilibrium in the magnetic meridian, it will set in such a position that in the lower half of each coil the current flows from *east to west.* We may then establish the following rule. *At the north pole (English) of a magnet the direction of the Ampèrian currents is opposite that of the hands of a watch, and at the south pole the direction is the same as that of the hands.*

Fig. 400.

481. **Terrestrial current.**—In order to explain on this supposition terrestrial magnetic effects, the existence of electrical currents is assumed which continually circulate round our globe from east to west, perpendicular to the magnetic meridian.

The resultant of their action is a single current traversing the magnetic equator from east to west. These currents are supposed to be thermo-electric currents due to the variations of temperature caused by the successive influence of the sun on the different parts of the globe from east to west.

These currents direct magnetic needles; for a suspended magnetic needle comes to rest when the molecular currents on its under surface are parallel, and in the same direction as the earth currents. As the molecular currents are at right angles to the direction of its length, the needle places its greatest length at right angles to east and west, or north and south. Natural magnetisation is probably imparted in the same way to iron minerals.

CHAPTER XI.

ELECTROMAGNETS. TELEGRAPHS AND ELECTROMAGNETIC MOTORS.

482. **Electromagnets.**—*Electromagnets* are bars of soft iron which, under the influence of a voltaic current, become magnets; but this magnetism is only temporary, for the coercive force of perfectly soft iron is null, and the magnetism ceases as soon as the current ceases to pass through the wire. If, however, the iron is not quite pure, it retains more or less traces of magnetism. The electromagnets have the horse-shoe form, as shown in fig. 401, and a copper wire, covered with silk or cotton, is rolled several times round them on the two branches, so as to form two bobbins, A and B. In order that the two ends of the horse-shoe may be of opposite polarity the winding on the two limbs, A and B, must be such that, if the horse-shoe were straightened out, it would be in the same direction.

Fig. 401.

Electromagnets, instead of being made in one piece, are frequently constructed of two cylinders, firmly screwed to a stout piece of the same metal. Such are the electromagnets in Morse's telegraph (487), the electromagnetic machine (502). The helices on them must be such that the current shall flow in the same direction as the hand of a watch as seen from the south pole, and against the hands of a watch as seen from the north pole.

The force of such magnets depends on their dimensions, on the number of turns of wire, and on the strength of the current. An electromagnet need not be very powerful to support one person (fig. 402). Electromagnets have extended applications, in telegraphs, in clocks, and in electromagnetic engines.

ELECTRIC TELEGRAPH.

483. **Electric telegraphs.**—These are apparatus by which gnals can be transmitted to considerable distances, and with normous velocity, by means of voltaic currents propagated in

Fig. 402.

etal wires. Towards the end of the last century, and at the ginning of the present, many philosophers proposed to corre- ond at a distance by means of the effects produced by electrical achines when propagated in insulated conducting wires. In 11, Sœmmering invented a telegraph in which he used the de- mposition of water for giving signals. In 1820, at a time when

the electromagnet was unknown, Ampère proposed to correspond by means of magnetic needles, above which a current was sent, as many wires and needles being used as letters were required. In 1834, Gauss and Weber constructed an electromagnetic telegraph, in which a voltaic current transmitted by a wire acted on a magnetised bar; the oscillations of which under its influence were observed by a telescope. They succeeded in thus sending signals from the Observatory to the Physical Cabinet in Göttingen, a distance of a mile and a quarter, and to them belongs the honour of having first demonstrated experimentally the possibility of electrical communication at a considerable distance. In 1837, Steinheil in Münich, and Wheatstone in London, constructed telegraphs in which several wires each acted on a single needle: the current in the first case being produced by an electromagnetic machine, and in the second by a constant battery.

Every electric telegraph consists essentially of three parts: 1, a *circuit*, consisting of a metallic connection between two places, and an *electromotor*, for producing the current; 2, a *communicator*, for sending the signals from one station; and, 3, an *indicator*, for receiving them at the other station. The manner in which these objects, especially the last two, are effected can be greatly varied; the three principal systems are the needle telegraph, the dial telegraph, and the printing telegraph.

The *needle telegraph* is essentially a vertical galvanometer; that is to say, a magnetic needle suspended vertically in a coil of insulated wire. To the needle is attached an index, which is seen on the front of the apparatus. The signs are made by transmitting



Fig. 403.

the current in different directions through the multiplier, by which the needle is deflected either to the right or left, according to the

will of the operator. The instrument by which this is effected is called a key, or *commutator*.

In the *dial* telegraph an electromagnet causes an idex to move over a dial provided with the twenty-six letters of the alphabet; that letter in front of which the needle stops, being the letter sent. By this kind of telegraph messages are not sent with great rapidity; yet, as the manipulation is very simple, it is frequently used on railways and in private offices.

484. **Principle of Morse's telegraph.**—This telegraph is based *on the temporary magnetisation of an electromagnet by the intermittent passage of currents.* Thus let E (fig. 403) be a fixed electromagnet, the insulated wires of which are attached to the two binding screws, *a* and *b*. Above this magnet is a lever, *mn*, movable about an axis, *i*, and ending in an armature of soft iron, *m*, so that, whenever the magnet is traversed by a current, the armature is attracted, and the part of the lever on the right of the fulcrum is lowered; then, when the current no longer passes, a spring, R, raises the lever to an extent regulated by a screw, O.

Suppose, for example, the electromagnet is at Bristol, and that there is a battery, P, at London, and two metal wires, A and B, by one of which the binding screw, *b*, is permanently connected with the negative pole of the battery, while the experimenter holds the other wire in his hand. So long as the experimenter does not place the wire which he holds in his hand in contact with the positive pole, the current does not pass; and, as the electromagnet does not act, the arm of the lever is raised (fig. 403). But the moment

Fig. 404.

contact is made, the current is closed, the electromagnet attracts, and the lever is lowered (fig. 404); but it resumes its original

position as soon as contact is broken, and so on at the will of the operator. Thus one person at London can cause the lever, *mn*, to oscillate at Bristol as often and as rapidly as possible as he desires. This is, in its simplest form, the principle of the elementary mechanism of electrical telegraphs based on electromagnetism. It only remains to give to these oscillations a definite meaning.

485. **Line wire.**—Of the various essentials for a telegraphic communication, the batteries or sources of power have been already described, and we shall therefore pass to the explanation of the *circuit*, or *line wire*.

Fig. 405.

Line wires are either *aerial*, *subterranean*, or *submarine*.

The aerial wire consists of a stout galvanised iron wire connecting two stations. At certain intervals are wooden posts, to which are attached insulating supports of porcelain, which sustain the wire (fig. 405). Subterranean wires are used for cases in which an aerial wire would not be sufficiently protected against accident, as in towns. They consist usually of copper wires covered with gutta percha; this insulates them from the earth in which they are placed.

Submarine wires or cables are such as are employed in deep seas where great strength is required. The ordinary form is represented in figs. 406 and 407. The *core* consists of seven fine wires of very pure

Fig. 406.



Fig. 407.

copper, which are twisted together and surrounded by an insulating covering. This is surrounded by an insulating coating of four concentric layers of gutta percha alternating with the same number

f layers of a material known as *Chatterton's compound*, which is ssentially a mixture of resin, pitch, and gutta percha applied hot. :ound this is a layer of tarred hemp, and this again is surrounded y a protective coating of steel wire coated with tarred hemp, which reserves it from the corrosive action of the sea.

Fig. 406 gives a longitudinal view of a submarine cable, and g. 407 a cross section. The diameter of the cable is about an ıch, and it weighs about a ton to the mile.

486. **The earth as a conductor.**—In figs. 403 and 404 we ave not merely a wire connecting the positive pole of the battery ith the electromagnet, but there is a second one which acts on a :turn wire. In 1837 Steinheil made the very important discovery ıat the earth might be utilised for the return conductor. This has ıe twofold advantage of doing away with the expense of a second ·ire, and also of lessening the resistance.

With this view, at the sending station, a long copper wire is ttached to the negative pole, which is fixed at the other end to a opper plate, Q. This plate is placed in water if possible (fig. 408), or



Fig. 408.

t all events is sunk some depth in earth. In like manner, at the :ceiving station, a similar wire and plate S are connected with the inding screw, *b*. Thus while the negative electricity passes into ıe ground by the plate, Q, the positive electricity which reaches ıe electromagnet and the binding screw, enters the ground by the late, S. Hence there is in the wire, A, and in the electromagnet, ıe same circulation, and therefore the same effects as when the inding screw, *b*, communicates directly with the negative pole of ıe battery by means of a metal wire.

487. **Morse's telegraph.**—Fig. 409 represents a station at which a despatch is being sent by the help of this apparatus, and fig. 410 represents the receiving station. At each station the apparatus is the same; it is double, and consists of two distinct parts, the *key*, by which the signals are sent, and the *receiving instrument* which registers them. These two parts are represented on a larger scale in figs. 411 and 412.

To understand how they work let us commence with fig. 409. Below the table is a box containing the battery, which furnishes the

Fig. 409.

current. This passes by the wire, P, into the key, which will be afterwards described (fig. 411). Thence it passes into a small galvanometer, *g*, which indicates by the deflection of its needle whether the

is passing or not. The current ultimately attains the , which acts as a lightning conductor, as we shall afterwards thence it goes to the wire, L, which is the *line wire.* wire is again seen at the top of fig. 410, whence the arriving again passes into the lightning conductor, then into a gal-

Fig. 410.

ter, and next a key, whence it passes into the electromag- ch makes part of the receiver. It then enters the wire, T, ads it to earth.

Morse's key and receiving instrument.—The general ment of the apparatus being understood, the following are ils of its action. The *key* consists of a small mahogany hich acts as support for a metallic lever, *hk* (fig. 411), mov-

able in its middle on a horizontal axis. The extremity, B, of this lever is always pressed upwards by a spring, *r*, beneath; at the other end a screw passes through it, which rests on a small metal support, in contact with the wire, A. Fig. 411 represents the key at the moment it receives the dispatch, as



Fig. 411.

at work for instance in fig. 410. The current enters then by the wire, L, which is the line wire, rises into the lever, *kh*, and descends by the screw pin, *a*, into the wire, A, which leads to the indicator. If, on the other hand, the key is to be used for sending a message, as represented in fig. 409, it will be seen that the lever, *kh*, does not touch the metal pin in which the wire, P, terminates. But if the lever, *h*, is lowered by pressing the end, B, contact is set up, and the current, P, at once passes into the lever, *hk*, and thence into the wire, L, which leads it to the station signalled to; for the same wire is used to send and to receive the message.

The *indicator* consists of an electromagnet, E (fig. 412), which whenever the current is transmitted, acts attractively on an armature of soft iron, *m*, fixed at the end of a lever, *mn*, movable about an axis; when the current is open, the lever is raised by a spring, R. At



Fig. 412.

the other end of the lever there is a pencil *x*, which writes the signals. For this purpose a long band of strong paper, *ab*, rolled round a drum, S (figs. 409 and 410), passes between two copper rollers with a rough surface, turning in contrary directions. Drawn in the direction of the arrows, the band of paper becomes rolled on

ond drum, Q, which is turned by hand. A clockwork motion d in the box, V, works the rollers, between which the band of r passes.

he paper being thus set in motion, whenever the electromagnet s, the point, *x*, strikes the paper, and, without perforating it, uces an indentation, the shape of which depends on the time ıg which the point is in contact with the paper. If it only es it instantaneously, it makes a dot (.) ; but if the contact is of greater duration a line or dash of corresponding length is pro-d. Hence, by varying the length of contact of the transmitting ıt one station, a combination of dots or dashes may be produced ıother station, and it is only necessary to give a definite meaning ese combinations.

his is effected as follows in Morse's alphabet :

	PRINTING.	SINGLE NEEDLE.		PRINTING.	SINGLE NEEDLE.
A	– —	\/	N	— ·	/\
B	— · · ·	/\\\	O	— — —	///
C	— · — ·	/\/\	P	· — — ·	\//\
D	— · ·	/\\	Q	— — · —	//\/
E	–	\	R	· — ·	\/\
F	· · — ·	\\/\	S	· · ·	\\\
G	— — ·	//\	T	—	/
H	· · · ·	\\\\	U	· · —	\\/
I	· ·	\\	V	· · · —	\\\/
J	· — — —	\///	W	· — —	\//
K	— · —	/\/	X	— · · —	/\\/
L	· — · ·	\/\\	Y	— · — —	/\//
M	— —	//	Z	— — · ·	//\\

Fig. 413.

he other signals are those of the single needle instrument). The signal \ denotes a deflection of the top of the vertical

needle to the left, and the signal / to the right. They correspond respectively to the dot and dash of the Morse alphabet.

Any one present while a message is being received at a telegraph station, is astonished at the promptitude and accuracy with which signals are read and transmitted by the operators. These acquire such skill that they can read a message by the sounds which the armature makes in striking against the electromagnet of the indicator.

Based on this fact a form of instrument invented in America has come into use for the purpose of reading by sound. The *sounder*, as it is called, is essentially a small electromagnet on an ebonite base, resembling the relay in fig. 416. The armature is attached to one end of a lever, and is kept at a certain distance from the electromagnet by a spring. When the current passes the armature is attracted against the electromagnet, with a sharp click, and when the current ceases it is withdrawn by the spring. Hence the interval between the sounds is of longer or shorter duration according to the will of the sounder, and thus in effect a series of short and long sounds can be produced which correspond to the dots and dashes of the Morse alphabet.

489. **Improvements in Morse's telegraph.**—In the apparatus just described, the indentations on the paper only give indistinct dots and dashes, unless the current transmitted be very powerful.



Fig. 414.

To get rid of this inconvenience, and to expend less force, the apparatus has been modified so that the signals can be traced in ink. With this view, all the other parts being the same, the following arrangement is made :

A roller, *a*, fig. 414, covered with flannel, is moistened with a uitable ink. Above the roller, and in contact with it, is an endless and, *p h*, rolled on two pulleys, *o*, *o'*, which are turned by the clock- ork motion which moves the paper. This is kept by a roller, , very near the chain, but not touching it. That being premised, henever the current passes in the electromagnet, the armature, A, s attracted, the arm of the lever *k*, is depressed, and a pin, *i*, at its nd rests on the band, and places it in contact with the paper. he band depositing the ink which it has taken from the roller, akes on the paper as it moves along, a dot or a dash, according o the length of time the current passes, and which dots and dashes ave the same meaning as above.

490. **Lightning conductor.**—Besides the parts of the telegraph lready described there are three of which mention must be made; he lightning conductor, the alarum, and the relay.

The influence of storm clouds in decomposing the natural elec- ricity of the wire, often produces sufficient tension, not merely to nterfere with the transmission of the despatches, but also to pro- luce dangerous discharges. The lightning conductor is designed o remedy these inconveniences.

Represented at M in figs. 409 and 410, it consists of a vertical tand on which are two copper plates, indented like a saw, and rranged so that the teeth are near each other but do not touch. One of these plates is connected with the earth, the other with the ine wire. Hence, when, by the inductive action of a storm cloud, lectricity accumulates in wires and in the apparatus, it escapes by he points to the plate which is connected with the ground, and hus all danger from a discharge is avoided.

491. **Electrical alarum.**—The electrical alarum is intended to arn the receiving station that a despatch is about to be sent. Represented in fig. 415, it consists of a board on which is fixed an lectromagnet by means of a piece of brass, E. The current from he line arriving by a binding screw, *m*, passes to the wire of the lectromagnet, thence into the armature, *a*, into a steel spring, *c*, hich presses against the armature, and ultimately emerges by a econd terminal, *n*.

Thus, whenever the current of the line wire reaches the electro- nagnet, the armature, *a*, is attracted, and a clapper, P, fixed to this rmature, strikes against a bell, T, and makes it sound. The noment the clapper strikes, as the armature is no longer in contact vith the spring, C, the current is open, the electromagnet no longer

attracts, and the armature reverts to its original position by the action of a spring, *e*, to which it is fixed.

The current being closed afresh, a second attraction takes place, and so on until the telegraph clerk, thus warned, lets the current pass directly into the indicator without passing through the alarum. This he accomplishes by means of an instrument called the *shunt*.



Fig. 415.

Relay. In describing the receiver we have assumed that the current of the line coming by the wire, C (fig. 416), entered directly into the electromagnet, and worked the armature, A, producing a despatch; but when the current has to traverse a distance of a few miles, owing to the resistance of the wire and the losses of insulation, its intensity is diminished so greatly that it cannot act upon the electromagnet with sufficient force to print a despatch. Hence it is necessary to have recourse to a relay, that is, to an auxiliary electromagnet, which is still traversed by the current of the line, but which serves to introduce into the communicator the current of a *local battery* of four or five elements placed at the station, and only used to print the signals transmitted by the wire.

For this purpose the current from the line entering the relay by the binding screw, L (fig. 416), passes into an electromagnet, E, whence it passes into the earth by the binding screw, T. Now, each time that the current of the line passes into the relay, the electromagnet attracts an armature, A, fixed at the bottom of a vertical lever, *p*, which oscillates about a horizontal axis.

At each oscillation the top of the lever, *p*, strikes against a button, *n*, and at this moment the current of the local battery which enters by the binding screw, *c*, ascends the column, *m*, passes into the lever, *p*, descends by the rod, *o*, which transmits it to the binding screw, T: thence it enters the electromagnet of the indicator, whence it emerges by the wire, Z, to return to the local battery from which it started. Then when the current of the line is open, the electro-

magnet of the relay does not act, and the lever, *p*, drawn by a spring, *r*, leaves the bottom, *n*, as shown in the drawing, and the local current no longer passes. Thus the relay transmits to the



Fig. 416.

indicator exactly the same phases of passage and intermittence as those effected by the key in the station which sends the despatch.

492. **Electromagnetic machines.**—Many physicists have attempted to utilise the attractive force of electromagnets as a motive power. M. Jacobi, of St. Petersburg, appears to have been the first to construct a machine of this kind, with which, in 1838, he moved on the Neva a small boat containing twelve persons. Since that time the construction of these machines has been materially modified; but in all the expense of zinc and acids which they use far exceeds that of steam engines of the same force. Until some cheaper source of electricity shall have been discovered there is no expectation that they can be applied at all advantageously.

Fig. 418 represents an electromagnetic machine constructed by Froment. It consists of four electromagnets acting in two couples, on two pieces of soft iron, P, only one of which is seen in the figure. This piece, attracted by the electromagnets, EF, transmits the motion by means of a connecting rod to a crank *m* fixed at the end of a horizontal axis. To this is fixed a fly-wheel like that of a steam engine, which is intended to regulate the rotatory motion. On this axis also is a piece of metal, *n*, of a greater diameter, the action of which will be described presently.

The current of the battery, entering at A, passes into a cast-iron base, B, then by various metallic connections it reaches the metal piece, *n*. Thence the current ought to pass alternately to the first



Fig. 417.

Fig. 418.

couple of electromagnets, EF, and then to the second, *ef*. In order to understand how this alteration in the path of the current is effected, let us refer to fig. 417 on the right of the picture, which represents a section of the piece, *n*, and its accessories. On this piece is a projection, *e*, which is called a *cam*, and which, during a complete turn, successively touches two springs, *a* and *b*; these are intended to transmit to the electromagnets the current, the direction of which is indicated by the unbarbed arrows; the barbed arrows do not show the direction of the current but the direction of the motion of the various pieces of the machine.

These details being known, it will be seen that the current passes alternately into two springs, *a* and *b*, and from thence into the two systems of electromagnets, EF and *ef*: the piece P is first of all attracted, then a similar one, which is placed at the other end of the axis of the fly-wheel. There is thus produced a continuous circulating motion, which is transmitted by an endless band to a system of wheel work, which works two lifting pumps.

CHAPTER XII.

INDUCTION BY CURRENTS.

493. **Induction by currents.**—We have already seen (398) that by the term *induction* is meant the action which electrified bodies exert at a distance on bodies in the natural state. Hitherto we have only had to deal with electrostatical induction: we shall now see that dynamical electricity produces analogous effects.

Faraday discovered this class of phenomena in 1832, and he gave the name of *currents of induction*, or *induced currents*, to instantaneous currents developed in metallic conductors under the influence of metallic conductors traversed by electric currents, or by the influence of powerful magnets, or even by the magnetic action of the earth; and the currents which give rise to them he called *inducing currents*.

The inductive action of currents at the moment of opening or closing may be shown by means of a coil with two wires. This consists (fig. 419) of a hollow cylinder of wood or of cardboard, on which a quantity of stout silk-covered copper wire is coiled; on this

is coiled a considerably greater length of fine copper wire, also insulated by being covered with silk. This latter coil, which is called the *secondary coil*, is connected by its ends with two binding screws, *a*, *b*, from which wires pass to a galvanometer G, while the thicker wire, the *primary coil*, is connected by its extremities with two binding screws, *c* and *d*. One of these, *d*, being connected with one pole of a battery, when a wire from the other pole is connected with *c*, the current passes in a primary coil, and in this alone. The following phenomena are then observed :

i. At the moment at which the thick wire is traversed by the current, the galvanometer, by the deflection of the needle, indicates the existence in the *secondary coil* of a current *inverse* to that in the primary coil, that is, in the contrary direction : this is only instantaneous, for the needle immediately reverts to zero, and remains so as long as the inducing current passes through *cd*.



Fig. 419.

ii. At the moment at which the current is opened, that is, when the wire, *cd*, ceases to be traversed by a current, there is again produced in the wire, *ab*, an induced current instantaneous like the first, but *direct*, that is, in the same direction as the inducing current.

494. **Induction by magnets and by the action of the earth.**— It has been seen that the influence of a current magnetises a steel bar ; in like manner a magnet can produce induced electrical currents in metallic circuits. Faraday showed this by means of a coil with a single wire of 200 to 300 yards in length. The two extremities of the wire being connected with the galvanometer, as shown in fig. 420, a strongly magnetised bar is suddenly inserted in the bobbin, and the following phenomena are observed :

i. At the moment at which the magnet is introduced, the galvanometer indicates in the wire the existence of a current, the direction of which is opposed to that which circulates round the magnet, considering the latter as a solenoid on Ampère's theory (480).

ii. The needle soon returns to zero, and remains there as long as the magnet is in the coil; when it is withdrawn, the needle of the galvanometer, which has returned to zero, indicates the existence of a direct current.

The inductive action of magnets may also be illustrated by the following experiment: A bar of soft iron is placed in the above bobbin and a strong magnet suddenly brought in contact with it; the needle of the galvanometer is reflected, but returns to zero when the magnet is stationary, and is deflected in the opposite direction when it is removed. The induction is here produced by



Fig. 420.

the magnetisation of the soft iron bar in the interior of the bobbin under the influence of the magnet.

Faraday discovered that terrestrial magnetism can develope induced currents in metallic bodies in motion; that it acts like a powerful magnet placed in the interior of the earth in the direction of the dipping needle, or according to the theory of Ampère, like a series of electrical currents directed from east to west parallel to the magnetic equator. He first proved this by placing a long

helix of copper wire covered with silk in the plane of the magnetic meridian parallel to the dipping needle; by turning this helix through a semicircle round an axis in its middle, perpendicular to its length, he observed that at each turn a galvanometer, connected with the two ends of the helix, was deflected.

495. **Properties of induced currents.**—Notwithstanding their instantaneous character, it appears mainly from the experiments of Faraday their discoverer, that induced currents have all the properties of ordinary currents. They produce violent physiological luminous, calorific, and chemical effects, and finally give rise to new induced currents. They also deflect the magnetic needle, and magnetise steel bars when they are passed through a copper wire coiled in a helix round the bars.

The intensity of the shock produced by induced currents renders their effects comparable to those of electricity in a state of tension. But as they act on the galvanometer the electricity is present, both in a state of tension and in the dynamical condition.

These phenomena of induction currents are well seen in Ruhmkorff's coil, which we shall now describe.

496. **Ruhmkorff's coil.**— This is an arrangement for producing induced currents, in which a current is induced by the action of an electric current, whose circuit is alternately opened and closed in rapid succession. These instruments, known as *inductoriums*, or *induction coils*, present considerable variety in their construction, but all consist essentially of a hollow cylinder in which is a bar of



Fig. 421.

soft iron, or bundle of iron wires, with two helices coiled round it, one connected with the poles of a battery, the current of which is

alternately opened and closed by a self-acting arrangement, and the other serving for the development of the induced current. By means of these apparatus, with a current of three or four Grove's cells, physical, chemical, and physiological effects are produced equal to and superior to those obtainable with electrical machines and even the most powerful Leyden batteries.

Of all the forms those constructed by Ruhmkorff in Paris, and by Ladd and Apps in this country, are the most powerful. Fig. 421 is a representation of one, the coil of which is about 14 inches in length. The *primary* or *inducing* wire is of copper, and is about 2 mm. in diameter, and 14 or 15 yards in length. It is coiled directly on a cylinder of cardboard, which forms the nucleus of the apparatus, and is enclosed in an insulating cylinder of glass, or of ebonite. On these is coiled the secondary or induced wire, which is also of copper, and is about $\frac{1}{3}$mm. in diameter. A great point of these apparatus is the insulation. The wires are not merely insulated by being in the first case covered with silk, but each individual coil is separated from the rest by a layer of melted shellac. The length of the secondary wire varies greatly; in some of the largest sizes it is as much as several miles. With these great lengths the wire is thinner, about $\frac{1}{5}$mm.

The following is the working of the apparatus. The current arriving by the wire, P, at a binding screw, *a*, passes thence into the commutator, C (fig. 421); thence by the binding screw, *b*, it enters the primary wire, where it acts inductively on the secondary wire; having traversed the primary wire it emerges by the wire, *s* (fig. 422). Following the direction of the arrows, it will be seen that the current ascends in the binding screw, *i*, reaches an oscillating piece of iron, *o*, called the ***hammer***, descends by the ***anvil***, *h*, and passes into a copper plate, K, which takes it to the commutator, C. It goes from there to the binding screw, *c*, and finally to the negative pole of the battery by the wire, N.



Fig. 422.

The current in the primary wire only acts inductively on the secondary wire (493), when it

opens or closes, and hence it must be constantly interrupted. This is effected by means of the oscillating hammer, *o*, omitted in figure 421, but represented on a larger scale in fig. 422. In the centre of the bobbin is a bundle of soft iron wires, forming together a cylinder a little larger than the bobbin, and thus projecting at the end as seen at A. When the current passes in the primary wire, this hammer, *o*, is attracted; but immediately, there being no contact between *o* and *h*, the current is broken, the magnetisation ceases, and the hammer falls; the current again passing, the same series of phenomena recommences, so that the hammer oscillates with great rapidity.

In proportion as the current passes thus intermittently in the primary wire of the bobbin, at each interruption an induced current, alternately direct and inverse, is produced in the secondary wire. But as this is perfectly insulated, the current acquires such an intensity as to produce very powerful effects. Fizeau increased this intensity by interposing a *condenser* in the induced circuit. As constructed by Ruhmkorff, for his largest apparatus, it consists of 150 sheets of tinfoil about 18 inches square; these sheets being joined are coiled on two sides of a sheet of oiled silk, which insulates them, forming thus two armatures; they are then coiled several times round each other, so that the whole can be placed below the helix in the base of the apparatus. One of these armatures, the positive, is connected with the binding screw, *i*, which receives the current on emerging from the bobbin; and the other, the negative, is connected with the binding screw, *m*, which communicates by the plate, K, with the commutator, C, and with the battery.

497. **Effects produced by Ruhmkorff's coil.**—The high degree of tension which the electricity of induction coil machines possesses has long been known, and many luminous and calorific effects have been obtained by their means. But it is only since the improvements which Ruhmkorff has introduced into his coil, that it has been possible to utilise all the tension of induced currents, and to show that these currents possess the properties of statical as well as dynamical electricity.

Induced currents are produced in the coil at each opening and breaking of contact. But these currents are not equal either in duration or in tension. The direct current, or that on *opening*, is of shorter duration, but more tension; that of *closing* of longer duration but less tension. Hence if the two ends P, and P', of the fine wire (figs. 421 and 422) are connected, as there are two equal

and contrary quantities of electricity in the wire the two currents neutralise each other. If a galvanometer is placed in the circuit, only a very feeble deflection is produced in the direction of the direct current. This is not the case if the two extremities, P and P′, of the wire are separated. As the resistance of the air is then opposed to the passage of the currents, that which has most tension, that is, the direct one, passes in excess, and the more so the greater the distance of P and P′ up to a certain limit at which neither pass. There are then at P and P′ nothing but tensions alternately in contrary directions.

The effects of the coil, like those of the battery, may be classed under the heads *physiological*, *chemical*, *calorific*, *luminous*, *mechanical*; they have this difference, that they are enormously more intense.

The *physiological* effects of Ruhmkorff's coil are very powerful; in fact, the shocks are so violent that many experimenters have been suddenly prostrated by them. A rabbit may be killed with an induction current arising from two of Bunsen's elements, and a somewhat larger number of couples would kill a man.

The *calorific* effects are also easily observed; it is simply necessary to interpose a very fine iron wire between the two ends, P and P′, of the induced wire; this iron wire is immediately melted, and burns with a bright light. The spark of the Ruhmkorff's coil is used to fire mines in military and mining operations.

The *chemical* effects are very varied, inasmuch as the apparatus produces both dynamical electricity and electricity in a high state of tension. Thus, according to the shape and distance of the platinum electrodes immersed in water, and to the degree of acidulation of the water, either luminous effects may be produced in water without decomposition, or the water may be decomposed and the mixed gases disengaged at the two poles, or the decomposition may take place, and the mixed gases separate either at a single pole or at both poles.

The *luminous* effects of Ruhmkorff's coil are also very remarkable and vary according as they take place in air, in vacuo, or in very rarefied vapours. In air the coil produces a very bright loud spark, which, with the largest-sized coils, has a length of eighteen inches. In vacuo the effects are also remarkable. The experiment is made by connecting the two wires of the coil, P and P′, with the two rods of the electrical egg (fig. 351), used for producing in vacuo the luminous effects of the electrical machine. A vacuum

having been produced, a beautiful luminous trail is produced from one knob to the other, which is virtually constant, and has the same intensity as that obtained with a powerful electrical machine when the plate is turned.

If this light be closely observed, it will be found that if some vapour of turpentine, or wood spirit, or bisulphide of carbon, have been introduced into the globe before exhaustion, instead of being continuous, the light consists of a series of alternately dark and bright zones, forming a pile of electric light between the two poles. This phenomenon is known as the *stratification of the electric light*, and is due to the circumstance that the current is discontinuous.

The brilliancy and beauty of the stratification of the electric light are most remarkable when the discharge of the Ruhmkorff's coil takes place in glass tubes containing a highly rarefied vapour or gas. These phenomena, which have been investigated by Masson, Grove, Gassiot, Plücker, etc., are produced by means of sealed glass tubes first constructed by Geissler, of Bonn. These tubes are filled with different gases or vapours, and are then exhausted. At the ends of the tubes two platinum wires are soldered into the glass. See figs. on the right and left in the coloured plate.

When the two platinum wires are connected with the ends of a Ruhmkorff's coil, magnificent lustrous striæ, separated by dark bands, are produced all through the tube. These striæ vary in shape, colour, and lustre with the degree of the vacuum, the nature of the gas or vapour, and the dimensions of the tube. The phenomenon has occasionally a still more brilliant aspect from the fluorescence which the electric discharge excites in the glass.

The figure on the left represents the appearance presented by hydrogen ; in the bulbs the light is a pale lavender blue, in the capillary parts it is red.

In carbonic acid the colour is greenish, and the striæ have not the same shape as in hydrogen ; in nitrogen, as represented in the figure on the right, the light is reddish violet. In chlorine the colour is reddish violet in the wide part of the tube, and in very narrow tubes green.

Mechanical effects. By means of Ruhmkorff's coil mechanical effects can also be produced, so powerful that, with the largest apparatus, glass plates two inches thick have been perforated. The result, however, is not obtained by a single discharge, but by several successive discharges.

The experiment is arranged as shown in fig. 423. The two poles of the induced current correspond to the binding screws, *a* and *b*; by means of a copper wire, *i*, the pole, *a*, is connected with the lower part of an apparatus for piercing glass like that already described (fig. 369), the other pole is attached to the upper conductor by a wire, *d*. This conductor is insulated in a large glass tube, *r*, filled with shellac, which is run in while in a state of fusion. Between the two conductors is the glass to be perforated, V. When this pre-



Fig. 423.

sents too great a resistance, there is danger lest the spark pass in the coil itself, perforating the insulated layer which separates the wire, and then the coil is destroyed. To avoid this, two wires, *e* and *c*, connect the poles of the coil with two metal rods, *m* and *n*, whose distance from each other can be regulated. If then the spark cannot penetrate through the glass, it bursts across with a bright spark and a loud report, and the coil is not injured.

498. **Rotation of induced currents by magnets.**—De la Rive has recently devised an experiment which shows in a most ingenious and beautiful manner that magnets act on the light in Geissler's tubes in accordance with the laws with which they act on any other movable conductor.

On the iron core of an electromagnet, M (see coloured plate) is a soft iron rod terminated at the top by an iron plate; this rod, with the exception of the top, *a*, is inserted in a very carefully insulated glass tube. The binding screw, *k*, is in conducting communication with this iron rod. The whole of the upper part of this arrange-

ment is fitted into the tubulure of an electrical egg; with which the brass tubulure, *dd*, which holds the glass tube is in conducting communication. By the stopcock at the top the electrical egg can be exhausted, and a few drops of alcohol are then introduced.

If now the wires from a Ruhmkorff's coil are connected with the binding screws, *h* and *k*, but without at the same time exciting the electromagnet, a more or less irregular luminous sheaf passes from the plate, *a*, to the ring, *dd*.

But if a voltaic current passes into the electromagnet the phenomenon is different; instead of starting from different points of the upper surface and the ring, the light is condensed and emits a single luminous arc. Further, and this is the most remarkable part of the experiment, this arc turns slowly round the magnetised cylinder, sometimes in one direction, and sometimes in another, according to the direction of the induced current, or the direction of the magnetisation evoked in the core. As soon as the magnetisation ceases the luminous phenomenon reverts to its original appearance.

This experiment is remarkable as having been devised *à priori* by De la Rive to explain, by the influence of terrestrial magnetism, a kind of rotatory motion from east to west, observed in the aurora borealis. The rotation of the luminous arc in the above experiment can evidently be referred to the rotation of currents by magnets.

CHAPTER XIII.

THERMOELECTRIC CURRENTS.

499. **Thermoelectricity.**—In 1821, Professor Seebeck, in Berlin, found that by heating one of the junctions of a metallic circuit, consisting of two metals soldered together, an electric current was produced. This phenomenon may be shown by means of the apparatus represented in fig. 424, which consists of a plate of copper, *mn*, the ends of which are bent and soldered to a plate of bismuth, *op*. In the interior of the circuit is a magnetic needle, *a*, moving on a pivot. When the apparatus is placed in the magnetic meridian, and one of the solderings gently heated, as shown in the figure, the needle is deflected in a manner which indicates the passage of a current from *n* to *m*, that is, from the heated to the cool junction in the copper. If, instead of heating the junction, *n*,

it is cooled by ice, or by placing upon it cotton wool moistened with ether, the other junction remaining at the ordinary temperature, a current is produced, but in the opposite direction; that is to



Fig. 424.

say, from *m* to *n*. In both cases the current is more energetic in proportion as the *difference* in temperature of the solderings is greater.

Seebeck gave the name *thermoelectric* to this current, and the couple which produces it, to distinguish it from the *hydroelectric* or ordinary voltaic current and couple.

500. **Thermoelectric series.**—If small bars of two different metals are soldered together at one end while the free ends are connected with the wires of a galvanometer, and if now the point of junction of the two metals be heated, a current is produced, the direction of which is indicated by the deflection of the needle of the galvanometer, figs. 426, 427. By experimenting in this way with dif-



Fig. 425.



Fig. 426.

ferent metals, they may be formed in a list such that each metal gives rise to positive electricity when associated with one of the following,

and negative electricity with one of those that precede ; that is, that in heating the soldering, the positive current goes from the positive to the negative metal across the soldering, just as if the soldering represented the liquid in a hydroelectrical element ; hence out of the element, in the connecting wire in the galvanometer for instance, the current goes from the negative to the positive metal. Thus a couple, bismuth-antimony, heated at the junction would correspond to a couple, zinc-copper, immersed in sulphuric acid. Fig. 426 represents a battery of such elements.

Of all bodies, bismuth and selenium produce the greatest electromotive force ; but from the expense of this latter element, and on account of its low conducting power, antimony is generally substituted. The antimony is the negative metal but the positive pole, and the bismuth the positive metal but the negative pole, and the current goes from bismuth to antimony across the junction.

501. **Nobili's thermoelectric pile.**—Nobili devised a form of thermoelectric battery, or pile as it is usually termed, in which there are a large number of elements in a very small space. For this purpose he joined the couples of bismuth and antimony in such a manner, that after having formed a series of five couples, as represented in fig. 427, the bismuth from *b* was soldered to the antimony of a second series arranged similarly ; the last bismuth of this to the antimony of a third, and so on for four vertical series, containing together twenty couples, commencing by antimony finishing by bismuth. Thus arranged, the couples are insulated from one another by means of small paper bands covered with varnish, and then enclosed in a copper frame, P (fig. 428), so that only the solderings appear at the two ends of the pile. Two small copper binding screws, *m* and *n*, insulated in an ivory ring, communicate in the interior, one with the first antimony, representing the positive pole and the other with the last bismuth, representing the negative pole. These binding screws communicate with the extremities of a galvanometer wire, when the thermoelectric current is to be observed.

Fig. 428.

Fig. 427.

A Nobili's pile in combination with a galvanometer constitutes the most delicate and accurate means of measuring a temperature. Such an arrangement was first used by Melloni in his researches on the transmission of radiant heat. The arrangement he used is represented in figure 429.

On a wooden base, provided with levelling screws, a graduated copper rule, about a yard long, is fixed edgeways. On this rule the various parts composing the apparatus are placed, and their distances can be fixed by means of binding screws. *a* is a support for



Fig. 429.

a Locatelli's lamp, or other source of heat; F and E are screens; C is a support for the bodies experimented on, and *m* is a thermo-electrical battery. Near the apparatus is a galvanometer, D, which has only a comparatively few turns of a tolerably thick (1mm.) copper wire. Such galvanometers are called *thermomultipliers* (473). The delicacy of this apparatus is so great that the heat of the hand is enough, at a distance of a yard from the pile, to deflect the needle of the galvanometer.

Erratum.

Page 354, line 9 from bottom, *for* **Decomposition** *read* **Recomposition.**

INDEX.

ABE

ABERRATION of refrangibility, chromatic, 359; spherical, 361
Absorption, 68, 137; of light, 302
Absorbing power, 213; causes which modify, 215
Accelerated motion, 17
Accelerating forces, 20
Accidental images, 356
Achromatic lenses, 350
Acidometer, 105
Acoustic foci, 164
Aerial wire, 485
Aeriform fluids, 5
Adhesion, 64
Affinity, 3, 4; chemical, 63
Air, atmospheric, 110; hygrometric state of, 273; weight of, 113
Air-guns, 13
Air-pump, 138, 260; gauge, 139; uses of, 140
Alarum, electrical, 491
Alcarrazas, 249
Alcohol thermometer, 201
Alcoholometer, Gay-Lussac's, 107; centesimal, 107
Alphabet, telegraphic, 488
Amalgam, 312
Ampère's rule, 471; stand, 472; theories of magnetism, 480
Amplitude of oscillation, 57
Analysis, spectrum, 350
Aneroid barometer, 135
Angle of incidence, 308; reflection, 308
Antipodes, 40
Apparent expansion, 225; rest, 14
Appert's method of preserving food, 141
Aqueous humour, 383
Aqueous vapour, 247
Arc, voltaic, 464

BAT

Archimedes' principle, 96, 102; applied to gases, 151
Armatures, 398, 428
Arms of a lever, 33
Artesian wells, 94
Astronomical telescopes, 364
Atmosphere, crushing force of, 115; electricity of, 441; experiments on weight of, 113; heat of, 194; height of, 130; pressure of, in all directions, 131
Atmospheric pressure, 114; amount of, 119
Atoms, 4, 8
Attraction, chemical, 3, 4; magnetic, 389; molecular, 4; universal, 36
Atwood's machine, 55
Aura, 420
Auroras, 394
Aurora borealis, 447
Aurum musivum, 413
Autoclaves, 267
Axis of suspension, 48

BALANCE, 48; conditions of accuracy and delicacy of, 49; Coulomb's, 405; hydrostatic, 96, 102, 103
Balloons, air, 152; construction and management of, 153
Band, endless, 261
Barker's mill, 79
Barometer, 120; cistern, 121; Fortin's, 122; height determined by, 129; mean height of, 125; precautions in reference to, 124; syphon, 123; variations of, 125
Barometric variations, 126, 127
Baroscope, 151
Battery, chemical effects of, 465; luminous effects, 464; physiological

BAT

effects of, 462 ; thermal effects, 463 ; voltaic, 456
Batteries, constant, 458 ; electric, 429 ; enfeeblement of the current in, 457
Beacons, 345
Beam, 48
Beating reed, 187
Beaumé's hydrometer, 106
Bellows, 155, 188
Bernouilli's laws, 189
Berthollet's apparatus, 136
Binocular vision, 385
Biot's experiment, 409
Bladder of fish, 99
Blood globules, 8
Bodies, equilibrium of, 45 ; general properties of, 6 ; internal constitution of, 4
Boiler, steam, 267
Boiling, 243 ; laws of, 244, 245
Bologna, Tower of, 47
Boyle's law, 133
Brahma's press, 83
British units, 104
Buffon's burning mirrors, 211
Bulb of thermometer, 198
Bulging of earth at the equator, 31
Bunsen's battery, 460 ; burner, 351
Bunsen and Kirchhoff's researches, 350, 351, 352
Bunten's barometer, 123
Buoyancy of liquids, 80
Burning glasses, 344 ; mirrors, 211

CÆSIUM, 353
Caloric, 256
Calorific capacity, 257
Calorific effects of the spectrum, 348
Calorimeter, Rumford's, 297
Calorimetry, 256
Camera obscura, 378, 379 ; portable, 378
Capillarity, 65
Captive balloon, 153
Cartesian diver, 98
Catoptric telescopes, 366
Celsius scale, 200
Centesimal alcoholometer, 107
Centigrade scale, 200
Centimeter, 104
Centre of gravity, 41 ; determination of, 43
Centrifugal force, 29
Charge of electrical machine, 413
Chatterton's compound, 485

CON

Chemical affinity, 63 ; attraction, 3, 4 ; combinations, 296 ; effects of the electric battery, 464 ; of the spectrum, 348 ; hygrometers, 273 ; phenomenon, 1
Cheval vapeur, 266
Chimes, electrical, 418
Chimneys, draughts in, 228
Chlorine, 229
Chords, 174 ; vocal, 193
Choroid, 383
Chromatic scale, 176 ; aberration, 359
Circuit, 483
Cirro-cumulus, 281
Cirro-stratus, 281
Cirrus, 281
Cistern barometer, 121
Climate, 279
Clouds, 281 ; formation of, 282
Coercive force, 392
Cohesion, 63
Coil, primary, 493 ; Ruhmkorff's, 496 ; secondary, 493
Cold, 298 ; by expansion of gases, 299 ; due to evaporation, 249 ; nocturnal radiation, 300
Collecting plate, 430
Collimation, 364
Collodion, 379
Colour of heat, 216
Colours of the spectrum, 346
Cooling, condensation by, 251
Combustion, 296
Comma, 174
Communicator, 483
Commutator, 483
Compass, inclination, 396 ; mariners', 395
Compensation pendulum, 224
Complementary colours, 356
Component forces, 24
Compound microscopes, 369
Compound musical tones, 179
Compound pendulum, 57
Compressibility, 11
Compression pump, 13
Concave mirrors, 211, 318 ; focus of, 319 ; formation of images in, 322 ; reflection of heat from, 211
Concert pitch, 177
Concurrent forces, 27 ; resultant of, 25
Condensation, heat disengaged during, 252 ; hygrometers, 273 ; by chemical affinity, 251 ; by cooling, 251 ; by pressure, 251 ; of vapours, 251

CON

d wave, 157
r, 260
's, limit of charge of, 427
ıg electroscope, 430; en-
5; plate, 430; pump, 142
ity of bodies, applications,
liquids, 219; of gases, 220;
s, 218
rs, 406; bad, 218; good,

r, the earth as a, 486; light-
6, 490
on, 233
focus, 320, 338
g rod, 261
ce, 174
batteries, 458
e force, 223
nses, 341, 342
nirrors, 318; formation of
in, 323
83
ıiston, 192
ar theory, 301
s balance, 405
des tasses, 456
, 364
t
ıss lens, 360
, 383
ıtion, 234
234
cpansion, 196, 222
:ratus, 281
281
132
electricity, 453; terrestrial,
ermo-electric, 499
n currents, reciprocal actions
; upon magnets, action of,
:tion of magnets and of the
n, 472; induction by, 493;
sation by, 475; properties
ed, 495
, 85
r motion, 15

ERREOTYPE, 379
nper of piano, 183
ıuppets, 419
battery, 458, 459; hygro-
273
s of the spectrum, 349
e, 317
ın, 394

ELE

Decomposed force, 26
Decomposition of light, 346; water, 465
Degrees, Fahrenheit, 200; Rèaumur 200
De la Rive's experiments, 498
Deliquescent salts, 272
Density 2, of gases, 229
Despretz's experiment, 463
Developer, 339
Dew, 284; point, 273
Dial telegraph, 483
Diamond, 326
Diathermaneity, 216
Differential thermometer, 203
Diffused light, 310
Digester, 246
Diorama, 381
Dip, magnetic, 396
Dipping needle, 396
Discharge, slow and instantaneous, 426
Discharger, universal, 434
Discharging rod, 426
Dispersion of light, 346
Dissolving views, 373
Dissonance, 174
Distance of distinct vision, 384
Distillation, 254
Divisibility, 8
Dominant chords, 174
Dove's law of rotation of winds, 290
Double action machine, 260; description of, 261
Drum, 157
Ductility, 72
Dynanometer, 23

EAR trumpet, 168
Earth currents, 447
Earth, flattening of at the poles, 31; radius of, 31; as a conductor, 486
Ebullition, 243; laws of, 244, 245
Eccentric, 262
Echelon, 345
Echoes, 164
Egg, electric, 421
Elastic force of aqueous vapour, 247; fluids, 109
Elasticity, 12, 13
Electric batteries, 429; egg, 421; spark, 416, 434; telegraphs, 483
Electric discharge, effects of, 431; phenomena of, 431; physiological effects of, 432
Electric light, 464; stratification of,

497; electric alarum, 491; attraction and repulsion, 404; chimes, 418; condensers, 425; discharge, magnetic effects of, 438; machine, 412; measurement of charge of, 413; pendulum, 401; whirl, 420
Electrical fluids, hypothesis of two, 403; portraits, 435; positive and negative, 403
Electricity, 399; atmospheric, 440; chemical effects of, 437; current, 453; in chemical actions, 452; by friction, law of 408 luminous effects of, 433; heating effects of, 434; induction, 409, 411; influence of shape of body on, 410; mechanical effects of, 436; on the surface of bodies, 409; sources of, 400; tension of, 409
Electrification of conductors, 407
Electro-chemical series, 466
Electrodes, 455
Electrodynamics, 476
Electro-gilding, 468
Electrolysis, 466
Electrolyte, 466
Electromagnets, 482
Electro-magnetic machines, 492
Electrometallurgy, 467
Electrometer, Henley's, 413
Electromotive force, 454; series, 454
Electromotor, 483
Electronegative and electropositive elements, 466; series, 454
Electrophorus, 414
Electroscopes, 401; condensing, 430; gold leaf, 415
Electrotype, 467
Elements, 3
Emission of heat, 194
Emission theory, 301
Emissive power, 214
Engines, fire, 148; high pressure, 265, 266
Eolipyle, 259
Epinus's condenser, 12
Equality of pressures, 76
Equilibrium, 28; of bodies, 45, 46; of floating bodies, 97; liquids, 84, 87, 88, 89
Escapement, 61; wheel, 61
Evaporation, 242; cold due to, 249; latent heat of, 248
Expansibility of gases, 5, 111
Expansion, 196, 222; of gases, cold produced by, 299; of liquids, 225; real or apparent, 225; of solids, 222, 223
Extension, 6
Eye, structure of, 383; white, 383

FAHRENHEIT degrees, 200; hydrometer, 103
Falling bodies, laws of, 52
Fata morgana, 331
Feed pump and cold water pump, 260, 264
Filtration, 10
Finder, 364, 366
Fire engines, 148
Fish, swimming-bladder of, 99
Flame, 296
Flexure, 12
Flint glass lens, 360
Float, 268
Florentine experiment, 9
Fluids, aeriform, 5; elastic, 109; magnetic, 390; vital, 449
Flute, 192
Fly wheel, 261
Foci, 337; acoustic, 164; and images, 341
Focus, 211, 318, 319; conjugate, 320, 338; virtual, 321, 339
Fogs, 280
Foot, cubic, 104; pound, 266
Force, centrifugal, 29; direction of, 22 pump, 147
Forces, 22, 23, 24, 25, 28
Fortin's barometer 122
Fountain, Hero's, 143; intermittent, 144; in vacuo, 140
Franklin's lightning conductor, 446; experiment on ebullition, 245; kite, 439
Frauenhofer's lines, 349
Freezing mixtures, 236
French units, 104
Fresnel's lenses, 345
Friction, 21
Friction, electricity by, 408; heat due to, 292; wheels, 55
Frog current, 450
Fulcrum, 33
Fulgurites, 444
Fusion, 230; laws of, 231; of ice, 258; vitreous, 230

GALILEO's telescope, 363
Gallon, 104

GAL

hock, 461
:xperiment, 449
eter, 473 ; uses of 474
3
:09 ; conductivity of, 220 ;
of, 229 ; expansibility of,
; laws of mixture of, 136 ;
ion of, 255 ; permanent,
lue of the expansion of,
ight of, 112
liquids, mixture of, 137
l Weber's electro-magnetic
h, 483
ies, 382
factors, 273
urning, 344
eather, 128
inous, 423
8
73 ; electroscope, 415
:r's skin, 73
:r, reflecting, 324

104
467
e's ring, 196
n, 37
specific, 101
8, 43 ; centre of, 43 ; flask,
; measurement of the force

e, 35
m, 277

286
rdness, scale of, 71
water, 52
s, 179, 189
triad, 174
:'s air-pump, 138
; applications, 217 ; atmo-
194 ; a condition of matter,
:olour of, 216 ; different
of, 291 ; form of motion,
ie to friction, 292 ; due to
: and percussion, 293 ; gene-
:ts of, 195 ; force of, 4 ; in-
ge of, 209 ; latent, of ice,
w of reflection of, 210 ; of
32 ; lightning, 442 ; radiant,
fraction of, 331, 344 ; from
mirrors, 211 ; specific, 257 ;
al, 295 ; in vacuo, 207
167
y steam, 253

ING

Height of the atmosphere, 130
Heights determined by barometer, 129
Heliostat, 324
Hemispheres, Magdeburg, 116
Henley's electrometer, 413
Hero's fountain, 143
Herschel's telescope, 367
Hiero's golden crown, 96
High pressure engine, 265
Hippocrates, strainer of, 10
Hoar frost, 284
Hooke's barometer, 128
Hope's experiments, 226
Horn, 192
Horse power, 266
Human voice, 193
Hydraulic press, 83 ; tourniquet, 79
Hydrofluoric acid, 200
Hydrometers, 103, 105, 106 ; Nicholson's, 102
Hydrostatic balance, 96, 102, 103 ; paradox, 81
Hydrostatics, 74
Hydrogen, density of, 229
Hydrometric state of air, 273
Hygrometry, 271
Hygroscopes and hygrometers, 272
Hyponitrous acid, 460

ICEBERGS, 233
Ice calorimeter, 258 ; expansive force of, 233 ; fusion of, 258 ; latent heat of, 232 ; machine, 236
Images, 312 ; accidental, 356 ; and foci, 343 ; in concave mirrors, 322 ; multiple, 315 ; real, 322, 341 ; and virtual, 314, 342 ; reversed, 316 ; symmetrical, 314
Imbibition, 69
Immersed bodies, equilibrium of, 97
Impenetrability, 7
Impermeable strata, 94
Incidence, angle of, 210, 325
Inclination compass, 396 ; magnetic, 396
Inclined plane, 53 ; bodies falling by, 54
Indicator, 483, 488
Indium, 352
Induced currents, properties of, 495
Induction, coils, 496 ; by the earth, 494 ; by currents, 493 ; electricity by, 411 ; magnetic, 391 ; by magnets, 392, 494
Inertia, 18, 19
Ingenhousz's apparatus, 218

INK

Inkstand, syphon, 145
Instruments, mouth, 192 ; wind, 192
Insulating bodies, 407 ; stool, 417
Intermittent springs, 150
Intervals, 174
Iris, 383
Irradiation, 357
Isochimenal lines, 278
Isochronism, 58
Isoclinic lines, 396
Isogeothermic lines, 278
Isotheral lines, 278
Isothermal lines, 278 ; zone, 278

JAR, Leyden, 428 ; luminous, 433
Jets of water, 92
Jupiter, 306

KATEIDOSCOPE, 317
Kamsin, 289
Kepler's telescope, 364
Key-note, 175
Kilogrammetre, 266
Kirchhoff's and Bunsen's researches, 351
Kite, Franklin's, 439
Knife-edge, 48

LACTOMETER, 108
Land breeze, 289
Latent heat, 232 ; of vapours, 248
Lateral pressures, 79
Latitude, influence of on temperature, 276
Lavoisier and Laplace's ice calorimeter, 258
Laws of falling bodies, 52 ; of radiation, 207
Leclanche's battery, 461
Length, unit of, 23
Lenses, 335 ; achromatic, 350 ; crown glass, 360 ; different kinds of, 335 ; flint glass, 360 ; principal axis of, 336 ; double convex, 340 ; real images in, 341
Leslie's cube, 212 ; differential thermometer, 203
Levelling staff, 90
Level of liquids, 85, 86 ; spirit, 91
Levers, 33 ; applications of, 35 ; arms of, 33 ; effect of, 34
Leyden jar, 428
Lift-pumps, 146
Lightning, 439, 442 ; effects of, 444 ; ascending, 444 ; conductor, 446, 490

MAR

Light, absorption of, 303 ; decomposition of, 346 ; diffused, 310 ; dispersion of, 346 ; electric, 464 ; intensity of, 307 ; propagation of, 304 ; recomposition of, 353 ; reflection of, 308 ; scattered, 310 ; sources of, 302 ; velocity of, 306
Lighthouses, 345
Line wire, 485
Linear expansion, 222
Litre, 104
Loadstone, 387
Long sight, 384
Loops, 189
Liquefaction of gases, 255 ; of vapours, 251
Liquids, 5 ; buoyancy of, 80 ; conducting power of, 218 ; equilibrium of, 84, 87 ; expansion of, 225 ; fixed, 237 ; level of, 85 ; pressures from, 78 ; specific gravity of, 103 ; superposed, 89 ; volatile, 237
Luminiferous ether, 301
Luminous globe and tube, 423

MACHINE, 32 ; weighing, 51
Mackarel sky, 281
Magdeburg hemispheres, 116
Magic lantern, 371 ; pane, 422
Magnetic attraction and repulsion, 389 ; batteries, 398 ; dip, 396 ; equator, 396 ; effects of electrical discharge, 438 ; fluids, 390 ; induction, 391 ; meridian, 394 ; needle, 387, 389, 471 ; poles, 390 ; substances, 391
Magnetisation of the earth, 397 ; by currents, 475 ; limit of, 480 ; by magnets, 397 ; by touch, 397
Magnetism, Ampère's theory of, 480 ; and electricity, 469
Magnets, action of current upon, 470 ; of the earth on, 393 ; consequent points of, 388 ; distribution of magnetic force in, 388 ; in the earth, 472 ; induction by, 494 ; influence of, in magnetic substances, 391 ; natural and artificial, 387
Major chord, 174 ; semitone, 174 ; tone, 174
Malleability, 73
Manhole, 267
Manometer, 134 ; compressed air, 134 ; open air, 134
Mares' tails, 281

ss, 395
33
184
us, 81

:y of water, 226
; temperature, 275

)multiplier, 501
:a, 471
ometers, 198, 202
250
etic, 394 ; quadrant

4

)8 ; compound, 369 ;
ise of, 370 ; photo-
; solar, 375
ometer, 204
74 ; semitone, 175 ;

ıpplications of, 324 ;
concave, 211, 318 ;
)herical, 318

)d of, 258
ım of temperature, 209
:tion, 4 ; forces, 4

:t, 488 ; key and re-
nent, 488 ; telegraph,

:lerated, 17 ; uniform,
accelerated, 17 ; re-

ıts, 186, 192; piece, 185

164 ; images, 315, 317
Leyden jar, 428
84 ; compound tones,
s, 174 ; scale, 173 ;
emperament, 176

:ate, 63
dipping, 396 ; mag-
arked end of, 389

Newcomen and Cowley's fire-pump, 259 single action machine, 260
Newton's disc, 353 ; telescope, 366 ; theory on light and colour 353
Nicholson's hydrometer, 102
Nimbus, 281
Nitrogen, 110 ; density of, 229
Nobili's thermo-electric pile, 501
Nodes and loops, 189
Noise, 169
Non-conductors, 406
Notes, fixed and variable, 192
Nut-crackers, 35

OCCULTATION of Jupiter, 306
Oersted's discovery, 470
Open pipes, laws of, 189
Optic nerve, 383
Optical centre, 336 ; instruments, 362–386
Orbits, 37
Organ pipes, 192
Oscillating motion, 56
Oscillation, 156 ; amplitude of, 56 ; of pendulum, 104
Otto von Guericke's air-pump, 138 ; electrical machine, 412 ; hemispheres, 116
Outcrop, 94
Overtones, 179
Oxygen, 110 density of, 229
Ozone, 437, 444

PALLETS, 61
Pandean pipe, 192
Papin's digester, 246
Parachute, 154
Paradox, hydrostatical, 81
Parallelogram, 260 ; of forces, 25, 26
Pascal's experiment, 82 ; on atmospheric pressure, 118 ; law, 76, 77
Pedal, 183
Pendulum, application of, to clocks, 61 ; compensation, 224 ; compound, 57 ; electrical, 401 ; simple, 56, 57 ; verification of laws of, 59
Penumbra, 305
Percussion, heat due to, 293
Periscopic glasses, 384
Permeable strata, 94
Perturbations, 394
Phantasmagoria, 372
Phial of four elements, 89
Phosphorescence, spontaneous, 302
Photo-electrical microscope, 374

PHO

Photography, 379
Photometer, 307
Physiological effects of the electric discharge, 432, 462
Piano, 183
Piezometer, 75
Pisa, Tower of, 47
Pitch, 170; concert, 177; pipe, 191
Plane, inclined, 53; mirrors, 313
Plumb-line, 41
Pluviometer, 283
Pneumatic syringe, 293
Points, power of, 410
Polarity, austral and boreal, 393
Poles, flattening of the earth at, 31; of the magnet, 388; magnetic, 396
Poles and electrodes, 455
Polyorama, 373
Pores, 4, 9
Porosity, 9
Positive electrical fluid, 403; on glass, 380; plate, 454
Pound avoirdupois, 104
Powers, 20
Presbytism, 384
Presbyoptic, 384
Press, hydraulic, 83
Pressure, atmospheric, 114; condensation by, 251; equality of, 76; heat due to, 293; horizontal, 78; of an atmosphere, 131, 244; on a liquid, 245; on a body in a liquid, 95; supported by a man, 132
Primary coil, 493; tones, 179
Prism, 333; paths of rays in, 334
Proof plane, 410
Propagation of light, 304; of sound, 157, 160
Psychrometer, 273
Pumps, 138, 142, 146, 147
Pupil, 383
Pyrheliometer, 294
Pyrometers, 205

QUADRANT electrometer, 413
Quadrant of the meridian, 104

RADIANT heat, 206, 208
Radiating powers, 215
Radiation, laws of, 207; solar, 294
Radius of the earth, 31
Rain, 283; gauge, 282
Rainbow, 358
Ramsden's electrical machine, 412
Rarefaction, measurement of, 139

SCA

Ray, incident, 210, 308, 325; reflected, 308, 325
Real expansion, 225
Real image, 322; in double convex lenses, 341; and virtual images, 314
Réaumur degree, 200; scale, 200
Receiver, 138, 255; air-pump, 138
Recomposition of white light, 353
Reed instruments, 187
Reflected ray, 308, 325
Reflecting telescopes, 365
Reflection, angle of, 210; of heat, 210, 211; internal, 330; of light, 308; from transparent bodies, 316; regular, 310; irregular, 310; of sound, 163; specular, 310
Refracting substances, 327
Refraction, 325; angle of, 325; change of, to reflection, 330; experimental proofs of, 328; of heat, 331, 344; laws of, 326; limit of, 330; various effects of, 329; through prisms and lenses, 332–340
Refractory substances, 230
Refrangibility, aberration of, 359
Regulator, 260, 263
Relay, 491
Repulsion, magnetic, 389
Resistances, 20, 33
Resonance, 164; box, 177; globes, 179; of air, 178
Resultant forces, 24
Rest, 14
Retina, 383
Return shock, 445
Reversed image, 316
Rheometer, 473
Rime, 284
Rope dancing, 47
Rotation of winds, 290
Rubbers, 413
Rubidium, 352
Ruhmkorff's coil, 496, 497
Rumford's calorimeter, 297
Rutherford's thermometers, 204

SACCHAROMETER, 105
Safety-valve, 246, 269; whistle, 270
Salts, deliquescent, 251, 272; from sea water, 242
Savart's apparatus, 172
Scale of thermometer, 200
Scale-pans, 48
Scattered light, 310

SCH

Schweigger's galvanometer, 473
Scissors, 35
Sclerotica, 383
Sea breeze, 289
Secondary coil, 493
Secondary currents, 457; rainbow, 357
Seconds pendulum, 61
Secular variations, 394
Semiconductors, 406
Semitones, 175
Shadow, 305; geometrical, 305
Shaft, horizontal, 261
Short sight, 384
Single-action machine, 260
Sirocco, 289
Sleet, 285
Slide valve, 262
Slow discharge, 426
Snow, 285
Solar microscope, 375; radiation, 294; spectrum, 346; time, 344
Solenoids, 477, 478, 479
Solids, 5; conductivity of, 218; expansion of, 222, 223; specific gravity of, 101, 103
Solidification, 233
Solution, 235
Sonometer, 182
Sonorous body, 156
Sound, 155; intensity of, 165; limit of, 172; post, 183; in pipes, 185; propagation of, 157; reflection of, 163; transmission of, 166; not propagated in vacuo, 159; velocity of, 161; in gases, 161; waves, 157
Soutter's lens, 345
Spark, electrical, 416
Speaking trumpet, 167; tubes, 166
Specific gravities, 101; tables of, 104
Specific gravity, 229; flask, 102, 103; of liquids, 103; properties of bodies, 6; of solids, 102, 103
Specific heat, 257; of solids and liquids, 258; table of, 258
Spectacles, 370
Spectroscope, 351, 352
Spectrum, 346; analysis, 350; colours of, 347; effects of, 348; dark lines of, 349
Specular reflection, 310
Spherical aberration, 361; mirrors, 318
Spirit-level, 91
Springs, 93; intermittent, 150
Staubbach, 52

TON

Steam boiler, 267; engine, 259, 265
Steel, 397
Steelyard, 23
Stereoscope, 386
Stethoscope, 166
Stills, 254
Stool, insulating, 417
Strata-permeable, 94
Stratification of the electric light, 497
Stratus clouds, 281
St. Elmo's fire, 448
Streams, 93
Stringed instruments, 183
Strings, transverse vibrations of, 180
Structure of the eye, 383
Sub-dominant chords, 174
Submarine wire, 485
Subterranean wire, 485
Suction pump, 146
Superficial expansion, 196
Surface, 6; atmospheric pressure on, 119
Suspension, axis of, 48
Swimming, 100; bladder of fishes, 99
Symmer's hypothesis, 403
Syphon, 149; barometer, 123; inkstand, 145
Syren, 171
Syringe, pneumatic, 293

TANTALUS'S cup, 150
Telegraph dial, 483; electric, 483; line wire, 485; Morse's, 487
Telescopes, 362–377
Tempered steel, 387
Temperature, 197; of the air, 276; mobile equilibrium of, 210
Tenacity, 70
Tension, 12; of gases, 109; maximum, 240; of vapours, 240; of electricity, 409
Terrestrial current, 481; heat, 295; telescope, 366
Thallium, 352
Thermal unit, 256
Thermoelectric pile, 501; series, 500
Thermo-electricity, 499
Thermometers, 198; alcohol, 201; differential, 203; graduation of, 199; mercurial, 198; scale of, 199, 200
Thermo-multipliers, 501
Thunder and lightning, 439, 443
Timbre, 170
Time, 344
Tone, major and minor, 174
Tonic chords, 174

TOR

Torricelli's experiment, 117; vacuum, 124
Torsion, 12
Tourniquet, hydraulic, 79
Tower of Pisa, 47; of Bologna, 47
Traction, 23
Trade winds, 289
Translucent bodies, 303
Transparent bodies, 303; colours of, 355; reflection from, 317
Triangle, 184
Trombone, 192
True time, 344
Trumpet, speaking, 167; ear, 168
Tube, graduation of, 121; luminous, 423; Mariotte's, 133; speaking, 166
Tuning-fork, 177, 184; normal, 177
Turning-table, 29
Tympanum, 157

UNDULATION of heat, 194
Undulatory theory, 301
Unison, 174
Unit of length, 23; thermal, 256
Units, British, 104; French, 10
Universal discharger, 434

VACUUM, 124, 141; formation of vapours in, 239
Valve chest, 262; slide, 262; safety, 269
Vane, electrical, 420
Vapour, 109; quantity which saturates a space, 241; latent heat of, 248
Vapours, 237; elastic force, 238; formation in a vacuum, 239, 240; liquefaction of, 251
Variable winds, 289
Variations, barometric, 125
Velocity, 16; of falling bodies, 52; of sound, 161; of light, 306
Ventral segment, 189
Vertical lines, 40; pressure, 80
Vesicular vapours, 281
Vibration, 156
Vibrations of strings, 180; laws of, 181; in pipes, 190; rods, 183
Virtual focus, 321, 339, 343; images, 314, 322, 342

ZON

Vision, mechanism of, 383; distance of distinct, 384; binocular, 385
Vital fluid, 449
Vitreous fusion, 230; humour, 383
Voice, human, 193
Volatile liquids, 237
Voltaic arc, 464; battery, 456, 462; couple, 451, 454; current, 456; pile, 451, 456
Volta's cannon, 424; condensing electroscope, 450; fundamental experiment, 450
Volume, 6, 101
Vowel sounds, 216

WATER, decomposition of, 465; hammer, 52; jets of, 92; latent heat of, 232; level, 90; maximum density of, 226; and mercury frozen in a vacuum, 250
Watt's steam engine, 260
Wave, condensed, 157; rarefied, 157
Weather, 127; glasses, 128
Weighing machines, 51; method of double, 50
Weight of the air, 113; of a body, 39, 42; of gases, 112; of liquids, 78
Wells, 93
Wet-bulb, hygrometer, 273
Wheel barometer, 128; escapement, 61; fly, 261; friction, 55
Whirl, electrical, 420
Whistle, safety, 270
White light, 346; recomposition of, 353
Whitworth's shells, 293
Winds, 287, 288; law of rotation of, 290; variable, 289
Wind instruments, 192; channel, 187; chest, 188
Wine tester, 131
Wollaston's battery, 456

YARD, 104

ZINC carbon battery, 460
Zone, isothermal, 278

Spottiswoode & Co., Printers, New-street Square, London.

WEINHOLD'S SELF-TEACHING IN PHYSICS.

Just published, in One Thick Volume, 8vo. with 3 Coloured Plates and 404 Woodcuts, price 31*s.* 6*d.* cloth.

INTRODUCTION

TO

EXPERIMENTAL PHYSICS,

THEORETICAL AND PRACTICAL:

INCLUDING

DIRECTIONS FOR CONSTRUCTING PHYSICAL APPARATUS,

AND FOR MAKING EXPERIMENTS.

BY A. F. WEINHOLD,

PROFESSOR IN THE ROYAL TECHNICAL SCHOOL AT CHEMNITZ.

Translated and Edited (with the Author's sanction) by B. LOEWY, F.R.A.S. With a Preface by G. C. FOSTER, F.R.S. Prof. of Physics, Univ. Coll. London.

OPINIONS OF THE PRESS.

'This is by far the best school-book of physics we have ever seen.'

NATURE (Notice of German Edition).

'We are glad to welcome the present translation of Prof. Weinhold's "Vorschule der Experimental Physik." By following the full and excellent directions given, any intelligent lad can be his own instrument maker; and besides the pleasure of construction, he will acquire a sound and extensive acquaintance with the elements of physics by the time he has carefully gone through the book. Knowledge thus obtained will be ineffaceably written on the memory, and its worth will be far greater than a corresponding expenditure of time spent in merely reading several of the ordinary class-books.....Nor is this work only useful for science students. We venture to say any intelligent boy from twelve to fourteen years old might begin this book by himself, and, steadily working at it out of school hours and during the vacation, would in twelve months' time have not only mastered its contents, but have made for himself a very respectable and thoroughly useful collection of physical apparatus, the history and meaning of every fragment of which will be known and loved as part of his nature.....The work is intended as an introduction to the study of physics, and, as such, it is altogether the best we have yet met with among English handbooks.'

NATURE, April 22, 1875.

'This excellent work, admirably translated and edited, is introduced by a valuable preface on self-culture and self-tuition in physics. We have so recently urged upon all students of electricity the necessity of experiment, that it is a matter of great satisfaction to find a work so speedily produced to meet the views propounded. There is no doubt that the only way to impress physical facts upon the minds of students is to make them experiment themselves, and to let them draw their own deductions from their own observations.'

TELEGRAPHIC JOURNAL.

WEINHOLD'S *Experimental Physics.*

'The book, which is complete in itself, may be confidently recommended to the student as a well stored repository of philosophical and operative instruction.' MORNING POST.

'Each experiment is minutely described, the necessary precautions pointed out, and the conditions of success clearly stated. The young student of Physics will find this work a most useful companion.' QUARTERLY JOURNAL OF SCIENCE.

'Whether the plan is likely to be a successful one, time can alone disclose. But that the scheme proposed in the present volume is one which we can highly commend, is altogether unquestionable. The book is upon Experimental Physics, but they are taught after a fashion perfectly new in this country, and which we trust may prove in the highest degree successful. It is at once a book in which are combined the knowledge to be derived from the lecture-room with that from the purely physical laboratory.' POPULAR SCIENCE REVIEW.

'Professor Weinhold does not conduct us to a house already built and stocked with everything requisite for the study of physical phenomena, but he tells us how to build the house and to fill it with the requisite appliances of the study.....The object of the work appears to be to give a good general insight into the processes of physical manipulation, and then to connect together the results obtained into a complete body of physics. The book will be found alike useful to the student and to the lecturer, who will obtain from it many hints for experiments.' ACADEMY.

Physics, or what used to be called Natural Philosophy, imperatively demands to be taught practically by means of experiment and demonstration. So far as possible the student should carry out for himself and by himself all the experiments requisite to give him a clear idea of the subject. Without this he will be quite unable to make any practical use of what little knowledge he may pick up. Prof. Weinhold's work, of which we have here an excellent translation, is exceedingly well adapted for a text-book for use in the laboratory. The directions are clear, precise, and minute.' GARDENERS' CHRONICLE.

'This splendid volume contains chapters on Mechanics, Acoustics, Optics, Electricity and Magnetism, and Heat. The names of Weinhold and Loewy are sufficient guarantee for the work being brought well up to the most recent discoveries, while an Introduction by Mr. G. C. Foster adds weight to the whole.....The book is extremely valuable. It is in the nature of scientific books which deal with any but the closed sciences to be liable to supersession by improvement of method or new discovery. The work before us, we believe, will last far longer than most scientific educational works, while its structure is such as to admit of any new development, without loss to the original scope of its author. We think that the book ought to be introduced into every school library, if not into every science class.' EDUCATIONAL TIMES.

'We find in this book a well-selected series of experiments, illustrating each division of physical inquiry. Full instructions are given for making the apparatus required for the experiment, and for using it, when made, in the most effective manner. These instructions will appear to many to be needlessly minute, but experience will prove that the exactness insisted on is an important element in the true system of teaching physics. Personal experience must be the real teacher, and the skill and the precision which has been gained by persevering industry over some practical operation will have a future value which will well repay a large expenditure of time and thought. The directions for constructing physical apparatus and for making experiments, which are given very concisely and clearly in this volume, remind us of Faraday's "Chemical Manipulations," and we believe this work will be found to be as useful to the earnest student of Physics as that one has proved itself to be to the student of chemistry.' ATHENÆUM.

'Prof. Weinhold, believing in the experimental method of teaching his subject, has founded a systematic treatise on Physics upon a series of experiments which he intends his readers to perform for themselves, and in order to facilitate the importance of this intention as much as possible, he gives full instructions as to the precautions to be observed in making the experiments, as well as in constructing the apparatus. That the experimental is the only thorough method of teaching and learning Physics is a proposition which admits of little controversy, and it is notorious that the cramming by which many students are enabled to pass examinations nowadays, does a vast deal more harm than good.....Mr. Loewy appears to have done his work carefully and well: the illustrations, over 400 in number, are drawn to scale, and many of them are in anisometric parallel projection which gives a very correct idea of the true proportions when compared with a standard scale. We shall have occasion to refer to the book again, but in the meantime we may say that it is well adapted for the use of the self-taught student, and will, we think, find much favour with science teachers.' ENGLISH MECHANIC.

London, LONGMANS & CO.

NOVEMBER 1874.

GENERAL LIST OF WORKS

PUBLISHED BY

MESSRS. LONGMANS, GREEN, AND CO.

PATERNOSTER ROW, LONDON.

History, Politics, Historical Memoirs, &c.

JOURNAL of the REIGNS of KING GEORGE IV. and KING WILLIAM IV. By the late CHARLES C. F. GREVILLE, Esq. Clerk of the Council to those Sovereigns. Edited by HENRY REEVE, Registrar of the Privy Council. 3 vols. 8vo. 36*s.*

RECOLLECTIONS and SUGGESTIONS of PUBLIC LIFE, 1813–1873. By JOHN Earl RUSSELL. 1 vol. 8vo. [*Nearly ready.*

The HISTORY of ENGLAND from the Fall of Wolsey to the Defeat of the Spanish Armada. By JAMES ANTHONY FROUDE, M.A. late Fellow of Exeter College, Oxford.

LIBRARY EDITION, Twelve Volumes, 8vo. price £8. 18*s.*
CABINET EDITION, Twelve Volumes, crown 8vo. price 72*s.*

The ENGLISH in IRELAND in the EIGHTEENTH CENTURY. By JAMES ANTHONY FROUDE, M.A. late Fellow of Exeter College, Oxford. 3 vols. 8vo. price 48*s.*

ESTIMATES of the ENGLISH KINGS from WILLIAM the CONQUEROR to GEORGE III. By J. LANGTON SANFORD. Crown 8vo. 12*s.* 6*d.*

The HISTORY of ENGLAND from the Accession of James II. By Lord MACAULAY.

STUDENT'S EDITION, 2 vols. crown 8vo. 12*s.*
PEOPLE'S EDITION, 4 vols. crown 8vo. 16*s.*
CABINET EDITION, 8 vols. post 8vo. 48*s.*
LIBRARY EDITION, 5 vols. 8vo. £4.

LORD MACAULAY'S WORKS. Complete and Uniform Library Edition. Edited by his Sister, Lady TREVELYAN. 8 vols. 8vo. with Portrait price £5. 5*s.* cloth, or £8. 8*s.* bound in tree-calf by Rivière.

On PARLIAMENTARY GOVERNMENT in ENGLAND; its Origin, Development, and Practical Operation. By ALPHEUS TODD, Librarian of the Legislative Assembly of Canada. 2 vols. 8vo. price £1. 17*s.*

The CONSTITUTIONAL HISTORY of ENGLAND, since the Accession of George III. 1760—1860. By Sir THOMAS ERSKINE MAY, C.B. The Fourth Edition, thoroughly revised. 3 vols. crown 8vo. price 18*s.*

DEMOCRACY in EUROPE; a History. By Sir THOMAS ERSKINE MAY, K.C.B. 2 vols. 8vo. [*In the press.*

The ENGLISH GOVERNMENT and CONSTITUTION from Henry VII. to the Present Time. By JOHN Earl RUSSELL, K.G. Fcp. 8vo. 3s. 6d.

The OXFORD REFORMERS — John Colet, Erasmus, and Thomas More; being a History of their Fellow-work. By FREDERIC SEEBOHM. Second Edition, enlarged. 8vo. 14s.

LECTURES on the HISTORY of ENGLAND, from the Earliest Times to the Death of King Edward II. By WILLIAM LONGMAN, F.S.A. With Maps and Illustrations. 8vo. 15s.

The HISTORY of the LIFE and TIMES of EDWARD the THIRD. By WILLIAM LONGMAN, F.S.A. With 9 Maps, 8 Plates, and 16 Woodcuts. 2 vols. 8vo. 28s.

INTRODUCTORY LECTURES on MODERN HISTORY. Delivered in Lent Term, 1842; with the Inaugural Lecture delivered in December 1841. By the Rev. THOMAS ARNOLD, D.D. 8vo. price 7s. 6d.

WATERLOO LECTURES; a Study of the Campaign of 1815. By Colonel CHARLES C. CHESNEY, R.E. Third Edition. 8vo. with Map, 10s. 6d.

HISTORY of ENGLAND under the DUKE of BUCKINGHAM and CHARLES the FIRST, 1624–1628. By SAMUEL RAWSON GARDINER, late Student of Ch. Ch. 2 vols. 8vo. *[In the press.*

The SIXTH ORIENTAL MONARCHY; or, the Geography, History, and Antiquities of Parthia. By GEORGE RAWLINSON, M.A. Professor of Ancient History in the University of Oxford. Maps and Illustrations. 8vo. 16s.

The SEVENTH GREAT ORIENTAL MONARCHY; or, a History of the Sassanians: with Notices, Geographical and Antiquarian. By G. RAWLINSON, M.A. Professor of Ancient History in the University of Oxford. 8vo. with Maps and Illustrations. *[In the press.*

A HISTORY of GREECE. By the Rev. GEORGE W. COX, M.A. late Scholar of Trinity College, Oxford. VOLS. I. & II. (to the Close of the Peloponnesian War) 8vo. with Maps and Plans, 36s.

The HISTORY OF GREECE. By Rev. CONNOP THIRLWALL, D.D. late Bishop of St. David's. 8 vols. fcp. 8vo. 28s.

GREEK HISTORY from Themistocles to Alexander, in a Series of Lives from Plutarch. Revised and arranged by A. H. CLOUGH. New Edition. Fcp. with 44 Woodcuts, 6s.

The TALE of the GREAT PERSIAN WAR, from the Histories of Herodotus. By GEORGE W. COX, M.A. New Edition. Fcp. 3s. 6d.

The HISTORY of ROME. By WILLIAM IHNE. VOLS. I. and II. 8vo. price 30s. VOLS. III. and IV. preparing for publication.

HISTORY of the ROMANS under the EMPIRE. By the Very Rev. C. MERIVALE, D.C.L. Dean of Ely. 8 vols. post 8vo. 48s.

The FALL of the ROMAN REPUBLIC; a Short History of the Last Century of the Commonwealth. By the same Author. 12mo. 7s. 6d.

The STUDENT'S MANUAL of the HISTORY of INDIA, from the Earliest Period to the Present. By Colonel MEADOWS TAYLOR, M.R.A.S. M.R.I.A. Second Thousand. Crown 8vo. with Maps, 7s. 6d.

The HISTORY of INDIA, from the Earliest Period to the close of Lord Dalhousie's Administration. By J. C. MARSHMAN. 3 vols. crown 8vo. 22s. 6d.

INDIAN POLITY; a View of the System of Administration in India. By Lieutenant-Colonel GEORGE CHESNEY, Fellow of the University of Calcutta. New Edition, revised; with Map. 8vo. price 21*s.*

The IMPERIAL and COLONIAL CONSTITUTIONS of the BRITANNIC EMPIRE, including INDIAN INSTITUTIONS. By Sir EDWARD CREASY, M.A. With 6 Maps. 8vo. price 15*s.*

The HISTORY of PERSIA and its PRESENT POLITICAL SITUATION; with Abstracts of all Treaties and Conventions between Persia and England, and of the Convention with Baron Reuter. By CLEMENTS R. MARKHAM, C.B. F.R.S. 8vo. with Map, 21*s.*

REALITIES of IRISH LIFE. By W. STEUART TRENCH, late Land Agent in Ireland to the Marquess of Lansdowne, the Marquess of Bath, and Lord Digby. Cheaper Edition. Crown 8vo. price 2*s.* 6*d.*

CRITICAL and HISTORICAL ESSAYS contributed to the *Edinburgh Review*. By the Right Hon. LORD MACAULAY.

CHEAP EDITION, authorised and complete. Crown 8vo. 3*s.* 6*d.*

CABINET EDITION, 4 vols. post 8vo. 24*s.* | LIBRARY EDITION, 3 vols. 8vo. 36*s.*
PEOPLE'S EDITION, 2 vols. crown 8vo. 8*s.* | STUDENT'S EDITION, 1 vol. cr. 8vo. 6*s.*

HISTORY of EUROPEAN MORALS, from Augustus to Charlemagne By W. E. H. LECKY, M.A. Second Edition. 2 vols. 8vo. price 28*s.*

HISTORY of the RISE and INFLUENCE of the SPIRIT of RATIONALISM in EUROPE. By W. E. H. LECKY, M.A. Cabinet Edition, being the Fourth. 2 vols. crown 8vo. price 16*s.*

The HISTORY of PHILOSOPHY, from Thales to Comte. By GEORGE HENRY LEWES. Fourth Edition. 2 vols. 8vo. 32*s.*

The HISTORY of the PELOPONNESIAN WAR. By THUCYDIDES. Translated by R. CRAWLEY, Fellow of Worcester College, Oxford. 8vo. 21*s.*

The MYTHOLOGY of the ARYAN NATIONS. By GEORGE W. COX, M.A. late Scholar of Trinity College, Oxford, 2 vols. 8vo. 28*s.*

HISTORY of CIVILISATION in England and France, Spain and Scotland. By HENRY THOMAS BUCKLE. New Edition of the entire Work, with a complete INDEX. 3 vols. crown 8vo. 24*s.*

SKETCH of the HISTORY of the CHURCH of ENGLAND to the Revolution of 1688. By the Right Rev. T. V. SHORT, D.D. Lord Bishop of St. Asaph. Eighth Edition. Crown 8vo. 7*s.* 6*d.*

HISTORY of the EARLY CHURCH, from the First Preaching of the Gospel to the Council of Nicæa, A.D. 325. By Miss SEWELL. Fcp. 8vo. 4*s.* 6*d.*

MAUNDER'S HISTORICAL TREASURY; General Introductory Outlines of Universal History, and a series of Separate Histories. Latest Edition, revised by the Rev. G. W. COX, M.A. Fcp. 8vo. 6*s.* cloth, or 10*s.* calf.

CATES' and WOODWARD'S ENCYCLOPÆDIA of CHRONOLOGY, HISTORICAL and BIOGRAPHICAL; comprising the Dates of all the Great Events of History, including Treaties, Alliances, Wars, Battles, &c.; Incidents in the Lives of Eminent Men and their Works, Scientific and Geographical Discoveries, Mechanical Inventions, and Social Improvements. 8vo. price 42*s.*

The FRENCH REVOLUTION and FIRST EMPIRE; an Historical Sketch. By WILLIAM O'CONNOR MORRIS, sometime Scholar of Oriel College, Oxford. With 2 Coloured Maps. Post 8vo. 7*s.* 6*d.*

The HISTORICAL GEOGRAPHY of EUROPE. By E. A. FREEMAN, D.C.L. late Fellow of Trinity College, Oxford. 8vo. Maps. *[In the press.*

EPOCHS of HISTORY; a Series of Books treating of the History of England and Europe at successive Epochs subsequent to the Christian Era. Edited by EDWARD E. MORRIS, M.A. of Lincoln College, Oxford. The three following are now ready:—

The Era of the Protestant Revolution. By F. SEEBOHM. With 4 Maps and 12 Diagrams. Fcp. 8vo. 2*s.* 6*d.*

The Crusades. By the Rev. G. W. COX, M.A. late Scholar of Trinity College, Oxford. With Coloured Map. Fcp. 8vo. 2*s.* 6*d.*

The Thirty Years' War, 1618–1648. By SAMUEL RAWSON GARDINER, late Student of Christ Church. With Coloured Map. Fcp. 8vo. 2*s.* 6*d.*

The Houses of Lancaster and York; with the Conquest and Loss of France. By JAMES GAIRDNER, of the Public Record Office. With Maps. Fcp. 8vo. 2*s.* 6*d.*

Edward the Third. By the Rev. W. WARBURTON, M.A. late Fellow of All Souls College, Oxford. With Maps. Fcp. 8vo. 2*s.* 6*d.*

Biographical Works.

AUTOBIOGRAPHY. By JOHN STUART MILL. 8vo. price 7*s.* 6*d.*

The LIFE of NAPOLEON III. derived from State Records, Unpublished Family Correspondence, and Personal Testimony. By BLANCHARD JERROLD. In Four Volumes. VOL. I. with 3 Portraits engraved on Steel and 9 Facsimiles. 8vo. price 18*s.* VOL. II. is in the press.

LIFE and CORRESPONDENCE of RICHARD WHATELY, D.D. Late Archbishop of Dublin. By E. JANE WHATELY. New Edition, in 1 vol. crown 8vo. [*In the press.*

LIFE and LETTERS of Sir GILBERT ELLIOT, First EARL of MINTO. Edited by the COUNTESS of MINTO. 3 vols. 8vo. 31*s.* 6*d.*

MEMOIR of THOMAS FIRST LORD DENMAN, formerly Lord Chief Justice of England. By Sir JOSEPH ARNOULD, B.A. K.B. late Judge of the High Court of Bombay. With 2 Portraits. 2 vols. 8vo. 32*s.*

ESSAYS in MODERN MILITARY BIOGRAPHY. By CHARLES CORNWALLIS CHESNEY, Lieutenant-Colonel in the Royal Engineers. 8vo. 12*s.* 6*d.*

ISAAC CASAUBON, 1559–1614. By MARK PATTISON, Rector of Lincoln College, Oxford. 8vo. [*In the press.*

BIOGRAPHICAL and CRITICAL ESSAYS, reprinted from Reviews, with Additions and Corrections. Second Edition of the Second Series. By A. HAYWARD, Q.C. 2 vols. 8vo. price 28*s.* THIRD SERIES, in 1 vol. 8vo. price 14*s.*

The LIFE of LLOYD, FIRST LORD KENYON, LORD CHIEF JUSTICE of ENGLAND. By the Hon. GEORGE T. KENYON, M.A. of Ch. Ch. Oxford. With Portraits. 8vo. price 14*s.*

MEMOIR of GEORGE EDWARD LYNCH COTTON, D.D. Bishop of Calcutta and Metropolitan. With Selections from his Journals and Correspondence. Edited by Mrs. COTTON. Crown 8vo. 7*s.* 6*d.*

LIFE of ALEXANDER VON HUMBOLDT. Compiled in Commemoration of the Centenary of his Birth, and edited by Professor KARL BRUHNS; translated by JANE and CAROLINE LASSELL, with 3 Portraits. 2 vols. 8vo. 36*s.*

ORD GEORGE BENTINCK; a Political Biography. By the Right Hon. BENJAMIN DISRAELI, M.P. Crown 8vo. price 6*s.*

he LIFE OF ISAMBARD KINGDOM BRUNEL, Civil Engineer. By ISAMBARD BRUNEL, B.C.L. With Portrait, Plates, and Woodcuts. 8vo. 21*s.*

ECOLLECTIONS of PAST LIFE. By Sir HENRY HOLLAND, Bart. M.D. F.R.S. late Physician-in-Ordinary to the Queen. Third Edition. Post 8vo. price 10*s.* 6*d.*

he LIFE and LETTERS of the Rev. SYDNEY SMITH. Edited by his Daughter, Lady HOLLAND, and Mrs. AUSTIN. Crown 8vo. price 2*s.* 6*d.*

EADERS of PUBLIC OPINION in IRELAND; Swift, Flood, Grattan, and O'Connell. By W. E. H. LECKY, M.A. New Edition, revised and enlarged. Crown 8vo. price 7*s.* 6*d.*

ICTIONARY of GENERAL BIOGRAPHY; containing Concise Memoirs and Notices of the most Eminent Persons of all Countries, from the Earliest Ages to the Present Time. Edited by W. L. R. CATES. 8vo. 21*s.*

IFE of the DUKE of WELLINGTON. By the Rev. G. R. GLEIG, M.A. Popular Edition, carefully revised; with copious Additions. Crown 8vo. with Portrait, 5*s.*

ELIX MENDELSSOHN'S LETTERS from *Italy and Switzerland*, and *Letters from* 1833 *to* 1847, translated by Lady WALLACE. New Edition, with Portrait. 2 vols. crown 8vo. 5*s.* each.

EMOIRS of SIR HENRY HAVELOCK, K.C.B. By JOHN CLARK MARSHMAN. Cabinet Edition, with Portrait. Crown 8vo. price 3*s.* 6*d.*

ICISSITUDES of FAMILIES. By Sir J. BERNARD BURKE, C.B. Ulster King of Arms. New Edition, remodelled and enlarged. 2 vols. crown 8vo. 21*s.*

he RISE of GREAT FAMILIES, other Essays and Stories. By Sir J. BERNARD BURKE, C.B. Ulster King of Arms. Crown 8vo. price 12*s.* 6*d.*

SSAYS in ECCLESIASTICAL BIOGRAPHY. By the Right Hon. Sir J. STEPHEN, LL.D. Cabinet Edition. Crown 8vo. 7*s.* 6*d.*

AUNDER'S BIOGRAPHICAL TREASURY. Latest Edition, reconstructed, thoroughly revised, and in great part rewritten; with 1,000 additional Memoirs and Notices, by W. L. R. CATES. Fcp. 8vo. 6*s.* cloth; 10*s.* calf.

ETTERS and LIFE of FRANCIS BACON, including all his Occasional Works. Collected and edited, with a Commentary, by J. SPEDDING, Trin. Coll. Cantab. Complete in 7 vols. 8vo. £4. 4*s.*

Criticism, Philosophy, Polity, &c.

A SYSTEMATIC VIEW of the SCIENCE of JURISPRUDENCE. By SHELDON AMOS, M.A. Professor of Jurisprudence to the Inns of Court, London. 8vo. price 18*s.*

A PRIMER of the ENGLISH CONSTITUTION and GOVERNMENT. By SHELDON AMOS, M.A. Professor of Jurisprudence to the Inns of Court. New Edition, revised. Post 8vo. [*In the press.*

The INSTITUTES of JUSTINIAN; with English Introduction, Translation and Notes. By T. C. SANDARS, M.A. Sixth Edition. 8vo. 18*s.*

SOCRATES and the SOCRATIC SCHOOLS. Translated from the German of Dr. E. ZELLER, with the Author's approval, by the Rev. OSWALD J. REICHEL, M.A. Crown 8vo. 8*s.* 6*d.*

The STOICS, EPICUREANS, and SCEPTICS. Translated from the German of Dr. E. ZELLER, with the Author's approval, by OSWALD J. REICHEL, M.A. Crown 8vo. price 14*s.*

The ETHICS of ARISTOTLE, illustrated with Essays and Notes, By Sir A. GRANT, Bart. M.A. LL.D. Third Edition, revised and partly rewritten. [*In the press.*

The POLITICS of ARISTOTLE; Greek Text, with English Notes. By RICHARD CONGREVE, M.A. New Edition, revised. 8vo. 18*s.*

The NICOMACHEAN ETHICS of ARISTOTLE newly translated into English. By R. WILLIAMS, B.A. Fellow and late Lecturer of Merton College, and sometime Student of Christ Church, Oxford. 8vo. 12*s.*

ELEMENTS of LOGIC. By R. WHATELY, D.D. late Archbishop of Dublin. New Edition. 8vo. 10*s.* 6*d.* crown 8vo. 4*s.* 6*d.*

Elements of Rhetoric. By the same Author. New Edition. 8vo. 10*s.* 6*d.* crown 8vo. 4*s.* 6*d.*

English Synonymes. By E. JANE WHATELY. Edited by Archbishop WHATELY. Fifth Edition. Fcp. 8vo. price 3*s.*

DEMOCRACY in AMERICA. By ALEXIS DE TOCQUEVILLE. Translated by HENRY REEVE, C.B., D.C.L., Corresponding Member of the Institute of France. New Edition, in two vols. post 8vo. [*In the press.*

POLITICAL PROBLEMS. Reprinted chiefly from the *Fortnightly Review*, revised, and with New Essays. By FREDERIC HARRISON, of Lincoln's Inn. 1 vol. 8vo. [*In the press.*

THE SYSTEM of POSITIVE POLITY, or TREATISE upon SOCIOLOGY, of AUGUSTE COMTE, Author of the System of Positive Philosophy. Translated from the Paris Edition of 1851–1854, and furnished with Analytical Tables of Contents. In Four Volumes, 8vo. to be published separately:— [*In the press.*

VOL. I. The General View of Positive Polity and its Philosophical Basis. Translated by J. H. BRIDGES, M.B.

VOL. II. The Social Statics, or the Abstract Laws of Human Order. Translated by F. HARRISON, M.A.

VOL. III. The Social Dynamics, or the General Laws of Human Progress (the Philosophy of History). Translated by E. S. BEESLY, M.A.

VOL. IV. The Synthesis of the Future of Mankind. Translated by R. CONGREVE, M.A.

BACON'S ESSAYS with ANNOTATIONS. By R. WHATELY, D.D. late Archbishop of Dublin. New Edition, 8vo. price 10*s.* 6*d.*

LORD BACON'S WORKS, collected and edited by J. SPEDDING, M.A. R. L. ELLIS, M.A. and D. D. HEATH. 7 vols. 8vo. price £3. 13*s.* 6*d.*

ESSAYS CRITICAL and NARRATIVE. By WILLIAM FORSYTH, Q.C. LL.D. M.P. for Marylebone; Author of 'The Life of Cicero,' &c. 8vo. 16*s.*

The SUBJECTION of WOMEN. By JOHN STUART MILL. New Edition. Post 8vo. *5s.*

On REPRESENTATIVE GOVERNMENT. By JOHN STUART MILL. Crown 8vo. price *2s.*

On LIBERTY. By JOHN STUART MILL. New Edition. Post 8vo. *7s. 6d.* Crown 8vo. price *1s. 4d.*

PRINCIPLES of POLITICAL ECONOMY. By the same Author. Seventh Edition. 2 vols. 8vo. *30s.* Or in 1 vol. crown 8vo. price *5s.*

ESSAYS on SOME UNSETTLED QUESTIONS of POLITICAL ECONOMY. By JOHN STUART MILL. Second Edition. 8vo. *6s. 6d.*

UTILITARIANISM. By JOHN STUART MILL. New Edition. 8vo. *5s.*

DISSERTATIONS and DISCUSSIONS, POLITICAL, PHILOSOPHICAL, and HISTORICAL. By JOHN STUART MILL. 3 vols. 8vo. *36s.*

EXAMINATION of Sir. W. HAMILTON'S PHILOSOPHY, and of the Principal Philosophical Questions discussed in his Writings. By JOHN STUART MILL. Fourth Edition. 8vo. *16s.*

An OUTLINE of the NECESSARY LAWS of THOUGHT; a Treatise on Pure and Applied Logic. By the Most Rev. W. THOMSON, Lord Archbishop of York, D.D. F.R.S. Ninth Thousand. Crown 8vo. price *5s. 6d.*

PRINCIPLES of ECONOMICAL PHILOSOPHY. By HENRY DUNNING MACLEOD, M.A. Barrister-at-Law. Second Edition. In Two Volumes. VOL. I. 8vo. price *15s.*

A SYSTEM of LOGIC, RATIOCINATIVE and INDUCTIVE. By JOHN STUART MILL. Eighth Edition. Two vols. 8vo. *25s.*

The ELECTION of REPRESENTATIVES, Parliamentary and Municipal; a Treatise. By THOMAS HARE, Barrister-at-Law. Crown 8vo. *7s.*

SPEECHES of the RIGHT HON. LORD MACAULAY, corrected by Himself. People's Edition, crown 8vo. *3s. 6d.*

Lord Macaulay's Speeches on Parliamentary Reform in 1831 and 1832. 16mo. *1s.*

FAMILIES of SPEECH: Four Lectures delivered before the Royal Institution of Great Britain. By the Rev. F. W. FARRAR, D.D. F.R.S. New Edition. Crown 8vo. *3s. 6d.*

CHAPTERS on LANGUAGE. By the Rev. F. W. FARRAR, D.D. F.R.S. New Edition. Crown 8vo. *5s.*

A DICTIONARY of the ENGLISH LANGUAGE. By R. G. LATHAM, M.A. M.D. F.R.S. Founded on the Dictionary of Dr. SAMUEL JOHNSON, as edited by the Rev. H. J. TODD, with numerous Emendations and Additions. In Four Volumes, 4to. price £7.

A PRACTICAL ENGLISH DICTIONARY, on the Plan of White's English-Latin and Latin-English Dictionaries. By JOHN T. WHITE, D.D. Oxon. and T. C. BONNEY, M.A. Assistant-Master, King Edward's Grammar School, Birmingham. Post 8vo. [*In the press.*

THESAURUS of ENGLISH WORDS and PHRASES, classified and arranged so as to facilitate the Expression of Ideas, and assist in Literary Composition. By P. M. ROGET, M.D. New Edition. Crown 8vo. 10*s.* 6*d.*

LECTURES on the SCIENCE of LANGUAGE. By F. MAX MÜLLER, M.A. &c. Seventh Edition. 2 vols. crown 8vo. 16*s.*

MANUAL of ENGLISH LITERATURE, Historical and Critical. By THOMAS ARNOLD, M.A. New Edition. Crown 8vo. 7*s.* 6*d.*

SOUTHEY'S DOCTOR, complete in One Volume. Edited by the Rev. J. W. WARTER, B.D. Square crown 8vo. 12*s.* 6*d.*

HISTORICAL and CRITICAL COMMENTARY on the OLD TESTAMENT; with a New Translation. By M. M. KALISCH, Ph.D. VOL. I. *Genesis*, 8vo. 18*s.* or adapted for the General Reader, 12*s.* VOL. II. *Exodus*, 15*s.* or adapted for the General Reader, 12*s.* VOL. III. *Leviticus*, PART I. 15*s.* or adapted for the General Reader, 8*s.* VOL. IV. *Leviticus*, PART II. 15*s.* or adapted for the General Reader, 8*s.*

A DICTIONARY of ROMAN and GREEK ANTIQUITIES, with about Two Thousand Engravings on Wood from Ancient Originals, illustrative of the Industrial Arts and Social Life of the Greeks and Romans. By A. RICH, B.A. Third Edition, revised and improved. Crown 8vo. price 7*s.* 6*d.*

A LATIN-ENGLISH DICTIONARY. By JOHN T. WHITE, D.D. Oxon. and J. E. RIDDLE, M.A. Oxon. Revised Edition. 2 vols. 4to. 42*s.*

WHITE'S COLLEGE LATIN-ENGLISH DICTIONARY (Intermediate Size), abridged for the use of University Students from the Parent Work (as above). Medium 8vo. 18*s.*

WHITE'S JUNIOR STUDENT'S COMPLETE LATIN-ENGLISH and ENGLISH-LATIN DICTIONARY. New Edition. Square 12mo. price 12*s.*

Separately { The ENGLISH-LATIN DICTIONARY, price 5*s.* 6*d.*
The LATIN-ENGLISH DICTIONARY, price 7*s.* 6*d.*

A LATIN-ENGLISH DICTIONARY, adapted for the Use of Middle-Class Schools. By JOHN T. WHITE, D.D. Oxon. Square fcp. 8vo. price 3*s.*

An ENGLISH-GREEK LEXICON, containing all the Greek Words used by Writers of good authority. By C. D. YONGE, B.A. New Edition. 4to. price 21*s.*

Mr. YONGE'S NEW LEXICON, English and Greek, abridged from his larger work (as above). Revised Edition. Square 12mo. price 8*s.* 6*d.*

A GREEK-ENGLISH LEXICON. Compiled by H. G. LIDDELL, D.D. Dean of Christ Church, and R. SCOTT, D.D. Dean of Rochester. Sixth Edition. Crown 4to. price 36*s.*

A Lexicon, Greek and English, abridged from LIDDELL and SCOTT'S *Greek-English Lexicon*. Fourteenth Edition. Square 12mo. 7*s.* 6*d.*

A SANSKRIT-ENGLISH DICTIONARY, the Sanskrit words printed both in the original Devanagari and in Roman Letters. Compiled by T. BENFEY, Prof. in the Univ. of Göttingen. 8vo. 52*s.* 6*d.*

A PRACTICAL DICTIONARY of the FRENCH and ENGLISH LANGUAGES. By L. CONTANSEAU. Revised Edition. Post 8vo. 10*s.* 6*d.*

Contanseau's Pocket Dictionary, French and English, abridged from the above by the Author. New Edition, revised. Square 18mo. 3*s.* 6*d.*

NEW PRACTICAL DICTIONARY of the GERMAN LANGUAGE; German-English and English-German. By the Rev. W. L. BLACKLEY, M.A and DR. CARL MARTIN FRIEDLÄNDER. Post 8vo. 7*s.* 6*d.*

The MASTERY of LANGUAGES; or, the Art of Speaking Foreign Tongues Idiomatically. By THOMAS PRENDERGAST. 8vo. 6*s*.

Miscellaneous Works and *Popular Metaphysics.*

ESSAYS on FREETHINKING and PLAIN-SPEAKING. By LESLIE STEPHEN. Crown 8vo. 10*s*. 6*d*.

THE MISCELLANEOUS WORKS of THOMAS ARNOLD, D.D. Late Head Master of Rugby School and Regius Professor of Modern History in the University of Oxford, collected and republished. 8vo. 7*s*. 6*d*.

MISCELLANEOUS and POSTHUMOUS WORKS of the Late HENRY THOMAS BUCKLE. Edited, with a Biographical Notice, by HELEN TAYLOR. 3 vols. 8vo. price 52*s*. 6*d*.

MISCELLANEOUS WRITINGS of JOHN CONINGTON, M.A. late Corpus Professor of Latin in the University of Oxford. Edited by J. A. SYMONDS, M.A. With a Memoir by H. J. S. SMITH, M.A. 2 vols. 8vo. 28*s*.

ESSAYS, CRITICAL and BIOGRAPHICAL. Contributed to the *Edinburgh Review*. By HENRY ROGERS. New Edition, with Additions. 2 vols. crown 8vo. price 12*s*.

ESSAYS on some THEOLOGICAL CONTROVERSIES of the TIME. Contributed chiefly to the *Edinburgh Review*. By HENRY ROGERS. New Edition, with Additions. Crown 8vo. price 6*s*.

LANDSCAPES, CHURCHES, and MORALITIES. By A. K. H. B. Crown 8vo. price 3*s*. 6*d*.

Recreations of a Country Parson. By A. K. H. B. FIRST and SECOND SERIES, crown 8vo. 3*s*. 6*d*. each.

The Common-place Philosopher in Town and Country. By A. K. H. B. Crown 8vo. price 3*s*. 6*d*.

Leisure Hours in Town; Essays Consolatory, Æsthetical, Moral, Social, and Domestic. By A. K. H. B. Crown 8vo. 3*s*. 6*d*.

The Autumn Holidays of a Country Parson; Essays contributed to *Fraser's Magazine*, &c. By A. K. H. B. Crown 8vo. 3*s*. 6*d*.

Seaside Musings on Sundays and Week-Days. By A. K. H. B. Crown 8vo. price 3*s*. 6*d*.

The Graver Thoughts of a Country Parson. By A. K. H. B. FIRST and SECOND SERIES, crown 8vo. 3*s*. 6*d*. each.

Critical Essays of a Country Parson, selected from Essays contributed to *Fraser's Magazine*. By A. K. H. B. Crown 8vo. 3*s*. 6*d*.

Sunday Afternoons at the Parish Church of a Scottish University City. By A. K. H. B. Crown 8vo. 3*s*. 6*d*.

Lessons of Middle Age; with some Account of various Cities and Men. By A. K. H. B. Crown 8vo. 3*s*. 6*d*.

Counsel and Comfort spoken from a City Pulpit. By A. K. H. B. Crown 8vo. price 3*s*. 6*d*.

CHANGED ASPECTS of UNCHANGED TRUTHS; Memorials of St. Andrews Sundays. By A. K. H. B. Crown 8vo. 3*s.* 6*d.*

Present-day Thoughts; Memorials of St. Andrews Sundays. By A. K. H. B. Crown 8vo. 3*s.* 6*d.*

SHORT STUDIES on GREAT SUBJECTS. By JAMES ANTHONY FROUDE, M.A. late Fellow of Exeter Coll. Oxford. 2 vols. crown 8vo. price 12*s.*

LORD MACAULAY'S MISCELLANEOUS WRITINGS:—

LIBRARY EDITION. 2 vols. 8vo. Portrait, 21*s.*
PEOPLE'S EDITION. 1 vol. crown 8vo. 4*s.* 6*d.*

LORD MACAULAY'S MISCELLANEOUS WRITINGS and SPEECHES.

STUDENT'S EDITION, in crown 8vo. price 6*s.*

The Rev. SYDNEY SMITH'S ESSAYS contributed to the Edinburgh Review. Authorised Edition, complete in 1 vol. Crown 8vo. price 2*s.* 6*d.*

The Rev. SYDNEY SMITH'S MISCELLANEOUS WORKS; including his Contributions to the *Edinburgh Review*. Crown 8vo. 6*s.*

The Wit and Wisdom of the Rev. Sydney Smith; a Selection of the most memorable Passages in his Writings and Conversation. 16mo. 3*s.* 6*d.*

The ECLIPSE of FAITH; or, a Visit to a Religious Sceptic. By HENRY ROGERS. Latest Edition. Fcp. 8vo. price 5*s.*

Defence of the Eclipse of Faith, by its Author; a rejoinder to Dr. Newman's *Reply*. Latest Edition. Fcp 8vo. price 3*s.* 6*d.*

CHIPS from a GERMAN WORKSHOP; Essays on the Science of Religion, and on Mythology, Traditions, and Customs. By F. MAX MÜLLER, M.A. &c. Second Edition. 3 vols. 8vo. £2.

ANALYSIS of the PHENOMENA of the HUMAN MIND. By JAMES MILL. A New Edition, with Notes, Illustrative and Critical, by ALEXANDER BAIN, ANDREW FINDLATER, and GEORGE GROTE. Edited, with additional Notes, by JOHN STUART MILL. 2 vols. 8vo. price 28*s.*

An INTRODUCTION to MENTAL PHILOSOPHY, on the Inductive Method. By J. D. MORELL, M.A. LL.D. 8vo. 12*s.*

ELEMENTS of PSYCHOLOGY, containing the Analysis of the Intellectual Powers. By J. D. MORELL, M.A. LL.D. Post 8vo. 7*s.* 6*d.*

The SECRET of HEGEL; being the Hegelian System in Origin, Principle, Form, and Matter. By J. H. STIRLING, LL.D. 2 vols. 8vo. 28*s.*

SIR WILLIAM HAMILTON; being the Philosophy of Perception: an Analysis. By J. H. STIRLING, LL.D. 8vo. 5*s.*

The SENSES and the INTELLECT. By ALEXANDER BAIN, M.D. Professor of Logic in the University of Aberdeen. Third Edition. 8vo. 15*s.*

MENTAL and MORAL SCIENCE: a Compendium of Psychology and Ethics. By the same Author. Third Edition. Crown 8vo. 10*s.* 6*d.* Or separately: PART I. *Mental Science*, 6*s.* 6*d.* PART II. *Moral Science*, 4*s.* 6*d.*

LOGIC, DEDUCTIVE and INDUCTIVE. By the same Author. In TWO PARTS, crown 8vo. 10*s.* 6*d.* Each Part may be had separately:—
PART I. *Deduction*, 4*s.* PART II. *Induction*, 6*s.* 6*d.*

The PHILOSOPHY of NECESSITY; or, Natural Law as applicable to Mental, Moral, and Social Science. By CHARLES BRAY. 8vo. 9*s*.

On FORCE, its MENTAL and MORAL CORRELATES. By the same Author. 8vo. 5*s*.

A MANUAL of ANTHROPOLOGY, or SCIENCE of MAN, based on Modern Research. By CHARLES BRAY. Crown 8vo. price 6*s*.

A PHRENOLOGIST AMONGST the TODAS, or the Study of a Primitive Tribe in South India; History, Character, Customs, Religion, Infanticide, Polyandry, Language. By W. E. MARSHALL, Lieutenant-Colonel B.S.C. With 26 Illustrations. 8vo 21*s*.

A TREATISE of HUMAN NATURE, being an Attempt to Introduce the Experimental Method of Reasoning into Moral Subjects; followed by Dialogues concerning Natural Religion. By DAVID HUME. Edited, with Notes, &c. by T. H. GREEN, Fellow and Tutor, Ball. Coll. and T. H. GROSE, Fellow and Tutor, Queen's Coll. Oxford. 2 vols. 8vo. 28*s*.

ESSAYS MORAL, POLITICAL, and LITERARY. By DAVID HUME. By the same Editors. 2 vols. 8vo. price 28*s*.

UEBERWEG'S SYSTEM of LOGIC and HISTORY of LOGICAL DOCTRINES. Translated, with Notes and Appendices, by T. M. LINDSAY, M.A. F.R.S.E. 8vo. price 16*s*.

A BUDGET of PARADOXES. By AUGUSTUS DE MORGAN, F.R.A.S. and C.P.S. 8vo. 15*s*.

Astronomy, Meteorology, Popular Geography, &c.

BRINKLEY'S ASTRONOMY. Revised and partly re-written, with Additional Chapters, and an Appendix of Questions for Examination. By J. W. STUBBS, D.D. Fellow and Tutor of Trinity College, Dublin, and F. BRUNNOW, Ph.D. Astronomer Royal of Ireland. Crown 8vo. price 6*s*.

OUTLINES of ASTRONOMY. By Sir J. F. W. HERSCHEL, Bart. M.A. Latest Edition, with Plates and Diagrams. Square crown 8vo. 12*s*.

ESSAYS on ASTRONOMY, a Series of Papers on Planets and Meteors, the Sun and Sun-surrounding Space, Stars and Star-Cloudlets; with a Dissertation on the approaching Transit of Venus. By RICHARD A. PROCTOR, B.A. With 10 Plates and 24 Woodcuts. 8vo. 12*s*.

THE TRANSITS of VENUS; a Popular Account of Past and Coming Transits, from the first observed by Horrocks A.D. 1639 to the Transit of A.D. 2112. By R. A. PROCTOR, B.A. Cantab. With 20 Plates and numerous Woodcuts. Crown 8vo. [*Nearly ready.*

The UNIVERSE and the COMING TRANSITS: Presenting Researches into and New Views respecting the Constitution of the Heavens; together with an Investigation of the Conditions of the Coming Transits of Venus. By R. A. PROCTOR, B.A. With 22 Charts and 22 Woodcuts. 8vo. 16*s*.

The MOON; her Motions, Aspect, Scenery, and Physical Condition. By R. A. PROCTOR, B.A. With Plates, Charts, Woodcuts, and Three Lunar Photographs. Crown 8vo. 15*s*.

The SUN; RULER, LIGHT, FIRE, and LIFE of the PLANETARY SYSTEM. By R. A. PROCTOR, B.A. Second Edition, with 10 Plates (7 coloured) and 107 Figures on Wood. Crown 8vo. 14*s.*

OTHER WORLDS THAN OURS; the Plurality of Worlds Studied under the Light of Recent Scientific Researches. By R. A. PROCTOR, B.A. Third Edition, with 14 Illustrations. Crown 8vo. 10*s.* 6*d.*

The ORBS AROUND US; a Series of Familiar Essays on the Moon and Planets, Meteors and Comets, the Sun and Coloured Pairs of Stars. By R. A. PROCTOR, B.A. Crown 8vo. price 7*s.* 6*d.*

SATURN and its SYSTEM. By R. A. PROCTOR, B.A. 8vo. with 14 Plates, 14*s.*

SCHELLEN'S SPECTRUM ANALYSIS, in its application to Terrestrial Substances and the Physical Constitution of the Heavenly Bodies. Translated by JANE and C. LASSELL; edited, with Notes, by W. HUGGINS, LL.D. F.R.S. With 13 Plates (6 coloured) and 223 Woodcuts. 8vo. price 28*s.*

A NEW STAR ATLAS, for the Library, the School, and the Observatory, in Twelve Circular Maps (with Two Index Plates). Intended as a Companion to 'Webb's Celestial Objects for Common Telescopes.' With a Letterpress Introduction on the Study of the Stars, illustrated by 9 Diagrams. By R. A. PROCTOR, B.A. Crown 8vo. 5*s.*

CELESTIAL OBJECTS for COMMON TELESCOPES. By the Rev. T. W. WEBB, M.A. F.R.A.S. Third Edition, revised and enlarged; with Maps, Plate, and Woodcuts. Crown 8vo. price 7*s.* 6*d.*

AIR and RAIN; the Beginnings of a Chemical Climatology. By ROBERT ANGUS SMITH, Ph.D. F.R.S. F.C.S. With 8 Illustrations. 8vo. 24*s.*

NAUTICAL SURVEYING, an INTRODUCTION to the PRACTICAL and THEORETICAL STUDY of. By J. K. LAUGHTON, M.A. Small 8vo. 6*s.*

MAGNETISM and DEVIATION of the COMPASS. For the Use of Students in Navigation and Science Schools. By J. MERRIFIELD, LL.D. 18mo. 1*s.* 6*d.*

DOVE'S LAW of STORMS, considered in connexion with the Ordinary Movements of the Atmosphere. Translated by R. H. SCOTT, M.A. 8vo. 10*s.* 6*d.*

KEITH JOHNSTON'S GENERAL DICTIONARY of GEOGRAPHY, Descriptive, Physical, Statistical, and Historical; forming a complete Gazetteer of the World. New Edition, revised and corrected to the Present Date by the Author's Son, KEITH JOHNSTON, F.R.G.S. 1 vol. 8vo. [*Nearly ready.*

The POST OFFICE GAZETTEER of the UNITED KINGDOM. Being a Complete Dictionary of all Cities, Towns, Villages, and of the Principal Gentlemen's Seats, in Great Britain and Ireland; Referred to the nearest Post Town, Railway and Telegraph Station: with Natural Features and Objects of Note. By J. A. SHARP. 1 vol. 8vo. of about 1,500 pages. [*In the press.*

The PUBLIC SCHOOLS ATLAS of MODERN GEOGRAPHY. In 31 Maps, exhibiting clearly the more important Physical Features of the Countries delineated, and Noting all the Chief Places of Historical, Commercial, or Social Interest. Edited, with an Introduction, by the Rev. G. BUTLER, M.A. Imp. 4to. price 3*s.* 6*d.* sewed, or 5*s.* cloth.

The PUBLIC SCHOOLS MANUAL of MODERN GEOGRAPHY. By the Rev. GEORGE BUTLER, M.A. Principal of Liverpool College; Editor of 'The Public Schools Atlas of Modern Geography.' [*In preparation.*

The PUBLIC SCHOOLS ATLAS of ANCIENT GEOGRAPHY Edited, with an Introduction on the Study of Ancient Geography, by the Rev. GEORGE BUTLER, M.A. Principal of Liverpool College. Imperial Quarto.
[*In preparation.*

A MANUAL of GEOGRAPHY, Physical, Industrial, and Political. By W. HUGHES, F.R.G.S. With 6 Maps. Fcp. 7*s.* 6*d.*

MAUNDER'S TREASURY of GEOGRAPHY, Physical, Historical, Descriptive, and Political. Edited by W. HUGHES, F.R.G.S. Revised Edition, with 7 Maps and 16 Plates. Fcp. 6*s.* cloth, or 10*s.* bound in calf.

Natural History and *Popular Science.*

TEXT-BOOKS of SCIENCE, MECHANICAL and PHYSICAL, adapted for the use of Artisans and of Students in Public and Science Schools. Edited by T. M. GOODEVE, M.A. and C. W. MERRIFIELD, F.R.S.

ANDERSON'S Strength of Materials, small 8vo. 3*s.* 6*d.*
ARMSTRONG'S Organic Chemistry, 3*s.* 6*d.*
BLOXAM'S Metals, 3*s.* 6*d.*
GOODEVE'S Elements of Mechanism, 3*s.* 6*d.*
——— Principles of Mechanics, 3*s.* 6*d.*
GRIFFIN'S Algebra and Trigonometry, 3*s.* 6*d.* Notes, 3*s.*6*d.*
JENKIN'S Electricity and Magnetism, 3*s.* 6*d.*
MAXWELL'S Theory of Heat, 3*s.* 6*d.*
MERRIFIELD'S Technical Arithmetic and Mensuration, 3*s.* 6*d.* Key, 3*s.* 6*d.*
MILLER'S Inorganic Chemistry, 3*s.* 6*d.*
SHELLEY'S Workshop Appliances, 3*s.* 6*d.*
THORPE'S Quantitative Chemical Analysis, 4*s.* 6*d.*
THORPE & MUIR'S Qualitative Analysis, 3*s.* 6*d.*
WATSON'S Plane and Solid Geometry, 3*s.* 6*d.*

*** Other Text-Books in active preparation.

ELEMENTARY TREATISE on PHYSICS, Experimental and Applied. Translated and edited from GANOT'S *Éléments de Physique* by E. ATKINSON, Ph.D. F.C.S. New Edition, revised and enlarged; with a Coloured Plate and 726 Woodcuts. Post 8vo. 15*s.*

NATURAL PHILOSOPHY for GENERAL READERS and YOUNG PERSONS; being a Course of Physics divested of Mathematical Formulæ expressed in the language of daily life. Translated from GANOT'S *Cours de Physique* and by E. ATKINSON, Ph.D. F.C.S. Crown 8vo. with 404 Woodcuts, price 7*s.* 6*d.*

HELMHOLTZ'S POPULAR LECTURES on SCIENTIFIC SUBJECTS. Translated by E. ATKINSON, Ph.D. F.C.S. Professor of Experimental Science, Staff College. With an Introduction by Professor TYNDALL. 8vo. with numerous Woodcuts, price 12*s.* 6*d.*

SOUND: a Course of Eight Lectures delivered at the Royal Institution of Great Britain. By JOHN TYNDALL, LL.D. D.C.L. F.R.S. New Edition, with 169 Woodcuts. Crown 8vo. 9*s.*

HEAT a MODE of MOTION. By JOHN TYNDALL, LL.D. D.C.L. F.R.S. Fourth Edition. Crown 8vo. with Woodcuts, 10*s.* 6*d.*

CONTRIBUTIONS to MOLECULAR PHYSICS in the DOMAIN of RADIANT HEAT. By J. TYNDALL, LL.D. D.C.L. F.R.S. With 2 Plates and 31 Woodcuts. 8vo. 16*s.*

RESEARCHES on DIAMAGNETISM and MAGNE-CRYSTALLIC ACTION; including the Question of Diamagnetic Polarity. By J. TYNDALL, M.D. D.C.L. F.R.S. With 6 plates and many Woodcuts. 8vo. 14*s.*

NOTES of a COURSE of SEVEN LECTURES on ELECTRICAL PHENOMENA and THEORIES, delivered at the Royal Institution, A.D. 1870. By JOHN TYNDALL, LL.D., D.C.L., F.R.S. Crown 8vo. 1*s.* sewed; 1*s.* 6*d.* cloth.

A TREATISE on MAGNETISM, General and Terrestrial. By HUMPHREY LLOYD, D.D., D.C.L., Provost of Trinity College, Dublin. 8vo. price 10*s.* 6*d.*

ELEMENTARY TREATISE on the WAVE-THEORY of LIGHT. By HUMPHREY LLOYD, D.D. D.C.L. Provost of Trinity College, Dublin. Third Edition, revised and enlarged. 8vo. price 10*s.* 6*d.*

LECTURES on LIGHT delivered in the United States of America in the Years 1872 and 1873. By JOHN TYNDALL, LL.D. D.C.L. F.R.S. With Frontispiece and Diagrams. Crown 8vo. price 7*s.* 6*d.*

NOTES of a COURSE of NINE LECTURES on LIGHT delivered at the Royal Institution, A.D. 1869. By JOHN TYNDALL, LL.D. D.C.L. F.R.S. Crown 8vo. price 1*s.* sewed, or 1*s.* 6*d.* cloth.

ADDRESS delivered before the British Association assembled at Belfast; with Additions and a Preface. By JOHN TYNDALL, F.R.S. President. 8vo. price 3*s.*

FRAGMENTS of SCIENCE. By JOHN TYNDALL, LL.D. D.C.L. F.R.S. Third Edition. 8vo. price 14*s.*

LIGHT SCIENCE for LEISURE HOURS; a Series of Familiar Essays on Scientific Subjects, Natural Phenomena, &c. By R. A. PROCTOR, B.A. First and Second Series. Crown 8vo. 7*s.* 6*d.* each.

The CORRELATION of PHYSICAL FORCES. By the Hon. Sir W. R. GROVE, M.A. F.R.S. one of the Judges of the Court of Common Pleas. Sixth Edition, with other Contributions to Science. 8vo. price 15*s.*

Professor OWEN'S LECTURES on the COMPARATIVE ANATOMY and Physiology of the Invertebrate Animals. Second Edition, with 235 Woodcuts. 8vo. 21*s.*

The COMPARATIVE ANATOMY and PHYSIOLOGY of the VERTE- BRATE ANIMALS. By RICHARD OWEN, F.R.S. D.C.L. With 1,472 Woodcuts. 3 vols. 8vo. £3. 13*s.* 6*d.*

PRINCIPLES of ANIMAL MECHANICS. By the Rev. S. HAUGHTON, F.R.S. Fellow of Trin. Coll. Dubl. M.D. Dubl. and D.C.L. Oxon. Second Edition, with 111 Figures on Wood. 8vo. 21*s.*

ROCKS CLASSIFIED and DESCRIBED. By BERNHARD VON COTTA. English Edition, by P. H. LAWRENCE; with English, German, and French Synonymes. Post 8vo. 14*s.*

The ANCIENT STONE IMPLEMENTS, WEAPONS, and ORNA- MENTS of GREAT BRITAIN. By JOHN EVANS, F.R.S. F.S.A. With 2 Plates and 476 Woodcuts. 8vo. price 28*s.*

PRIMÆVAL WORLD of SWITZERLAND. By Professor OSWALD HEER, of the University of Zurich. Translated by W. S. DALLAS. F.L.S., and edited by JAMES HEYWOOD, M.A., F.R.S. 2 vols. 8vo. with numerous Illustrations. [*In the press.*

The ORIGIN of CIVILISATION and the PRIMITIVE CONDITION of MAN; Mental and Social Condition of Savages. By Sir JOHN LUBBOCK, Bart. M.P. F.R.S. Third Edition, revised, with Woodcuts. [*Nearly ready.*

BIBLE ANIMALS; being a Description of every Living Creature mentioned in the Scriptures, from the Ape to the Coral. By the Rev. J. G. WOOD, M.A. F.L.S. With about 100 Vignettes on Wood. 8vo. 21*s.*

HOMES WITHOUT HANDS; a Description of the Habitations of Animals, classed according to their Principle of Construction. By the Rev. J. G. WOOD, M.A. F.L.S. With about 140 Vignettes on Wood. 8vo. 21*s.*

INSECTS AT HOME; a Popular Account of British Insects, their Structure, Habits, and Transformations. By the Rev. J. G. WOOD, M.A. F.L.S. With upwards of 700 Illustrations. 8vo. price 21*s.*

INSECTS ABROAD; a Popular Account of Foreign Insects, their Structure, Habits, and Transformations. By J. G. WOOD, M.A. F.L.S. Printed and illustrated uniformly with 'Insects at Home.' 8vo. price 21*s.*

STRANGE DWELLINGS; a description of the Habitations of Animals, abridged from 'Homes without Hands.' By the Rev. J. G. WOOD, M.A. F.L.S. With about 60 Woodcut Illustrations. Crown 8vo. price 7*s.* 6*d.*

OUT of DOORS; a Selection of original Articles on Practical Natural History. By the Rev. J. G. WOOD, M.A. F.L.S. With Eleven Illustrations from Original Designs engraved on Wood by G. Pearson. Crown 8vo. price 7*s.* 6*d.*

A FAMILIAR HISTORY of BIRDS. By E. STANLEY, D.D. F.R.S. late Lord Bishop of Norwich. Seventh Edition, with Woodcuts. Fcp. 3*s.* 6*d.*

FROM JANUARY to DECEMBER; a Book for Children. Second Edition. 8vo. 3*s.* 6*d.*

The SEA and its LIVING WONDERS. By Dr. GEORGE HARTWIG. Latest revised Edition. 8vo. with many Illustrations, 10*s.* 6*d.*

The TROPICAL WORLD. By Dr. GEORGE HARTWIG. With above 160 Illustrations. Latest revised Edition. 8vo. price 10*s.* 6*d.*

The SUBTERRANEAN WORLD. By Dr. GEORGE HARTWIG. With 3 Maps and about 80 Woodcuts, including 8 full size of page. 8vo. price 21*s.*

THE AERIAL WORLD. By Dr. GEORGE HARTWIG. With 8 Chromoxylographs and 60 Illustrations engraved on Wood. 8vo. price 21*s.*

The POLAR WORLD, a Popular Description of Man and Nature in the Arctic and Antarctic Regions of the Globe. By Dr. GEORGE HARTWIG. With 8 Chromoxylographs, 3 Maps, and 85 Woodcuts. 8vo. 10*s.* 6*d.*

KIRBY and SPENCE'S INTRODUCTION to ENTOMOLOGY, or Elements of the Natural History of Insects. 7th Edition. Crown 8vo. 5*s.*

MAUNDER'S TREASURY of NATURAL HISTORY, or Popular Dictionary of Birds, Beasts, Fishes, Reptiles, Insects, and Creeping Things. With above 900 Woodcuts. Fcp. 8vo. price 6*s.* cloth, or 10*s.* bound in calf.

MAUNDER'S SCIENTIFIC and LITERARY TREASURY. New Edition, thoroughly revised and in great part rewritten, with above 1,000 new Articles, by J. Y. JOHNSON. Fcp. 8vo. 6*s.* cloth, or 10*s.* calf.

HANDBOOK of HARDY TREES, SHRUBS, and HERBACEOUS PLANTS, containing Descriptions, Native Countries, &c. of a Selection of the Best Species in Cultivation; together with Cultural Details, Comparative Hardiness, Suitability for Particular Positions, &c. By W. B. HEMSLEY. Based on DECAISNE and NAUDIN'S *Manuel de l'Amateur des Jardins*, and including the 264 Original Woodcuts. Medium 8vo. 21*s.*

A GENERAL SYSTEM of BOTANY DESCRIPTIVE and ANALYTICAL. I. Outlines of Organography, Anatomy, and Physiology; II. Descriptions and Illustrations of the Orders. By E. LE MAOUT, and J. DECAISNE, Members of the Institute of France. Translated by Mrs. HOOKER. The Orders arranged after the Method followed in the Universities and Schools of Great Britain, its Colonies, America, and India; with an Appendix on the Natural Method, and other Additions, by J. D. HOOKER, F.R.S. &c. Director of the Royal Botanical Gardens, Kew. With 5,500 Woodcuts. Imperial 8vo. price 52*s.* 6*d.*

The TREASURY of BOTANY, or Popular Dictionary of the Vegetable Kingdom; including a Glossary of Botanical Terms. Edited by J. LINDLEY, F.R.S. and T. MOORE, F.L.S. assisted by eminent Contributors. With 274 Woodcuts and 20 Steel Plates. Two Parts, fcp. 8vo. 12*s.* cloth, or 20*s.* calf.

The ELEMENTS of BOTANY for FAMILIES and SCHOOLS. Tenth Edition, revised by THOMAS MOORE, F.L.S. Fcp. with 154 Woodcuts, 2*s.* 6*d.*

The ROSE AMATEUR'S GUIDE. By THOMAS RIVERS. Fourteenth Edition. Fcp. 8vo. 4*s.*

LOUDON'S ENCYCLOPÆDIA of PLANTS; comprising the Specific Character, Description, Culture, History, &c. of all the Plants found in Great Britain. With upwards of 12,000 Woodcuts. 8vo. 42*s.*

A DICTIONARY of SCIENCE, LITERATURE, and ART. Fourth Edition, re-edited by W. T. BRANDE (the original Author), and GEORGE W. COX, M.A., assisted by contributors of eminent Scientific and Literary Acquirements. 3 vols. medium 8vo. price 63*s.* cloth.

Chemistry and *Physiology.*

A DICTIONARY of CHEMISTRY and the Allied Branches of other Sciences. By HENRY WATTS, F.R.S. assisted by eminent Contributors. 6 vols. medium 8vo. price £8. 14*s.* 6*d.* SECOND SUPPLEMENT *in the Press.*

ELEMENTS of CHEMISTRY, Theoretical and Practical. By W. ALLEN MILLER, M.D. late Prof. of Chemistry, King's Coll. London. New Edition. 3 vols. 8vo. £3. PART I. CHEMICAL PHYSICS, 15*s.* PART II. INORGANIC CHEMISTRY, 21*s.* PART III. ORGANIC CHEMISTRY, 24*s.*

A Course of Practical Chemistry, for the use of Medical Students. By W. ODLING, F.R.S. New Edition, with 70 Woodcuts. Crown 8vo. 7*s.* 6*d.*

A MANUAL of CHEMICAL PHYSIOLOGY, including its Points of Contact with Pathology. By J. L. W. THUDICHUM, M.D. With Woodcuts. 8vo. price 7*s.* 6*d.*

SELECT METHODS in CHEMICAL ANALYSIS, chiefly INORGANIC. By WILLIAM CROOKES, F.R.S. With 22 Woodcuts. Crown 8vo. price 12*s.* 6*d.*

A PRACTICAL HANDBOOK of DYEING and CALICO PRINTING. By WILLIAM CROOKES, F.R.S. With 11 Page Plates, 49 Specimens of Dyed and Printed Fabrics, and 36 Woodcuts. 8vo. 42*s.*

OUTLINES of PHYSIOLOGY, Human and Comparative. By JOHN MARSHALL, F.R.C.S. Surgeon to the University College Hospital. 2 vols. crown 8vo. with 122 Woodcuts, 32*s.*

PHYSIOLOGICAL ANATOMY and PHYSIOLOGY of MAN. By the late R. B. TODD, M.D. F.R.S. and W. BOWMAN, F.R.S. of King's College. With numerous Illustrations. Vol. II. 8vo. 25*s.*

VOL. I. New Edition by Dr. LIONEL S. BEALE, F.R.S. in course of publication, with many Illustrations. PARTS I. and II. price 7*s.* 6*d.* each.

The Fine Arts, and *Illustrated Editions.*

A DICTIONARY of ARTISTS of the ENGLISH SCHOOL: Painters, Sculptors, Architects, Engravers, and Ornamentists; with Notices of their Lives and Works. By S. REDGRAVE. 8vo. 16*s.*

The THREE CATHEDRALS DEDICATED to ST. PAUL, in LONDON; their History from the Foundation of the First Building in the Sixth Century to the Proposals for the Adornment of the Present Cathedral. By WILLIAM LONGMAN, F.A.S. With numerous Illustrations. Square crown 8vo. 21*s.*

IN FAIRYLAND; Pictures from the Elf-World. By RICHARD DOYLE. With a Poem by W. ALLINGHAM. With Sixteen Plates, containing Thirty-six Designs printed in Colours. Second Edition. Folio, price 15*s.*

ALBERT DURER, HIS LIFE and WORKS; including Autobiographical Papers and Complete Catalogues. By WILLIAM B. SCOTT. With Six Etchings by the Author, and other Illustrations. 8vo. 16*s.*

The NEW TESTAMENT, illustrated with Wood Engravings after the Early Masters, chiefly of the Italian School. Crown 4to. 63*s.* cloth, gilt top; or £5 5*s.* elegantly bound in morocco.

LYRA GERMANICA; the Christian Year and the Christian Life. Translated by CATHERINE WINKWORTH. With about 325 Woodcut Illustrations by J. LEIGHTON, F.S.A. and other Artists. 2 vols. 4to. price 42*s.*

The LIFE of MAN SYMBOLISED by the MONTHS of the YEAR. Text selected by R. PIGOT; Illustrations on Wood from Original Designs J. LEIGHTON, F.S.A. 4to. 42*s.*

SACRED and LEGENDARY ART. By MRS. JAMESON.

Legends of the Saints and Martyrs. New Edition, with 19 Etchings and 187 Woodcuts. 2 vols. square crown 8vo. 31*s.* 6*d.*

Legends of the Monastic Orders. New Edition, with 11 Etchings and 88 Woodcuts. 1 vol. square crown 8vo. 21*s.*

Legends of the Madonna. New Edition, with 27 Etchings and 165 Woodcuts. 1 vol. square crown 8vo. 21*s.*

The History of Our Lord, with that of his Types and Precursors. Completed by Lady EASTLAKE. Revised Edition, with 31 Etchings and 281 Woodcuts. 2 vols. square crown 8vo. 42*s.*

DAEDALUS; or, the Causes and Principles of the Excellence of Greek Sculpture. By EDWARD FALKENER, Member of the Academy of Bologna, and of the Archæological Institutes of Rome and Berlin. With Woodcuts, Photographs, and Chromolithographs. Royal 8vo. 42*s.*

FALKENER'S MUSEUM of CLASSICAL ANTIQUITIES; a Series of Essays on Ancient Art. New Edition, complete in One Volume, with many Illustrations. Royal 8vo. price 42*s.*

The Useful Arts, Manufactures, &c.

HISTORY of the GOTHIC REVIVAL; an Attempt to shew how far the taste for Mediæval Architecture was retained in England during the last two centuries, and has been re-developed in the present. By C. L. EASTLAKE, Architect. With 48 Illustrations Imperial 8vo. 31*s.* 6*d.*

GWILT'S ENCYCLOPÆDIA of ARCHITECTURE, with above 1,600 Engravings on Wood. Fifth Edition, revised and enlarged by WYATT PAPWORTH. 8vo. 52*s.* 6*d.*

A MANUAL of ARCHITECTURE: being a Concise History and Explanation of the principal Styles of European Architecture. Ancient, Mediæval, and Renaissance; with a Glossary of Technical Terms. By THOMAS MITCHELL. Crown 8vo. with 150 Woodcuts, 10*s.* 6*d.*

HINTS on HOUSEHOLD TASTE in FURNITURE, UPHOLSTERY, and other Details. By CHARLES L. EASTLAKE, Architect. New Edition, with about 90 Illustrations. Square crown 8vo. 14*s.*

PRINCIPLES of MECHANISM, designed for the Use of Students in the Universities, and for Engineering Students generally. By R. WILLIS, M.A. F.R.S. &c. Jacksonian Professor in the University of Cambridge. Second Edition, enlarged; with 374 Woodcuts. 8vo. 18*s.*

GEOMETRIC TURNING: comprising a Description of Plant's New Geometric Chuck, with directions for its use, and a series of Patterns cut by it, with Explanations. By H. S. SAVORY. With numerous Woodcuts. 8vo. 21*s.*

LATHES and TURNING, Simple, Mechanical, and Ornamental. By W. HENRY NORTHCOTT. With about 240 Illustrations. 8vo. 18*s.*

PERSPECTIVE; or, the Art of Drawing what One Sees. Explained and adapted to the use of those Sketching from Nature. By Lieut. W. H. COLLINS, R.E. F.R.A.S. With 37 Woodcuts. Crown 8vo. price 5*s.*

INDUSTRIAL CHEMISTRY; a Manual for Manufacturers and for use in Colleges or Technical Schools. Being a Translation of Professors Stohmann and Engler's German Edition of PAYEN'S *Précis de Chimie Industrielle*, by Dr. J. D. BARRY. Edited and supplemented by B. H. PAUL, Ph.D. 8vo. with Plates and Woodcuts. [*In the press.*

URE'S DICTIONARY of ARTS, MANUFACTURES, and MINES. Sixth Edition, rewritten and enlarged by ROBERT HUNT, F.R.S. assisted by numerous Contributors eminent in Science and the Arts, and familiar with Manufactures. With above 2,000 Woodcuts. 3 vols. medium 8vo. £4 14*s.* 6*d.*

HANDBOOK of PRACTICAL TELEGRAPHY. By R. S. CULLEY Memb. Inst. C.E. Engineer-in-Chief of Telegraphs to the Post Office. Sixth Edition, with 144 Woodcuts and 5 Plates. 8vo. price 16*s.*

The ENGINEER'S HANDBOOK; explaining the Principles which should guide the Young Engineer in the Construction of Machinery, with the necessary Rules, Proportions, and Tables. By C. S. LOWNDES. Post 8vo. 5*s.*

ENCYCLOPÆDIA of CIVIL ENGINEERING, Historical, Theoretical, and Practical. By E. CRESY, C.E. With above 3,000 Woodcuts. 8vo. 42*s.*

The STRAINS IN TRUSSES computed by means of Diagrams; with 20 Examples drawn to Scale. By F. A. RANKEN, M.A. C.E. With 35 Diagrams. Square crown 8vo. 6*s.* 6*d.*

TREATISE on MILLS and MILLWORK. By Sir W. FAIRBAIRN, Bart. F.R.S. New Edition, with 18 Plates and 322 Woodcuts, 2 vols. 8vo. 32*s.*

USEFUL INFORMATION for ENGINEERS. By Sir W. FAIRBAIRN, Bart. F.R.S. Revised Edition, with Illustrations. 3 vols. crown 8vo. price 31*s.* 6*d.*

The APPLICATION of CAST and WROUGHT IRON to Building Purposes. By Sir W. FAIRBAIRN, Bart. F.R.S. Fourth Edition, enlarged; with 6 Plates and 118 Woodcuts. 8vo. price 16*s.*

GUNS and STEEL; Miscellaneous Papers on Mechanical Subjects. By Sir JOSEPH WHITWORTH, Bart. C.E. Royal 8vo. with Illustrations, 7*s.* 6*d.*

A TREATISE on the STEAM ENGINE, in its various Applications to Mines, Mills, Steam Navigation, Railways, and Agriculture. By J. BOURNE, C.E. Eighth Edition; with Portrait, 37 Plates, and 546 Woodcuts. 4to. 42*s.*

CATECHISM of the STEAM ENGINE, in its various Applications to Mines, Mills, Steam Navigation, Railways, and Agriculture. By the same Author. With 89 Woodcuts. Fcp. 8vo. 6*s.*

HANDBOOK of the STEAM ENGINE. By the same Author, forming a KEY to the Catechism of the Steam Engine, with 67 Woodcuts. Fcp. 9*s.*

BOURNE'S RECENT IMPROVEMENTS in the STEAM ENGINE in its various applications to Mines, Mills, Steam Navigation, Railways, and Agriculture. By JOHN BOURNE, C.E. New Edition, with 124 Woodcuts. Fcp. 8vo. 6*s.*

HANDBOOK to the MINERALOGY of CORNWALL and DEVON; with Instructions for their Discrimination, and copious Tablets of Localities. By J. H. COLLINS, F.G.S. With 10 Plates. 8vo. 6*s.*

PRACTICAL TREATISE on METALLURGY, adapted from the last German Edition of Professor KERL'S *Metallurgy* by W. CROOKES, F.R.S. &c. and E. RÖHRIG, Ph.D. M.E. With 625 Woodcuts. 3 vols. 8vo. prices £4 19*s.*

MITCHELL'S MANUAL of PRACTICAL ASSAYING. Fourth Edition, for the most part rewritten, with all the recent Discoveries incorporated, by W. CROOKES, F.R.S. With 199 Woodcuts. 8vo. 31*s.* 6*d.*

LOUDON'S ENCYCLOPÆDIA of AGRICULTURE: comprising the Laying-out, Improvement, and Management of Landed Property, and the Cultivation and Economy of Agricultural Produce. With 1,100 Woodcuts. 8vo. 21*s.*

Loudon's Encyclopædia of Gardening: comprising the Theory and Practice of Horticulture, Floriculture, Arboriculture, and Landscape Gardening. With 1,000 Woodcuts. 8vo. 21*s.*

Religious and *Moral Works.*

SERMONS; Including Two Sermons on the Interpretation of Prophecy, and an Essay on the Right Interpretation and Understanding of the Scriptures. By the late Rev. THOMAS ARNOLD, D.D. 3 vols. 8vo. price 24*s.*

CHRISTIAN LIFE, its COURSE, its HINDRANCES, and its HELPS; Sermons preached mostly in the Chapel of Rugby School. By the late Rev. THOMAS ARNOLD, D.D. 8vo. 7*s.* 6*d.*

CHRISTIAN LIFE, its HOPES, its FEARS, and its CLOSE; Sermons preached mostly in the Chapel of Rugby School. By the late Rev. THOMAS ARNOLD, D.D. 8vo. 7*s.* 6*d.*

SERMONS chiefly on the INTERPRETATION of SCRIPTURE. By the late Rev. THOMAS ARNOLD, D.D. 8vo. price 7*s.* 6*d.*

SERMONS preached in the Chapel of Rugby School; with an Address before Confirmation. By the late Rev. THOMAS ARNOLD, D.D. Fcp. 8vo. price 3*s.* 6*d.*

THREE ESSAYS on RELIGION: Nature; the Utility of Religion; Theism. By JOHN STUART MILL. 8vo. price 10*s.* 6*d.*

INTRODUCTION to the SCIENCE of RELIGION. Four Lectures delivered at the Royal Institution; with Two Essays on False Analogies and the Philosophy of Mythology. By F. MAX MÜLLER, M.A. Crown 8vo. 10*s.* 6*d.*

SUPERNATURAL RELIGION; an Inquiry into the Reality of Divine Revelation. Third Edition, revised. 2 vols. 8vo. 24*s.*

ESSAYS on the HISTORY of the CHRISTIAN RELIGION. By JOHN Earl RUSSELL. Cabinet Edition, revised. Fcp. 8vo. price 3*s.* 6*d.*

The NEW BIBLE COMMENTARY, by Bishops and other Clergy of the Anglican Church, critically examined by the Right Rev. J. W. COLENSO, D.D. Bishop of Natal. 8vo. price 25*s.*

REASONS of FAITH; or, the ORDER of the Christian Argument Developed and Explained. By the Rev. G. S. DREW, M.A. Second Edition, revised and enlarged. Fcp. 8vo. price 6*s.*

SYNONYMS of the OLD TESTAMENT, their BEARING on CHRISTIAN FAITH and PRACTICE. By the Rev. R. B. GIRDLESTONE, M.A. 8vo. 15*s.*

An INTRODUCTION to the THEOLOGY of the CHURCH of ENGLAND, in an Exposition of the Thirty-nine Articles. By the Rev. T. P. BOULTBEE, LL.D. New Edition, Fcp. 8vo. price 6*s.*

SERMONS for the TIMES preached in St. Paul's Cathedral and elsewhere. By the Rev. THOMAS GRIFFITH, M.A. Crown 8vo. 6*s.*

An EXPOSITION of the 39 ARTICLES, Historical and Doctrinal. By E. HAROLD BROWNE, D.D. Lord Bishop of Winchester. New Edit. 8vo. 16*s.*

The LIFE and EPISTLES of ST. PAUL. By the Rev. W. J. CONYBEARE, M.A., and the Very Rev. J. S. HOWSON, D.D. Dean of Chester:—

LIBRARY EDITION, with all the Original Illustrations, Maps, Landscapes on Steel, Woodcuts, &c. 2 vols. 4to. 48*s.*

INTERMEDIATE EDITION, with a Selection of Maps, Plates, and Woodcuts. 2 vols. square crown 8vo. 21*s.*

STUDENT'S EDITION, revised and condensed, with 46 Illustrations and Maps. 1 vol. crown 8vo. price 9*s.*

The VOYAGE and SHIPWRECK of ST. PAUL; with Dissertations on the Life and Writings of St. Luke and the Ships and Navigation of the Ancients. By JAMES SMITH, F.R.S. Third Edition. Crown 8vo. 10*s.* 6*d.*

COMMENTARY on the EPISTLE to the ROMANS. By the Rev. W. A. O'CONOR, B.A. Crown 8vo. price 8*s.* 6*d.*

The EPISTLE to the HEBREWS; with Analytical Introduction and Notes. By the Rev. W. A. O'CONOR, B.A. Crown 8vo. price 4*s.* 6*d.*

A CRITICAL and GRAMMATICAL COMMENTARY on ST. PAUL'S Epistles. By C. J. ELLICOTT, D.D. Lord Bishop of Gloucester and Bristol. 8vo.

Galatians, Fourth Edition, 8*s.* 6*d.*

Ephesians, Fourth Edition, 8*s.* 6*d.*

Pastoral Epistles, Fourth Edition, 10*s.* 6*d.*

Philippians, Colossians, and Philemon, Third Edition, 10*s.* 6*d.*

Thessalonians, Third Edition, 7*s.* 6*d.*

HISTORICAL LECTURES on the LIFE of OUR LORD. By C. J. ELLICOTT, D.D. Bishop of Gloucester and Bristol. Fifth Edition. 8vo. 12*s.*

EVIDENCE of the TRUTH of the CHRISTIAN RELIGION derived from the Literal Fulfilment of Prophecy. By ALEXANDER KEITH, D.D. 37th Edition, with Plates, in square 8vo. 12*s.* 6*d.*; 39th Edition, in post 8vo. 6*s.*

The HISTORY and LITERATURE of the ISRAELITES, according to the Old Testament and the Apocrypha. By C. DE ROTHSCHILD and A. DE ROTHSCHILD. Second Edition, revised. 2 vols. post 8vo. with Two Maps, price 12*s.* 6*d.* Abridged Edition, in 1 vol. fcp. 8vo. price 3*s.* 6*d.*

An INTRODUCTION to the STUDY of the NEW TESTAMENT, Critical, Exegetical, and Theological. By the Rev. S. DAVIDSON, D.D. LL.D. 2 vols. 8vo. 30*s.*

HISTORY of ISRAEL. By H. EWALD, Prof. of the Univ. of Göttingen. Translated by J. E. CARPENTER, M.A., with a Preface by RUSSELL MARTINEAU, M.A. 5 vols. 8vo. 63s.

The TREASURY of BIBLE KNOWLEDGE; being a Dictionary of the Books, Persons, Places, Events, and other matters of which mention is made in Holy Scripture. By Rev. J. AYRE, M.A. With Maps, 16 Plates, and numerous Woodcuts. Fcp. 8vo. price 6*s.* cloth, or 10*s.* neatly bound in calf.

LECTURES on the PENTATEUCH and the MOABITE STONE. By the Right Rev. J. W. COLENSO, D.D. Bishop of Natal. 8vo. 12*s.*

The PENTATEUCH and BOOK of JOSHUA CRITICALLY EXAMINED. By the Right Rev. J. W. COLENSO, D.D. Bishop of Natal. Crown 8vo. 6*s.*

THOUGHTS for the AGE. By ELIZABETH M. SEWELL, Author of 'Amy Herbert,' &c. New Edition, revised. Fcp. 8vo. price 3*s.* 6*d.*

PASSING THOUGHTS on RELIGION. By Miss SEWELL. Fcp. 8vo. 3*s.* 6*d.*

SELF-EXAMINATION before CONFIRMATION. By Miss SEWELL. 32mo. price 1*s.* 6*d.*

READINGS for a MONTH preparatory to CONFIRMATION, from Writers of the Early and English Church. By Miss SEWELL. Fcp. 4*s.*

READINGS for EVERY DAY in LENT, compiled from the Writings of Bishop JEREMY TAYLOR. By Miss SEWELL. Fcp. 5*s.*

PREPARATION for the HOLY COMMUNION; the Devotions chiefly from the Works of JEREMY TAYLOR. By Miss SEWELL. 32mo. 3*s.*

THOUGHTS for the HOLY WEEK for Young Persons. By Miss SEWELL. New Edition. Fcp. 8vo. 2*s.*

PRINCIPLES of EDUCATION Drawn from Nature and Revelation, and applied to Female Education in the Upper Classes. By Miss SEWELL. 2 vols. fcp. 8vo. 12*s.* 6*d.*

LYRA GERMANICA, Hymns translated from the German by Miss C. WINKWORTH. FIRST and SECOND SERIES, price 3*s.* 6*d.* each.

SPIRITUAL SONGS for the SUNDAYS and HOLIDAYS throughout the Year. By J. S. B. MONSELL, LL.D. Fcp. 8vo. 4*s.* 6*d.*

ENDEAVOURS after the CHRISTIAN LIFE: Discourses. By the Rev. J. MARTINEAU, LL.D. Fifth Edition, carefully revised. Crown 8vo. 7*s.* 6*d.*

HYMNS of PRAISE and PRAYER, collected and edited by the Rev. J. MARTINEAU, LL.D. Crown 8vo. 4*s.* 6*d.*

WHATELY'S INTRODUCTORY LESSONS on the CHRISTIAN Evidences. 18mo. 6*d.*

BISHOP JEREMY TAYLOR'S ENTIRE WORKS. With Life by BISHOP HEBER. Revised and corrected by the Rev. C. P. EDEN. Complete in Ten Volumes, 8vo. cloth, price £5. 5*s.*

Travels, Voyages, &c.

EIGHT YEARS in CEYLON. By Sir SAMUEL W. BAKER, M.A. F.R.G.S. New Edition, with Illustrations engraved on Wood, by G. Pearson. Crown 8vo. 7*s.* 6*d.*

The RIFLE and the HOUND in CEYLON. By Sir SAMUEL W. BAKER, M.A. F.R.G.S. New Edition, with Illustrations engraved on Wood by G. Pearson. Crown 8vo. 7*s.* 6*d.*

MEETING the SUN; a Journey all round the World through Egypt, China, Japan, and California. By WILLIAM SIMPSON, F.R.G.S. With 48 Hellotypes and Wood Engravings from Drawings by the Author. Medium 8vo. 24*s.*

UNTRODDEN PEAKS and UNFREQUENTED VALLEYS; a Midsummer Ramble among the Dolomites. By AMELIA B. EDWARDS. With a Map and 27 Wood Engravings. Medium 8vo. 21*s.*

The DOLOMITE MOUNTAINS; Excursions through Tyrol, Carinthia, Carniola, and Friuli, 1861-1863. By J. GILBERT and G. C. CHURCHILL, F.R.G.S. With numerous Illustrations. Square crown 8vo. 21*s.*

The VALLEYS of TIROL; their Traditions and Customs, and how to Visit them. By Miss R. H. BUSK, Author of 'The Folk-Lore of Rome,' &c. With Maps and Frontispiece. Crown 8vo. 12*s.* 6*d.*

HOURS of EXERCISE in the ALPS. By JOHN TYNDALL, LL.D. D.C.L. F.R.S. Third Edition, with 7 Woodcuts by E. Whymper. Crown 8vo. price 12*s.* 6*d.*

The ALPINE CLUB MAP of SWITZERLAND, with parts of the Neighbouring Countries, on the Scale of Four Miles to an Inch. Edited by R. C. NICHOLS, F.S.A. F.R.G.S. In Four Sheets, price 42*s.* or mounted in a case, 52*s.* 6*d.* Each Sheet may be had separately, price 12*s.* or mounted in a case, 15*s.*

MAP of the CHAIN of MONT BLANC, from an Actual Survey in 1863–1864. By ADAMS-REILLY, F.R.G.S. M.A.C. Published under the Authority of the Alpine Club. In Chromolithography on extra stout drawing-paper 28in. × 17in. price 10*s.* or mounted on canvas in a folding case, 12*s.* 6*d.*

TRAVELS in the CENTRAL CAUCASUS and BASHAN. Including Visits to Ararat and Tabreez and Ascents of Kazbek and Elbruz. By D. W. FRESHFIELD. Square crown 8vo. with Maps, &c. 18*s.*

PAU and the PYRENEES. By Count HENRY RUSSELL, Member of the Alpine Club, &c. With 2 Maps. Fcp. 8vo. price 5*s.*

HOW to SEE NORWAY. By Captain J. R. CAMPBELL. With Map and 5 Woodcuts. Fcp. 8vo. price 5*s.*

GUIDE to the PYRENEES, for the use of Mountaineers. By CHARLES PACKE. With Map and Illustrations. Crown 8vo. 7*s.* 6*d.*

The ALPINE GUIDE. By JOHN BALL, M.R.I.A. late President of the Alpine Club. 3 vols. post 8vo. Thoroughly Revised Editions, with Maps and Illustrations:—I. *Western Alps*, 6*s.* 6*d.* II. *Central Alps*, 7*s.* 6*d.* III. *Eastern Alps*, 10*s.* 6*d.*

Introduction on Alpine Travelling in General, and on the Geology of the Alps, price 1*s.* Each of the Three Volumes or Parts of the *Alpine Guide* may be had with this INTRODUCTION prefixed, price 1*s.* extra.

VISITS to REMARKABLE PLACES: Old Halls, Battle-Fields, and Stones Illustrative of Striking Passages in English History and Poetry. By WILLIAM HOWITT. 2 vols. square crown 8vo. with Woodcuts, 25*s.*

The RURAL LIFE of ENGLAND. By the same Author. With Woodcuts by Bewick and Williams. Medium 8vo. 12*s.* 6*d.*

Works of *Fiction.*

WHISPERS from FAIRYLAND. By the Rt. Hon. E. H. KNATCHBULL-HUGESSEN, M.P. Author of 'Stories for my Children,' 'Moonshine,' 'Queer Folk,' &c. With Nine Illustrations from Original Designs engraved on Wood by G. Pearson. Crown 8vo. price 6*s.*

ELENA, an Italian Tale. By L. N. COMYN, Author of 'Atherstone Priory.' 2 vols. post 8vo. 14*s.*

CENTULLE, a Tale of Pau. By DENYS SHYNE LAWLOR, Author of 'Pilgrimages in the Pyrenees and Landes. Post 8vo. 10*s.* 6*d.*

LADY WILLOUGHBY'S DIARY, 1635—1663; Charles the First, the Protectorate, and the Restoration. Reproduced in the Style of the Period to which the Diary relates. Crown 8vo. price 7*s.* 6*d.*

TALES of the TEUTONIC LANDS. By the Rev. G. W. Cox, M.A. and E. H. Jones. Crown 8vo. 10*s.* 6*d.*

The FOLK-LORE of ROME, collected by Word of Mouth from the People. By Miss R. H. Busk, Author of 'Patrañas,' &c. Crown 8vo. 12*s.* 6*d.*

NOVELS and TALES. By the Right Hon. B. Disraeli, M.P. Cabinet Edition, complete in Ten Volumes, crown 8vo. price £3.

Lothair, 6*s.*	Henrietta Temple, 6*s.*
Coningsby, 6*s.*	Contarini Fleming, &c. 6*s.*
Sybil, 6*s.*	Alroy, Ixion, &c. 6*s.*
Tancred, 6*s.*	The Young Duke, &c. 6*s.*
Venetia, 6*s.*	Vivian Grey, 6*s.*

The MODERN NOVELIST'S LIBRARY. Each Work, in crown 8vo. complete in a Single Volume:—

Atherstone Priory, 2*s.* boards; 2*s.* 6*d.* cloth.
Melville's Gladiators, 2*s* boards; 2*s.* 6*d.* cloth.
——— Good for Nothing, 2*s.* boards; 2*s.* 6*d.* cloth.
——— Holmby House, 2*s.* boards; 2*s.* 6*d.* cloth.
——— Interpreter, 2*s.* boards; 2*s.* 6*d.* cloth.
——— Kate Coventry, 2*s.* boards; 2*s.* 6*d.* cloth.
——— Queen's Maries, 2*s.* boards; 2*s.* 6*d.* cloth.
——— Digby Grand, 2*s.* boards; 2*s.* 6*d.* cloth.
——— General Bounce, 2*s.* boards; 2*s.* 6*d.* cloth.
Trollope's Warden, 1*s.* 6*d.* boards; 2*s.* cloth.
——— Barchester Towers, 2*s.* boards; 2*s.* 6*d.* cloth.
Bramley-Moore's Six Sisters *of the* Valleys, 2*s.* boards; 2*s.* 6*d.* cloth.
The Burgomaster's Family, 2*s.* boards; 2*s.* 6*d.* cloth.

CABINET EDITION of STORIES and TALES by Miss Sewell:—

Amy Herbert, 2*s.* 6*d.*	Ivors, 2*s.* 6*d.*
Gertrude, 2*s.* 6*d.*	Katharine Ashton, 2*s.* 6*d.*
The Earl's Daughter, 2*s.* 6*d.*	Margaret Percival, 3*s.* 6*d.*
Experience *of* Life, 2*s.* 6*d.*	Laneton Parsonage, 3*s.* 6*d.*
Cleve Hall, 2*s.* 6*d.*	Ursula, 3*s.* 6*d.*

CYLLENE; or, the Fall of Paganism. By Henry Sneyd, M.A. University College, Oxford. 2 vols. post 8vo. price 14*s.*

BECKER'S GALLUS; or, Roman Scenes of the Time of Augustus: with Notes and Excursuses. New Edition. Post 8vo. 7*s.* 6*d.*

BECKER'S CHARICLES; a Tale illustrative of Private Life among the Ancient Greeks: with Notes and Excursuses. New Edition. Post 8vo. 7*s.* 6*d.*

TALES of ANCIENT GREECE. By George W. Cox, M.A. late Scholar of Trin. Coll. Oxon. Crown 8vo. price 6*s.* 6*d.*

Poetry and *The Drama.*

FAUST: a Dramatic Poem. By Goethe. Translated into English Prose, with Notes, by A. Hayward. Ninth Edition. Fcp. 8vo. price 3*s.*

MOORE'S IRISH MELODIES, Maclise's Edition, with 161 Steel Plates from Original Drawings. Super-royal 8vo. 31*s.* 6*d.*

Miniature Edition of Moore's Irish Melodies, with Maclise's Designs (as above) reduced in Lithography. Imp. 16mo. 10*s.* 6*d.*

BALLADS and LYRICS of OLD FRANCE; with other Poems. By A. LANG, Fellow of Merton College, Oxford. Square fcp. 8vo. price 5*s*.

MOORE'S LALLA ROOKH. Tenniel's Edition, with 68 Wood Engravings from Original Drawings and other Illustrations. Fcp. 4to. 21*s*.

SOUTHEY'S POETICAL WORKS, with the Author's last Corrections and copyright Additions. Medium 8vo. with Portrait and Vignette, 14*s*.

LAYS of ANCIENT ROME; with IVRY and the ARMADA. By the Right Hon. Lord MACAULAY. 16mo. 3*s*. 6*d*.

LORD MACAULAY'S LAYS of ANCIENT ROME. With 90 Illustrations on Wood, from the Antique, from Drawings by G. SCHARF. Fcp. 4to. 21*s*.

Miniature Edition of Lord Macaulay's Lays of Ancient Rome, with the Illustrations (as above) reduced in Lithography. Imp. 16mo. 10*s*. 6*d*.

The ÆNEID of VIRGIL Translated into English Verse. By JOHN CONINGTON, M.A. New Edition. Crown 8vo. 9*s*.

HORATII OPERA. Library Edition, with Marginal References and English Notes. Edited by the Rev. J. E. YONGE. 8vo. 21*s*.

The LYCIDAS and EPITAPHIUM DAMONIS of MILTON. Edited, with Notes and Introduction (including a Reprint of the rare Latin Version of the Lycidas, by W. Hogg, 1694), by C. S. JERRAM, M.A. Crown 8vo. 3*s*. 6*d*.

BOWDLER'S FAMILY SHAKSPEARE, cheaper Genuine Editions. Medium 8vo. large type, with 36 WOODCUTS, price 14*s*. Cabinet Edition, with the same ILLUSTRATIONS, 6 vols. fcp. 8vo. price 21*s*.

POEMS. By JEAN INGELOW. 2 vols. fcp. 8vo. price 10*s*.
FIRST SERIES, containing 'DIVIDED,' 'The STAR'S MONUMENT,' &c. Sixteenth Thousand. Fcp. 8vo. price 5*s*.
SECOND SERIES, 'A STORY of DOOM,' 'GLADYS and her ISLAND,' &c. Fifth Thousand. Fcp. 8vo. price 5*s*.

POEMS by **Jean Ingelow.** FIRST SERIES, with nearly 100 Illustrations, engraved on Wood by Dalziel Brothers. Fcp. 4to. 21*s*.

Rural Sports, &c.

DOWN the ROAD; Or, Reminiscences of a Gentleman Coachman. By C. T. S. BIRCH REYNARDSON. With Twelve Chromolithographic Illustrations from Original Paintings by H. Alken. Medium 8vo. [*Nearly ready.*

The DEAD SHOT; or, Sportsman's Complete Guide: a Treatise on the Use of the Gun, Dog-breaking, Pigeon-shooting, &c. By MARKSMAN. Revised Edition. Fcp. 8vo. with Plates, 5*s*.

ENCYCLOPÆDIA of RURAL SPORTS; a complete Account, Historical, Practical, and Descriptive, of Hunting, Shooting, Fishing, Racing, and all other Rural and Athletic Sports and Pastimes. By D. P. BLAINE. With above 600 Woodcuts (20 from Designs by JOHN LEECH). 8vo. 21*s*.

The FLY-FISHER'S ENTOMOLOGY. By ALFRED RONALDS. With coloured Representations of the Natural and Artificial Insect. Sixth Edition, with 20 coloured Plates. 8vo. 14*s.*

A BOOK on ANGLING; a complete Treatise on the Art of Angling in every branch. By FRANCIS FRANCIS. New Edition, with Portrait and 15 other Plates, plain and coloured. Post 8vo. 15*s.*

WILCOCKS'S SEA-FISHERMAN; comprising the Chief Methods of Hook and Line Fishing, a Glance at Nets, and Remarks on Boats and Boating. New Edition, with 80 Woodcuts. Post 8vo. 12*s.* 6*d.*

HORSES and STABLES. By Colonel F. FITZWYGRAM, XV. the King's Hussars. With Twenty-four Plates of Illustrations, containing very numerous Figures engraved on Wood. 8vo. 10*s.* 6*d.*

The HORSE'S FOOT, and HOW to KEEP it SOUND. By W. MILES, Esq. Ninth Edition, with Illustrations. Imperial 8vo. 12*s.* 6*d.*

A PLAIN TREATISE on HORSE-SHOEING. By W. MILES, Esq. Sixth Edition. Post 8vo. with Illustrations, 2*s.* 6*d.*

STABLES and STABLE-FITTINGS. By W. MILES, ESQ. Imp. 8vo. with 13 Plates, 15*s.*

REMARKS on HORSES' TEETH, addressed to Purchasers. By W. MILES, Esq. Post 8vo. 1*s.* 6*d.*

A TREATISE on HORSE-SHOEING and LAMENESS. By JOSEPH GAMGEE, Veterinary Surgeon. 8vo. with 55 Woodcuts, price 10*s.* 6*d.*

The HORSE: with a Treatise on Draught. By WILLIAM YOUATT. New Edition, revised and enlarged. 8vo. with numerous Woodcuts, 12*s.* 6*d.*

The DOG. By WILLIAM YOUATT. 8vo. with numerous Woodcuts, 6*s.*

The DOG in HEALTH and DISEASE. By STONEHENGE. With 70 Wood Engravings. Square crown 8vo. 7*s.* 6*d.*

The GREYHOUND. By STONEHENGE. Revised Edition, with 24 Portraits of Greyhounds. Square crown 8vo. 10*s.* 6*d.*

The OX; his Diseases and their Treatment: with an Essay on Parturition in the Cow. By J. R. DOBSON. Crown 8vo. with Illustrations, 7*s.* 6*d.*

Works of *Utility* and *General Information.*

The THEORY and PRACTICE of BANKING. By H. D. MACLEOD, M.A. Barrister-at-Law. Second Edition, entirely remodelled. 2 vols. 8vo. 30*s.*

M'CULLOCH'S DICTIONARY, Practical, Theoretical, and Historical, of Commerce and Commercial Navigation. New and revised Edition. 8vo. 63*s.*

The CABINET LAWYER; a Popular Digest of the Laws of England, Civil, Criminal, and Constitutional: intended for Practical Use and General Information. Twenty-fourth Edition. Fcp. 8vo. price 9*s.*

BLACKSTONE ECONOMISED, a Compendium of the Laws of England to the Present time, in Four Books, each embracing the Legal Principles and Practical Information contained in their respective volumes of Blackstone, supplemented by Subsequent Statutory Enactments, Important Legal Decisions, &c. By D. M. AIRD, Barrister-at-Law. Revised Edition. Post 8vo. 7*s.* 6*d.*

PEWTNER'S COMPREHENSIVE SPECIFIER; a Guide to the Practical Specification of every kind of Building-Artificers' Work, with Forms of Conditions and Agreements. Edited by W. YOUNG. Crown 8vo. 6*s.*

COLLIERIES and COLLIERS; a Handbook of the Law and Leading Cases relating thereto. By J. C. FOWLER. Third Edition. Fcp. 8vo. 7*s.* 6*d.*

HINTS to MOTHERS on the MANAGEMENT of their HEALTH during the Period of Pregnancy and in the Lying-in Room. By the late THOMAS BULL, M.D. Fcp. 8vo. 5*s.*

The MATERNAL MANAGEMENT of CHILDREN in HEALTH and Disease. By the late THOMAS BULL, M.D. Fcp. 8vo. 5*s.*

The THEORY of the MODERN SCIENTIFIC GAME of WHIST. By WILLIAM POLE, F.R.S. Fifth Edition, enlarged. Fcp. 8vo. 2*s.* 6*d.*

CHESS OPENINGS. By F. W. LONGMAN, Balliol College, Oxford. Second Edition revised. Fcp. 8vo. 2*s.* 6*d.*

THREE HUNDRED ORIGINAL CHESS PROBLEMS and STUDIES. By JAMES PIERCE, M.A. and W. T. PIERCE. With numerous Diagrams. Square fcp. 8vo. 7*s.* 6*d.* SUPPLEMENT, price 2*s.* 6*d.*

A PRACTICAL TREATISE on BREWING; with Formulæ for Public Brewers, and Instructions for Private Families. By W. BLACK. 8vo. 10*s.* 6*d.*

MODERN COOKERY for PRIVATE FAMILIES, reduced to a System of Easy Practice in a Series of carefully-tested Receipts. By ELIZA ACTON. Newly revised and enlarged; with 8 Plates and 150 Woodcuts. Fcp. 8vo. 6*s.*

MAUNDER'S TREASURY of KNOWLEDGE and LIBRARY of Reference; comprising an English Dictionary and Grammar, Universal Gazetteer, Classical Dictionary, Chronology, Law Dictionary, a synopsis of the Peerage useful Tables, &c. Revised Edition. Fcp. 8vo. 6*s.* cloth, or 10*s.* calf.

Knowledge for the *Young.*

The STEPPING-STONE to KNOWLEDGE; or upwards of 700 Questions and Answers on Miscellaneous Subjects, adapted to the capacity of Infant minds. 18mo. 1*s.*

SECOND SERIES of the STEPPING-STONE to KNOWLEDGE: Containing upwards of 800 Questions and Answers on Miscellaneous Subjects not contained in the FIRST SERIES. 18mo. 1*s.*

The STEPPING-STONE to GEOGRAPHY: Containing several Hundred Questions and Answers on Geographical Subjects. 18mo. 1*s*

The STEPPING-STONE to ENGLISH HISTORY; Questions and Answers on the History of England. 18mo. 1*s.*

The STEPPING-STONE to BIBLE KNOWLEDGE; Questions and Answers on the Old and New Testaments. 18mo. 1*s.*

The STEPPING-STONE to BIOGRAPHY; Questions and Answers on the Lives of Eminent Men and Women. 18mo. 1*s.*

The STEPPING-STONE to IRISH HISTORY: Containing several Hundred Questions and Answers on the History of Ireland. 18mo. 1*s.*

The STEPPING-STONE to FRENCH HISTORY: Containing several Hundred Questions and Answers on the History of France. 18mo. 1*s.*

The STEPPING-STONE to ROMAN HISTORY: Containing several Hundred Questions and Answers on the History of Rome. 18mo. 1*s.*

The STEPPING-STONE to GRECIAN HISTORY: Containing several Hundred Questions and Answers on the History of Greece. 18mo. 1*s.*

The STEPPING-STONE to ENGLISH GRAMMAR: Containing several Hundred Questions and Answers on English Grammar. 18mo. 1*s.*

The STEPPING-STONE to FRENCH PRONUNCIATION and CONVERSATION: Containing several Hundred Questions and Answers. 18mo. 1*s.*

The STEPPING-STONE to ASTRONOMY: Containing several Hundred familiar Questions and Answers on the Earth and the Solar and Stellar Systems. 18mo. 1*s.*

The STEPPING-STONE to MUSIC: Containing several Hundred Questions on the Science; also a short History of Music. 18mo. 1*s.*

The STEPPING-STONE to NATURAL HISTORY: VERTEBRATE OR BACK-BONED ANIMALS. PART I. *Mammalia*; PART II. *Birds, Reptiles, Fishes.* 18mo. 1*s.* each Part.

THE STEPPING-STONE to ARCHITECTURE; Questions and Answers explaining the Principles and Progress of Architecture from the Earliest Times. With 100 Woodcuts. 18mo. 1*s.*

INDEX.

ACTON'S Modern Cookery 27
AIRD'S Blackstone Economised 27
Alpine Club Map of Switzerland 23
Alpine Guide (The) 23
AMOS'S Jurisprudence 5
——— Primer of the Constitution 5
ANDERSON'S Strength of Materials..... 13
ARMSTRONG'S Organic Chemistry..... 13
ARNOLD'S (Dr.) Christian Life 20
——— Lectures on Modern History 2
——— Miscellaneous Works 9
——— School Sermons 20
——— Sermons 20
——— (T.) Manual of English Literature 8
ARNOULD'S Life of Denman 4
Atherstone Priory 24
Autumn Holidays of a Country Parson 9
AYRE'S Treasury of Bible Knowledge 21

BACON'S Essays, by WHATELY 6
——— Life and Letters, by SPEDDING 5
——— Works, edited by SPEDDING 6
BAIN'S Logic, Deductive and Inductive..... 10
——— Mental and Moral Science 10
——— on the Senses and Intellect 10
BAKER'S 2 works on Ceylon..... 23
BALL'S Alpine Guide 24
BECKER'S Charicles *and* Gallus 24
BENFEY'S Sanskrit Dictionary 8
BLACK'S Treatise on Brewing 27
BLACKLEY'S German-English Dictionary... 8
BLAINE'S Rural Sports..... 25
BLOXAM'S Metals 13
BOULTBEE on 39 Articles 20
BOURNE'S Catechism of the Steam Engine. 19
——— Handbook of Steam Engine 19
——— Improvements in the Steam Engine..... 19
——— Treatise on the Steam Engine ... 19
BOWDLER'S Family SHAKSPEARE 25
BRAMLEY-MOORE'S Six Sisters of the Valleys..... 25
BRANDE'S Dictionary of Science, Literature, and Art 16
BRAY'S Manual of Anthropology 11
——— Philosophy of Necessity 11
——— on Force 11
BRINKLEY'S ASTRONOMY 11
BROWNE'S Exposition of the 39 Articles..... 20
BRUNEL'S Life of BRUNEL 5
BUCKLE'S History of Civilization 3
——— Miscellaneous Writings..... 9
BULL'S Hints to Mothers 27
——— Maternal Management of Children 27
Burgomaster's Family (The) 25
BURKE'S Rise of Great Families..... 5
——— Vicissitudes of Families..... 5
BURN'S Folk-Lore of Rome 24
——— Valleys of Tirol 23

Cabinet Lawyer 16
CAMPBELL'S Norway 23
CATES'S Biographical Dictionary 5
——— and WOODWARD'S Encyclopædia 3
Changed Aspects of Unchanged Truths..... 10
CHENNEY'S Indian Polity 3
——— Modern Military Biography ... 4
——— Waterloo Campaign..... 2
CLOUGH'S Lives from Plutarch 2
COLENSO (Bishop) on Pentateuch 21
——— on Moabite Stone, &c. 21
——— on Speaker's Bible Commentary 20
COLLINS'S Mineralogy of Cornwall 19
——— Perspective..... 8
Commonplace Philosopher, by A.K.H.B. ... 9
COMTE'S Positive Philosophy 6
COMYN'S Elena 23
CONGREVE'S Politics of Aristotle 6
CONINGTON'S Translation of the *Æneid* ... 25
——— Miscellaneous Writings..... 9
CONTANSEAU'S French-English Dictionaries 8
CONYBEARE and HOWSON'S St. Paul 20
COTTON'S (Bishop) Memoir 4
Counsel and Comfort from a City Pulpit..... 9
COX'S Aryan Mythology..... 3
——— Crusades..... 4
——— History of Greece 2
——— Tale of the Great Persian War 3
——— Tales of Ancient Greece..... 24
COX and JONES'S Tales of Teutonic Lands 24
CRAWLEY'S Thucydides..... 3
CREASY on British Constitutions .....
CRESY'S Encyclopædia of Civil Engineering 19
Critical Essays of a Country Parson 9
CROOKE'S Chemical Analysis..... 16
——— Dyeing and Calico Printing 17
CULLEY'S Handbook of Telegraphy..... 19
CUSACK'S History of Ireland 3

DAVIDSON'S Introduction to New Testament 21
Dead Shot (The), by MARKSMAN 25
DECAISNE and LE MAOUT'S Botany 16
DE MORGAN'S Budget of Paradoxes..... 11
DE TOCQUEVILLE'S Democracy in America 6
DISRAELI'S Lord George Bentinck 5
——— Novels and Tales 24
DOBSON on the Ox..... 26
DONKIN on Diabetes..... 17
DOVE on Storms 12
DOYLE'S Fairyland 17
DREW'S Reasons of Faith 20

EASTLAKE'S Hints on Household Taste..... 18
——— Gothic Revival 18
EDWARDS'S Travels in Tyrol 22
Elements of Botany 16

ELLICOTT'S Commentary on Ephesians 21
——— Galatians 21
——— Pastoral Epist. 21
——— Philippians, &c 21
——— Thessalonians 21
——— Lectures on the Life of Christ... 21
Epochs of History 4
ERICHSEN'S Surgery 16
EVANS'S Ancient Stone Implements..... 14
EWALD'S History of Israel 21

FAIRBAIRN'S Applications of Iron 19
——— Information for Engineers ... 19
——— Mills and Millwork 19
FALKENER'S Daedalus 18
——— Museum of Classical Antiquities 18
FARRAR'S Chapters on Language 7
——— Families of Speech 7
FITZWYGRAM on Horses and Stables 26
FORSYTH'S Essays..... 6
FOWLER'S Collieries and Colliers 27
FRANCIS'S Fishing Book 26
FREEMAN'S Historical Geography of Europe 3
FRESHFIELD'S Travels in the Caucasus..... 23
From January to December 15
FROUDE'S English in Ireland..... 1
——— History of England 1
——— Short Studies on Great Subjects 10

GAIRDNER'S Houses of Lancaster and York 4
GAMGEE on Horse-Shoeing 26
GANOT'S Elementary Physics 13
——— Natural Philosophy 13
GARDINER'S Buckingham and Charles 2
——— Thirty Years' War 4
GILBERT and CHURCHILL'S Dolomites..... 23
GIRDLESTONE'S Bible Synonymes..... 20
GOETHE'S Faust, translated by Hayward ... 24
GOLDSMITH'S Poems, Illustrated 26
GOODEVE'S Mechanism 13
——— Mechanics..... 13
GRANT'S Ethics of Aristotle 6
Graver Thoughts of a Country Parson 9
GRAY'S Anatomy 17
GREVILLE'S Journal 1
GRIFFIN'S Algebra and Trigonometry 13
GRIFFITH'S Sermons for the Times..... 20
GROVE on Correlation of Physical Forces... 14
GUYOT'S Earth and Man 14
GWILT'S Encyclopædia of Architecture..... 18

HARDING'S Texts and Thoughts 22
HARE on Election of Representatives 7
HARRISON'S Political Problems..... 6
HARTWIG'S Aerial World..... 15
——— Polar World 15
——— Sea and its Living Wonders ... 15
HARTWIG'S Subterranean World..... 15
——— Tropical World..... 15
HAUGHTON'S Animal Mechanics 14
HAYWARD'S Essays 4
HELMHOTZ'S Popular Lectures 13
HEER'S Switzerland 15
HEMSLEY'S Handbook of Trees and Plants 16
HERSCHEL'S Outlines of Astronomy 11
HOLLAND'S Recollections 5
HOWITT'S Rural Life of England 23
——— Visits to Remarkable Places..... 23
HUGHES'S (W.) Manual of Geography 13
HUMBOLDT'S Centenary Biography 4
HUME'S Essays 1
——— Treatise on Human Nature 11

IHNE'S Roman History 2
INGELOW'S Poems 25

JAMESON'S Saints and Martyrs 17
——— Legends of the Madonna 17
——— Monastic Orders 17
JAMESON and EASTLAKE'S Saviour 17
JENKIN'S Electricity and Magnetism..... 13
JERRAM'S Lycidas of Milton 25
JERROLD'S Life of Napoleon 4
JOHNSTON'S Geographical Dictionary..... 12

KALISCH'S Commentary on the Bible 8
KEITH on Fulfilment of Prophecy..... 21
KENYON, Life of the First Lord 4
KERL'S Metallurgy 19
KIRBY and SPENCE'S Entomology..... 15
KNATCHBULL-HUGESSEN'S Whispers from Fairyland 23

Landscapes, Churches, and Moralities, by A. K. H. B. 9
LANG'S Ballads and Lyrics 25
LATHAM'S English Dictionary 7
LAUGHTON'S Nautical Surveying 13
LAWLOR'S Centulle 23
LAWRENCE on Rocks 14
LECKY'S History of European Morals..... 3
——— Rationalism 3
——— Leaders of Public Opinion 5
Leisure Hours in Town, by A.K.H.B..... 9
Lessons of Middle Age, by A.K.H.B. 9
LEWES' History of Philosophy 3
LIDDELL and SCOTT'S Two Lexicons 8
Life of Man Symbolised 17
LINDLEY and MOORE'S Treasury of Botany 15
LLOYD'S Magnetism 14
——— Wave-Theory of Light 14

LONGMAN'S Edward the Third 2
——— Lectures on History of England 2
——— Old and New St. Paul's 17
——— Chess Openings 27
LOUDON'S Agriculture 19
——— Gardening 19
——— Plants 16
LOWNDES' Engineer's Handbook 19
LUBBOCK on Origin of Civilisation 15
Lyra Germanica 17, 22

MACAULAY'S (Lord) Essays 3
History of England 1
——— Lays of Ancient Rome 25
——— Miscellaneous Writings 10
——— Speeches 7
——— Complete Works 1
MACLEOD'S Economical Philosophy 7
——— Theory and Practice of Banking 26
MCCULLOCH'S Dictionary of Commerce ... 26
MARKHAM'S History of Persia 3
MARSHALL'S Physiology 17
——— Todas 11
MARSHMAN'S Life of Havelock 5
——— History of India 2
MARTINEAU'S Christian Life 22
——— Hymns 22
MAUNDER'S Biographical Treasury 5
——— Geographical Treasury 13
——— Historical Treasury 3
——— Scientific and Literary Treasury 15
——— Treasury of Knowledge 27
——— Treasury of Natural History ... 15
MAXWELL'S Theory of Heat 13
MAY'S Constitutional History of England... 1
History of Democracy 1
MELVILLE'S Novels and Tales 24
MENDELSSOHN'S Letters 5
MERIVALE'S Fall of the Roman Republic... 2
——— Romans under the Empire 2
MERRIFIELD'S Arithmetic & Mensuration. 13
Magnetism 12
MILES on Horse's Feet and Horseshoeing ... 26
——— Horses' Teeth and Stables.. 26
MILL (J.) on the Mind.. 10
MILL (J. S.) on Liberty 7
——— on Representative Government 7
——— on Utilitarianism 7
'S (J.S.) Autobiography... 4
——— Dissertations and Discussions 7
——— Essays on Religion &c. 20
——— Political Economy 7
——— System of Logic 7
——— Hamilton's Philosophy 7
——— Subjection of Women 7
——— Unsettled Questions 7
MILLER'S Elements of Chemistry 16
Inorganic Chemistry 13
MINTO'S (Lord) Life and Letters 4
MITCHELL'S Manual of Architecture 18
——— Manual of Assaying 19
MONSELL'S Spiritual Songs 22

MOORE'S Irish Melodies 24
——— Lalla Rookh 25
MORELL'S Elements of Psychology 10
Mental Philosophy 10
MORRIS'S French Revolution 3
MÜLLER'S (MAX) Chips from a German Workshop 10
——— Lectures on Language 8
Science of Religion 20

New Testament, Illustrated Edition 17
NORTHCOTT'S Lathes and Turning 18

O'CONOR'S Commentary on Hebrews 21
O'CONOR'S Commentary on Romans 21
ODLING'S Course of Practical Chemistry ... 16
OWEN'S Lectures on the Invertebrata 14
——— Comparative Anatomy and Physiology of Vertebrate Animals ... 14

PACKE'S Guide to the Pyrenees 23
PATTISON'S Casaubon 4
PAYEN'S Industrial Chemistry 18
PEWTNER'S Comprehensive Specifier 27
PIERCE'S Chess Problems 27
POLE on Whist 27
PRENDERGAST'S Mastery of Languages 9
Present-Day Thoughts, by A. K. H. B. 10
PROCTOR'S Astronomical Essays 11
——— Moon 11
——— New Star Atlas 12
——— Orbs Around Us..... 12
——— Plurality of Worlds 12
——— Saturn and its System 12
——— Scientific Essays.... 14
——— Sun 12
——— Transits of Venus..... 11
——— Universe 11
Public Schools Atlases (The) 12
——— Modern Geography..... 12

RANKEN on Strains in Trusses 19
RAWLINSON'S Parthia..... 2
——— Sassanian Monarchy 2
Recreations of a Country Parson 9
REDGRAVE'S Dictionary of Artists 17
REILLY'S Map of Mont Blanc 24
REYNARDSON'S Down the Road..... 25
RICH'S Dictionary of Antiquities 8
RIVERS' Rose Amateur's Guide 16
ROGERS'S Eclipse of Faith..... 10
——— Defence of ditto 10
——— Essays..... 10

ROGET's English Words and Phrases 7
ROMALD's Fly-Fisher's Entomology 26
ROTHSCHILD's Israelites..... 21
RUSSELL's (Count) Pau and the Pyrenees... 23
RUSSELL (Lord) on Christian Religion..... 20
———— on Constitution & Government 2
———— 's Recollections and Suggestions 1

SANDARS's Justinian Institutes 6
SANFORD's English Kings..... 1
SAVORY's Geometric Turning 18
SCHELLEN's Spectrum Analysis..... 12
SCOTT's Albert Durer 17
Seaside Musings by A. K. H. B. 9
SEEBOHM's Oxford Reformers of 1496 2
———— Protestant Revolution 4
SEWELL's Examination for Confirmation... 21
———— History of the Early Church 3
———— Passing Thoughts on Religion ... 21
———— Preparations for Communion..... 22
———— Principles of Education 22
———— Readings for Confirmation 21
———— Readings for Lent 22
———— Tales and Stories 24
———— Thoughts for the Age..... 21
———— Thoughts for the Holy Week..... 22
SHARP's Post Office Gazetteer 12
SHELLEY's Workshop Appliances..... 13
SHORT's Church History..... 3
SIMPSON's Meeting the Sun 22
SMITH's (J.) Paul's Voyage and Shipwreck 21
———— (SYDNEY) Essays 10
———— Life and Letters 5
———— Miscellaneous Works ... 10
SMITH's (SYDNEY) Wit and Wisdom 10
———— (Dr. R. A.) Air and Rain..... 12
SNEYD's Cyllene..... 24
SOUTHEY's Doctor..... 8
———— Poetical Works 25
STANLEY's History of British Birds 15
STEPHEN's Ecclesiastical Biography 5
———— Freethinking & Plain Speaking 9
Stepping Stones (the Series)..... 27, 28
STIRLING's HAMILTON 10
———— HEGEL 10
STONEHENGE on the Dog 26
———— on the Greyhound..... 26
STRICKLAND's Queens of England..... 5
Sunday Afternoons, by A. K. H. B. 9
Supernatural Religion 20

TAYLOR's History of India 2
———— (Jeremy) Works, edited by EDEN 22
Text-Books of Science 13
THIRLWALL's History of Greece 2
THOMSON's Laws of Thought 7
THORPE's Quantitative Chemical Analysis 13
THORPE and MUIR's Qualitative Analysis 13
THUDICHUM's Chemical Physiology 16
TODD (A.) on Parliamentary Government... 1
TODD and BOWMAN's Anatomy and Physiology of Man 17
TRENCH's Realities of Irish Life..... 3
TROLLOPE's Barchester Towers 25
———— Warden 25
TYNDALL on Diamagnetism 14
———— Electricity 14
———— Heat 13
———— Sound 13
———— American Lectures on Light. 14
———— Belfast Address 14
———— Fragments of Science 14
———— Hours of Exercise in the Alps 23
———— Lectures on Light 14
———— Molecular Physics 14

UEBERWEG's System of Logic..... 11
URE's Arts, Manufactures, and Mines..... 18

WARBURTON's Edward the Third 4
WATSON's Geometry 13
WATTS's Dictionary of Chemistry..... 16
WEBB's Objects for Common Telescopes ... 12
WELLINGTON's Life, by GLEIG 5
WHATELY's English Synonymes 6
———— Life and Correspondence..... 4
———— Christian Evidences 22
———— Logic..... 6
———— Rhetoric 6
WHITE's Latin-English and English-Latin Dictionaries 8
WHITE & DONKIN's English Dictionary ... 7
WHITWORTH on Guns and Steel 19
WILCOCKS's Sea Fisherman 26
WILLIAMS's Aristotle's Ethics 6
WILLICH's Popular Tables 28
WILLIS's Principl of Mechanism 19
WILLOUGHBY's (Lady) Diary..... 23
WOOD's Bible Animals 15
———— Homes without Hands 15
———— Insects at Home 15
———— ———— Abroad..... 15
———— Out of Doors 15
———— Strange Dwellings 15

YONGE's English-Greek Lexicons..... 8
———— Horace..... 25
YOUATT on the Dog 26
———— on the Horse 26

ZELLER's Socrates..... 6
———— Stoics, Epicureans, and Sceptics. 6

Spottiswoode & Co., Printers, New-street Square, London.